

LAFAYETTE

RADIO ELECTRONICS

CAT. 626

LAFAYETTE "TINY" 6-TRANSISTOR RADIO

SENSATIONAL PERFORMANCE IN A SMALL PACKAGE!

NEW LOW PRICE **997**

PLUS DIODE AND THERMISTOR

- Vest Pocket Size—Only 4Hx2½Wx1¼"D
- Earphone Jack Built In For Private Listening
- Full Tone Dynamic Speaker
- Trouble-Free Printed Circuit
- Built-In Ferrite Bar Antenna
- Superheterodyne Circuit
- Economical—Uses Only One Battery

INCLUDING EARPHONE, BATTERY AND CARRYING CASE

Engineered and constructed with the jewel like precision of a fine watch... true superhet trouble free printed circuit with push pull audio output utilizes 6 ultra modern Transistors plus a Germanium Diode and Thermistor—achieves absolutely fantastic reception over the entire broadcast band. Requires only a single long-life 9 volt battery due to the exceptionally low battery drain. Smart black and gold case of rugged durable plastic. Soft leather carrying case with attached earphone pouch. Just 4Hx2½Wx1¼" thick and weighs a mere 10 ounces. Includes battery carrying case and earphone for personal listening... all at an unbelievably low price! Shpg. wt., 2 lbs. Net 9.97

FS-243L "Tiny" 6-Transistor Radio Net .21

Extra Battery for FS-206 (1 required) Net .21

BA-2 Shpg. wt., 2 oz.





LAFAYETTE RK-125 4 TRANSISTOR PORTABLE TAPE RECORDER WITH BUILT-IN SPEAKER

Complete with TELEPHONE PICK-UP, EARPHONE, PATCH CORD, MICROPHONE, 3" REEL OF TAPE, EMPTY REEL, BATTERIES

Was **21.50** NOW BARGAIN PRICED AT **15.95**

Camera Size—Only 6"Dx8¼"Wx2¾"H.

- Records and Plays Up to 20 Minutes with 1 Standard 3" Reel
- Built-in Speaker and 4-Transistor Amplifier with Push-Pull Output
- Record, Rewind, Playback and Erase

A precision, full function miniature tape recorder perfect for home, office or travel; weighs only 2½ lbs. and slips easily into a briefcase or handbag. Utilizing sophisticated transistor circuitry with 4 transistors, the RK-125AL contains its own 2"x3" FM speaker and amplifier with push-pull output stage. Engineered for ease of operation, all controls readily accessible from the front panel. A single function control provides for Rewind, Stop and Forward. Volume control. Play or Record functions are chosen by a simple slide switch. Microphone and earphone jacks are located on front panel. RK-125AL Employs a half track tape head for maximum tape economy. 6Dx8¼Wx2¾"H. Shpg. wt., 5 lbs. RT-20 3" REEL 300 Ft. ½ MIL MYLAR TAPE. Shpg. wt., ¼ lb. BA-2 9V TRANSISTOR BATTERY. Shpg. wt., 2 oz. BA-156 1.5V Battery (2 required). Shpg. wt., 2 oz.


Net 15.95
Net .68
Net .21
Net .13



SUMMER SPECIALS

NO MONEY DOWN! 24 MONTHS TO PAY! SEE PAGE 54

MODEL LT-81 FM STEREO TUNER




LAFAYETTE FM TUNER WITH BUILT-IN MULTIPLEX

- Built-In Multiplex Circuit with 30 db Separation @ 400 CPS
- Foster-Seeley Discriminator and Dual Tuned Limiters
- AFC
- AFC Off
- Extremely Sensitive—2.0 µV for 20 db Quieting
- 12 Tube Performance
- 10 Tubes (2-dual purpose)
- Freq. Response 20-20,000 CPS ± 2 db
- Low Silhouette Styling
- 3 Gang Tuning Condenser
- Tuned Grounded Grid RF Stage

76.50

NO MULTIPLEX ADAPTER REQUIRED! NO MONEY DOWN

3 Gong Condenser with Added Tuned RF Stage for Exceptional Sensitivity and Selectivity

TRULY remarkable, quality performance and styling that is in every respect the equal to and often superior to FM Stereo tuners priced far above the modest cost of this fine instrument. Designed and constructed of the finest components with jewel like precision (each unit has been hand wired and individually tested at the factory) in order to insure that each tuner will maintain its excellence year after year with a minimum of maintenance. Engineered to provide high quality FM and FM stereo multiplex broadcasts the LT-81 has an Armstrong circuit and a Foster-Seeley discriminator with dual tuned limiters. The multiplex circuit provides a stereo separation of 30 db at 400 cycles with less than 1% distortion. Controls consist of power on/selector switch for FM, Stereo MULTIPLEX, noise filter; AFC slide switch with off position, tuning Meter, Stereo dimension control to custom blend stereo reception (in rear), and Flywheel action tuning control gives velvet smooth tuning action. Pilot light goes on in stereo position. Two stereo output jacks on rear panel. Tube Complement: (2) 12AX7, (3) 6AU6, (2) 6BA6, (2) 6AQ8, 6x4 and 4 germanium diodes. Handsome low silhouette enclosure looks good in any room setting. Beautifully finished in gold and white with a contrasting black dial face. Complete with cage and legs. Dimensions: 5¾Hx13¼Wx9¼"D. LT-81WX Shpg. wt., 12 lbs. Net 76.50

SEE LAFAYETTE'S FAMOUS CITIZENS BAND TRANSCEIVERS..PAGES 6-8 Model HE-20C NOW APPROVED FOR USE IN CANADA

NEW! LAFAYETTE'S teleSpan TWO WAY RADIO COMMUNICATION

TRANSISTORIZED CITIZENS BAND "WALKIE TALKIE" 11.95 Each

21.95

NO LICENSE, TEST OR AGE LIMIT

- Superregen Receiver, Xtal Controlled Transmitter
- Simple enough for a child to operate—it requires no licenses or tests of any kind under Federal law. Perfect for camping, sports, etc. Rugged 2-transistor circuit features a powerful super-regenerative receiver with plug-in earphone for private listening. Will receive and transmit up to ¼ mile under average conditions. Fingertip push-to-talk switch provides instant X-tal controlled transmitter operation. Durable printed circuit and 9-volt battery shock mounted, assure reliable operation. A removable carrying case can be carried separately in the carrying case pouch when not being used. On-off switch is only other control. Complete with carrying case, earphones, antennas and 1.9V. Battery Size: 5¼Hx2½Wx1¼"D. Shpg. wt., 3 lbs. Net 21.95

HE-37L Set of 2 Walkie-Talkies Net 11.95

HE-38L 1 Walkie-Talkie Net ea. .21

BA-2 Extra batteries for above



LAFAYETTE PURCHASES MANUFACTURER'S ENTIRE STOCK OF FM CAR CONVERTERS FAMOUS GONSET MODEL 3311

Save Over 55%!

Below Regular Distributor's Cost! Lafayette's LOW, LOW SENSATIONAL PRICE

Was **79.50** NOW ONLY **34.95**

- 7 TUBES
- DRIFT-FREE RECEPTION
- AFC TO INSURE PERFECT STABILITY
- QUICK, UNDER - DASH INSTALLATION
- ADD HI-FI TO YOUR PRESENT CAR RADIO

Get added pleasure from your auto radio listening with the GONSET FM Converter. Now you can enjoy fine music in full high fidelity while driving. This FM tuner gives drift-free reception and eliminates "drop-out" from high tension lines and similar interference. Features include: High sensitivity (3.5 µV for 20 db quieting), high image rejection, AFC to insure perfect stability, accurately calibrated illuminated slide rule dial and instantaneous warmup. Front panel switch selects AM or FM instantly. Tube complement: 2-12Z6C, 3-12Z6, 1-12A5, 1-12AD6. Complete with mounting bracket and fused cord. Easily installed in minutes. For 12-volt negative ground operation only. Shpg. wt., 5¼ lbs. Net 34.95

SP-281 AA-41 FM Halo Antenna for Gonset 3311 Net 4.95



LAFAYETTE RADIO

SHOP BY PHONE DEPT. WALNUT 1-7500 ALL DEPARTMENTS WALNUT 1-7700

Mail Order and Sales Center
111 JERICHO TPKE., SYOSSET, L. I., N. Y.
Open Mon., Thurs. and Fri., 'till 8:45 p.m.



- JAMAICA**
165-08 Liberty Ave.
Jamaica 33, N. Y.
Axtel 1-7000
Open MON. & FRI. 'till 8:45 P.M.
July & Aug. Fri. only
- NEW YORK**
100 6th Avenue
New York 13, N. Y.
Worth 6-5300
Open THUR. 'till 8:45 P.M.
Except during July & Aug.
- BRONX**
542 E. Fordham Rd.
Bronx 58, N. Y.
Fordham 7-8813
Open THUR. 'till 8:45 P.M.
Except during July & Aug.
- NEWARK**
24 Central Avenue
Newark 2, N. J.
Market 2-1661
Open WED. 'till 8:45 P.M.
- PLAINFIELD**
139 W. 2nd Street
Plainfield, N. J.
Plainfield 6-4718
Open THUR. 'till 8:45 P.M.
- PARAMUS**
182 Route 17
Paramus, N. J.
Colfax 1-8800
Open MON., WED.,
FRI. 'till 8:45 P.M.
- BOSTON**
110 Federal Street
Boston 10, Mass.
Hubbard 2-7850
Open MON., WED.,
'till 8:45 P.M.



9 TRANSISTOR FM/AM PORTABLE RADIO

NOW HAVE HI-FI Wherever You Go!

- Full FM and AM Broadcast Bands
- 2 Antennas • 2 Antenna Extension Jacks
- 3 Outputs—Speaker, Earphone and Tuner
- Operates on 4 Inexpensive Flashlight Batteries
- 9-Transistor Superheterodyne Circuit
- Complete with Earphone, and Case

**NEW!
POWERFUL!**

69⁹⁵
NO MONEY DOWN



Now you can have all the advantages of a portable radio with all the power of a console... at a price lower than you expect. A wonderful combination of advanced technique and design in an extremely efficient 9-transistor AM and FM portable radio. Features a tuner output that converts this portable to a transistorized AM/FM tuner—real hi-fi. Other highlights include speaker output, earphone output for private listening, separate AM and FM antenna extension jacks, built-in AM antenna, and 7-section telescopic FM antenna. Convenient carrying handle; on/off switch on volume control; vernier tuning knob. 2-position band selector—FM Band 86.5-108 MC, AM band 535-1605 KC. Economical "C" type flashlight batteries. Overall 10x2 3/4 x 6 3/4". Net 69.95 Shpg. wt., 5 1/2 lbs. ea. Net .13

to operate—only 4 of the most popular priced "C" type flashlight batteries. Complete with Earphone, Batteries and Case. Overall 10x2 3/4 x 6 3/4". Net 69.95 FS-92L Shpg. wt., 5 1/2 lbs. ea. Net .13

BA-156 Extra Burgess No. 1 Battery

8 TRANSISTOR 2 BAND-AM/MARINE PORTABLE RADIO with TUNING METER

23⁹⁵
NO MONEY DOWN



- AM — 550 to 1600 KC
- MARINE — 1.6 MC to 4.6 MC
- Highly Sensitive Rod-Antenna Plus Built-in Ferrite Core Antenna
- Strong and Shock Resistant Plastic Case • Covers .55 — 4.6 Mc
- Specially Designed Tuning and Battery Energy Indicator
- Earphone for Private Listening • Practical Leather Case

This fine transistorized portable covers both the general broadcast band plus the 1.6-4.6 mc marine band. Your perfect listening companion even when at sea. A built-in antenna is used for the broadcast band and a telescoping antenna for the marine band. The telescoping antenna is readily detachable and may be carried in the same manner as a pocket pen. The receiver circuitry utilizes 8 transistors, 1 diode, and 1 Varistor Superheterodyne system with A.G.C. Also includes a specially designed tuning and battery energy indicator which allows you to check the strength of the batteries to assure maximum performance. The built-in speaker can be shut off by inserting an external earphone (supplied) for personal listening. Operates on 4 inexpensive Z cells giving up to 3 times longer life than ordinary 6 volt batteries. Comes complete with telescoping antenna, carrying case and earphone. Measures 5 1/2 x 3 1/2 x 1 1/2". Shpg. wt., 2 lbs. Net 23.95

Replacement cells for FS-244L, 4 required. Shpg. wt., 4 oz. Net each .095

CLOSEOUT SPECIAL!


NEW!

FROM WESTCLOX

— THE TRANSALARM[®] THE AUTOMATIC TRANSISTOR CLOCK RADIO

WAS 21.95

**NEW
SENSATIONAL
LOW PRICE!** **15⁸⁸**



- Automatic Radio Alarm—Turns on Radio at Preset Time • 6 Transistor Radio
- Powerful, Full Tone Speaker • 32-Hour Key-wound Clock
- Pocket or Purse Size • Earphone For "Silent" Listening

Automatic Alarm Wakes You To Music or Favorite Program. Dependable Keywound Clock Cannot Drain Battery. Private Earphone Available for "Silent" Listening. Shock Resistant Case. weight too! Radio is keyed to receive special CONEL-RAD Civil Defense broadcasts. Easy-to-read program selector—large station numbers pop into view. Beautiful black and gold break-resistant Polystyrene case. Makes a perfect gift for any occasion. Complete with battery and earphone, for private listening. Shpg. wt., 1 lb., 10 oz. Net 15.88 FS-242L Extra 9-V battery for above. Net .39 BA-2

The world's largest manufacturer of timepieces, WEST-CLOX has something new in the clock-radio design. Features automatic "wake-up-to music" alarm which turns the radio to any preset time selected. Clock operates for 32 hours on one winding—it cannot drain radio battery. Large dial face "shines" in the dark for visibility at night. Powerful 6-transistor radio with built-in ferrite antenna plays at room filling volume. Compact, only 6Wx3 1/2 x 1 1/2" D make it ideal for night table, desk or travel use. Light-



POPULAR FISHER X-101B

52 WATT STEREO
MASTER CONTROL-AMPLIFIER

QUANTITY LIMITED! REG. 189.50

**SALE
SPECIAL**
159⁵⁰


Offers 26 watts of music power output per channel, controls and switches for every stereo and monophonic application. center channel output, 14 inputs and internal switching for tape monitoring and playback. Center channel switch disconnects center speaker without affecting left and right channel speakers. High filter attenuates 12 db/octave above 5 kc, low filter 15 db/octave below 50 cps, subsonic filter 12 db/octave below 18 cps. Controls: dual input, dual MONO-STEREO, dual bass, center channel, dual treble, balance, blend, master volume equalization, low filter, high filter, dual magnetic input level, tape monitor, phase reverse and loudness. SPECIFICATIONS: Overall response 20-20,000 ± 1 db; hum and noise —65 db (low level, 6 mv ref.). Distortion 0.5% harmonic, 0.8% intermod. @ rated power: 47591 output tubes. Size: 4 1/2 x 15 1/2 x 10 7/8". Net 159.50 G-402WX Less Cabinet. Shpg. wt., 25 lbs. Net 15.95

NO MONEY DOWN

HI-FI OUTDOOR WEATHER PROOF SPEAKERS

- Completely Weatherproof Construction
- 120 Dispersion • Handles 30 Watts
- Perfect for Schools, Clubs, Churches
- True Hi-Fi Performance

AS LOW
AS
52⁹²




NO MONEY DOWN

MUSICASTOR—Designed for superior voice and music reproduction. Provides unusual bass response and balanced highs in a compact diecast aluminum enclosure. Rugged 8" Radax speaker, weather-proof cone. Ideal for schools, clubs, churches, and general auditorium use. Freq. response 60-13,000 cps, EIA rating 48 db. Power handling capacity 30 watts, impedance 8 ohms. Dispersion: 120°. Dimensions 21 1/2 x 21 1/2 x 8 1/2". Universal "U" mounting bracket Shpg. wt., 34 lbs. Net 52.92 PE-14WX

Musicaster II—Same as above, except wider coverage up to 18,000 cps. Has built in Range Extender w/in crossover. Shpg. wt., 36 lbs. Net 73.49 PE-15WX

Model MB-1 Bracket to mount Musicaster flat against wall. Shpg. wt., 1 lb. Net 2.65 PE-16

NEW! ELECTRONIC TRANSISTORIZED INTERCOM SYSTEM



**ONLY
19⁹⁵**

- Works Instantly—No Warm-up Required • 6 Station Master Accommodates up to 6 Remote Stations • garage, workshop, bedrooms, offices, etc.
- Keep in Touch Instantly with Playroom, garage, workshop, bedrooms, offices, etc.
- Supplied With 2 Remote Stations

An efficient intercommunication center that is fun for the whole family. Attractively styled to enhance the appearance of any room or office. More than adequate volume with clear tone. Easy to use—just set selector to desired station—talk and listen. No need to be close to instrument when talking. Excellent for all intercom communications as well as for baby sitting. May be placed on desk or mounted on wall. Operates on 4 inexpensive "D" type flashlight batteries. Complete with 50 ft. of connecting wire, neatly packaged in carton, less batteries. Shpg. wt., 14 lbs. Net 19.95

PA-395 Master and 2 remotes

Extra remotes for above. Shpg. wt., 1 1/2 lbs. Net 3.98 PA-396

1 1/2 volt battery (4 required) for above. Net ea. .13

BA-157 Shpg. wt., 8 oz. Net ea. .13

Additional 2 conductor intercom wire. Net .89

WR-12 100' coil. Shpg. wt., 2 lbs.

MUSICAL-AIRE SOUND SYSTEM

- Fits Air Conditioning and Forced Air Heating Ducts
- Easily Installed
- Every Register Acts as a Speaker
- Costs Far Less Than Complicated Speaker Systems



Musical-Aire, a home sound system devised for use in forced air central heating and air conditioning systems. Transforms every register throughout the home—to a speaker. Little time required for installation. No marring or breaking of wall required. Converts to any musical sound-producing mechanism: radio, TV, phonograph, etc. Unit is equipped with special baffling and antichatter materials. Use 2 units in both hot air and cold air return for a "stereo" effect. Specs: Speaker range from 55 to 12,000 cps. Resonance of voice coil at 120 cps. Size 6x9". Shpg. wt., 5 lbs., 9 oz. Net 39.95 PA-397

NEW 10 TRANSISTOR LAFAYETTE PORTABLE BROADCAST RADIO

- 10 Transistors, 2 Diodes, 1 Thermistor
- Powerful Performance — Compact Size
- Big Clear Tone — 2 3/4" Speaker
- Earphone, Leather Case Included



A remarkable achievement in compact design. 10 transistors and 2 diodes provide brilliant performance—equal to table model sets. This means more stations, greater selectivity and sensitivity. Large, dynamic 2 3/4" speaker gives you big tone, indoors, outdoors—wherever you go. Plays for hours on 4 penite cells carefully encased to protect set against battery acid corrosion. Fine quality leather cases are included for the radio and separate earphone. Two controls for simplicity: volume-off and Tune. Easy-to-read vertical slide rule dial. Complete with batteries and earphone. Size: 3 1/4" x 6 1/2" x 1 3/4" D. FS-129L Shpg. wt., 1.5 lbs. Net 22.95

WAS 25.95
NOW!
22.95

4 Additional batteries for above. Net ea. .095
BA-155 (4 required)

NEW! 9 TRANSISTOR FM/AM PORTABLE RADIO WITH PUSHBUTTON CONTROLS

- 3 ANTENNAS
- PUSH BUTTON CONTROLS
- BIG TONE PM SPEAKER

SAVE \$10.00


1962 Catalog Price 49.95

SENSATIONAL LOW PRICE



39.95
NO MONEY DOWN

This superb Lafayette radio will recreate for you all the glorious tones of thrilling, static-free FM programming as well as standard AM broadcast. Styled for tomorrow, the FS-245 features a beautiful block plastic case with carrying handle. Off, FM and AM modes are selected by positive push-buttons. A precision slide rule dial with high gear ratio tuning makes this set one of the easiest to tune. Two 22" telescoping antennas pull in most FM stations with ease while the large 3x5" PM dynamic speaker assures you of glorious tone. Other features include, built-in ferrite rod antenna for AM, tone control and 2 earphone output jacks. Sensitive circuit incorporates 9 transistors, 4 diodes 1 varistor, automatic gain control. Four inexpensive "C" type cells power the unit. Complete with batteries and earphone. Size: 9 1/4" x 5 3/4" x 2 1/2" D. FS-245L Shpg. wt., 4.5 lbs. Net 39.95



New! 9 TRANSISTOR 3 BAND PORTABLE RADIO

- Receives Standard AM Broadcasts, International and Marine on 3 Bands
- Three Built-in Antennas — 30 Inch SW Telescoping whip; 2 Ferrite Rod Antennas for BC Band and Long Wave
- AGC For Steady Reception
- Variable Tone Control
- Earphone For Private Listening
- Hi-impact plastic Case
- Combination Handle and Easel Stand
- LONGWAVE • AM BROADCAST • SHORTWAVE



29.88
NO MONEY DOWN

- 9 TRANSISTORS, 1 Diode plus one Thermistor for powerful reception
- With carrying case, earphone and batteries
- Includes short wave Listening chart

You'll get tremendous listening pleasure from this smart looking all-transistor portable. Three separate bands will afford the utmost in varied listening. The Standard AM broadcast band includes markings of two conelrad stations for quick easy location on the dial. The Long wave band between 130 and 400 KC provides Marine, Aeronautical and FAA weather broadcasts and the 4 to 12 MC Shortwave band enables you to hear International and Ham Stations. Truly a unique opportunity to explore the world's airwaves. Precision engineered the FS-128L features high sensitivity and selectivity with separate mixer and RF oscillator Stages. Self-compensating AVC avoids sudden blasts of volume and an AGC Transistorized Stage prevents sound Fade-out when the radio is repositioned. A true-tone 2 1/2" Alnico Speaker and push-pull output Stage provide the finest audio reproduction. Other features at no extra cost include three separate built-in antennas for each band including a 30" telescoping whip for better short wave reception; precision tuning on an indirect slide views dial; variable tone control; separate battery compartment to minimize damage from leaky batteries; high impact plastic case, resists breakage and chipping and a combination handle and back easel stand for easy placement on table or desk. Operates on 4 inexpensive penlite cells for long life. With leather carrying case, strap, earphone and set of 4 batteries; Size: 6 1/4 x 4 3/4 x 1 3/4". Shpg. wt., 1 1/2 lbs. FS-128L Net 29.88

BA-155 Replacement Batteries Net ea. .095

SUMMER SPECIAL!

Transtext™ WAS 6.95
NOW!

2-TRANSISTOR PORTABLE with BUILT-IN SPEAKER 5.55




- 2-TRANSISTORS + 1 DIODE • BUILT-IN SPEAKER
- COMPLETE WITH TELESCOPING ANTENNA, EARPHONE & CARRYING CASE

A two-transistor powerhouse that will amaze you with its performance and sound quality. Here's the perfect gift for that youngster who has always wanted a portable radio or use it yourself—take it anywhere, it plays everywhere. Equipped with both a ferrite antenna and detachable telescoping antenna to assure outstanding reception. In addition to its own built-in speaker the radio is supplied with an earphone for private listening. Small enough to fit in the palm of your hand it measures a mere 4x2 1/2x1 1/4". Complete with earphone, telescoping antenna, carrying case and battery. Shpg. wt., 1 lb. Imported. Net 5.55

BA-2 Replacement Battery. Shpg. wt., 3 oz. Net .39

LAFAYETTE "LONG DISTANCE" AM-SHORTWAVE TABLE RADIO

SW VALUE of The Year 1962 Catalog Price 26.50 SMASHING SUMMER SPECIAL! NOW!



19.95

- Attractive Decorator Cabinet
- Power Packed 7 Tube Performance — 5 Tubes (2-dual purpose)
- Large Slide Rule Tuning Dial with Automatic Indicator Lights
- Provision For External Phonograph
- "Big Speaker" Sound

A smart new way to enjoy yourself—listen to short-wave radio! Never before has a SW receiver of this quality been offered at such a low, low price. Beautifully styled to fit into any room, the 231 features 7 tube performance from 5 tubes (2 dual purpose) for maximum station "pulling" power. Separate SW antenna terminal to permit antenna selection suitable for location. Large PM speaker and 3-step tone control enhance your audio pleasure. Extremely legible slide-rule dial has separate pilot lights of different color which automatically switch-on to quickly identify band in use. In addition a phono jack is provided in the rear of the set for connecting any external phonograph. Covers the entire broadcast band and SW band from 3.8—12 MC. Tubes: 6BE6, 6BD6, 6AV6, 6AR5, 6X4. For 117 V, 60 cycles AC. Size 16Wx5 1/4 Dx 5 1/2" H. Shpg. wt., 10 1/2 lbs. Net 19.95

NEW! FM-AM DELUXE TABLE RADIO WITH DUAL SPEAKERS

NEW LOW PRICE

33.50
NO MONEY DOWN




- 7 Tubes plus 1 Selenium Rectifier
- Your Choice of Rich Walnut or Mahogany Wood Cabinets
- Two 4" Speakers
- Built-In Ferrite Core Antenna
- Provision For Remote Speakers & Tape Recorder

Sound, performance and features that are astounding in table model radio at this low Lafayette price. Powerful 7 tube plus rectifier FM-AM circuit pulls in stations loud and clear with an absolute minimum of distortion. Two high-quality 4 inch speakers assures you of full fidelity on both FM and AM. Controls include: Power Switch—Tone Control, Volume Control, FM-AM Band Selector and Tuning Control. Output terminals located at the rear provide for the addition of a remote speaker or for recording with your tape recorder. Cabinets are beautifully crafted and finished in your choice of rich walnut or mahogany woods. Beautifully styled to fit with virtually any decor. Supplied complete with wire antenna for FM. Covers 88 mc - 108 mc on FM; 5.3 to 10 Kc on AM. Size: 17 1/2 W x 7 1/4 H x 5 3/4 D. For 117V AC 60 cycle operation.

FS-123 Mahogany Cabinet Net 33.50
FS-125 Walnut Cabinet Net 33.50

LAFAYETTE 3 BAND 9 TRANSISTOR PORTABLE RADIO



WEATHER, AVIATION, BEACON, MARINE, AND STANDARD BROADCAST BANDS

EMPLOYS 9 TRANSISTORS, 2 DIODES, PLUS A THERMISTOR FOR HIGH GAIN PERFORMANCE

For The First Time A Radio That Receives 190-400 KC Weather, Airplane and Direction Beacon Band Plus 1.6-5 MC Marine Band Plus Broadcast Band

1962 CAT. PRICE 49.95

NO MONEY DOWN

NOW 39.95

- Three Bands Long Wave Weather Band 190-400 KC Broadcast—540-1600 KC Short Wave Marine Band 1.6-5 MC • Built-In Quality Speaker • Telescoping 9 Section Antenna • Earphone With Cord, Plug, and Leather Case • Sensitivity Control • Tone Control • Powered by 4 Inexpensive 1.5V Batteries • An Outstanding Value At Any Price • Compact, Lightweight, Self-Contained • Jack For External Speaker • Microphone Adapter for P.A. Use

A mighty-mite in any class, the Lafayette 3 band portable outperforms many home radios. Combining extremely sensitive receiver circuitry with compact design, this receiver is the answer to many boatmen, aviators, weather observers, and outdoorsmen. Giving versatility rarely obtainable in other portable receivers, this unit covers Long Wave, Broadcast, and Shortwave Marine Bands. It can be used to receive Weather, Broadcast, Marine, Aviation, Beacon, and Ham Stations. Features a handsome cabinet with clearly marked slide-rule dial. Nine Transistors, 2 diodes, and 1 thermistor. Built for years of trouble-free operation. SPECIFICATIONS: BANDS—190-400 KC, 540-1600 KC, 1.6-5MC CONTROLS—ON-OFF Switch, Volume, Tuning, Sensitivity, Tone, and Band Switch. Two antennas—A 9-section telescoping antenna for long and short waves and a powerful built-in ferrite antenna for Broadcast stations. PUSH-PULL AUDIO POWER OUTPUT STAGE. OUTPUTS—2 Phone jacks, phono. This compact, highly sensitive receiver comes complete with a handsome leather carrying case, earphone, plug, earphone case, cord, shoulder strap, battery and adapter for an external speaker. Size—8½x4¾x1¾". Carrying weight—less than 3 lbs. Shpg. wt., 4½ lbs.

FS-93L

Net 39.95

Replacement battery for above receiver (Four Required).

BA-156

Net each .13


For Planes



For Boats



Weather Reports



- Adapter for External Speaker
- Earphones with Cord, Plug and Case
- PRECISION DESIGN FOR TOP PERFORMANCE

LAFAYETTE 7-Transistor Marine & Broadcast 2-Band Radio



SEAFARER SPECIAL!

1962 Catalog Price 29.50

19.95

9 SECTION ANTENNA EXTENDED

Carrying Case

EARPHONE

A MUST for Marine Enthusiasts

- Covers AM Broadcast Plus 1.6-4.8 MC. Marine Band • Sensitive Receiver Uses 7 Transistors, 2-Diodes, And 1-Thermistor
- 2 Built-In Antennas, Including 9 Section Telescoping Antenna for Marine Band • Operates on 2 Inexpensive Penlight Batteries
- Complete With Carrying Case, Batteries, and External Earphone • A Must For Marine Enthusiasts • Compact and Light-Weight

With this new sensitive transistorized radio, Lafayette answers the needs of the marine enthusiast. Designed to be used by the week-end sailor as well as the serious yachtsman; the FS-223 is a power-packed, 7 Transistor, superheterodyne receiver. It receives both the standard AM broadcast band and the Marine Band (1.6-4.8 MC). A built-in antenna is used for the broadcast band and a 9 section telescoping antenna for the marine band. The telescoping antenna is readily detachable and may be carried in the same manner as a pocket pen. The receiver circuitry utilizes 7 transistors, 2 diodes and 1 thermistor for power-packed performance. Simple selector switch allows choice of Broadcast or Marine Bands and a clearly marked slide dial makes tuning simple. The built-in speaker can be shut-off by inserting an external earphone (supplied) for personal listening. Operates on 2 inexpensive Z cells giving up to 3 times longer life than ordinary 9 volt batteries. Comes complete with 9 section telescoping antenna, carrying case and earphone. Measures only 5½x3½x1½". Shpg. wt. 2 lbs.

FS-223L

Net 19.95

Replacement batteries for FS-223 7 Transistor radio, 2 required.

BA-155 Z Cells

Net each .095

CARDIO-MASTER

- CONVERT YOUR TRANSISTOR RADIO TO A CAR RADIO.
- FDR ALL MAKES OF CARS—CABS—TRUCKS



Cardio-Master is a magnetic holder which will hold your miniature portable transistor radio firmly to the car's dash. Your radio can be easily removed at any time for out of car use. Includes magnetic base, brackets, hardware and complete instructions. AA-45 Shpg. wt. 2 lbs.

2.98

Net 2.98



LAFAYETTE SUPER-DELUXE "MINI" 6™ TRANSISTOR RADIO

LOWEST PRICE EVER!

12.33

- 6 Transistors Plus Germanium Diode and Thermistor
- Vest Pocket Size—Only 3½ H x 2½ W x 1" D.
- Weighs only 7 ounces with batteries

- Penlight Powered For Economy—Long Life • Earphone Jack Built-in For Private Listening • Rich Tone Dynamic Speaker • Trouble-Free Printed Circuit • Built-in Ferrite Bar Antenna • Superheterodyne Circuit

A truly remarkable radio, the "MINI" 6 is so compact and lightweight (just 7 oz.) you hardly know you're carrying it—turn it on and get the biggest, clearest sound yet, from a pocket 6 transistor set. Precision engineered—true superheterodyne printed circuit board assures long trouble-free operation. Push-pull audio output, 6 transistors, one diode and one thermistor are utilized to obtain really phenomenal reception across the entire broadcast band. Only 2 two inexpensive penlight cells are required. This cuts down battery drain and lengthens playing time considerably over ordinary single cell radios. 'Jewel' black and gold case of durable plastic and soft attractive black leather carrying case with attached earphone pouch complete this smart set. Includes 2 batteries, carrying case and matched earphone for personal listening. All at our low, low price. Shpg. wt., 1.5 lbs.

FS-235L "MINI" 6 transistor Radio

Net 12.33

Extra batteries for FS-235L Type Z (2 required). Shpg. wt., 4 oz.

BA-155

Net ea. .095



LAFAYETTE "Symphonette" FM-AM TABLE RADIO

FM-AM TABLE RADIO

WITH AUTOMATIC FREQUENCY CONTROL

- 6 Tubes, 3 Diodes for 10 Tube Performance
- 4 Inch PM Speaker • 2 Built-in Antennas • Provision For External Speaker • External 300 Ohm Antenna Input Terminal
- Shielded to Meet FCC Radiation Requirements

Now you can enjoy the pleasure of quality FM as well as AM radio at a price previously reserved for AM radios alone. The Lafayette "Symphonette" is a complete AM-FM table model radio for AC and DC operation. Incorporating features found only in more expensive units, it brings the luxury of FM reception right to your fingertips. Improved AFC Action-by capacity variable diode, locks in stations and assures drift-free operation. Lock-in of FM stations eliminates annoying retuning. Automatic Volume Control softens any sudden blasts of volume and makes tuning stations of different levels a cinch. A supersensitive AM antenna brings in stations clearly while reducing unwanted noise. An FM wire antenna is provided for to assure all benefits of clear, pure reception. Built-in input terminals are also provided for external 300 ohm FM Antenna. The 4" PM speaker produces rich sound from low to high range to enhance your music-listening pleasure. A stylish polished plastic cabinet in distinctive black and white has an easy to read slide rule dial with an on-off neon indicator light. Contains 6 tubes, 1 varicap, 2 diode detectors and 1 silicon diode rectifier. An output jack on the rear of the radio permits simple plug-in connection of an external speaker. For 110-120 volts, 60 CPS AC or DC. Size: 10W x 5D x 5¼"H. Shpg. wt. 5 lbs.

FS-221A

Net 29.50

JUST COMPARE 29.50 NO MONEY DOWN

NEW! LAFAYETTE AM/FM CLOCK RADIO



39.95

- Sleep-Switch - Lulls You To Sleep
- Completely Automatic
- AC Appliance Outlet
- Big Set Tone

NO MONEY DOWN

The FS-239 combines a fully automatic Telechron clock movement with a 5 AM-FM broadcast radio. Handy sleep-switch permits you to slowly drift to dreamland while the radio 'shuts itself off' at a preset time. A buzzer alarm is included. In addition to a standard AM broadcast radio, a quality FM radio will expand your listening pleasure plus a 600 watt appliance outlet—useful to turn on the coffee pot, light etc. Slide rule dial for easier tuning. Beautiful low boy plastic cabinet in antique white with gold trim. Tubes: 50C5, 12AU6, 12AL5, 12BA6, 12BE6, 17EW8 plus a selenium rectifier. Size: 14½x6¼x6".

FS-239 Shpg. wt., 8 lbs.

Net 39.95

BIG SAVINGS VALUES

POWERFUL

8-Transistor POCKET SIZE RADIO

PERFORMS AS WELL
AS RADIOS 10 TIMES
ITS SIZE!



WAS ~~18.77~~
LOWEST PRICE
EVER!

15⁷⁷

- 8 TRANSISTORS
+ 1 THERMISTOR
+ 1 DIODE

For music, sporting events or the latest news, carry this lightweight compact portable with you anywhere. Measuring only 1x2 1/2x4 3/8" and small enough to fit in your pocket, it provides phenomenal reception throughout the entire AM broadcast band. Constructed with watch-maker precision its 8-transistor circuit pulls in the weakest stations while a full 2 1/2 inch speaker provides clear undistorted sound even at high volumes. Additional features include earphone jack for private listening, magnifying optic glass over dial for easier tuning, thumb-off volume control, vernier tuning for pinpoint selectivity and a built-in easel stand. Complete with genuine leather case, magnetic earphone with case and battery. Shpg. wt., 1 lb. FS-118L Net 15.77


BA-2 Replacement Battery. Net .39
Shpg. wt., 3 oz.

- MEASURES ONLY 1"x2 1/2"x4 3/8"
- PINPOINT VERNIER TUNING
- 2 1/2" SPEAKER

"CONTEMPORARY" AC/DC RADIO

10⁹⁹

- Styled For Any Decor!
- Priced For Every Pocket!
- Put One In Every Room!
- 5 Tubes For Peak Performance!
- Swivel Base



A "better" 5 tube radio — engineered and styled to last. Petite, contemporary design maintains clean, good looks and peak performance. 5 tubes (2 dual purpose), plus a Hi-Q ferrite rod antenna pulls in more distant AM stations. 3V. P.M. speaker, properly baffled in a sturdy, vented cabinet for clear tonal quality. Muted colors to match any color-scheme; gold trim. Pedestal base swivels for sound and reception directivity. Cabinet measures 8 1/2" x 4 1/2" x 4" overall. Tubes: 35W4, 50C5, 12AV6, 12BA6, 12BE6. For 117 V. A.C./DC. Shpg. wt., 3 lbs. FS-233 Net 10.99

NEW! HOUSE N' CAR RADIO

18⁶⁶

- Plays In Any 12V. Car or Boat or on 117V AC/DC
- No Installation — Just Plug In Lighter
- Needs No Outside Antenna
- Complete With Generator Condenser and Noise Suppressor



Play this radio anywhere! In the home — car — boat — trailer! Any place you can obtain a 12 V.D.C. or 117 V AC/DC supply! The radio (our FS-233) and the new Dynamo inverter form a customized package to suit a wealth of needs. You can even run your shaver in your car or boat! Shpg., wt., 5 lbs. SP-229 Net 18.66



AUTOMATIC 6-TRANSISTOR CLOCK-RADIO with 7-JEWEL PRECISION ALARM-CLOCK

- 7-Jewel, 11 Ligne, One-Day Alarm Movement
- Automatically Turns Radio On or Off
- Superhet Circuit — 6 Transistors, 1 Diode, 1 Thermistor
- Pocket Size — 4 3/4 x 3 1/4 x 7/8"
- Complete With Earphone, Batteries and Handsome Gift Case

29⁹⁵
NO MONEY
DOWN

More than just a clock-radio, the FS-124 is an all-transistor clock-radio featuring a patented 7-jewel watch movement with a 11 ligne one-day alarm which automatically turns the radio on at a preset time or lets you go to sleep to music and automatically shuts off. The superhet circuit uses 6 transistors, one diode and one thermistor for more power and better sensitivity. Other advanced engineering features include AVC, push-pull output stage, ferrite rod antenna, 2" speaker, gear vernier tuning. Magnifying optic glass over dial plate for easier selectivity. Operates on 3 inexpensive penlight batteries. High-impact plastic case resists breaking and chipping. Complete with earphone for private listening, batteries, gift case. Shpg. wt., 2 lbs. FS-124L Net 29.95

Extra penlight batteries for above. Net ea. .095
BA-155



NEW 7 TRANSISTOR EXECUTIVE DESK RADIO



- It's a 7-Transistor Radio!
- It's a Cigarette Box!
- It's a Pen Holder!
- Handsome Black Case with Gold Trim!
- Perfect Gift For The Man On The Way Up!

Now a Three-in-one desk set. A powerful 7 transistor AM broadcast radio specially designed to harmonize with the entire unit. Radio operates on four economical penlight cells to give long dependable service. The dial face is tilted and tuning knobs top mounted for maximum legibility and accessibility. Includes Earphone too for private listening! Right hand portion holds an extra large compartment useful for cigarettes or paper clips, etc. Two convenient penholders complete the set (Pens are not included). Beautiful black and gold finish make the set a most attractive addition to a desk. The ideal gift. Complete with 4 penlight cells and earphone. Size: 11 3/4 x 2 3/4 x 6" D. Net 19.50
FS-238L Shpg. wt., 6 lbs. Extra penlight batteries, 4 required. BA-155 Net ea. .095; 2 for .19

19⁵⁰

LAFAYETTE FM RADIO FEATURES QUALITY

5 TUBE CIRCUITRY WITH AFC

- Automatic Frequency Control Locks In Stations
- Full 4" Speaker
- Rugged Printed Circuit

WAS ~~21.50~~



NEW LOW,
LOW PRICE!

14⁹⁵

Here's the perfect FM radio for your bedroom, kitchen, office or anywhere you want the music that only FM can provide. Outstanding performance and quality for an FM radio of this size and low price. Specially designed 5 tube circuit together with a high quality 4 inch Afnic magnet speaker provides clear, undistorted reception. Automatic Frequency Control locks in the station and prevents drift while an AFC defeat switch permits tuning weak stations adjacent to strong stations. Front panel contains a pilot light, station selector (covers 88-108mc) and velvet smooth On-Off volume control. Rugged printed circuitry will provide years of trouble-free use. Supplied with antenna. Attractive modern two-tone cabinet is an asset to any decor. For 117V 60 cycle operation. Size: 5 1/2 x 9 3/8 x 4 1/2" D. Covers full FM band from 88 mc to 108 mc. Shpg. wt., 6 lbs. FS-236 Net 14.95

SUB-MINIATURE AND TRANSISTOR HEARING AID

ONLY 2 1/2" LONG x 1 3/4" WIDE x 3/8" THICK

- Lightweight—Weighs Less than 2 oz. Including Battery
- Small Enough To Be Carried in Breastpocket
- Utilizes Economical Penlight Battery
- Unique Telephone Switch Allows Telephone Conversation
- Latest Electro-Magnetic Earphone and Miniature Crystal Microphone

22⁵⁰

Features an extremely advanced circuit with 4 transistors, a high performance crystal microphone. 3 ft. thin plug-in colorless flexible cord and a unique magnetic earphone providing the clearest reception and sound reproduction yet achieved. Supplied with leather carrying case, earphone and battery. Shpg. wt., 1 lb. 1 F-480L Net 22.50


BA-153 Extra Battery (1 required) Burgess NE type. Net .08
Shpg. wt., 3 oz. Net .55
F-567 Extra Plug-In Cord For F-480 Net .55
F-568 Extra Earphone For F-480 Net 1.59



NEW! LAFAYETTE MULTIPLEX OUTPUT JACK FM TUNER

FULLY WIRED — NOT A KIT

Only **16⁹⁵**



- SLIDE RULE TUNING DIAL
- SIMPLEST OPERATION

- CONNECTS TO HI-FI, TV or RECORDER

A Lafayette low cost exclusive! The Model FS-234 Tuner is a real compact beauty. Ideal for use as a "second" FM Tuner—perfect for Students and Teenagers. Just one cable connects it to your Hi-Fi amplifier, TV or tape recorder input to give you static free FM listening enjoyment. Features a built-in multiplex jack for future adaptor installation if desired. Complete with 1 connecting cable. Most radios, TV sets, phonographs and tape recorders have phono input jacks to take the shield-plug connection

from the tuner. For equipment not provided with input jack, the necessary connections can easily be made by any serviceman. SPECIFICATIONS: Tuning Range: FM 88 to 108 MC. Controls on/off—volume, tuning. Antenna: Provision for external twin lead antenna. Power: 110-125 VAC, 30 watts. Tubes: (2) 12BA6, 12DT8, 12AL5. Size: 6 1/2 x 4 1/4 x 5 1/4" D. Shpg. wt., 4 lbs. FS-234 Net 16.95



NEW! LAFAYETTE HE-20C Deluxe CITIZENS BAND TRANSCEIVER



NOW APPROVED for use in




CANADA



By Canadian Dept. of Transport
Type Approval No. 169361029

EXCELLENT FOR BUSINESS, FARM, INDUSTRY,
CAR, BOAT, PERSONAL AND SPORTS USE



LOOK AT THESE QUALITY FEATURES

- 1 14-Tube Performance, 3 Diodes
- 2 } 8 Crystal-Controlled Transmit Positions
- 3 } 8 Crystal-Controlled Receive Positions
- 3 Tuneable Receiver over all 23 channels
- 4 Calibrated "S" Meter with Switch To Measure Signal Strength and To Check on Wattage Input to Final
- 5 Dependable Push-To-Talk Ceramic Microphone
- 6 Adjustable Squelch Control
- 7 Receive Tuneable or Fixed Crystal Selector Switch
- 8 Illuminated Dial
- 9 Highly Effective Automatic Series Gate Noise Limiter
- 10 Built-in 12 or 6 volt Power Supply for Mobile Use
- 11 Complete with channel 9 Transmit & Receive Crystals.

Not A Kit!
COMPLETELY WIRED!

MADE IN U.S.A.

109⁵⁰
NO MONEY
DOWN

NOW WITH . . .
8 CRYSTAL RECEIVE POSITIONS
8 CRYSTAL TRANSMIT POSITIONS

New Communications Microphone

Quality engineering, design, and features give this Deluxe transceiver a place all-its-own in the Citizens Band Field. Operating within the limits prescribed by the FCC, the HE-20C supplies you with a highly efficient 2-way radio-telephone communications system from your office, truck, auto, boat, store, home, etc. Two or more will serve as an effective communications system over a distance of up to 20 miles or more, depending on the terrain and the height of the antenna.


3 dual-function tubes, 1-Quadri-purpose tube, 3 tubes, and 2 Silicon rectifiers give 14 tube performance. The transmitter section features precision engineering to insure power-packed communications. The 5 watt-input crystal-controlled transmitter may be operated on any 8 of the 23 channels assigned by the FCC. The operating channel can be selected by a knob on the front panel (transceiver comes with pair of crystals for channel 9). The receiver circuits provide for 8 crystal controlled receiving channels plus a tuneable superheterodyne receiver that covers all 23 assigned channels, with a sensitivity of 1 microvolt. Effective built-in Squelch circuit quiets the receiver when no signal is being received. Series Gate Noise Limiter materially reduces ignition noise and other unwanted interference. An illuminated dial with planetary vernier tuning is clearly marked with channel numbers and lights up when tuned to any channel. New tuneable or fixed receiver switch permits selection of tuneable and fixed receive operation. The receiver terminates in 4" speaker amply supplied by over 2 watts of audio power. The unit

comes complete with a push-to-talk ceramic microphone that is conveniently mounted to the side of the transceiver. Push-to-Talk operation is accomplished with a sturdy, dependable relay. An "S" meter calibrated in 5 units 1-9 and to 30 db. above 5-9, allows measurement of incoming signal strength. The meter is wired with a switch to enable monitoring of final amplifier wattage. Incorporates Pi-network for optimum matching to 30-100 ohm antenna for high signal output. A low-loss antenna jack is mounted at the rear of the cabinet to accept the popular PL-259 connector used with dipole, ground plane, rod, and direct mounting (Lafayette HE-19) Antennas. Rugged, low silhouette case with a bracket handle for installation at any location and in any position. Tube line up 1-6AW8A, Oscillator/Amplifier; 1-6BA6, RF Amplifier; 1-6AU6 1st IF Amplifier; 1-6EAB/6UBA, mixer/rec. osc. 1-6EAB, 2nd IF Amplifier and 1st Audio Amplifier; 1-6AQ5 Audio Output/Modulator; 1-6T8, ANL, Detector, AGC, Squelch Clamp and 2nd Audio Amplifier. Size 12x5x8 1/2"D. With 115 Volts AC/12 Volts DC or 115 Volts AC/6 Volts DC Power supply. Shpg. wt., 14 lbs.

| | |
|---|------------|
| HE-20CW 115 AC/12 Volts DC | Net 109.50 |
| HE-43BW 115 Volts AC/6 Volts DC | Net 109.50 |
| HE-830L Transmit Crystal (Specify Channel or Frequency) | Net 2.25 |
| HE-22L Receive Crystal (Specify Channel) | Net 2.25 |
| Direct plug in antenna for short distance communications. | |
| HE-19 Shpg. wt., 1 lb. | Net 3.95 |



NEW! LAFAYETTE HE-15B SUPERHET CITIZENS BAND TRANSCEIVER!



MADE IN U.S.A.



NEW
8 Crystal Transmit Positions
Increased Selectivity in IF's
Attractive Modern Styling

ONLY **59⁵⁰** NO MONEY
DOWN

COMPLETE 2-WAY COMMUNICATIONS FOR
BUSINESS, HOME, FARM, BOAT, AND SPORTS

Not Superregenerative but SUPERHET!
NOW WITH ADDED FEATURES

- 8 Crystal-Controlled Transmitting Positions
- Effective Full-Wave Variable Noise Limiter
- RF Jack on Front Panel
- Ceramic Temperature-Free Microphone

- IMPROVED SELECTIVITY AND POWER OUTPUT
- SUPER-HETERODYNE TUNEABLE RECEIVER OVER FULL 23 CHANNELS
- 4 DUAL FUNCTION TUBES, PLUS 2 SINGLE-FUNCTION TUBES, PLUS 2 RECTIFIERS FOR 12-TUBE PERFORMANCE
- PLANETARY VERNIER TUNING
- COMPLETE WITH TRANSMITTING CRYSTAL FOR CHANNEL 9

THE GREATEST VALUE
in the CITIZENS BAND FIELD

The Lafayette HE-15B Superheterodyne Transceiver is both a compact precision transmitter and receiver designed to operate on the new class D "Citizens Band." Two or more of these units furnish your own communications system covering up to a 20 mile or more radius depending on antenna height and terrain. The Transceiver features 8 crystal controlled transmitting channels operating at a maximum legal power input of 5 watts fully modulated, RF stage in both transmitter and receiver. The 8 position crystal selector on the front panel selects any one of 8 transmitting frequencies. These 8 crystals are readily accessible by means of a removable front plate. The superheterodyne receiver is tuneable over the full 23-channel band, with 3 watts audio output, AVC, and an amazingly effective Full-Wave Variable Noise Limiter. The Noise Limiter is continuously variable from the front panel for diminishing ignition and other unwanted noise pickup.

RF jack on the front panel may be used to monitor the current in the final tube using external meter. Controls include a 3-position function switch (transmit, receive, and transmit with spring return), planetary vernier tuning, plus variable noise limiter. Output impedance matches 52 and 72 ohm antenna with Amphenol type coax connector. Has large PM speaker; input jack for crystal or ceramic microphone; power receptacle in rear

for AC line and 6 or 12 volt external power supply. Supplied with single transmitting crystal for channel 9, high output ceramic microphone, and brackets for easy mounting of units in auto, boat, etc. Operates on 115 volts AC. Addition of 6 or 12 volt power supply (separately supplied) adapts transceiver for mobile operation. Size 10 1/2 x 6 x 4 1/2 "D. Tube complement: 2-6U8A/6EA8, 1-6AL5, 1-6V6, 1-12AX7, 1-6AW8. HE-15BW Shpg. wt., 11 lbs. Net 59.50

POWER SUPPLY: Adapts HE-15B for mobile operation. Complete with cable, 6 or 12 volt vibrator and mounting flanges. Completely enclosed. Size 4 1/2 x 6 x 4 1/2 "H. Shpg. wt., 4 lbs. Net 10.95

HE-16W For 12 Volts Net 10.95

HE-18W For 6 Volts Net 10.95

ANTENNA: Base loaded telescoping whip antenna with PL259 coax connector. Mounts directly on rear of cabinet. Telescopes to only 15". For short distances. HE-19 Shpg. wt., 2 lbs. Net 3.95

TRANSMITTING CRYSTALS: For any of the 23 channels. Specify channel or frequency. HE-830L Net 2.25

CITIZENS BAND—The New Two-Way Personal Communications Method for Everyone—Fill out the FCC form enclosed with each Lafayette Transceiver. No examination or technical knowledge required—Any citizen 18 years or older is eligible for a license.

LAFAYETTE OUTSTANDING VALUES IN CITIZENS BAND ANTENNAS & ACCESSORIES



New Lafayette Fiberglass CB Antenna 48" CONTINUOUSLY LOADED CITIZENS BAND COWL MOUNT ANTENNA

695

- Rugged Fiberglass Construction
- Easily Mounts On Cowl or Rear Deck

Lafayette makes antenna news with this new continuously loaded fiberglass antenna — only 48" high but performs like 102" antennas. Designed for cowl mounting this latest development in mobile antennas provides an excellent radiation pattern. Substitutes for conventional 1/4 wave whips as well as base-loaded and center loaded antennas in the 27 mc band. The four foot whip eliminates the possibility of striking overhead objects. A black plastic covering of whip insures against shorting. Specially designed rocker support assures 8 point grounding and permits mounting up to 35° angle on fender, cowl or rear deck — Fits any 3/8" to 1 1/4" mounting hole. Complete with 5 ft. of RG-58U cable.

HE-57W Shpg. wt., 3 lbs. Net 6.95

NEW "BLACK BOX" M-82 CB ANTENNA AMPLIFIER

- Produces Constant 100% Legal Power at the Antenna
- Increases the Effective Transmitted Modulation Gain by 10 db, The Received Gain by a Minimum of 20 db.
- Drastically Reduces Inherent Mobile Interference

An entirely new class of CB power accessory that gives you fantastic new performance into and out of your present CB equipment. Increases the effective transmitted modulation gain by 10 db, the received gain by 20 db (minimum). SPECS: Control Box—On/Off Switch, Neon Pilot Light, Fused; with 10' RG-58/u Cable and PL-259 Connector. 3x4x5". Amplifier—Aluminum Weatherproof Case, 4 tubes, 10' RG-58/u Cable, Self-powered, 3 1/2" dia. x 14" deep, Meets FCC Limitations. Easy to install. Shpg. wt., 15 lbs.

HE-969WX Net 78.35

LAFAYETTE TELESCOPIC CITIZEN'S BAND WHIP ANTENNA

SENSATIONAL VALUE
IN A DIRECT
MOUNTING CITIZENS
BAND ANTENNA **395**

Sturdy, attractive chrome plated whip antenna that telescopes from approx. 45" fully extended to only 15" to facilitate portability and storage. Ideal for shorter distances up to several miles. Has enclosed base loading coil for proper impedance matching. Complete with removable PL-259 connector that permits direct top, side or rear mounting to transceiver.

HE-19 Shpg. wt., 1 lb. Net 3.95

NEW "SPEAKEASY" AUDIO COMPRESSOR AMPLIFIER for CITIZEN BAND TRANSCIVER

• For Mobile and Base Transceivers • Built-in Modulation Meter • Works with all Popular CB Units

Automatically and effectively increases average modulation, voice, readability, and therefore distance without over modulation. Speak Easy is suitable for mobile or base use, and is available for 115/12 or 115/6 volts. Final power input to transmitter remains within legal 5 watt limit, but effective voice power is increased many times. Easily attaches to your CB transceiver, requires practically no power for operation. Complete operational and installation instructions are provided.

2 1/4 Hx 5 L x 4 D. Shpg. wt., 3 lbs. HE-905 "Speak Easy" 115VAC/12DC Net 34.75 HE-906 "Speak Easy" 115VAC/6DC Net 34.75

LOW COST — ECONOMY CITIZENS-BAND GROUND PLANE ANTENNA NEW! The Ideal Antenna For Your C B Base Station

880

Here's rugged performance in a Citizens-Band base station antenna at a truly economical price. Incorporating a special "drooping radial" design for improved impedance characteristics, this excellent ground plane antenna utilizes a 360° polar pattern to provide complete coverage in any direction. Made-to-last construction features a rugged 1 inch diameter radiating element. A double U-bolt arrangement provides the strongest possible mount under the most severe conditions.

HE-694WX Shpg. wt., 6 lbs. Net 8.80

THE LAFAYETTE "Super-Beam" ANTENNA

A 3 Element Vertical or Horizontal Beam Antenna For Citizens Band.

MULTIPLIES
POWER 8 TIMES **2595**
No Money Down

Developing a tremendous forward gain of 9db this new Lafayette "Super Beam" is the most powerful CB antenna available. Works equally well for transmitting and receiving. Front to back ratio of 25 db and front to side ratio of 40 db. Provided with bracket for vertical mounting for contacting mobile stations or ground plane equipped base stations. Units may be stacked horizontally or vertically for an additional 3db gain which effectively redoubles power, making the effective radiated power of your 5-watt CB transmitter equivalent to approximately 80 watts input. Ruggedly constructed of all aluminum heat treated alloy. Two inch O.D. boom is 8 feet long. Elements measure 16 1/2 ft. long with 3/4" to 5/8" O.D.

HE-64WX Shpg. wt., 18 lbs. Net 25.95

ANTENNA SPECIALISTS MAGNUM-27 1/2 WAVE 27MC ANTENNA

Compact vertical radiator with an actual 6 DB gain over any single element omni-directional antenna. Constructed of rigid aluminum and cadmium plated steel, it is corrosion resistant, waterproof and fits on most masts or directly into wooden areas. Hi-"Q" phasing transformer provides proper resonance over entire CB band. Direct ground lightning protection. 50 ohm feed. Total height is only 18" 2". (17" 3" radiator, 4-54" radials. Shpg. wt., 12 lbs.)

HE-487WX Net 27.88

TENNA C-BAM AUTOMATIC MOBILE CB ANTENNA

Operates Electrically At The Touch Of A Switch.

Revolutionary automatic cowl mount antenna that operates electrically at the touch of a switch. Sturdy, compact and most resistant, it extends to 55"—collapses to 19 1/2". Top mounted coil is not exposed when collapsed—completely disappears into antenna. Includes: switch w/bracket, 72" electric harness, 60" RG 58/u cable plus a PL-259 plug and UG-175 adaptor, 54" radar type copper shielded cable and hardware. For 12 volts only.

HE-927W Shpg. wt., 6 lbs. Net 23.02

LAFAYETTE "DUMMY" ANTENNA LOAD FOR CB TRANSCEIVERS

A 52 ohm non-inductive load for testing and tuning-up Citizens Band transmitters up to 5 watts. It permits tune-up into a non-radiating element instead of into antenna — in compliance with F.C.C. regulations. Built-in PL-259 coaxial plug is easily connected and disconnected from equipment. Shpg. wt., 1 lb.

HP-203 Net .98

BLITZ BUG LIGHTNING PROTECTOR

Designed to fit any standard coaxial cable, the "Blitz Bug" employs the spark gap principle to eliminate static build up on coaxial cables. Provides a constant drain off, reducing chances of a direct lightning strike and in many cases eliminating noise problems. Constructed of 3/4" O.D. brass by 2 1/4" long. Employs one PL-259 plug and one DKCB connector (takes PL-259 plug.) Shpg. wt., 1 lb.

HP-50 Net 3.95

CDR AR-22 AUTOMATIC ROTOR FOR CITIZENS BEAM

This heavy-duty rotor unit will handle antennas up to 150 lbs. Simply set the control unit pointer to the desired direction, and the antenna will automatically rotate to this position and stop. Perfect for TV, Ham or Citizen Band application. Rotor unit employs 12 heavy duty ball bearings in two 6 1/2" races. Weather-proof motor reverses instantly and is factory lubricated for life. Reversible clamps on rotor will take masts from 7/8" to 2". O.D. Control unit is marked in compass points. N.S.E.W. NW, NE, SW, and SE. Housed in attractive brown plastic cabinet with rubber feet. Complete with rotor, control unit and instructions. For 110-120 volts 50-60 cps AC. Requires 4 conductor cable.

HE-476WX Net 32.77

4-Conductor cable for HE-476WX rotor WR-24 ea. ft. Net .03; 100 ft. Net 2.39

"NOISTOP" IGNITION NOISE ELIMINATOR

1661

Effective as both a noise limiter and a positive squelch the "Noistop" improves reliability and operating pleasure, when vehicle is in traffic. Measures only

1 1/2 x 2 1/2 x 4". Complete with tubes (6AL5 and 12AX7) and instructions for easy installation in most available transceivers. For use with super-heterodyne type transceivers. Furnished with cable and gold anodized cabinet with black perforated cover. Mounts in any position. Shpg. wt., 10 oz.

HE-802 Net 16.61

LAFAYETTE GENERATOR NOISE FILTER

• Frequency Range 3-30 mcs • Simple to install • Maximum Current 25 Amps • Adjustable

Enables quiet receiver operation for Citizens Band, Amateur and industrial frequencies. Standard frequency range 3-30 mcs. Maximum current 25 amps.

CF-135 Shpg. wt., 1 lb. Net 2.49

B & W 424 CB LOW PASS FILTER

Designed to effectively reduce TVI — Radiated spurious and other undesirable signals higher than 35 MC are attenuated by at least 60 db—power rating: 100 watts max. Frequency Range: 1.5 to 30 MC, Impedance: 50/75 ohms (reversible) Size: 5x2x1 3/4".

HE-304 Shpg. wt., 1 1/2 lbs. Net 8.65

LAFAYETTE TM-59'er "S" METER

- Now For Hams, SWL's and CB'ers—A Signal Strength Meter Using VTVM Principles • Easy To Install and Operate
- Magnetic Feet For Mobile Dashboard Mounting
- Sensitivity and Zero Adjust Controls

Designed for use with any superheterodyne receiver employing AVC, the TM-59'er utilizes a high input Wheatstone bridge circuit which produces no detrimental loading effect upon the receiver. Meter is calibrated in "S" units from 1 to 9, and in db up to 40db over S9. Includes zero adjust and sensitivity controls. Partial peak clipping is provided for noise limiting. Installation is simple—only 4 leads to connect for input, B+, filament and ground. The use of a 12AU7 tube makes the TM-59'er adaptable to either 6 or 12 volt equipment, and to receivers using 150 ma or 300 ma series string filament systems. Requires 150-200 VDC for B+ which can be "stolen" from most receiver power supplies. Complete with 12AU7 and installation instructions.

TM-59A Shpg. wt., 2 lbs. Net 8.95

LAFAYETTE TRANSISTORIZED FIELD STRENGTH METER

- Permits Easy Tune-Up For Maximum Transmitter Output
- Earphone Jack to Monitor Audio • Tuned Input from 2.53 to 57 MC

A transistorized, tuned field strength meter covering 2.530 Mc to 57,000 Mc in 3 bands. Ideal for use with ham, Citizens Band or other transmitters within this frequency range. Enables user to tune his transmitter and antenna for maximum RF output. The RF is sampled by a plug-in telescoping antenna (supplied) and relative field strength is read on a 200 μ a meter calibrated from 0 to 10. Earphone jack provided for the monitoring of any audio on the signal. Electrical and mechanical zero adjustments on front panel. Other controls: gain/on-off switch, tuning, and band selector switch. Powered by single small 1 1/2 volt battery with lifetime approaching "shelf life"—can be operated anywhere. In attractive metal cabinet with telescoping antenna and battery.

TM-16A Shpg. wt., 2 lbs. Net 15.95

High output earpiece for use with TM-16A. MS-439 Net 1.09

BA-155 Replacement battery for above Net .095

1595



LAFAYETTE MODEL TM-15A WAVE-METER for AMATEUR and CITIZEN BANDER

895

A miniature wavemeter for checking transmitter output. Determines relative strength of fundamental frequency and any harmonic or parasitic radiator, and in so doing aids in elimination of these unwanted emissions. Complete and self contained, the TM-15A requires no power source. Telescoping antenna is included. Merely choose proper band and turn tuning knob until edgewise 3/4" panel meter indicates the presence of RF. If indications occur at several points within the range of the wavemeter, the transmitter is probably radiating spurious frequencies. Tunes 1.6 to 150 mc in four calibrated bands. Only 3 1/4 W x 2 3/4 H x 1 1/2 D. Antenna is 10 3/4" extended. 3 1/4" telescoped, is fitted with a banana plug and is removable. Total shpg. wt., 8 oz.

TM-15A Net 8.95

LAFAYETTE RADIO FIELD INDICATOR

- A MUST FOR ALL HAM AND CB OPERATORS
- Continuously indicates transmitter output
- Rugged 200 μ a meter movement
- Requires no Electricity, Batteries, or Transmitter Connection
- Powerful Magnet on Bottom Plate for Mounting on Dashboard or Other Metal Surface

With this rugged, new radio field indicator you can check performance of your marine, mobile or fixed transmitter. Features a 200 μ a meter movement with variable sensitivity control. Earphones can be plugged in for an aural check of output. Antenna extends from 3 1/4" to 10 3/4". Powerful magnet on bottom plate allows easy mounting on car dashboard or metal surfaces. Use anywhere — requires no electricity or batteries. Dimensions: (less antenna) 3 1/4 W x 2 1/4 H x 2 D.

TM-14 Shpg. wt., 7 oz. Net 6.95

High output crystal earpiece for use with TM-14. MS-439 Net 1.09

695



CITIZENS BAND 2-WAY RADIO COMMUNICATIONS

FREE! CITIZENS BAND ANTENNA

Select 1 of the 4 CB antennas listed below and receive this antenna free with the purchase of any Citizens Band Transceiver on this page.

NEW GROUND PLANE ANTENNA



1195

Solid aluminum 108 inch heat-treated radials and radiator. Elements supplied in two 54 inch lengths joined by threading coupling nuts. Radials droop for 50 ohm match. Accepts 1 1/4 inch tubing RG-58/U cable and PL-259 connector. Shpg. wt., 4 lbs.
HE-890W Net 11.95


BUMPER MOUNT ANTENNA



1595

Adaptable to virtually all American and Foreign cars. Includes double bumper mount with cable terminals, cadmium plated spring, 102" stainless steel whip, 20 ft. of RG-58 U cable with PL-259 connector on one end, solder lugs on the other, and whip hold-down clip. Shpg. wt., 5 lbs.
SP-198WX Net 15.95


MOBILE REAR COWL MOUNT ANTENNA



1852

Complete Antenna Kit for rear deck or side mounting. Consists of cadmium plated base, special alloy cadmium plated spring, 102" stainless steel whip, cable and gutter clip. Furnished with 20 ft. RG-58/U cable, having PL-259 connectors on both ends. Shpg. wt., 6 lbs.
HE-674WX Net 18.52

COAXIAL ANTENNA



1495

The half-wave coaxial antenna is widely used in commercial and emergency communications. It consists of a quarter-wave vertical element (108" long) above a quarter-wave cylindrical "skirt" which surrounds and is concentric with the mast. Constructed entirely of aluminum, it requires 15 ft. 1 1/2" TV masting or 12 ft. aluminum tubing for support. Uses RG-59/U or RG-11/U coaxial line. Overall height 17'6". Shpg. wt., 5 lbs.
HE-804WX Net 14.95




JOHNSON VIKING "MESSENGER" CB TRANSCEIVER AS LOW AS **13495**

Designed for reliability and easy installation in your home, business location, car, truck or boat. Excellent receiver sensitivity and selectivity. Features 5 crystal controlled receiving and transmitting channels. Transceiver has 10 tubes (including rectifier). Compact modern styling. 5 1/2"x7 1/2"x1 1/2" D. Complete with tubes, push-to-talk microphone, and crystals for one channel. Shpg. wt., 15 1/2 lbs.

HE-447WX Model 242-128 115VAC/12VDC Net 144.95
HE-448WX Model 242-127 115VAC/6VDC Net 144.95
HE-451WX Model 242-126 115VAC Net 134.95
Universal Dash Mounting Kit for HE-447WX, HE-448WX, HE-451WX. Shpg. wt., 2 lbs.
HE-407 Model 251-828 Net 2.50
Lafayette transmit type crystal for Johnson "Messengers." Net 2.25
HE-830 (Specify Frequency) Lafayette receiver type crystal for Johnson "Messengers." Net 2.25
HE-832L (Specify Frequency) Net 2.25

OSBORNE 300 ALL TRANSISTORIZED CITIZENS BAND RADIO **14950**
NO MONEY DOWN



The Osborne 300 employs 9 transistors in a deluxe, ultra-compact transceiver unit. Receiver sensitivity is better than 1 uv, typically 0.5 uv, for a 10 db (S+N)/N ratio. High selectivity (2.6Kc at 6 db down) results in adjacent channel attenuation of 50 db. Includes built-in squelch circuit. Total receiver power drain is 3 watts. Transmitter has input of 3.2 watts P.E.P., crystal controlled within a frequency tolerance of +/- .005%. Includes push-to-talk microphone, power supply, 1 set of crystals. Modern decorator styling, in jet black.
HE-838WX Model 300, for 117VAC — Shpg. wt., 6 lbs. Net 149.50
Model 830 6VDC converter for mobile use with Model 300
HE-837 Net 15.00
Model 840, 12 VDC converter for mobile use with Model 300
HE-836 Net 15.00
Lafayette matched receive/transmit crystals for Osborne 300
HE-831L Net 4.50

SONAR MODEL E 5 WATT CITIZENS BAND RADIO

17950

NO MONEY DOWN

The Model E combines a highly sensitive superheterodyne receiver with a 5 watt transmitter in a completely self-contained, compact unit. Receiver features a sensitivity of 0.5 microvolt for 10 db quieting, an adjustable squelch and an automatic series noise limiter. Selectivity is 5 KC at 6 db down. Can be operated on 8 crystal controlled channels or tuned over all 22. Transmitter input is a full 5 watts (FCC limit), modulated up to 100%. Operates on 8 crystal controlled channels, with a frequency stability of .005% or better. Adjustable squelch. Includes high impedance ceramic microphone with push-to-talk switch. Completely self-contained dual power supply. Measures only 11 1/2"x9 1/2"x4 3/4" H.

HE-372WX For 117VAC/12VDC — Shpg. wt., 12 lbs. Net 179.50
HE-373WX For 117VAC/6VDC Net 179.50
Lafayette matched receive/transmit crystals for Model E
HE-832L (Specify frequency) Net 4.50



NEW POLY-COMM "N" CB TRANSCEIVER

18950

Designed for continuous, heavy-duty operation, the "N" with a NuVistor front end, an ultra high-gain stage which pulls in the weakest signals, provides sensitivity of better than 0.1 uv for 6 db S/N and better than 0.14 uv for 10 db S/N. Precision engineered and tested to fine professional performance. Equipped with all electronic transmit/receive switching and 4 crystal controlled transmit/receive channels. Other features include dual conversion superheterodyne receiver with adjustable squelch circuit and floating series gate type noise limiter, built-in carrier and modulation indicator, 4 full watts audio output. Minimum of 3 watts power output to antenna. Adjustable antenna matching for 52 or 72 ohms. Weather-proof 4" pm speaker, cadmium plated weatherproof steel case and chassis. Shock proof ceramic microphone has press-to-talk switch and retractable coil cord. 11 tubes and 7 diodes give eighteen tube performance. Complete with crystals for one channel. Microphone and instructions. Size 11x7 1/2"x5". Shpg. wt., 18 lbs.

HE-293WX 115VAC/12VDC Net 189.50
HE-294WX 115VAC/6VDC Net 189.50
Lafayette matched crystals (receiver/transmit) for Poly-Comm "N".
HE-297L (Specify Channel) Net 4.50




ALL STAINLESS STEEL CITIZEN BAND MOBILE ANTENNA OUTSTANDING FEATURES

- 102 1/2" Stainless Steel Whip For Optimum 11 Meter Performance
- Heavy-Duty Chrome Plated Stainless Steel Spring
- Chrome Plated Swivel Ball Jointed Mount Base

695

Chrome plated swivel ball mount base designed to be mounted on any surface. Stainless steel spring holds rod in properly adjusted position and prevents rod damage from shocks and blows. Stainless steel whip for maximum resiliency and strength. Shpg. wt., 4 lbs. Has lug terminals for HP-52 cable assembly.
HE-800WX Net 6.95



NEW! LAFAYETTE CHROME PLATED MOBILE BUMPER MOUNT WITH STAINLESS STEEL STRAP

- Completely Adjustable For Use With Most Types of Automobile Bumpers
- Highly Reliable and Durable!

395

An outstanding new Lafayette mobile bumper mount featuring chrome plated mount and stainless steel strap which is completely adjustable for vertical mounting on most types of automobile bumpers. Eliminates need of cumbersome link type chain mounts. Shpg. wt., 1 1/2 lbs.
HE-33 Net 3.95



NEW UNIVERSAL LAFAYETTE CITIZENS BAND AMATEUR SPRING AND SWIVEL BALL-MOUNT BASE

289

- Heavy-Duty Chrome Plated Stainless Steel Spring



195

- Chrome Plated Swivel Ball Jointed Mount Base



New universal Lafayette HE-53 chrome plated swivel ball mount base with lug terminals for use with mobile antennas. Exclusive Lafayette design provides easy adjustment and at the same time prevents loosening by vibration or shock. Can be mounted vertically or horizontally on any surface. With lug terminals for use with mobile antennas.
HE-53 Net 1.95


New Universal Lafayette HE-54 Heavy duty chrome plated stainless steel spring. Provide maximum support for long whips and heavy center-loaded whips.
HE-54 Net 2.89

LAFAYETTE AUTO-MARINE ENGINE NOISE SUPPRESSOR KIT

945

- A Must For Mobile CB & Ham Operators
- 14 Components Plus Hook-Up Wire

This easily installed kit will effectively suppress ignition, generator and voltage regulator noise. Consists of 8 spark plug suppressors; 1 distributor suppressor, 1 voltage regulator suppressor; 4 coaxial capacitors; shielded cable and braid for wiring filter system. All necessary hardware and instructions for installation are included. Shpg. wt., 2 lbs.
HP-204 Net 9.45



JUST OUT!

NEW LAFAYETTE CITIZENS BAND COLINEAR GROUND PLANE ANTENNA



- Double Power In All Directions
- 3.4 DB Gain Over Normal Ground Plane Antennas
- Built-To Heavy-Duty Commercial Specifications

Only **2495**
No Money Down

Increase the performance of your Citizens Band rig with this newly developed Lafayette antenna. Utilizes a new concept in CB antenna design which achieves gain through colinear action. Concentrates more power at lower angles to the horizon. Performs equally well receiving or transmitting, greatly increasing the range of consistent CB communications. Precision Tuned and matched for 52-ohm coaxial cable, either RG-8/U or RG-58/U. Overall only 20-ft. high; radiation is 1 1/2" O.D. to 3/4" O.D. heavy wall heat-treated aluminum tubing, 9-ft. long radials of 3/8" O.D. aluminum tubing. Accepts all masts up to 1 3/8" diameter. Complete with matching stub and assembly instructions. Shpg. wt., 10 lbs.
HE-63WX Net 24.95

SQUELCH THAT INTERFERENCE!

NEW LAFAYETTE HE-55 SQUELCHER



- PROVIDES FULL SQUELCH AND NOISE LIMITING TO ANY SUPERHETERODYNE TRANSCEIVER OR RECEIVER
- VASTLY IMPROVES MOBILE TRANSCEIVERS WHEN VEHICLE IS IN TRAFFIC
- REDUCES NOISE FROM IGNITION SYSTEMS AND OTHER SOURCES

1095


The Lafayette "Squelcher" noise eliminator and squelch was designed to improve reception and reliability in all superheterodyne transceivers or receivers including the Lafayette HE-15A, HE-158, HE-20A, HE-20B, HE-30, HE-45, HE-50, and KT-320. Reduces noise from ignition systems and other sources. Quiets receiver when no

signal is received. Vastly improves sensitivity of mobile transceiver when operating in traffic. Complete with 2 tubes (6AL5 and 12AX7), instructions for any installation in any receiver. In Satin aluminum with blue gray perforated cover. Furnished with cable. Size: 2-3/10x3 1/2x4 1/4".
HE-55 Shpg. wt., 1 1/4 lbs. Net 10.95

LAFAYETTE 12 POSITION CRYSTAL SELECTOR

650


Houses and selects up to 12 crystals - increases channel coverage. Chassis has 12 ceramic crystal sockets, wired to a 12 position, no stop selector switch. Long reach shaft permits practical mounting. Chassis size: 2 1/4" D x 2 1/4" W x 2 1/4" H. Shpg. wt., 1 lb.
HP-201 Net 6.50



20 FT. RF COAXIAL CABLE ASSEMBLIES FOR CITIZENS BAND EQUIPMENT



2.95



2.45

These cable assemblies are necessary for connection between Citizens Band Transceiver and Antenna.
TYPE A—Consists of 20 ft. RG-58/U cable with PL-259 plus UG-175/U on both ends. Required for Ground Plane and Coaxial and Mobile Antennas terminating in a coaxial jack. Shpg. wt., 8 oz.
HP-51 Type A 20 ft. length Net 2.95
TYPE B—Same as type A except one end is terminated with PL-259 plus UG-175/U and other end with universal ring type terminal lugs for mobile antennas. Shpg. wt., 8 oz. RECOMMENDED FOR USE WITH HE-800WX MOBILE ANTENNA
HP-52 Type B 20 ft. length Net 2.45

LAFAYETTE BROADCAST TO CITIZENS BAND COUPLER

695

Specially designed network permits any Citizen's band mobile antenna to be used also for broadcast reception. No switching necessary. With SO-239 antenna receptacle, 2 ft. lead with coaxial auto plug for broadcast radio connection and 2 ft. lead with PL-259 coaxial plug for transceiver connection. Shpg. wt., 1 1/4 lb.
HP-202 Net 6.95



SELECTED AMATEUR EQUIPMENT and ACCESSORIES



FREE! FAMOUS NAME ELECTRIC WORLD CLOCK WITH PURCHASE OF HALLICRAFTERS S-120


Only **69⁹⁵** No Money Down

NEW! HALLICRAFTERS S-120 RECEIVER
Covers Broadcast Band 550-1600 KC plus 3 Short Wave Bands 1600 Kc to 30 Mc. 3 Antennas, Slide Rule Bandspread Dial, New Compact Styling.

This new precision built receiver features electrical bandspread with slide rule bandspread dial and separate bandspread tuning condenser. Front panel head-phone jack which automatically disconnects self-contained speaker may be used to drive remote 8 ohm speaker. Has 3 antennas (ferrite loop for broadcast band; adjustable whip for short wave; wire antenna).

Tube complement: 12BE6 Converter, 12BA6 I-F amplifier, B.F.O., 12AV6 Audio amplifier, AVC detector, 50C5 Audio, plus Selenium Rectifier, 455KC IF. Attractive gray steel cabinet with silver trim. 13¹/₂Wx5⁷/₈Hx8³/₄"D. (U/L Approved). Operates on 105-125V 50/60 cycles. AC/DC. Shipping weight 12 lbs. SP-257 S-120 R/CVR plus free Electric Clock 69.95

NEW HE-56 LAFAYETTE 6-METER CONVERTER



ONLY **29⁹⁵** NO MONEY DOWN

- Self-Powered
- Printed Circuit
- 7-11 Mc. Output

A deluxe 6 meter converter designed to respond to the weakest signals with very low noise. The HE-56 will convert any shortwave receiver that tunes 7-11 Mc. to cover 50-54Mc. Easy to install between main antenna and receiver's antenna terminals. When the converter's control switch is in the DFF position, signals from the main antenna will be fed around the converter circuit into the receiver thus the receiver will receive both the original frequencies and the 6 meter band. Rugged printed circuit and heavy gauge steel chassis make this unit as durable as the receiver it's connected to. SPECS: Freq. range—50-54Mc. Crystal freq.—43Mc. Sensitivity—better than 1 microvolt for 40 db s/n ratio. Image Rejection— in excess of 40 db. Antenna input impedance—52 ohms. Tubes—6AQ8, 6BL8, For 117VAC, 50-60 cps. Size: 7¹/₂Hx3¹/₂Wx5¹/₂"D. HE-56 Shpg. wt., 6 lbs. Net 29.95

NEW! HE-34 SWR AND FORWARD POWER METER




16⁹⁵

- Reads SWR and Relative Power Output Up To 1 KW
- Highly Compact—Only 2¹/₂x5x2¹/₂"
- For Continuous Use in 52 Ohm Lines
- Switch Selects SWR or Forward Power—No Reversing Necessary

A compact SWR and relative power meter which can be permanently inserted into a 52 ohm coaxial line to monitor transmitter and antenna performance. The ideal aid in adjusting beams, trap antennas, matching networks, etc., or for tuning transmitters for maximum output. Designed for the frequency range from 3 to 200 mc, and for powers from 25 watts to a full kilowatt. Above 7 Mc, as little as 10 watts will provide adequate sampling; above 100 Mc as little as 5 watts. The unit is installed by means of a standard coaxial connector on

each side, and becomes part of the 52 ohm line. Insertion loss is negligible. Once installed the unit need never be reversed. A switch on the front panel is set to SWR SET for relative forward power readings up to 1 KW on a scale calibrated from 0 to 10; and for adjustment of the sensitivity control for SWR readings. The switch is set to SWR for measurement of reflected power, on an SWR scale calibrated from 1:1 to 100:1. The HE-34 measures only 2¹/₂x5x2¹/₂", excluding coax connectors. Imported. HE-34 Shpg. wt., 1¹/₄ lbs. Net 16.95

NEW! LAFAYETTE TM-26 ILLUMINATED COMMUNICATIONS



2³/₈" "S" METER

Only **3⁹⁵**

- Replaces Many Communications Receiver "S" Meters
- 2 Jewel Movement • Clear Plastic Front
- Calibrated to S9 + 40 db
- BIG BROTHER TO THE LAFAYETTE TM-11

A new signal strength meter (basic 1 ma, 2 jewel movement) designed to replace many "S" meters used in communications receivers. Clear plastic front measures 2³/₈" square and meter fits standard 2¹/₈" round hole. Perfect for the experimenter and amateur. Complete with mounting screws, instructions for installation and use. For 6 volt or 12 volt operation. Zero adjustment control on front panel. Imported. Shpg. wt., 1 lb. Net 3.95

NEW LAFAYETTE HE-26 HYBRID PHONE PATCH



24⁵⁰ NO MONEY DOWN

Enjoy the pleasure of handling phone patch traffic with this deluxe hybrid patch. Hybrid circuit permits use of AM or SSB with voice control by effectively isolating the receiver audio output from the transmitter audio input. Provides an accurate balance between 500 ohm line and station equipment—with negligible insertion loss. Four connections on rear for receiver output (voice coil, 3-4 ohms), transmitter input, Station microphone, and telephone. Easy to operate after a few preliminary adjustments, all from the front panel. Null and balance controls are adjusted with the aid of readings on the edgewise panel VU

meter, for balance and maximum receiver-transmitter isolation. Thus the receiver audio signal, which would ordinarily trip the VOX circuit, is balanced out from the transmitter audio section. The gain control is adjusted for proper transmitter and receiver audio level. VU meter continuously monitors line level. The patch can be switched in and out by means of a front panel switch, so that it may be permanently installed. Compact, sloping cabinet will fit into any station arrangement. Sits on 4 non-slip rubber feet. Size: 3¹/₂Hx5¹/₂Wx4"D. HE-26 Shpg. wt., 3 lbs. Net 24.50

National 60 SPECIAL "B" RECEIVER



National's new all-wave low-priced receiver which features continuous coverage of AM Broadcast, Amateur and World Wide Short Wave Bands: brilliantly styled by Peter Quay Yang for easy operation, ready reading and attractive decor. Features include: 4 separate bands—540 Kc-1600 Kc; 1.6-4.5 Mc; 4-12 Mc; 10.5-31 Mc with police, CD, marine, aircraft, amateur, etc. stations clearly marked; plus 0-100 logging and bandspread scale. Bandspread operative on all bands. Audio section drives built-in speaker or front panel phone jack. Has AM, CW switch, standby-receive switch, 2 degrees of selectivity, complement of 4 tubes plus rectifier, superheterodyne circuit. Finish is two tone black and gray enamel. Size: 7³/₈Hx8³/₄Wx13¹/₂"D. Shpg. wt., 15 lbs. HE-200WX Net 59.95

FREE WITH PURCHASE OF NC-60 SPECIAL "B"

ME-42 Headset, Shpg. wt., 1¹/₂ lbs. Net 1.05
KT-77 Shortwave Antenna Kit, Shpg. wt., 1¹/₂ lbs. Net 2.35
REGULAR PRICE 3.40
SPECIAL LAFAYETTE OFFER
HE-200WX plus KT-77 plus ME-42. Shpg. wt., 18 lbs. Net 59.95
SP-178WX

New! National 105



No Money Down **119⁹⁵**

An efficient fixed tuned peaking type Q multiplier provides continuously variable IF selectivity—from 7 KC for full fidelity music reception to 500 cycles for crowded CW Band conditions. Large edge-type illuminated S-meter operates during AM, SSB and code reception for accurate measurement and logging of signal strength. Separate combination BFO/product and CW reception. Calibration charts are provided for all popular amateur and foreign broadcast bands. Exclusive tuner output permits detector to be fed into hi-fi amplifier for quality reception for tapping SW. a functional steel cabinet or custom oiled walnut enclosure. Dimensions (in steel cabinet) 7³/₈Hx13¹/₂Wx27 lbs. For 105-125 A.C., 60/60 cycles. Shpg. wt., HE-222WX Steel Cabinet Net 119.95
HE-223WX Oiled Walnut Cabinet Net 139.95

SENSATIONAL LAFAYETTE ANTENNA PACKAGE FOR AMATEURS

YOU SAVE **24⁸³**

Reg. Price 144.78 Lafayette Price 119.95

- ON SYSTEM CONSISTING OF:
- CDR AR22 Heavy Duty Automatic Rotor
 - Hy-Gain TH-3 3 Element Antenna
 - 100' RG8/U Cable • 100' Rotor Cable

NEW! Hy-gain TH-3 3-ELEMENT ANTENNA

The finest 3-element trap tribander for amateur communications on 10, 15 and 20 meters. All-aluminum construction of 2" O.D. beams and 1¹/₄" telescoping to 3/4" O.D. elements. Plastic and steel gusset bracket assemblies; all steel fixtures and hardware. 100% rust proof. Less than 2 to 1 SWR on all bands. New "solid state" slim traps (1¹/₂" in diam.). Withstand 1000 watts CW or AM and 2000 watts SSB. Overall beam length 14 ft., longest element 26 ft. Shpg. wt., 29 lbs. HE-773WX Net 99.95
WR-131 100-Ft. RG-8/U Coaxial Cable Net 9.87
WR-151 100-Ft. 4 Cond. Rotor Cable Net 2.39

CDR AR-22 AUTOMATIC ROTOR

This heavy-duty rotor unit will handle antennas up to 150 lbs. Simply set the control unit pointer to the desired direction, and the antenna will automatically rotate to this position and stop. Perfect for TV, Ham or Citizen Band application. Rotor unit employs 12 heavy duty ball bearings in two 6¹/₂" races. Weatherproof motor reverses instantly and is factory lubricated for life. Reversible clamps on rotor will take masts from 7/8" to 2". O.D. Control unit is marked in compass points. N.S.E.W. NW, NE, SW, and SE. Housed in attractive brown plastic cabinet with rubber feet. Complete with rotor, control unit and instructions. For 110-120 volts 50-60 cps AC. Requires 4 conductor cable. HE-476WX Net 32.77

SPECIAL LAFAYETTE PACKAGE
Includes: AR-22 Rotor; TH-3 3 Element antenna; 100' RG-8/U; 100' 4 Cond. Rotor Cable. SP-228WX Shpg. wt., 61 lbs. Net 119.95

NEW DRAKE 2B RECEIVER FOR SSB AM & CW



Model 2B Model 2BQ **279⁹⁵** NO MONEY DOWN

Top performance on SSB, AM and CW. The 2B is a highly sensitive, triple conversion receiver with 60 db image rejection. Covers 3.5 - 4.1 Mc, 6.9 - 7.5 Mc, 13.9 - 14.5 Mc, 20.9 - 21.5 Mc, 28.5 - 29.1 Mc, with a crystal controlled high frequency oscillator (crystals supplied). Highly stable variable oscillator. Sensitivity: 0.5 microvolt for 10 db S/N ratio. 50 Kc last i.f.—selectivity of 2.4 Kc at 6 db down. Receiver has 7" slide-rule dial with markings every 10 Kc. Additional features: slow or fast AVC action, accurate "S" meter, distortion-free product detector. For 110-120V., 60 cps. Size: 12Wx7Hx9"D. HE-180WX Shpg. wt., 15 lbs. Net 279.95
Model 2BQ Q-multiplier and deluxe speaker. For 2B receivers. HE-181 Net 39.95
HE-182-2AC crystal calibrator for 2B (not illus.) Net 16.95


NEW HAMMARLUND HQ-100A

A highly sensitive and selective redesigned version of the famous HQ-100, continuously tunable from 540 Kc to 30 Mc in four bands. Accurately calibrated electrical bandspread on the 80, 40, 20, 15 and 10 meter bands. Sensitivity: 1.75 microvolts for 10-1 signal-to-noise ratio, One r.f., 2 i.f. stages. Temperature compensation, voltage regulation and rugged construction in the separate high-frequency oscillator section result in high stability. Other features: Q-multiplier for variable selectivity, AVC, variable BFO, effective series noise limiter. "S" meter, panel-controlled antenna compensator. "Auto-Response" feature automatically adjusts audio bandwidth to fit receiving conditions. For 105-125V., 50/60 cps. Dimensions: 16¹/₄Lx9³/₄Wx9³/₄"D. HE-175WX Shpg. wt., 33 lbs. Net 189.00
MODEL HQ-100 AC Receiver w/clock Net 199.00
HE-174WX Shpg. wt., 33 lbs. Net 199.00
MODEL S-100. Matching speaker Net 14.95
HS-152 Shpg. wt., 10 lbs. Net 15.95
MODEL XC-100, 100 KC crystal calibrator. Net 15.95
HE-153 Shpg. wt., 3 lbs. Net 15.95

LAFAYETTE SPEAKER FOR AMATEUR and SHORTWAVE RECEIVERS **4⁹⁵**

An efficient, attractive speaker especially designed to complement your communications receiver. The 4 inch speaker is housed in a handsome, tapered grey metal cabinet which reduces QRN and voice frequency peaks. Impedance 4 ohms. Size: 7³/₈Hx5¹/₂Wx4¹/₂"D. HE-14 Shpg. wt., 4 lbs. Net 4.95

FREE "ON THE AIR" SIGN with E. F. JOHNSON "CHALLENGER" TRANSMITTER



A full size transmitter with plenty of reserve. The "Challenger" features 70 watts phone input on 80 through 6 meters—120 watts CW input on 80-10 meter—85 watts CW input on 6 meters. Uses front-panel plug in crystals or external V.F.O. Special "LC" keying circuit provides true CW waveform, suppresses clicks and chirps. HI-Q output circuit handles 40-600 ohm antennas; tunes out large amounts of reactance. Plate circuit capacitor switching provides the best combination of variable and padding capacity for easy tuning and proper loading. Filtered for effective TVI suppression. Operates on 105-125 volts AC, 50-60 CPS less mike, key and crystal. Size: 13¹/₄Wx9¹/₂Hx10¹/₂"D. Shpg. wt., 28 lbs. "Challenger" trans. plus free on the air sign. SP-261WX Net 154.75

B&W 550A COAXIAL SWITCH

An inexpensive multi-position coaxial switch that eliminates the annoyance of changing coaxial connections. Permits you to instantly select any one of five r-f generating devices using 52 or 75 ohm line. The switch handles up to 1 kw of modulated power with a maximum cross-talk of -45db at 30mc. HP-9T Shpg. wt., 2 lbs. Net 8.25


NEW! ANOTHER SMASHING LAFAYETTE HAM VALUE!

DELIVERY JUNE 15, 1962

SEE THESE ALL STAR FEATURES

- ★ 90 watts phone or CW — 80-10 meters
- ★ Built-in 3-section Low Pass Filter
- ★ Neutralized Final Amplifier
- ★ Clear, Chirpless Grid Block Keying

COMPARE!
7950
NO MONEY DOWN



LAFAYETTE STARFLITE™ 90 WATT PHONE AND CW TRANSMITTER KIT

The new Lafayette Starflite Transmitter Kit was designed to meet the needs of the greatest number of amateurs — General AM Phone or CW. Easy to build, its many quality design features offer superior engineering and premium quality components comparable to high-priced commercial units. Single-knob bandswitching provides instant coverage of 80 through 10 meters. The Starflite operates on a power input of 90 watts. A front panel switch selects any of five crystal positions with provisions for an external VFO. Controlled carrier modulator permits almost 100% of the CW input to be used on AM peaks. Grid-block keying provides chirp-free operation; a rugged efficient full-wave silicon diode power supply effects extremely low output ripple for cleaner CW transmission. Other quality features include an electron-coupled Pierce oscillator capacitance bridge neutralization of the 6146 final and a three stage low-pass filter. An illuminated edgewise Or Arsonval panel meter indicates final grid or plate current for easy tune-up. Pi-network output provides the proper match between the impedance plate circuit and any 50-72 ohm coaxial antenna. Assembly is simplified by the clearly written and profusely illustrated Lafayette Instruction manual. Modern low silhouette in heavy gauge steel cabinet. KT-390 Shpg. wt., 25 lbs. No. 79.50

SPECIFICATIONS:
POWER INPUT — 90 watts peak; OPERATION: CW, AM phone — crystal or VFO control; Band Coverage: 80 to 10 meters; COUPLING: Pi-network; Tubes: 6146, (2) 6CL6, 12AX7, 6DE7. LOW PASS FILTER. Power requirements: 105-125VAC, 50/60 CPS. 225 watts.

NEW! TRANSISTORIZED 100 KC CRYSTAL CALIBRATOR MODEL TE-29



ONLY **1195**

- Generates Useful 100 Kc Harmonics Up To 54 Mc
- Transistorized, Self-Powered and Self-Contained
- Completely Wired—Not a Kit
- Tunes to WWV Signals

The TE-29 is a transistorized 100 Kc oscillator with an output of high harmonic content. It will provide accurate markings every 100 Kc up to 54 Mc. Can be used to calibrate receivers and VFO's, or to mark band edges to insure in-band operation. The TE-29 may also be used as a constant signal source. The output may be coupled to the receiver directly. Can be tuned to WWV signals for accurate frequency calibration and the coil can be peaked for optimum output. These points are easily accessible from the bottom of the unit. Powered by a small 9 volt battery, the transistor oscillator is completely self-contained—requires no "digging" into the receiver for power. Housed in a 5Wx2 1/4x2 1/4"H sturdy metal box. Complete with battery.

Net 11.95
Net .49

NEW! TRANSISTORIZED 100 KC & 1 MC MARKER CALIBRATOR



ONLY **1795**

- Gives Markers Every 1 Mc, or Every 100 Kc, at the Flick of a Switch
- Fully Transistorized, Self-Contained and Self-Powered
- Completely Wired—Not a Kit
- Tunes to WWV Signals

Here is a unique marker calibrator offering all the features of a conventional calibrator plus many unusual advantages. It consists of two crystal controlled transistor oscillators running at 100 Kc and 1 Mc, respectively. The function switch on the front panel has 3 positions: Off 1 Mc, and 100 Kc. The 1 Mc markers are useful in locating amateur band edges up through 6 meters, and for rough calibration of general coverage receivers. Since they are farther apart, they are easier to identify in frequency than the 100 Kc markers, so that they may be used as starting points in calibration. Once the 1 Mc intervals are established and identified, the switch may be thrown to the 100 Kc up to 54Mc, so that the calibration may be refined to intervals of tenths of a megacycle. Completely self-contained and powered by a small 9 volt battery. Output is taken from one TE-27

Net 17.95
Net .49

NEW! LAFAYETTE CERAMIC COMMUNICATIONS MICROPHONE



Only **695**

Perfect for all Ham or Citizens Band mobile rigs. Rugged plastic case, capable of continuous service. Easy to hold; has momentary Push-To-Talk switch. Excellent voice reproduction. Equipped with 11" retracted, 5' extended rubber coiled cord with 5 prong plug and standard mounting bracket for any transceiver. Shpg. wt., 1 lb. PA-374 Net 6.95

HIGH QUALITY TOP NOTCH CRYSTAL MICROPHONE



395

PRICED EXTRA LOW!
COMPARE FOR VALUE

Lafayette makes history with a high quality CRYSTAL MICROPHONE at a price that is less than any comparable Crystal Microphone on the market today. Excellent for PA systems, home recorders and general applications. Frequency response 30 to 10,000 cycles. Output level—52 db. provides ample output for use with low gain amplifiers. Uses quality moisture sealed crystal; Die cast case in rich green baked enamel finish, with chrome grill. Completely equipped with 5 feet of Shielded cable. Mike may be used on any stand with 5/8"-27 thread. Grill diameter 2 3/4", depth 4 1/4", height 4 1/2". Shpg. wt., 3 1/2 lbs. PA-24 Net 3.95

3 WAY SLIM CRYSTAL MICROPHONE



395

- May be hand-held, stand mounted or suspended by lavalier cord!
- RESPONSE 60-10,000 CPS
- ON-Off Switch

A tremendous value! Unique design, only 4 5/8x1 1/8" diam. Comes complete with swivel adapter to fit all standard mike stands, and lavalier cord and bracket which leaves both hands free. Smooth wide range response. Locking type on-off side switch. Detachable 7 ft. cable and connector. Shpg. wt., 2 lbs. PA-31 Singly Each 3.95

STUDIO CRYSTAL MICROPHONE



- DUAL CRYSTAL CARTRIDGES
- ALL DIRECTIONAL
- FINE QUALITY
- HIGH OUTPUT

495

Here is a microphone with a 360° pickup, and the added power and sensitivity of two individually shock mounted and phased crystal cartridges. This arrangement assures you of maximum pickup from all sides. Swivel mounted to give fuller flexibility. Case is chrome plated. Standard 5/8"-27 thread. Overall size 7Hx3"W complete with 4 ft. cable. Shpg. wt., 4 lbs. PA-17 Net 4.95

NEW! DUAL IMPEDANCE SLIM DYNAMIC MICROPHONE



1195

- ON-OFF SWITCH
- RUGGEDLY CONSTRUCTED
- 600 & 50,000 OHM IMPEDANCES SELECTED BY SIMPLE ROTATION OF PLUG

Beautiful, professional-looking dynamic with solidly-cast, tapered, slim case with satin-chrome finish. Heavy duty slide-type on-off switch. Built-in transformer supplies dual unbalanced impedances—low Z is 600 ohms, high Z is 50,000 Ohms. Swivel mount fits all standard 5/8"-27 threaded stands. Blast filter eliminates unpleasant "pops" with voice use. Omnidirectional when used vertically—cardioid pattern when tilted. Engineering design and finish are of the highest quality, making this microphone excellent for any application. Complete with 5 ft. plug-in cable. Shpg. wt., 2 1/2 lbs. PA-46 Net 11.95

TRANSISTORIZED MIKE MIXER




695

- Up to 4 Channels
- Matches Hi Impedance Microphones

A compact microphone mixer capable of providing professional results. Mixer controls from one to four signals from hi-impedance microphones, tuner, phonograph and/or recorder. Permits amplifying or fading of any channel while holding the volume of other channels. Inputs accept standard 2-circuit phone plugs—output jack accepts standard circuit phone pin plugs. Requires single 9-volt battery (not supplied). Size 6Wx2 1/4Hx3 1/4"D. Shpg. wt., 1 1/4 lbs. PA-292 Net 6.95

ATLAS MICROPHONE ACCESSORIES



1.85 .85

Amphenol Mike Switch. Attach between male and female of 75 series connectors. Push-to-talk with lock. Shpg. wt., 6 oz. CM-67 Amphenol 75-MC1S Net 1.85
"Y" Connector. Has 2 males and 1 female. Shpg. wt., 2 oz. MS-84 Net .85

DYNAMIC PUSH-TO-TALK MICROPHONE FOR CITIZENS BAND TRANSCEIVERS




895

Specifically designed for Citizens Band Use!

- Specifically designed For CB Use
- Momentary-on Spring Return Switch
- Lightweight • Deluxe Styling

Lafayette now offers a new top quality dynamic microphone at an unusually low price. Specifically designed for citizen band and communication transceivers. Attractive design in black and chrome; tapered styling to fit the hand easily. High impedance dynamic transducer will not be adversely affected by heat and smooth frequency response of 100 to 11,000 cycles make it most suitable for communications work — indoors or out. Comes equipped with a momentary push-to-talk switch, coiled rubber cable with a 5 prong plug and a convenient hang up bracket. Shpg. wt., 1 lb. PA-274 Net 8.95

NEW "DYNA-SLIM" MICROPHONE



- HIGH IMPEDANCE 50,000 OHMS
- ON-OFF SWITCH
- "QUICK-SLIP" ADAPTER

695

New dynamic, high output microphone with many features of "mikes" sold above Lafayette's price! Output level —55 db. Smooth response from 60 to 10,000 cycles. Omnidirectional head. External on-off switch. Slips on or off stand adapter in a wink. Standard 5/8"-27 adapter permits tilting mike for multi-angle use. Satin black and chrome finish. Complete with detachable cable and connector. 8" long, 1 1/4" max. dia. tapered barrel 7". Shpg. wt., 2 lbs. PA-43 Net 6.95

MICROPHONE VOLUME CONTROL



176

No more running to the P.A. amplifier to adjust volume. Now, control volume output right at the microphone. Attached between the microphone and the cable. Can be used at any desired distance. Fitted on one end with a female mike connector and male mike connector on the opposite end. Shpg. wt., 12 oz. MS-755 Remote Volume Control Net 1.76

Sensational Values In Lafayette Communication Receivers!

LAFAYETTE Professional Quality AMATEUR COMMUNICATIONS RECEIVER

Designed for TODAY'S
CROWDED AMATEUR BANDS


8 TUBE PLUS RECTIFIER TUBE
SUPERHETERODYNE CIRCUIT




HE-30 WIRED
99⁹⁵
NO MONEY
DOWN

KT-320
SEMI-KIT
79⁹⁵

- 8 TUBES PLUS RECTIFIER TUBE
- 1 RF + 2 IF STAGES FOR HIGH GAIN RECEPTION
- EASY-TO-READ, ILLUMINATED, SLIDE RULE DIAL
- BUILT-IN Q-MULTIPLIER FOR CROWDED PHONE OPERATION
- ANTENNA TRIMMER FOR OPTIMUM PERFORMANCE ON ALL BANDS
- CALIBRATED ELECTRICAL BANDSPREAD ON AMATEUR BANDS 80 THRU 10 METERS
- 0-100 LOGGING SCALE FOR SWL'S
- EFFECTIVE AUTOMATIC NOISE LIMITER
- AVC-MVC SELECTOR ON FRONT PANEL
- STABLE OSCILLATOR AND BFO FOR CLEAR CW AND SSB RECEPTION
- BUILT-IN EDGEWISE S-METER



795
RECEIVER
SPEAKER-MATE



Outstanding Bandsread, Selectivity with a built-in Q-multiplier, and sensitivity combine to make the HE-30 one of the "hottest" general coverage bandsread receivers ever priced below \$200. For the crowded amateur bands—illuminated Slide Rule Dial, bandsread with markings every 5 KCS on 80 and 40 meters (IT TAKES 16 REVOLUTIONS OF THE BANDSPREAD DIAL TO COVER EACH OF THESE BANDS), every 20 KCS on 20 and 15 meters, and every 50 KCS on 10 meters, plus an edgewise S-meter. For the SWL—a 0-100 logging scale for "instant reset" to a desired station plus coverage from 0.55-30 MCS. The 8 tube (plus a husky 5Y3 Rectifier) circuit provides an RF stage with an antenna trimmer for peak performance PLUS 2 IF stages for improved selectivity. The HE-30 utilizes a 5Y3 tube in a transformer Full Wave rectifier power supply for performance with a minimum of hum. Receiver sensitivity—1.0 microvolts for 10db Signal-to-Noise Ratio. The Built-in BFO can be used to separate CW stations by means of the pitch control, while the Q-multiplier adds the selectivity needed for crowded phone band operation. Front panel controls: FUNCTION SWITCH, AUDIO GAIN, SELECTIVITY

(Q-Multiplier), FREQUENCY (BFO), BAND SELECTOR, IF GAIN, TRIMMER, AVC-MVC SWITCH, ANL SWITCH, MAIN TUNING BANDSPREAD TUNING, and headphone jack. Selectivity — 60db at 10KC, 0.8 KC @ 6db (with Q-multiplier), IF — 455KCS, Speaker — External PM type (not supplied), 4 or 8 ohms impedance, Audio Output — 1.5 watts. Tubes — 6BA6 — RF Amplifier, 6BE6 Mixer, 6BE6 — Oscillator, 6AV6 — Q-Multiplier-BFO, 2-6BA6 — IF Amplifier, 6AV6 — Detector-AF Amplifier — ANL 6AQ5 — Audio Output, 5Y3 — Rectifier. Size — 7Hx15Wx10"D. For 105-120, 60 cps AC, 50 watts.

HE-30WX Shpg. wt., 25 lbs. Net 99.95

NEW! KT-320 SEMI-KIT
This receiver is also available in kit form with all major components and front end pre-mounted and pre-calibrated. All other components supplied for easy mounting.

KT-320 Semi Kit Net 79.95
RECEIVER SPEAKER MATE
SPECIAL 3x5 speaker in handsomely styled cabinet to match HE-30. Gives clean audio response. 8 ohm impedance. Size: 7 3/4 Hx 3 1/2 Wx 5" D. Shpg. wt., 4 lbs. Net 7.95

LAFAYETTE AMATEUR COMMUNICATIONS RECEIVERS

SUPERHETERODYNE CIRCUIT UTILIZING
8 TUBES & RECTIFIER TUBE

KT-200
SEMI-KIT
6450

HE-10
WIRED
7995

NO MONEY
DOWN

- BANO SPREAD FOR EASY TUNING
- BUILT-IN "S" METER WITH ADJUSTMENT CONTROL
- EXCELLENT SELECTIVITY
- ACCESSORY POWER SOCKET PROVIDED
- ALL TRIMMERS PRE-ALIGNED
- COVERS 550KC. TO 31MC. IN FOUR BANDS
- VARIABLE BFO AND AF — IF GAIN CONTROLS
- SWITCHABLE AVC & AUTOMATIC NOISE LIMITER
- ALL MAJOR COMPONENTS PRE-MOUNTED
- DUAL 4 AND 8 OHM OUTPUT IMPEDANCES
- 1 RF + 2 IF STAGES FOR HIGH GAIN RECEPTION

The KT-200 represents a significant departure from usual kit designs. As soon as it is unpacked, it is already half finished. All of the mechanical mounting is completed. Tube sockets, transformers, main tuning capacitor, filter capacitor, controls, even knobs and pilot lamps are all in place. The tuning assembly is installed and operative. Most important of all, the complex coil assembly and alignment capacitors for the oscillator mixer and rf amplifier stages are factory mounted and pre-aligned. Thus only a slight touch up will be required to achieve maximum sensitivity and selectivity. Features such as built-in "S" meter with

adjustment control, switchable AVC and automatic noise limiter make the KT-200 worth many times its low price. Supplied with all components.

KT-200WX Net 64.50

HE-10WX Same as above, factory wired Net 79.95

RECEIVER SPEAKER MATE

The HE-48 speaker is handsomely styled to enhance your KT-200 or HE-30. Special 3 x 5 speakers gives distortion free response. 8 ohm impedance. Size: 7 3/4 Hx 3 1/2 Wx 5" D. Shpg. wt., 4 lbs. Net 7.95

HE-48 Net 7.95

SPECIFICATIONS:

AM, 80-40-20-15-10 meter bands. Pre-calibrated band spread. Sensitivity: 1.25 mv for 10 db Signal-to-noise ratio. Selectivity: ± 10KC.—60db (at 1MC), Audio Output: 1.5 watts. Tubes: 3—6BD6, 2—6BE6, 2—6AV6, 1—6AR5, 1—5Y3. Power: 100-125 V AC 50/60 cps. Size: 15 1/2 Lx 8 1/4 Hx 12" D. Shpg. wt., 22 lbs.

ELECTRONICS ILLUSTRATED

"... even the most inexperienced constructor should have no trouble."
"Sensitivity was so great the IF gain had to be turned all the way down to prevent overloading."

15 **73** 7
"... excellent value"
"... rugged, well made, and uses good components."



RECEIVER
SPEAKER-MATE

HE-48

795

Exceptional
Value

49⁹⁵

NO MONEY
DOWN



DELUXE 4-BAND SHORTWAVE BROADCAST RECEIVER

- Electrical Bandsread
- Built-in "S" Meter
- 3 Short-Wave Bands, 1 BC Band
- AVC — Noiselimiter
- Big 5 Inch Speaker
- BFO
- Phone Jack

A SMARTLY STYLED DURABLE METAL CABINET

Now, you can tune in the world with this fabulous, new Lafayette HE-40 BC-SW receiver. Keep up to date with on the spot news coverage. Power packed superheterodyne circuit covers the broadcast band (550-1600 KC) and shortwave from 1600 KC to 30 MC in four bands. The perfect radio for shortwave listeners. Features a precision electrical bandsread with slide rule bandsread dial, 0-100 logging scale for easy self-calibration. Separate bandsread tuning condenser and calibrated "S" meter for accurate tuning. Meter can be electrically adjusted by rear panel control. Sensitive circuit features AVC (Automatic Volume Control) to minimize blasting and/or fade out; Automatic noise limiter to reduce annoying interference. Includes convenient front panel B.F.O./selectivity control to allow for reception of CW (telegraphy). Also has convenient front panel headphone

jack which automatically disconnects speaker. Jack can be used to drive an external speaker. Built-in 5" PM speaker provides big, clear sound on all stations. Useful tone switch is included to vary sound to suit conditions, or taste. Three antennas (ferrite loop for broadcast band, adjustable 58" whip for short wave and wire antenna) provide high sensitivity and flexibility for best reception. Low impedance phones are recommended for use with this unit. Evenly illuminated dial for nighttime tuning. Attractively styled steel cabinet with silver trim. Powered by 4 tubes plus a selenium rectifier. 1—12BE6; Converter, 1—12BA6; IF Amplifier, B.F.O., 1—12AU6; Audio Amplifier AVC detector; 1—50C5; Audio output. Operates on 105-125V; 50/60 cycle AC/DC. Size 13 1/2 Wx 5 7/8 Hx 8 3/4" D. Shpg. wt., 12 lbs. HE-40

Net 49.95


New! LAFAYETTE Deluxe 6 METER TRANSCEIVER MODEL HE-45A

NOW! front panel antenna loading controls!
VFO POWER JACK! popular new ham mike!

- Highly Sensitive Superheterodyne Receiver Section for 50-54 Mc
- 3-Stage, 12 Watt Transmitter with 2E26 Final
- With minimum drift circuitry
- Pi-Network Transmitter Output
- Built-in 117 VAC and 12 VDC Power Supplies
- Effective Series Gate Noise Limiter
- Complete With Push-To-Talk Ceramic Microphone

Now, for 6 meters, Lafayette offers a deluxe transmitter-receiver in a single package, with features which make the low price hard to believe. Provides maximum convenience and flexibility in either mobile or fixed operation. The superheterodyne receiver section employs an RF stage with peaking control on front panel, and two i.f. stages at 1650 Kc. for 1 μ v sensitivity and 35 db image rejection. Tunes the entire 6 meter band from 50 to 54 Mc. with calibrated illuminated vernier tuning dial. Features an adjustable series gate noise limiter. Illuminated panel meter serves as an "S" meter when meter function switch is set to the proper position. Transmitter section employs a 6U8 oscillator and buffer multiplier driving a 2E26 final with a plate input of approximately 12 watts on AM. Pi-network coaxial output, and front panel antenna loading controls. Sockets for 28 Mc fundamental crystals, plus an input for external VFO on the front panel chosen by 3-position selector switch. VDC is built in, making the HE-45A perfect for mobile operation. A spotting switch reads plate current when switch is set to proper position. Panel meter complement: 12BA6 RF amplifier, 1-6U8 6EA8 osc. mixer, 12BA6 1st i.f. amp. and 1-6U8 6EA8 transmitter oscillator and buffer multiplier, 1-6AQ5 audio output and transmitter modulator. Housed in a rugged, low-silhouetted base with attractive, metal panel, the HE-45A comes complete with push-to-talk ceramic microphone, crystal for 50.12 Mc, detachable mounting bracket, and all power cables. Only 12x5x8 1/2" D. Shpg. wt. 15 lbs.

114⁹⁵
NO MONEY DOWN



LAFAYETTE 6 METER TRANSCEIVER

SMALL, COMPACT COMPLETE 6 METER STATION-TAKE IT WITH YOU ANYWHERE!

57⁵⁰
NO MONEY DOWN


- Superhet Receiver Tunes Entire Band (50-54 mc)
- Efficient Adjustable Noise Limiter
- 7 Watts Input to 6CX8 Pentode Final
- New Efficient Pi-Network Output with Hi-"Q" Tuned Circuit
- Separate Oscillator—Final Stage
- Accessible Front Panel Socket With Crystal For 50.2 MC Output

Meet the enjoyable challenge of 6 meter operation efficiently and economically with the Lafayette HE-35 6 meter transceiver. This small, compact transceiver features a Transmitter with 7 watts input to a 6CX8 pentode final, high quality plate modulation, built-in adjustable TVI filter, and antenna matching network for 30 to 100 ohm antenna. Superheterodyne receiver tunes entire 6 meter band (50-54 mc) and includes variable noise limiter. The transmitter uses a 3rd overtone crystal in easily accessible socket located on front panel; has RF output and modulation indicator. Low-loss SO-239 coaxial antenna output jack. Complete with attractive high output ceramic microphone, crystal for 50.2 Mc. and mounting brackets for mobile use. Operates on 110-120 volts, 60 cycle. 10 $\frac{1}{2}$ "x5 $\frac{1}{2}$ "x8 $\frac{1}{2}$ " D. Tubes: 2-6U8A 6EA8, 6AL5, 12AX7, 6V6GT, 6CX8. HE-35AWX Shpg. wt., 11 lbs.

MOBILE POWER SUPPLIES. 5 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "x2 $\frac{1}{4}$ ". Shpg. wt., 4 lbs.


Net 57.50
Net 10.95
Net 10.95
Net 4.95

LAFAYETTE 6 METER PACKAGE SPECIAL!



Lafayette Famous HE-35A 6 Meter Transceiver Plus Popular HE-49 6 Meter Mobile Antenna Plus Extra HE-36 Crystal.

LAFAYETTE SPECIAL PACKAGE PRICE
REGULAR CATALOG PRICE 69.40
59⁹⁵
NO MONEY DOWN



• Ceramic Temperature-Free Microphone

MADE IN U.S.A.

LAFAYETTE 10 METER TRANSCEIVER MODEL HE-50

- Effective Series Gate Noise Limiter
- With Push-To-Talk Ceramic Microphone
- 12-Watt Transmitter with Pi-Network Output
- VDC—Ideal for Mobile or Fixed Operation
- Superhet Receiver Tunes 10 Meter Phone Band from 28 to 30 Mc

109⁵⁰
NO MONEY DOWN

Here is a new transceiver with the deluxe mechanical and electrical features of the HE-45, applied to the 10 meter amateur phone band. Receiver has 1 μ v sensitivity. The i.f. of 1650 Kc. results in a 45 db image rejection on 10 meters. Includes automatic series gate noise limiter. Transmitter runs 12 watts input to a 2E26 final, with pi-network coax output to match any antenna. Transmitter runs fundamental crystals or external VFO. Sockets for 5 crystals plus VFO input, with corresponding 6-position selector switch, located on front panel. Physical layout is identical to that of the HE-45. Includes big illuminated tuning dial and illuminated panel meter which serves as "S" meter and final plate current meter. Built-in dual power supply for 117 VAC and 12VDC make the HE-50 the ideal solution to the problem of finding a compact, completely self-contained 10 meter rig which can be operated mobile or used at home without modification. The many transmitter and receiver features which are combined in this single package make it a value that is hard to beat, at a price designed for the conservative budget. Tube complement: 1-6BA6 RF amplifier, 1-6U8 6EA8 osc. mixer, 1-6BA6 1st i.f. amp., 1-6U8 6EA8 2nd i.f. amp 1st audio, 1-6CN7 detector noise limiter, 1-6AQ5 audio output and transmitter modulator, 1-6U8 6EA8 transmitter oscillator and buffer multiplier, and 1-2E26 transmitter final amplifier. Housed in a rugged, low-silhouetted case with attractive, metal panel, the HE-50 comes complete with push-to-talk ceramic microphone, crystal for 2830 Mc, detachable mounting bracket, and all power cables. Only 12x5x8 1/2" D.

HE-50WX Shpg. wt., 15 lbs.

LAFAYETTE 10 METER SUMMER SPECIAL

HE-50 10 Meter Transceiver

PLUS

HE-62 10 Meter VFO

HE-67WXM Combination HE-50 and HE-62

Reg. 129.45
COMBINATION SPECIAL 114⁹⁵
YOU SAVE 14.50

Net 114.95

NEW! LAFAYETTE 10 METER VFO

- HIGHLY STABLE OSCILLATOR CIRCUIT
- FULLY WIRED — NOT A KIT

A highly stable variable frequency oscillator designed for HE-50 or any 10 meter rig, employing a standard oscillator circuit assures drift-free performance. Uses OA2 VR tube to eliminate possible drift effects from line voltage variation. Supplied with cable to connect to HE-50. Instructions are given for connections to units not equipped with 5-prong VFO Jack. Illuminated dial is calibrated from 28 to 30 megacycles. Precision planetary gear mechanism with single knob control of 180° rotation. Tube complement consists of one 12BA6 oscillator and an OA2 voltage regulator. Size 3 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "x4 $\frac{1}{2}$ " D. Shpg. wt., 3 lbs.

19⁹⁵

Net 19.95



Made in U.S.A.

NEW! LAFAYETTE 6 METER VFO for 6 METER TRANSMITTERS AND TRANSCEIVERS

- HIGHLY STABLE OSCILLATOR CIRCUIT
- FULLY WIRED — NOT A KIT

A deluxe 6 meter variable frequency oscillator designed for high stability and versatility. Completely shielded, the tuning components are isolated from direct heat of components. A High-Q Clapp oscillator circuit assures drift-free performance. An OA2 VR tube further eliminates any effects due to line voltage variation. Operating in the 3 to 4 $\frac{1}{2}$ Megacycle range, the output frequency is 8 MC. Ferrite tuned coil output is approximately 10 volts. The HE-61 can be used with any transceiver which has a standard 8 MC crystal. Cable with 5-prong power plug for units equipped with VFO 5-prong power jack input. Instructions supplied for units not equipped with 5-prong VFO jack. Also supplied with cable and standard crystal plug for VFO input. The dial is calibrated from 50.54 megacycles and is illuminated for your tuning convenience. Precision planetary drive mechanism with single knob control of 180° rotation. Tube complement consists of one 12BA6 oscillator and an OA2 Voltage regulator. Furnished complete with cable and instructions. Size: 3 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "x4 $\frac{1}{2}$ " D. Shpg. wt., 3 lbs.

Net 19.95



Made in U.S.A.

19⁹⁵

NOW! NO MONEY DOWN WITH LAFAYETTE'S NEW 3-IN-1 EASY-PAY-PLAN



Model HE-51
10 tube 30-50 MC


- Tuneable and Crystal Controlled

52⁵⁰

NO MONEY DOWN

LAFAYETTE FM AM POLICE RECEIVERS

- 10 TUBES
- BUILT-IN 4" PM SPEAKER
- EASY-VISION SLIDE RULE DIAL
- DRIFT-COMPENSATED



Model HE-52
10 tube 145 - 175 MC

- Tuneable

52⁵⁰

NO MONEY DOWN

Delivery August 15, 1962

Here is a quality communications receiver which picks up police calls, fire department, CD etc., all over town. Keep alert to emergencies at any hour. Quality built, it is safe to say that a better communications receiver could not be found at twice its price. Look at these features: Powerful 10 tube performance, even a short length of wire will suffice to bring in strong local signals; 3 IF stages; Crystal controlled and tuneable, the HE-51 can be accurately tuned to a pre-selected frequency for long periods of time. Critical tuning and drift problems are virtually eliminated. The crystals for fixed frequency operation can be ordered separately—(See below) Through most signals in the 30-50

MC range will be FM, some transmissions are AM and a handy front panel FM-AM slide is provided. Built-in squelch circuit reduces background noise, without adversely affecting its sensitivity. The built-in 4" speaker can be cut-out for headphone operation with a panel mounted slide switch. Either high or low impedance phones may be used. Provision has been made for connection of a larger external amplifier if desired. Tube complement: 6AQ8, 6BC5, 6U8, (3) 6AU6, 6AL5, 12AX7, 6AQ5, 6X4 for 105-120 VAC. Size: 12 1/2 x 4 1/2 x 6 1/2". Shpg. wt., 14 lbs.

HE-51WX Net 52.50

Crystal for Fixed Freq. operation—30-50 MC. Please specify exact operating freq.—supplied within .005%. Allow 30 days for delivery.

HE-759L Net 5.95

M-80LB Window mount antenna for 30-50 MC. Shpg. wt., 3 lbs.

HE-959W Net 7.35

Now you too can "listen-in" to police, fire, forestry, civil defense, marine and other important municipal and industrial activities right in your own home. Keep yourself constantly alert to emergencies at any hour. Quality built, the HE-52 offers powerful 10 tube performance at a low, low Lafayette price. Look at these features: Sensitive RF stage for maximum low noise amplification—even a short length of wire (2 1/2 to 5 ft.) will suffice to bring in sufficiently powerful signals. Provision has been also made for connection of more elaborate 75 or 300 ohm antennas if needed. 3

IF stages; built-in squelch circuit functions without reducing the receiver's sensitivity to information-bearing signals. The built-in 4" speaker may be turned off when switching to phone operation. Either high or low impedance earphones may be used if they are terminated by phone tips. An amplifier jack is provided on the rear of the unit to enable connection of a larger external amplifier if desired. Tube Complement: 6C4, 6AQ8, (3) 6AU6, 6AL5, 12AX7, 6AQ5, 6X4. For 105-120VAC. Dimensions: 12 1/2 x 4 1/2 x 6 1/2". Shpg. wt., 14 lbs.

HE-52WX Tuneable only Net 52.50

M-7A low power, high quality ground plane antenna for 145-175 MC.

HE-960 Shpg. wt., 1.5 lbs. Net 5.39



POLICE CALLS



OCEAN TUGS



FIRE ALARMS

Sonar

TRANSISTORIZED 35 WATT RADIO TELEPHONE

NEW MODEL 30 **299⁹⁵** NO MONEY DOWN



Features 6 marine channels in the 2000-6000 Kc range plus tuneable standard broadcast band. High level class "B" modulation controlled to 100%; high level speech limiter. Push-pull power supply over 80% efficient—low battery drain. Front panel tuning with antenna RF indicator. Harmonic attenuation exceeds FCC requirements. Receiver RF sensitivity control. Provisions for remote control. All aluminum, non-magnetic construction treated against effects of salt water and fungus—installs in any position. Complete with 3 pairs of crystals, plug-in push-to-talk mike, and power cable. 12 volts only. Size: 13 1/2 x 10 1/2 x 6 1/4" H.

HE-368WX Shpg. wt., 15 lbs. Net 299.95


LAFAYETTE CLASS D C.B. CRYSTALS

For Popular CB Transceivers

Extremely accurate 3rd overtone crystals. Meet F.C.C. tolerance requirements of .005%. For use as transmit crystal for the following popular 11 meter CB transceivers:

LAFAYETTE HE15A
LAFAYETTE HE15B
LAFAYETTE HE20A
LAFAYETTE HE20B
LAFAYETTE HE20C
LAFAYETTE HE29A
LAFAYETTE HE29B
BROWNING S-9
EICO 772
GEN. RAD. MC1
GEN. RAD. MC2
GEN. RAD. MC3
GLOBE CB100
GLOBE CB100A
HAMMARLUND HQ105TR
JOHNSON VIKING

HEATH CBI
HEATH GW10
LASALLE LA-101
MIRATEL CR117
PHILMORE --90
RADSON R1-4A
RAY JEFFERSON
RCA MARK VII
SHELL CB-12
SONAR MODEL "D"
TEL-RAD
UTICA MC27
WESTRON 909
WORLD RADIO ECBK
DEWALO TR910



As low as **195** each in lots of 3 assorted

Pin spacing, .486" pin diam., .050". Frequencies available:

27 MC TRANSMIT CRYSTAL FREQUENCY CHART

| Channel | Meg. | Channel | Meg. | Channel | Meg. |
|---------|--------|---------|--------|---------|--------|
| 1 | 26.965 | 9 | 27.065 | 17 | 27.165 |
| 2 | 26.975 | 10 | 27.075 | 18 | 27.175 |
| 3 | 26.985 | 11 | 27.085 | 19 | 27.185 |
| 4 | 27.005 | 12 | 27.105 | 20 | 27.205 |
| 5 | 27.015 | 13 | 27.115 | 21 | 27.215 |
| 6 | 27.025 | 14 | 27.125 | 22 | 27.225 |
| 7 | 27.035 | 15 | 27.135 | 23 | 27.235 |
| 8 | 27.055 | 16 | 27.155 | | |

HE-830 Specify Channel or Crystal each, 2.25 in lots of any 3 assorted, each, 1.95



Sonar

D-120B DEPTH INDICATOR

- Measures Depth from 1-ft. to 250-ft.
- Easy-To-Install
- Complete with Transducer, Gimbal and Fairing Block

Accurate, rugged depth indicator, measuring from 1 to 250 feet. Easily installed, requires 6 or 12 VDC. Size: 9 1/2 x 7 x 6". Complete with transducer, gimbal and fairing block. Shpg. wt., 13 lbs.

MODEL D-120B for bulkhead mounting. Net 139.50

HE-356WX Specify 6 or 12 volts

MODEL D-125 DEPTH ALARM. Same as above with automatic safety alarm added. Alarm sounds off when boat reaches any predetermined minimum depth. Set it and forget it. Shpg. wt., 12 lbs.

HE-358WX Specify 6 or 12 volts Net 198.50

MODEL D-600. Deep sea version of model D-120B. Reads 0-600 feet. 11 3/4 x 7 1/2 x 7 1/2". Shpg. wt., 10 lbs.

HE-359WX Specify 6 or 12 volts Net 249.50

139⁵⁰

NO MONEY DOWN

MODEL D-60 TRANSISTOR DEPTH INDICATOR

114⁹⁵ NO MONEY DOWN

Fully transistorized, can be installed anywhere in any size boat. Reads up to 120 feet on two revolutions (1-60 ft. on 360° scale; 1 ft. calibrations). A valuable aid in finding fish in salt or fresh water; in navigating through shallow waters; in spotting wrecks, obstructions, types of bottom. Constructed of aluminum, non-magnetic salt water spray-resistant case. Complete with transducer and gimbal. Operates from battery or 6 or 12 volt source. Measures 5 1/2 x 5 1/2 x 6" D. Shpg. wt., 2 1/2 lbs.

HE-366WX Specify 6 or 12 volt Net 114.95



HARTMAN SHIP-TO-AUTO ALL TRANSISTOR CONVERTER



CONVERTER

ONLY **19⁹⁵**

LISTEN TO:

- Ship-to-Ship Broadcast
- Marine Telephone
- WWV
- Coast Guard (weather)
- Ship-to-Shore Conversations

Now you can listen to marine broadcasts on your car radio. A flick of the switch and your auto radio becomes a powerful long range marine receiver. Switch back and it plays the normal broadcast band. All transistor circuitry uses only 1/2000 of an amp from built-in battery; virtually the batteries entire shelf life. Converter selects any frequency between 2000 KC and 3000 KC. Operates with either 6V or 12V automobile ignition system.

HE-646 Net 19.95



Hi-gain
SWI ANTENNA FOR INDOOR USE

Convenient indoor Model SWI improves the performance of any shortwave receiver. Covers 5-30 Mc. Easy to install and operate. Six-foot cable (included) is attached to receiver, the telescoping "rabbit ears" extended, and the "match" and "tune" controls set for maximum signal strength. Attractively housed in unbreakable plastic with chrome-plated antennas. Model SWI. Shpg. wt., 2 1/2 lbs.

HE-973 Net 14.75

HYGAIN MODEL SWO FOR OUTDOOR USE

Model SWO high efficiency doublet antenna for outdoor use. Traps peaked on the 11, 13, 16, 19, 24, 31 and 40 meter shortwave bands. Only 40 feet long. With insulators, 100 ft. of lead-in wire and instructions. Shpg. wt., 2 1/2 lbs.

HE-972 (Not illustrated) Net 14.75

LAFAYETTE NEW UNIVERSAL 6 METER AND BROADCAST MOBILE ANTENNA

ONE ANTENNA FOR BROADCAST AND 6 METERS! AT A SENSATIONALLY LOW PRICE OF

475

Here is a highly efficient 6 meter antenna that replaces your Auto radio antenna for operation on both 6 meters and for regular AM broadcast reception. 59" stainless steel mast, all chrome ball type base adjustable to 180° for front rear or side mount. Complete with 54" lead. Highly versatile and durable. Shpg. wt., 4 lbs.

HE-801WX Net 4.75

Hi-Par "SATURN 6" MOBILEER

A compact, horizontally polarized mobile antenna for 6 meters. It is essentially an end-loaded folded dipole with 3 ring design, approximately 20" in diameter, 5" high. Design center is 50.5 Mc but resonant frequency may be varied between 50.5 and 53.0 Mc. Easily fed with RG58/U coax. Rigid aluminum construction; net weight under 2 lbs. Easily supported on pipe, tubing or stiff rod.

Model S-1—"Saturn 6" Antenna, 2-piece adjustable aluminum mast, mast bracket, universal bumper hitch. No holes to drill. Less coax feed line. Shpg. wt., 5 lbs.

HE-805W Net 16.59

5 ELEMENT 6 METER BEAM

A rugged, Full size 6 meter beam constructed of 3/4" 0.050 wall aluminum tubing with hardwood dowling at high stress points. Boom is 0.058 wall drawn aluminum. Driven element is concentric gamma matched for direct coax feed. Light enough for any heavy duty TV rotator. Turning radius — 7'6"; Forward Gain — 9.5 db; F/B ratio — 29 db. Comes with all parts marked for quick, neat assembly and center band operation. Shpg. wt., 15 lbs.

HE-746WX Net 19.50

New ALL STAINLESS

6 METER MOBILE ANTENNA

6⁹⁵

OUTSTANDING FEATURES

- 58 in. Stainless Steel Whip For optimum 6 Meter Performance
- Heavy-Duty Chrome Plated Stainless Steel Spring
- Chrome Plated Swivel Ball Jointed Mount Base

Chrome swivel ball mount base designed to be mounted on any surface. Stainless steel spring holds rod in properly adjusted position and prevents rod damage from shocks and blows. Stainless steel whip for maximum resiliency and strength. Shpg. wt., 4 lbs.

HE-49W Net 6.95



BRAND NEW LAFAYETTE HE-48 SPEAKER

DESIGNED TO GIVE SUPERIOR VOICE REPRODUCTION FOR SSB, AM, CW AND OTHER VOICE APPLICATIONS.

The HE-48 speaker is handsomely styled to enhance your present facilities. Special 3x5 speakers gives distortion free response. 8 ohm impedance.

HE-48 Net 7.95

795



MARK MOBILE HELIWHIP ANTENNAS FOR 6 & 10 METERS

995

HWM-1

Fiberglass molded continuously loaded whip antennas designed to replace conventional stainless steel 1/4 wave whips. The Heliwhip can be positioned on the upper portion of the vehicle such as trunk lid, cowl, fender or hood without danger of shorting to power lines. Offers superior performance on 49-55 KC bandwidth (6 meters) plus blends in with auto styling. Produces 50 ohm match at resonant frequency. Shpg. wt., 1 lb.

HE-740W 6 meter Heliwhip Net 9.95

HE-739W 10 Meter Heliwhip Net 9.95

HE-896 HWM-1 Antenna Mount for above. Shpg. wt., 2 lbs. Net 7.50

LOW LOSS RG/8U FOAM POLYETHYLENE COAXIAL CABLE



.15 per ft.

With new foam polyethylene coaxial cable you can increase signal strength up to 35%. Designed for application whenever low loss 50 ohm cable is required. Attenuation and capacitance approximately 15% less than standard RG-8U; low loss foam polyethylene cable has same core, braid and jacket as standard RG-8U, but uses a larger center conductor to maintain 50 ohm nominal impedance.

WR-165 per ft. Net .15

WR-166 100 ft. coil Net 13.50

WR-167WX 1000 ft. spool Net 120.00

MOTOROLA RADIOS for FOREIGN & DOMESTIC CARS

ALL NEW TRANSISTORIZED AUTOMOBILE RADIOS Complete with Mounting Kit

5-TRANSISTOR MANUAL CAR RADIO



39⁹⁵
NO MONEY DOWN

• In-dash or Under-dash Mounting
A tremendous value in an all-transistor car radio. Hand-wired chassis with 5 transistors, 2 diodes, 1 thermistor. Built-in Golden-Voice hi-fi speaker. Set plays as soon as you turn it on—no warm-up time required. Custom fits most cars, sport cars, trucks and boats—in-dash or under-dash installation. Low battery drain. Features

• All-Transistor, Hand-Wired Chassis
full variable tone control, cool chassis operation, band pass circuit, automatic gain control. For 12-volt cars, reverse polarity. Size: 6⁷/₈Wx2¹/₂Hx7¹/₄"D. Shpg. wt., 7 lbs.
CR-128 Model 320T Net 39.95

6-TRANSISTOR MANUAL CAR RADIO



51⁹⁵
NO MONEY DOWN

• Custom Fits "Difficult to Fit" Cars
A flexible car radio with movable control shafts to accommodate the most difficult-to-fit cars. Push/Pull audio system gives smooth high-fidelity sound and delivers a full 12 watts of peak power output. Employs 6 transistors, 2 diodes and 1 thermistor in a hand-wired chassis. Low battery drain of only .5 amp. Features

• Push/Pull Audio System for Hi-Fi Sound
tunes Golden-Voice hi-fi speaker, full variable tone control, automatic gain control. Plays as soon as you turn it on—no warm-up needed. 12-volt cars, negative ground. Size: 7⁵/₈Wx2Hx5"D. Shpg. wt., 7 lbs.
CR-129 Model 2MT Net 51.95

ALL-TRANSISTOR PUSHBUTTON CAR RADIO FOR FOREIGN CARS



54⁹⁵
NO MONEY DOWN

• Pushbutton Convenience • 5 Transistors, 2 Diodes, 1 Thermistor
Simple, pushbutton convenience with all-transistor power and dependability. Hand-wired, transistor chassis means instant play without warm-up, cool chassis operation, and 64% less battery drain, only .7 amp. Full variable tone control, automatic gain control, band

pass circuit, plus the exclusive Golden-Voice hi-fi speaker. For 12-volt cars, reversible polarity. Size: 6⁷/₈Wx2¹/₂Hx7¹/₄"D. Shpg. wt., 8 lbs.
CR-130 Model 520T Net 54.95

6-TRANSISTOR PUSHBUTTON CAR RADIO For Domestic Cars



59⁹⁵
NO MONEY DOWN

• 6 Transistors, 2 Diodes, 1 Thermistor
A new, all-transistor car radio designed to custom fit most domestic cars on the road. The push/pull audio principle results in smooth, uninterrupted sound. Delivers 12 watts of peak power output. Features 30% cooler chassis operation: 64% less

• Push-Pull Audio System for Hi-Fi Sound
battery drain; instant play... no warm-up; full variable tone control; automatic gain control. Exclusive Golden Voice 6x9" speaker. Size: 9¹/₄Wx3Hx7¹/₄"D. For 12 volt cars, negative ground.
CR-131 Model 12AT-2 (6x9 speaker) Net 59.95
CR-132 Model 12AT1S (5x7 speaker) Net 59.95

MODEL 406 — TUBE & TRANSISTOR AUTO RADIO



39⁹⁵
NO MONEY DOWN

• For 6-Volt System
Compact radio set that is ideal for custom underdash or in-dash installation. "Golden Transistor" circuit employs 2 transistors and 4 tubes. "Volumatic" constant level output eliminates

fading and distortion. Antenna band pass filter. Reverse polarity. Size: 6⁷/₈Wx2¹/₂Hx7¹/₄"D. Shpg. wt., 6 lbs.
CR-28 Model 406 Net 39.95

Full 1-year warranty on all parts and labor. Manufacturer's guarantee covers free exchange or repair of any component power defective in normal use. Removal and re-installation labor extra. Arranged through your local service dealer.

Consult This Chart To Determine Which Sets Fit American Cars, Sports Cars and Foreign Cars.

The below chart shows the make and model of cars which use the above Motorola Car Radios. The "Use-Set" column indicates the stock number of the radio or stock number when ordering. Also list make, model and year of your car.

| MAKE, MODEL AND YEAR | USE SET | MAKE, MODEL AND YEAR | USE SET | MAKE, MODEL AND YEAR | USE SET |
|---------------------------------|------------------------|----------------------------|------------------------|----------------------------------|------------------------|
| Austin Healy 1957-62 | CR-128 | Falcon 1960-62 | CR-128, CR-129, CR-132 | Plymouth 1956-62 | CR-128, CR-129, CR-131 |
| Borgward 1957-62 | CR-28 | Fiat 600-1100 1957-62 | CR-128 | Rambler 1959-62 | CR-128, CR-129 |
| Buick 1954-62 | CR-128, CR-129 | Ford 1957-62 | CR-128, CR-131 | Rambler-American 1960-62 | CR-128, CR-129, CR-132 |
| Buick Special (Compact) 1961-62 | CR-128, CR-129, CR-131 | Hillman Minx 1957-62 | CR-128 | Renault Dauphine 6 Volt 1955-58 | CR-128 |
| Chevrolet 1958-60 | CR-128 | Karmann-Ghia (V.W.) 58-62 | CR-28 | Renault Dauphine 12 Volt 1958-62 | CR-128 |
| Chevrolet 1961-62 | CR-128, CR-129 | Mercedes Benz 1958-62 | CR-128, CR-130 | Studebaker Lark 1959-62 | CR-128, CR-129, CR-131 |
| Citroen ID-19, DS-19 6 Volt | CR-28 | M. G. Magnette MGA 1957-62 | CR-128, CR-130 | Sunbeam Rapier 1957-62 | CR-28 |
| Citroen 1958-62 12 Volt | CR-128 | Morris Minor 1957-62 | CR-128, CR-130 | Taurus 1958-62 | CR-28 |
| Comet, 1960-62 | CR-128, CR-129, CR-132 | Oldsmobile F-85 1961-62 | CR-128, CR-129, CR-131 | Triumph TR-3 1958-62 | CR-128, CR-130 |
| Corvair 1960-62 | CR-128, CR-129 | Opel 1957-62 | CR-28 | Valiant 1960-62 | CR-128, CR-132 |
| Dodge Dart 1957-62 | CR-129, CR-131 | Peugeot 1958-62 | CR-128, CR-130 | Volkswagen 1952-62 | CR-28 |
| Dodge Lancer 1961-62 | CR-128, CR-129, CR-132 | Pontiac Tempest 1961-62 | CR-128, CR-129, CR-131 | Volkswagen Bus 1952-62 | CR-28 |
| English Ford 1957-62 | CR-128, CR-130 | Porsche 1957-62 | CR-28 | Volvo PV-444, PV-544 1957-62 | CR-28 |
| | | | | Volvo 12 Volt | CR-128 |

NEW! TRANSISTOR POWERED ALL AMERICAN AUTO RADIO WITH FREE ANTENNA



• Instant Sound Without Warm-up
• Convenient Under Dash Mounting
• Low Battery Drain
ONLY 29⁹⁵
NO MONEY DOWN

BUY THE CAR RADIO, GET AN ANTENNA FREE!!
Transistor powered car radio with 2 transistors and 3 tubes for trim under-dash mounting. Plays as soon as you turn it on—no warm-up required. 5" speaker has 1 oz. magnet. Separate tone control; extra speaker jack. For 12-volt, reverse polarity cars. Size: 6x7¹/₂x3". Top cowl mount, 3-section antenna measures 23" closed, 58" open. Total shpg. wt., 5¹/₂ lbs.
CR-134 Radio plus Antenna Net 29.95

AUTOMOBILE ANTI-THEFT PROTECTOR



Protects Your Car from Being Stolen

6.98

- Protects Your Car by Sounding An Alarm
- Prevents Ignition Switch from being Jumped
- Prevents Car's Lights and Accessories from Working
- Easy to Install

Here is the ideal auto protection for salesmen, servicemen, delivery vans... all motorists. Not only will it prevent your parked car from being stolen, but will also safeguard valuables in the trunk as well as parts under the hood. Sounds an alarm in case of attempted theft and completely immobilizes the car—ignition can't be jumped, lights and accessories will not operate. Instructions included for easy installation.
AA-111 Shpg. wt., 1¹/₂ lbs. Net 6.98

NEW! RADIO TRANSVERTER Converts Transistor Radio to Car Radio




1.47

- For all 9-Volt Transistor Radios
- Plugs into Cigarette Lighter
- Fits all Cars

Now you can avoid the expense of buying a car radio with this new radio transverter. Simple to operate—remove 9-volt battery from your transistor radio, connect contacts from transverter to battery contacts in the radio, and then plug into the cigarette lighter. Fits all cars. Shpg. wt., 6 ozs.
AA-102 For 12-volt Cars Net 1.47
AA-103 For 6-volt Cars Net 1.47

CARDIO-MASTER



- Convert your Transistor Radio into a Car Radio
- For all Makes of Cars — Cabs — Trucks

2.98

Cardio master is a magnetic device designed to hold a portable transistor radio in the area of a car's windshield to make it operate as an auto radio. Car's owner can remove a radio from the Cardio master for use as portable or to avoid theft while the car is parked. Fits any "pocket" transistor radio. Will not come loose in the bumpiest roads. Includes magnetic base, brackets, hardware, adjustable band and complete, illustrated instructions.
AA-45 Shpg. wt., 2 lbs. Net 2.98

NEW! POCKET TIMER

Set It and Forget It


2.95

- Set Timer Up to 60 Minutes
- Swiss Precision Watch Movement
- Hairline Accuracy
- Hundreds of Uses

The new pocket timer is an invaluable aid for most anyone, anywhere. With its 60 minute time set, it can be used as a reminder when parking meter time runs out, for appointments, take pills or medicines, etc. Also use as a timer on phone calls, cooking, photography, etc. Shpg. wt., 1/2 lb.
MS-888L Net 2.95



REAR SEAT AUTO SPEAKER KITS



AS LOW AS **3.05**

6" x 9" KIT WITH CHROME OR GOLD GRILLE

Complete kit for adding second speaker in rear of your car. Includes a 6x9" PM speaker, 3-position selector switch for cutting in front, rear, or both speakers; dial plate with mounting bracket, knob, and hardware; chrome or gold grille; wire and wiring instructions. Simple to install. Shpg. wt., 5 lbs.
SK-94 Speaker kit chrome grille Net 3.45
SK-196 With gold grille Net 3.45

DELUXE 6"x9" KIT with 2.15 oz. ALNICO V MAGNET

Same as above but with deluxe speaker with extra-heavy Alnico V magnet (2.15 oz.). This is same speaker used in kits selling at twice the price. Shpg. wt., 5 lbs.
SK-37 Speaker kit chrome grille Net 4.65
SK-197 With gold grille Net 4.65

5" x 7" KIT

Same as SK-94 but with 5x7" speaker and grille, 5 lbs.
SK-42 Chrome grille Net 3.05
SK-198 With gold grille Net 3.05

FADER TYPE AUTO KITS

Rear-seat speaker kits identical to those above except with fader-type controls to cut either speaker in or out or balance both. Shpg. wt., 5 lbs.
SK-55 5x7" kit. Same as SK-42 but with fader control. Chrome grille Net 3.29
SK-199 With gold grille Net 3.29
SK-95 6x9" kit. Same as SK-94 but with fader control. Chrome grille Net 3.69
SK-200 With gold grille Net 3.69

DELUXE 6" x 9" FADER KIT

Deluxe kit with extra-heavy-magnet 6x9" speaker, plus fader control. Shpg. wt., 5 lbs.
SK-56 6x9" kit. Same as SK-37 but with fader. Chrome grille Net 4.89
SK-201 With gold grille Net 4.89

HI-FI REAR SEAT AUTO SPEAKER KITS



AS LOW AS **8.80**

- FEATURING 6x9 COAXIAL SPEAKER WITH TWIN TWEETERS

- ADD HI-FI LISTENING TO YOUR CAR
- FEATURING 6x9 COAXIAL SPEAKER WITH TWIN TWEETERS

Identical to SK-37 auto speaker kit shown on this page except has hi-fi 6x9" coax speaker instead of single-cone unit. Excellent for music lover who wants quality reproduction. Shpg. wt., 6 lbs.
SK-77 With Chrome Grille Net 8.80
SK-202 With Gold Grille Net 8.80

FADER TYPE AUTO KIT

Coaxial speaker kit (same as SK-77) with fader for flexible control of both front seat and rear speakers and sound balancing. Shpg. wt., 6 lbs.
SK-78 With Chrome Grille Net 9.00
SK-203 With Gold Grille Net 9.00

INSTANT FLAT TIRE REPAIR

- No Jacks, No Tools, No Removing Tires
- Seals and Inflates Tires in ONLY 2 MINUTES
- For Tube-Type and Tubeless Tires

GIANT 19 oz. CYLINDER!

2.59

You'll never change a punctured flat on the road again. Just attach the valve of any tube or tubeless tire and the amazing sealant instantly plugs the puncture as the tire is inflated to a satisfactory driving pressure. Will not affect wheel balance. No tools needed, no removing tires, no dirty hands—any woman can use it too. Road tested for performance. Shpg. wt., 3 lbs.
AA-84 Net 2.59

3-WAY PUSH-BUTTON SWITCH



.89

Lots **.75** of 3 ea.

Just push a button to select either front speaker alone, rear speaker alone or both together. Comes completely assembled on black & silver metal plate with cable, hardware and simple instructions. Imported. Shpg. wt., 1/2 lb.
MS-890 Lots of 3, ea. .75 singly, each .89

MAGNETIC UTILITY LIGHT



4.95

- Hi-Intensity Lamp
- Powerful Magnet Holds Anywhere on The Car
- Leaves Both Hands Free To Work

High intensity trouble lamp for car or boat. Powerful magnetic base holds easily to metal surface. Double ball joint for use at every possible angle. Folds down to an "egg" sized unit. Long life, horizontal filament lamp, gives more light than conventional types. Heavy chrome plate over brass plated steel for exceptional corrosion resistance. 15 ft. cord gives plenty of leeway in positioning. Includes red filter for use as a warning light, lighter plug and vinyl case for storage. For 12V. DC only. Shpg. wt., 1 lb.
F-631 Net 4.95
Spare Bulb for F-631
F-632 Shpg. wt., 2 oz. Net .28

NYLON "BULLDOG" 10 FT. TOW CABLE

- 100% DuPont Nylon
- 10-ft. Long
- Guaranteed 5,000 lb. Test Strength
- Attaches Instantly to Any Bumper



3.75

The perfect cable for towing ANYTHING UP TO 5,000 LBS. Constructed of heavy-duty, 1" wide, DuPont Nylon webbing that stretches 25% to take up shocks for smooth, safe towing. Oil, grease and water resistant too! Dual, self-aligning clip attaches to any bumper. Shpg. wt., 3 lbs.
AA-57 Net 3.75

NEW! Lafayette ELECTRONIC AUTO TESTER

COMPLETELY ASSEMBLED

NOT A KIT!

A TRUE VTVM IGNITION ANALYZER

Compact Combination Automobile Test Instrument

CHECK ✓ Power ✓ Performance ✓ Economy



39⁹⁵

NO MONEY DOWN

- No Complex "Curves" • "Scope" Type Indications are converted into Direct Meter Readings • Check Your Car's Ignition System—Plugs, Coils, Condenser, Points, Wiring • Special Capacitive Clip Prevents Overloads and Shocks Even when Ignition System is Operating • Large, Easy-to-Read Dial Face • Operates from 12-Volt Car Battery

The new Lafayette Electronic Auto Analyzer will pinpoint auto ignition trouble quickly and accurately without confusing curves or complicated interpretations. As accurate as an expensive oscilloscope, the TE-40 incorporates a highly sensitive VTVM to locate troubles in coils, plugs, points, condensers, etc. without any circuit drain. The large, easy-to-read multi-colored meter eliminates complicated curves and scope interpretations—you get direct, simple readings.

Featured is a variable resistance loading circuit which simulates a heavy engine load such as driving at high speed or hill climbing—you test under conditions simulating actual driving. The TE-40 also has a special capacitance clip which enables you to make high voltage measurements, including surges, without danger of shock. Operates on 12-volt auto batteries. Complete, ready-to-use with detailed operating instructions. Shpg. wt., 16 lbs. Net 39.95

THE GAUGES DETROIT LEFT OUT!

LAFAYETTE AMMETER & OIL PRESSURE GAUGES

449



DON'T trust flashing indicator lights—a burned out bulb can ruin your motor or strand you with a dead battery. All cars with warning lights for oil and battery need these precision gauges. Lights only indicate when oil pressure falls below 15 lbs. or whether or not the generator is working. These Lafayette gauges will replace your panel lights (or if you wish to use both lights and gauges, buy the Tee fitting listed below). Keep a constant check on the condition and performance of your car's electrical and oil pressure systems. The ammeter calibrated in a 60-0-60 scale measures the actual rate of current flow... helps prevent generators from burning out and overcharging or discharging the battery. Exact oil pressure from 0 to 80 lbs. is indicated. Easily installs in any 6 or 12 volt car below the dash, without drilling or can be mounted right in the dash. Both meters are mounted in an attractive chrome panel. Easy to read meters feature 1 3/4" diam. black dial faces with calibrations in white. Size: 5 1/4" x 2 7/8" x 2 1/4" D. Supplied with all necessary fittings plus full instructions. Net 4.49 MS-788 Shpg. wt., 1 1/4 lbs. Net .49 MS-912 Tee fitting

ILLUMINATED TYPE Same as above, but gauges are illuminated. Supplied with lamp sockets and both 6 and 12 volt bulbs. Net 6.49 MS-792 Shpg. wt., 1 1/2 lbs.

PROFESSIONAL BATTERY CHARGER 8.95

- 3 Amp Tapering Charge
- For Both 6 and 12 Volts
- Positive Automatic Overload Protection



A professional type 6 - 12 volt battery charger with reset circuit breaker. Indicator light flashes on when circuit breaker trips. Front panel switch for charger from 6 to 12 volts. Delivers a tapering charge starting at 3 amps for 6 volts. Noiseless, aircooled construction. Oversized components and vented case for trouble-free operation. Runs cool even under constant use. 4 1/2 ft. charging cables with heavy duty, 25 amp battery clips. Measures 5x3 1/2 x 3". For 105-125 volt, 50-60 cycle A.C. Shpg. wt., 5 lbs. Net 8.95 CV-50

CHARGER PLUG: Permits charger to be plugged into lighter receptacle. Shpg. wt., 8 oz. Net 1.15 MS-707 For 6V Cars Net 1.15 MS-708 For 12V Cars


2-IN-1 BATTERY CHARGER 4.95



- Full 1 Amp Charge Rate on 6 or 12 Volt Batteries
- Automatic Taper Rate—Can't Overcharge
- Manual Reset Circuit Breaker

End dead battery trouble in your car, boat, truck or tractor. This powerhouse battery charger keeps all 6 and 12 volt batteries fully charged for peak performance even at 40° below freezing. Full 1 amp "safe" charge rate prevents flaking and plate buckling—same method used by storage battery dealers. Easy to use—plug the line cord into any 110V outlet, connect the two terminals and forget it. Warning trouble light indicates incorrect terminal connection. Can't overcharge—automatically tapers off. Welded constructed steel. Shpg. wt., 3 1/2 lbs. Net 4.95 CV-56

AUTOMOTIVE TESTING EQUIPMENT



(A) MOTOR ANALYZER

All the advantages of a well-equipped service shop in a light, hand-held package. Ideal for do-it-yourselfers, sports car Rallyers, etc. The Analyzer enables you to test ignition coil output, spark plugs, insulation breakdowns; locates poorly adjusted carburetor, sticky or burnt valves, weak valve springs; checks valve timing, choke, muffler, vacuum tank, manifold, fuel pump vacuum and pressure and vacuum operated equipment. 14x7 1/4 x 3 1/2" D. Shpg. wt., 5 1/2 lbs. Net 15.95 AA-49

(B) REMOTE STARTER SWITCH

Eliminates the need of a second man when making compression, fuel pump, generator, starter, and electrical tests. Permits the mechanic to crank the engine from any position. Shpg. wt., 1/2 lb. Net 2.59 AA-50

(C) MOTOR GUIDE-VACUUM FUEL PUMP TESTER

Combination motor guide, vacuum and fuel pump tester, 4 color zones. Economy Driving, Fast Pick-up, Coasting and Idle. Promotes good driving habits and economical gas-mileage. Warns when tuneups are necessary. Shpg. wt., 12 oz. Net 3.75 AA-51

(D) COMPRESSION TESTER

Gives quick, accurate readings of compression pressure. Merely unscrew the spark plug, plug tester into spark plug hole and read pressure. 2 1/2" dial reads to 300 lbs. Stem is offset 15° for reaching back cylinders. Complete with instructions. Shpg. wt., 12 oz. Net 3.75 AA-52

(E) STANDARD TIMING LIGHT

Employs the stroboscopic principle of light synchronized with motion for adjustment and setting of ignition timing under actual operating conditions. Shpg. wt., 1 lb. Net 3.25 AA-53

(F) TACHOMETER

Here's the instrument for the most important check of an engine's performance: the RPM test. Tests 4, 6 and 8 cylinder engines with both 6 and 12 volt systems. Operated by two inexpensive penlight batteries which last about a year. Large dial reads 0-1000 and 0-5000 RPM. Shpg. wt., 2 1/2 lbs. Net 28.50 AA-54

CAM-DWELL INDICATOR 3.95

A high quality instrument for solving all CAM-DWELL problems. Checks the number of degrees a distributor can rotate while the breaker points remain closed. Too much rotation means points are set too close, too little means breaker points are not closed long enough for adequate arcing across points. Requires no electrical outlet. Distributor need not be removed. Compact, portable. Complete with case and includes chart showing specifications for all popular cars. Net 3.95 AA-98 Shpg. wt., 2 lbs.

EMERGENCY BLINKER 1.49




- OPERATES ON 2 FLASHLIGHT BATTERIES
- MAGNETIC BASE
- VISIBLE FOR 1000 FEET

Every motorist needs it. Bulb flashes 60 times a minute. Stands by itself on road; has hanger or magnetic base which holds it firmly to any metal surface. Rugged plastic dome, 5 3/4" diam. x 3 1/4" high. Shpg. wt., 2 lbs. With spare, non-blinking bulb for steady light, less batteries. Net 1.49 BA-157 #2 batteries (2 needed) ea. Net .13

MOTOROLA ALL-ELECTRONIC ALTERNATOR SYSTEM

30-Amp System 59.95

45-Amp System 74.95



Always Charges Battery Even at "Idle" Speed

- All-Transistor Voltage Regulator and Advanced New 7-Diode Alternator
- Extends Battery Life
- Reduces Maintenance Cost Caused by Generator and Regulator Failures
- Fits 12-Volt Cars with Negative Ground

• GUARANTEED FOR 3 YEARS (OR 30,000 MILES)*

Tired of replacing expensive car batteries? Frustrated by stalling cars and costly towing? Now you can save time, money and trouble with Motorola's all-electronic alternator system. This is the low cost solution to the heavy demands made by your car on its electrical system... heaters, radios, defrosters, air conditioners, power seats and windows. The new Motorola alternator eliminates all the fuss and expense caused by chronic run-down battery due to generator and voltage regulator failures. Unlike D.C. generators, it supplies a charge at idle speeds and keeps the battery at a uniform high level of charge. The all-transistor voltage regulator has no contact points to stick or burn... nothing but trouble-free transistors and diodes that virtually never wear out. So reliable it's sealed for life and is not affected by shock, vibration, moisture or

dust. The alternator is 50% smaller than a generator and weighs 50% less. Guaranteed for 3 years or 30,000 miles.* Motorola's advanced new alternator fits all domestic cars with 12-volt, negative ground electrical systems. Available in 2 sizes: 30-amp for autos and light trucks; 45-amp for police cars, taxis, and heavy duty use. The complete system includes: alternator (with standard-size pulley), all-transistor regulator (with all connecting wires), universal mounting bracket; instructions for installation in less than 1 hour. AA-109 30-Amp (shpg. wt., 11 1/2 lbs.) Net 59.95 AA-110 45-Amp (shpg. wt., 13 1/4 lbs.) Net 74.95 *Manufacturer's guarantee covers repair or replacement of parts within 3 years or 30,000 miles (whichever occurs first).



Lafayette HOT CAR-GO Starts Your Car INSTANTLY

OUR LOWEST PRICE EVER!

- Starts Wet or Cold Motors Instantly
- Saves Battery and Gasoline
- Installs Easily and Quickly
- 6 and 12 Volt Cars

2.95

Avoid excess wear and tear on your motor and battery—install Lafayette's Hot Car-Go. Provides 5 times the normal spark for fast starting in any weather, and automatically disconnects when engine is running. Will not damage plugs or distributor. Simple to install—instructions included. Shpg. wt., 1 lb. Net 2.95 MS-784

NEW! DO-IT-YOURSELF PLATING KIT

Tune Up Your Chrome—Plate or Replate Most Metal Surfaces



- Fast-Easy-Inexpensive
- Non-Electric
- For Use in Home, Car, Boat, Office

3.98

• Combination of Cadmium, Nickel, Chromium Now you can replate worn, rusted or pitted iron, steel, copper or brass—even metal parts that have never been plated before! Your finished plating is a combination of cadmium for rust-proofing, nickel for protection and luster, chromium for hardness and brilliance. Ideal for car, plumbing fixtures, door hardware, and most any metal surface except aluminum. Kit consists of 4 oz. copper chelate, 4 oz. chrome chelate, 1/2 pint plating sealer, sponge, catalizer wool, 1" brush, sandpaper, steel wool, 4 oz. rust remover. Shpg. wt., 2 lbs. Net 3.98 AA-106

SUPER PLATING KIT

Similar to above but in larger quantities. 12 oz. copper chelate, 12 oz. chrome chelate, 12 oz. spray can of plating sealer (no brush needed), 12 oz. rust remover, sponges, catalizer wool, sandpaper, steel wool. Shpg. wt., 4 lbs. Net 9.98 AA-107

"RUSTY" RUST REMOVER 86c

- Dissolves Rust from Iron and Steel
- Cleans Stains from Porcelain, Cement, Tile
- Frees Frozen Nuts and Bolts

A few drops of Rusty and rust dissolves without affecting the sound metal. No more heat or torches necessary; no more long waits. Use for car or home—anywhere there is rust, corrosion, stained porcelain and cement. Frees frozen nuts and bolts; loosens frozen pipe joints. Non-flammable; safe to use. Shpg. wt., 8 oz. Net .86 AA-108

TIMING & OCTANE SELECTOR 4.54



Increases Gas Mileage & Horsepower

- Advances or Retards Spark As You Drive
- Spark Indicator Light Shows Engine Load
- Gives Longer Engine Life
- Premium Performance on Regular Gas

Recover the gas mileage and power your car is now wasting with this Timing and Octane Selector. Enables you to dial-in the most effective spark timing from the dash, as you drive. Harmful ping and spark knock are eliminated—you get premium performance from regular gas. Will not interfere with your distributor's advance mechanism. Mounts on your dash. Simple, do-it-yourself installation instructions—no tools needed. Shpg. wt., 1 1/4 lbs. Net 4.54 AA-112

SAVE! BATTERIES, CHARGERS, "HAM" CODE EQUIPMENT

LAFAYETTE BATTERIES AT TREMENDOUS SAVINGS



These popular batteries are for Portable and Transistor radios, R/C equipment, experimenters, labs, and hobbyists, etc.

FRESH STOCK — BRAND NEW GUARANTEED

Here are six of the most popular types used and at RIDICULOUSLY LOW PRICES

| Stock No. | Voltage | Singly | Lots 10 Each | RCA | REPLACEMENTS FOR Burgess Eveready Others |
|-----------|---------|--------|--------------|-------------------|--|
| BA-1 | 67½ | 1.49 | 1.39 | VS215 VS216 VS218 | P45 P45M 477 BL-M145 |
| BA-2 | 9 | .21 | .29 | VS312 VS323 | 2U6 216 BL-006F |
| BA-3 | 9 | .34 | .29 | VS300A VS314 | P6 P6M 226 BL-M106 |
| BA-5 | 67½ | 1.29 | 1.19 | VS318 | UX45 416 BL-045 |
| BA-6 | 67½ | 1.45 | 1.35 | VS016 | XX45 467 BL-145 |
| BA-7 | 9 | .53 | .45 | VS309A | YL-6 E-177 TR-177 |

LAFAYETTE PHOTOFLASH, BC AND HEARING AID BATTERIES

| Stock No. | V. | Singly | Lots 10 Ea. | Fig. | Replacements for Burgess Eveready RCA | Shgp. Wt. |
|-----------|-----|--------|-------------|------|---------------------------------------|-----------|
| BA-11 | 15 | .49 | .44 | A | Y10 504 | 3 oz. |
| BA-14 | 22½ | .59 | .53 | A | Y15 505 | 3 oz. |
| BA-12 | 22½ | .59 | .53 | B | U15 412 VS084 | 3 oz. |
| BA-16 | 45 | 1.98 | 1.83 | C | M30 482 VS013 | 2 lb. |
| BA-15 | 90 | 2.36 | 2.12 | D | N60 490 VS090 | 1 lb. |
| BA-13 | 240 | 4.50 | — | E | U160 491 | 1 lb. |

Eveready, Burgess, RCA, Mallory Batteries

PORTABLE A TYPES

| Lafayette Stock No. | "Eveready" No. | Burgess | R.C.A. | Voltage | Shgp. Wt. Lbs. | Net |
|---------------------|----------------|---------|--------|---------|----------------|--------|
| BA-100 | A100 | 230 | VS336 | 1½ | ¼ | \$.16 |
| BA-101 | 720 | 2D | VS069 | 1½ | ¾ | .84 |
| BA-104 | 964 | 21R | VS236 | 1½ | ¾ | .32 |
| BA-109 | 724 | Z4 | VS068 | 6 | ¾ | .70 |
| BA-112 | 713 | B5 | VS129 | 7½ | ¾ | 1.92 |
| BA-113 | 717 | C5 | VS065 | 7½ | ½ | 1.15 |
| BA-276 | 206 | — | VS327 | 9 | ½ | .53 |

PORTABLE B TYPES

| BA | No. | U | VS | Voltage | Shgp. Wt. Lbs. | Net |
|--------|-----|------|-------|---------|----------------|--------|
| BA-114 | 411 | U10 | VS083 | 15 | ¼ | \$.81 |
| BA-115 | 417 | K10 | — | 15 | ¼ | 1.16 |
| BA-116 | 504 | Y10 | — | 15 | ¼ | .81 |
| BA-117 | 412 | U15 | VS084 | 22½ | ¼ | 1.05 |
| BA-118 | 420 | K15 | — | 22½ | ¼ | 1.23 |
| BA-119 | 505 | Y15 | — | 22½ | ¼ | 1.05 |
| BA-120 | 413 | U20 | VS085 | 30 | ¼ | 1.23 |
| BA-122 | 506 | Y20 | — | 30 | ¼ | 1.30 |
| BA-123 | 507 | Y20S | — | 30 | ¼ | 1.30 |
| BA-124 | 415 | U30 | VS086 | 45 | ½ | 1.75 |
| BA-125 | 455 | XX30 | VS055 | 45 | ½ | 2.08 |
| BA-126 | 482 | M30 | VS013 | 45 | 1 | 2.70 |
| BA-130 | 416 | UX45 | VS118 | 67½ | ¼ | 2.07 |
| BA-131 | 457 | K45 | VS082 | 67½ | ½ | 2.42 |
| BA-132 | 467 | XX45 | VS016 | 67½ | ½ | 2.45 |
| BA-133 | 477 | P45 | VS218 | 67½ | ½ | 2.27 |

PORTABLE A-B TYPES

| BA | No. | VS | Voltage | Shgp. Wt. Lbs. | Net |
|--------|-----|-------|---------|----------------|-----------|
| BA-143 | 729 | 4T260 | VS064 | 1½, 90 | 2½ \$4.38 |
| BA-146 | 755 | T5250 | VS050 | 6, 7½ | 5.08 |
| BA-149 | 756 | T6260 | VS057W | 75 | 3½ 4.87 |
| BA-151 | 752 | G6B60 | VS047 | 90 | 2½ 5.78 |

ELECTRONIC PHOTOFLASH AND HIGH VOLTAGE TYPES

| | | | | | |
|--------|-----|------|---|-----|-----------|
| BA-226 | 497 | U320 | — | 510 | 1¼ 111.16 |
|--------|-----|------|---|-----|-----------|

MERCURY ENERGIZERS

| Lafayette Stock No. | "Eveready" No. | Mallory | R.C.A. | Voltage | Shgp. Weight Lbs. | Net |
|---------------------|----------------|---------|--------|---------|-------------------|------|
| BA-227 | E 1 | RM-1R | VS143 | 1.35 | 0.43 | .38 |
| BA-230 | E 9 | ZM-9 | VS313 | 1.40 | 1.05 | .51 |
| BA-231 | E 9N | DM-9N | — | 1.40 | 1.05 | .54 |
| BA-232 | E 12 | RM-12R | VS144 | 1.35 | 1.4 | .75 |
| BA-233 | E 132 | TR-132R | VS148 | 2.70 | 0.9 | .92 |
| BA-234 | E 133 | TR-133R | VS149 | 4.05 | 1.4 | 1.00 |
| BA-235 | E 134 | TR-134R | — | 5.40 | 1.9 | 1.45 |
| BA-236 | E 146 | TR-146R | VS312 | 8.40 | 1.6 | 1.02 |
| BA-237 | E 23J | TR-233R | VS400 | 4.20 | — | 1.80 |
| BA-238 | E 400 | RM-400R | VS145 | 1.35 | 0.04 | .24 |
| BA-239 | E 401 | RM-401R | — | 1.35 | 0.04 | .33 |
| BA-240 | E 502 | RM-502R | — | 1.35 | 1.05 | .62 |
| BA-241 | E 625 | RM-625R | — | 1.35 | 0.14 | .34 |
| BA-242 | E 630 | RM-630R | — | 1.35 | 0.17 | .30 |
| BA-522 | — | RM-675 | — | 1.4 | 0.09 | .26 |

FLASHLIGHT, LANTERN BATTERIES General Purpose, Portable Lighting

| | | | | | | |
|--------|---------|--------|--------|----|----|------|
| BA-154 | 912 | 7 | VS074 | 1½ | ¼ | .10 |
| BA-155 | 915 | Z | VS034 | 1½ | ¼ | .095 |
| BA-156 | 935 | 1 | VS035 | 1½ | ¼ | .13 |
| BA-157 | 950 | 2 | VS036 | 1½ | ¼ | .13 |
| BA-158 | D-99 | — | — | 1½ | ¼ | .16 |
| BA-159 | 735 | 4FH | VS106 | 1½ | ¼ | .84 |
| BA-160 | =6 lgn. | 6 lgn. | VS006S | 1½ | 2½ | .84 |
| BA-161 | 509 | F4H | VS040C | 6 | 1½ | .79 |
| BA-162 | 510S | F4BP | VS040S | 6 | 1½ | .79 |
| BA-163 | 731 | TW1 | VS317 | 6 | 3¼ | 1.83 |
| BA-164 | 706 | 4F4H | VS103 | 6 | 5¼ | 4.01 |
| BA-273 | 2709 | — | — | 9 | 1½ | 1.05 |
| BA-275 | 560 | — | — | 7½ | 2 | 3.50 |
| BA-309 | 904 | NE | VS073 | 1½ | 1 | .08 |
| BA-311 | 715 | 4F5H | VS139 | 7½ | 1½ | 4.86 |

LAFAYETTE "B" BATTERY ELIMINATOR and CHARGER for TRANSISTOR RADIOS



This simple "B" battery and eliminator has provision for replacing snap terminals on all 9-volt transistor batteries. Now when indoors you can operate your portable transistor set on regular 110V AC house current without using up your expensive "B" battery. . . Best of all you may also recharge your used battery for many extra hours of use. Complete with AC cord and assorted snap terminals to fit all 9-volt transistor batteries. Size: 3½x3¾x2½"D. Shgp. wt., 1 lb. Net 2.95

TRANSISTORIZED CODE PRACTICE OSCILLATOR



- MINIATURE-PORTABLE
- SELF CONTAINED BATTERY POWER SUPPLY
- PRODUCES CLEAR, CRISP, CW NOTE

Here is an ideal, inexpensive code practice oscillator for the amateur radio enthusiast. Long 38 inch wire from oscillator to earpiece, allows two persons to practice without interference. The unit is completely portable, and weighs only 6 oz. Tone produced is clear and crisp, similar to that received during F.C.C. licensing examinations. Low voltage transistorized circuit utilize 1.5 volt penlight type battery which completely eliminates any possible shock hazard. Earpiece is crystal type, and housed in sanitary plastic. Shgp. wt., 5 oz.

F-429 Oscillator only Net 2.29
229 CODE PRACTICE OSCILLATOR WITH KEY
 Above oscillator plus adjustable telegraph key (MS-319). Key has spade lug connectors, making it possible to disconnect the key from the oscillator and use it separately if desired. Shgp. wt., 9 oz.
 F-479 MS-319 Key and Oscillator Net 2.95

"B" BATTERY ELIMINATOR and CHARGER



245

Replaces Eveready 416, Burgess UX-45, and RCA VS 318 67½V B batteries used in Radio Control units and many portables. Just plug in the AC cord and you can save your battery for outdoor use. Also recharges your battery. 110 volts. 3½x1½x¾". Shgp. wt., 7 oz.
 F-550 Net 2.45

NEW! "STORAGE CELL" for TRANSISTOR RADIOS!

ONE CHARGEABLE BATTERY OUTLASTS 100 CONVENTIONAL BATTERIES

- Replaces 2U6, 216, BL-006P and BA-2
- Fluid Storage Type—Can't Leak Out
- Plays About 15 Hours on One Charging
- Battery Recharges Overnight
- Battery Can Be Used Over and Over Again
- Complete—Battery Plus Charger

The next best thing to a battery that will last a lifetime—this battery can be used for 100 to 1500 hours of playing time, AND MORE, its long life is based on 2 new features: 1. A fine storage battery that cannot have fluid leakage; 2. Recharges Overnight—just plug the battery into the charger, the charger into your electrical outlet. Let it charge for 10-12 hours. It cannot burn out on recharge. After charging, the battery is good for about 15 hours of playing time. When the battery runs down, just charge it up and it's ready to play. Will outlast more than 100 conventional batteries. 9V Battery complete with charger. Battery 1½x1½"; charger 3½x1½x¾".
 F-619 Battery and Charger. Shgp. wt., 6 oz. Net 2.69
 BA-8 Battery Replacement for above Net 1.48

Reg. 1.48
NOW .95

10 LESSONS ON A 12" LP RECORD

SAVE OVER 35% ! CODE PRACTICE SET


Set consists of key and buzzer. Key of chrome and nickel plated metal parts, molded phenolic base. Adjustable spring tension and contact clearance. 2 mounting holes. Buzzer of molded phenolic housing, has screw adjustment for changing tone. Works with 1½ volt battery. Shgp. wt., 18 oz. SP-278M Net .95

LAFAYETTE SPECIAL CODE COURSE

Learn Morse Code the modern practical way. Supplied with 10 lessons and a non-breakable high quality 33½ rpm long playing record, recorded with code sound to provide further aid. Perfect for home studying. Speed progresses steadily from 2 to 15 wpm. Complete with sturdy record album and instruction manual. Shgp. wt., 1½ lbs.
 PR-13 Lafayette Code Course Net 3.50

BATTERY RECHARGER and ELIMINATOR

- Recharges All Standard "Flashlight" Batteries ("C", "D", and Penlite "Z")
- Restores "Life" to Battery-Operated Toys
- Safe, Isolated Power Supply



The new dry cell battery recharger and eliminator is like having an endless supply of flashlight batteries. Recharges "C", "D" and "Z" cell batteries in 2 to 4 hours—keeps battery-operated toys always on the go. It's a battery eliminator too—simply plug into any 110V AC outlet. Delivers 4 to 6 V. DC for "recharge" or "eliminate." Shgp. wt., 1½ lbs. CV-59 Net 4.95

CODE PRACTICE SET LAFAYETTE SPECIAL



179

Key has adjustable spring tension, and contact clearance. High frequency buzzer has frequency and tension adjustment with lock nuts. Provision for insertion of head set. For individual, group or remote listening. Uses Burgess #2 1½ Volt battery. Overall length 8½". Shgp. wt., 2 lbs. (less practice set).
 MS-438—Code practice set Net 1.79
 BA-157—Burgess #2 Net .13
 MS-369—Stethoscope Headset Net 1.39

ECONOMY ALL-PURPOSE DYNAMIC EARPHONE

- For Transistor and Subminiature Receivers
- For Silent Radio and TV Listening

A sensitive all-purpose earphone designed with both your listening pleasure and pocketbook in mind. Extensive range and excellent tone combine, to provide excellent reproduction. Lightweight, equipped with a practically invisible ear support, that slips comfortably over either ear, from which the earphone can't slip out or fall. Ideal for use with TV and radio sets, amplifiers, miniature and transistor receivers, etc. Shiny chrome finish. 3 ft. cord. 6 ohm impedance, with subminiature phone plug.
 MS-591 Shgp. wt., 5 oz. Net .79

TEST-O-CHARGE-5-IN-1 ELECTRONIC MARVEL



- It's a 3 Amp 6V/12V Battery Charger
- It's a Tube Tester
- It's a 9V Transistor Battery Charger
- It's an Electric Appliance Tester
- It's a Shock Hazard Detector

A new, multi-functional compact unit for home, farm, garage. Combines 5 practical and useful units for everyday use by practically everyone. Will charge any 6V or 12V car, marine or farm battery over-night—can be plugged into cigarette lighter. Circuit breaker protects Test-O-Charge and the battery. Will also test appliances and power tools by tracing faulty parts; detects any shock hazard on electrical devices; checks tubes for burned out filaments. 5¼x3¼x3". For 110-125V AC 60 cycles. Shgp. wt., 4 lbs. CV-60 Net 9.95

COLD-START BOOSTER-CHARGER

The First Combination Battery Charger and Booster

- 50 Amp Booster (6 volt)
- 25 Amp Booster (12 volt)
- 10 Amp Charger (6/12 volt)

2150

Perfect for starting 6V, 8V, 12V cars. Works as a booster—as a charger. As a booster will supply a maximum of 50 amps; as a charger, 10 amps. Supplied with heavy copper cables; thermal switch prevents overheating; works up to 200-ft. away from AC power source. Power output: 12V Boost, 25 amps maximum; 6V Boost, 50 amps max.; 6/12V Charge, 10 amps tapering to 5 amps max.; Power Input: 5 amps max. at 117V AC, 60 cycles. Shgp. wt., 9½ lbs. CV-58 Net 21.50



LAFAYETTE AWARD WINNING Tape Recorder VALUES

New LAFAYETTE 2-SPEED TAPE RECORDER FEATURES 4-TRACK MONAURAL RECORD PLAYBACK WITH 4-TRACK STEREO PLAYBACK*

Contains Every Quality
Tape Recorder Feature

- Two Speeds—3 3/4 & 7 1/2 ips
- Sensitive Hand-Held Dynamic Microphone with Swivel Desk Stand
- Pause Lever Provides Instant Stop For Editing
- Record-Erase Safety Switch
- Fast, Rugged Shift Lever Control
- Extension Speaker Jack
- High Impedance Monitoring Jack
- VU Meter Recording Level Indicator
- Electronic Track Selector Switch
- Specially Designed Heavy Duty 6x4 PM Speaker
- Separate Erase and Record Heads.

We've tested, we've compared and Lafayette's engineers have certified this new RK-137 Tape Recorder as containing one of the finest, quality constructed, smoothest performing tape mechanisms available. And, at its remarkably low price, the RK-137 must be ranked near the top in Lafayette's long history of best buys. Engineered to provide virtually every wanted tape recorder feature, the RK-137 performs brilliantly, with facilities for 4-track monaural record/playback and 4-track stereo playback *(when used with a second channel containing a tape head input such as found in a component Hi-Fi system). Controls are completely functional and are designed and arranged to make the RK-137 a genuine pleasure to use.

Features include: a rugged, easy to use shift lever for fast rewind, fast forward, play and record functions; a special push-button safety record switch assures against accidental erasure of tapes; velvet-smooth volume and on-off tone controls; a pause lever instantly stops tape in motion, especially useful for editing; track switch provides fast, dependable electronic switching between tape tracks 1-4 and 3-2. In addition a VU recording level meter has been incorporated to indicate correct volume-setting for recording. Speeds are adjustable from 3 3/4 to 7 1/2 inches per second by means of a simple capstan adjustment. Tape economy is unmatched—from a standard 7 1/2" 1200 ft. reel the RK-137 provides over 2 hours monaural record/playback time at 7 1/2 ips and over 4 hours at 3 3/4 ips. Jacks are furnished for microphone input, High-Impedance Radio-Phono Input, Extension Speaker Output, Monitor Output and Stereo Head Output for a playback of 2nd stereo channel RK-137WX Shpg. wt., 22 lbs. Net \$9.50

ACCEPTS FULL 7" REEL OF TAPE



8950

NO MONEY DOWN

INCLUDES
LIGHTWEIGHT
CARRYING CASE

LEVER
ACTION
CONTROL

SPEECHES
PUBLIC MEETINGS

SCHOOL WORK
VOICE TRAINING

TAPE
FM
BROADCASTS

with
ELECTRONIC
TRACK
SELECTOR
SWITCH

RK-137

COMPLETE with MIKE, SHIELDED
PATCH CORDS, EMPTY 7" REEL
and 7" REEL RECORDING TAPE.

Response: 40-15,000 cps at 7 1/2 ips. 40-9,000 cps at 3 3/4 ips. Signal-to-Noise Ratio: 42db. Wow & Flutter: less than 0.3%. Interchannel separation. Complete in attractive vinyl covered two-tone case and equipped with a dynamic mike, cable assembly for recording from your phono or radio, stereo head input cable for stereo playback, 1200 ft. 7" Reel recording tape with a 7" take up reel. Size: 13 1/2"Wx6 1/2"Hx10 3/4"D. For 110-120 VAC 60 cycles operation.

SONY

MODEL 464-D STERECORDER

19950

NO MONEY DOWN

- 4 TRACK STEREO & MONO RECORD/PLAY
- BUILT-IN RECORD-PLAY PREAMPS
- 2 SPEEDS—7 1/2 & 3 3/4 ips
- REMOTE CHANNEL INTEGRATOR CONTROL UNIT
- SOUND-ON SOUND



The compact 464-D is a 2-speed 4-track stereo and monophonic record/play tape recorder designed for custom installation. Contains built-in record and play pre-amplifiers with frequency response of 40-15,000 CPS @ 7 1/2, 40-10,000 @ 3 3/4 ips and 40-10,000 CPS @ 7 1/2, 40-10,000 @ 3 3/4 ips and 40-10,000 CPS @ 7 1/2, 40-10,000 @ 3 3/4 ips. Features include: belt-free drive mechanism, sound-on-sound and sound-with-drive mechanism, sound-on-sound and sound-with-drive mechanism, sound-on-sound and sound-with-drive mechanism, sound-on-sound and sound-with-drive mechanism. Signal-to-noise ratio better than 50 db. Special compact accessory panel permits easy accessibility to microphone input, extension speaker and sound-on-sound switching—Less case. Size: 13 1/4"Wx11 3/4"Dx6"H. RK-286WX Shpg. wt., 23 lbs. Net 199.50



Technicorder

MINIATURE TRANSISTORIZED 2-SPEED TAPE RECORDER

6 Transistors plus a Thermistor for high gain with Push-Button Controls

7950

NO MONEY DOWN

- Weighs Only 6 lbs. With Batteries
- Fully Transistorized—6 Transistors plus 1 Thermistor
- Records & Plays Up to 64 Minutes
- Dual Track
- Two Speeds—3 3/4 ips & 1 1/2 ips
- Push Button Controls
- Built-In Speaker
- Use Anywhere—Powered By 4 Inexpensive Flashlight Batteries
- Rugged Dynamic Microphone
- Special Synchro-rod Synchronized Tape Speed With Your 8mm Home Movies

Employs the most advanced transistor circuitry (6 transistors plus 1 thermistor). Operation is accomplished entirely by push-button with rewind, stop, play and record functions furnished by 3 simple push-button controls. In addition as a safety feature, a special record button is provided to prevent accidental erasure. The correct reading level and battery condition is given by a VU meter located on the front panel. Convenient volume control adjustment with jacks external speaker and microphone are easily accessible at the side. For home movie fans a specially designed Synchro-rod is provided, which, when screwed into the capstan allows synchronizing the speed of the RK-126 with that of your 8mm projector. Two speeds, 3 3/4 and 1 1/2 are provided, with speed changes easily accomplished by means of a simple capstan adjustment. Designed for maximum tape economy, the Technicorder utilizes precision

dual track heads (1 erase plus 1 record/playback) to provide record/playback time at 3 3/4 ips for 16 minutes per single track and 32 minutes per dual track; at 1 1/2 ips time is extended to 32 minutes per single track and 64 minutes per dual track. Exceptional fidelity and sound quality are achieved by means of a specially developed 2 3/4"x8 1/4" oval speaker and AC recording bias system, with a signal/noise ratio of —49 db. Housed in an attractive tan and black hi-impact poly-vinyl case, the Technicorder features a handy snap-open plexiglass top for fast, efficient tape loading. Supplied complete with shoulder strap, vinyl carrying case, dynamic microphone and case, 3" reel of tape and empty reel, batteries, splicing tape and extension speaker cord. Size: 3Hx9 1/2"Wx7 3/4"D. RK-126L Shpg. wt., 8 lbs. Net 79.50



- TECHNICORDER ACCESSORIES
- RK-216 AC Adaptor for 115V, 60 cycles AC. Shpg. wt., 3 lbs. Net 17.95
 - RK-128 Telephone Pickup. Shpg. wt., 1/2 lb. Net 3.95
 - RK-129 Foot Switch for dictation. Shpg. wt., 1 1/2 lbs. Net 4.95
 - RK-131 Mike w/Remote Switch for RK-126 Technicorder. Net 7.95
 - RT-20 Tape—3" reel of 300 ft. 1/2 mil nylon tape. Shpg. wt., 1/2 lb. Net .69
 - BA-157 Replace Batt. for RK-126, 4 reqd. Shpg. wt., 4 ozs. Net ea. .13

NEW BELL PROFESSIONAL STEREO TAPE DECK MODEL T-337



Features Built-in
Stereo Record
Playback Pre-
Amplifier

29395

NO MONEY DOWN

- 4 TRACK STEREO RECORD/PLAYBACK
- 2 TRACK STEREO PLAYBACK
- PUSH-BUTTON OPERATION

An extremely versatile tape deck with facilities for making 2-track and 4-track stereo tapes, off-the-air stereo recordings, copy stereo tapes and discs etc. Professional features include 3 heavy-duty 4-pole motors. Wow and flutter less than 0.2%. Frequency response of 18-16,500 CPS ± 3 db @ 7 1/2 CPS & 18-15,000 CPS ± 3 db @ 3 3/4 IPS (overall record-playback). Playback only extends to 20,000 cps. Signal-to-noise ratio—better than 50 db. Maximum reel size 7". Preamp has 4 inputs—2 high impedances for mikes; 2 high impedance for amps, tuners, etc. 4 outputs and 6 tubes. Has front panel mike jacks, pushbutton speed, off and pause selection, Index counter, 2 VU meters. Mounts anywhere, plays in any position. Wood grain finish. Size 15 1/4"Wx 13 1/2" front-to-back; 5" below mounting surface, 2" above mounting surface (Includes Preamp). RK-271WX Shpg. wt., 23 lbs. Net 293.95

Wollensak TAPE RECORDERS

AT PRICES YOU CAN AFFORD



T1500
T-1515-4
T1700

LAFAYETTE PRICES

T1500 156 50 T-1515-4 173 95 T1700 199 45



1010

MODEL T-1500 HI-FI TAPE RECORDER

• 10 WATTS PUSH-PULL OUTPUT! • RESPONSE 40-15,000 CPS ± 3 DB AT 7 1/2 IPS! • DISTORTION LESS THAN 0.8%! • WOW AND FLUTTER BELOW 0.3%! • SIMPLIFIED KEYBOARD CONTROL! • WEIGHS ONLY 18 LBS.! A really precision portable high fidelity recorder made by a famous manufacturer of precision optics. This latest model T-1500 is made available, for the FIRST TIME AT THIS PRICE, BY LAFAYETTE! Dual speed (3.75 and 7.5 inches per second), dual track—provides up to 4 hrs. of record or playback time. Utilizes miniaturized components and all-metal airplane-type construction to achieve real portability—weighs only 18 lbs., measures 6 1/2"x10 1/4"x11 3/4". Takes reels up to 7". Additional features of this outstanding recorder include: signal-to-noise ratio 45 db; 2 special hum balance controls; "Balanced Tone" high fidelity; exclusive high speed rewind lever; 2-level recording indicator; precision index counter. Supplied complete with ceramic wide-range microphone, 1 reel of tape, 1 empty take-up reel, radio-tv attachment cord and hi-fi cable. For 110-120 volts, 60 cycles AC. Shpg. wt., 21 lbs. Also available in 50 cycle units; specify. RK-405WX Net 156.50

MODEL T-1515-4 FOUR TRACK STEREO HI-FI TAPE RECORDER

The Hi-Fi enthusiast's dream in a compact portable tape recorder for true stereo performance. Has all the styling and superb features of the famous monaural T-1550, plus stereo head and built-in second preamplifier. Plays 2 and 4 track monaural and 2 and 4 track stereo. Records up to 4 separate monaural tracks on single roll of tape. 6 1/2"x10 1/4"x11 3/4". Shpg. wt., 24 lbs. RK-417WX Net 173.95

NEW! Model T-1700 Mobile Tape Recorder

New listen and record outdoors and indoors with true hi-fidelity. The T-1700 is a full size, portable tape recorder designed to operate from both a home AC outlet or a 12 volt car or boat battery by simply plugging into your cigarette lighter. Same fine performance and specifications of the T-1500. Complete with microphone, reels (one with tape), battery clip and connector, lighter plug plus 12 volt power cord. Shpg. wt., 27 lbs. RK-423WX Net 199.45

1010 STEREO MATE FOR T-1515-4

The Model 1010 is a second channel amplifier for the T-1515 and T-1616 tape recorders. Self-contained hi-fi amp and speaker combination with 10-watt peak power output from a push-pull amplifier and 4-tube circuitry. Special 6x9" dual cone speaker utilizes built-in crossover network for distortion-free lows and sharp highs. Freq. response 30-10,000 cps; separate volume and tone controls. Use with any stereo tape recorder or phono, or in conjunction with a tuner. Size: 6 1/2"x12 1/2"x12". Shpg. wt., 9 lbs. RK-422W Net 37.50

SAVE \$5.50 — SPECIAL COMBINATION OFFER

Model 1515-4 Stereo Tape Recorder plus 10-10 Mate. SP-200WX Net 209.95



New! LAFAYETTE 4 TRANSISTOR PUSH-BUTTON TAPE RECORDER



Miniature -
8x3 1/2 x 7 3/8" D

RK-133L

COMPLETE WITH MICROPHONE, EARPHONE, 3" REEL OF TAPE, EMPTY REEL, BATTERIES

29⁹⁵
NO MONEY DOWN

INCLUDES



FOR HOME SCHOOL and OFFICE

- Lightweight—A mere 2 1/4 lbs.
- Records and plays up to 20 minutes with 1 Standard 3" Reel
- Pushbutton Play, Rewind, Off
- Battery operated
- Completely Portable—Take it with you Anywhere

A real triumph in miniature recorders. Space age printed circuitry using a 4 transistor push-pull amplifier and built-in oval 2 1/2 x 4" PM Speaker provides quality sound. Light weight makes it ideal for travel, business use. Has all the most wanted features. Convenient push-button fast Rewind, Off and Play controls. Record safety interlock prevents accidental erasure of tape; volume control is independent of Off switch; erases automatically in record position. No need for AC adapter; operates on 2 inexpensive batteries. Inputs for microphone and earphone for private playback. Designed for maximum tape economy, the RK-133 employs a half-track tape head—upper half is recorded first and turning over tape records lower half. Plays 10 minutes per side with standard tape—more with 1/2 mil long play tape. The handsome two-tone plastic case features a sloping speaker grille which faces front for optimum sound and a snap open top for fast, easy tape loading. Power is supplied by 1 standard 1.5v standard flashlight cell and one 9V transistor battery. Supplied with crystal lapel microphone, magnetic earphone, batteries, 200 ft. 3" reel of tape and an empty reel. Dimensions: 8Wx3 1/2 Hx7 3/8" D. Shpg. wt., 4 lbs.

| | |
|---|-------------|
| RK-133L | Net 29.95 |
| REPLACEMENT BATTERIES FOR RK-133 | |
| BA-2 9 volt transistor battery | ea. Net .39 |
| BA-157 1.5 volt | ea. Net .13 |

LAFAYETTE RK-138 2-SPEED 4-TRACK TAPE RECORDER SECOND PREAMP for STEREO PLAYBACK



NO MONEY DOWN

MADE IN U.S.A.


SPECIFICATIONS:
Response: 50-10,000 cps. Wow & Flutter: less than 0.3%. Signal-to-Noise Ratio: 40db. Outputs: Include 2 output jacks—1) second-channel external amplifier. 2) external speaker.

- Plays Back 4-Track Stereo & Records Dual Track Monophonically
- Two Speeds—7 1/2 ips & 3 3/4 ips
- Accepts Up To 7" Reel
- Has 2 Playback Preamplifiers
- Neon Recording Level Indicator

Reg. 99.95 **79⁹⁵**
SUMMER SUPER SPECIAL!

Loaded with features, precision engineered and built to last, the new Lafayette tape recorder must be classified a best-buy by any standards. Designed for complete flexibility, the RK-138 offers both stereo and monophonic facilities. In addition to being able to record and play back 2-track monoaural material, through its own speaker and amplifier, you can use the RK-138 for 4-track playback of the latest stereo tapes through your own component stereo system. Or, if you wish, use its self contained 6-watt amplifier and speakers (5" woofer, 4" tweeter with electronic crossover) as a second stereo channel in association with your monaural hi-fi system, radio, T.V., or with RK-139 matching speaker/amplifier with patch cord for radio, T.V., or tuner input. Functional design utilizes a single, easy-to-use lever to select "Play-Idle-Record" positions. A special safety interlock in record position insures against accidental erasure of tapes. Fast rewind is accomplished by means of a lock-in lever control with tone and loudness adjusted by a concentric front panel control. Equipped with sensitive microphone, 7" reel of tape with 7" take up reel and patch cord. For 110-120V, 60 cycle AC operation. RK-138WX Shpg. wt., 24 lbs. Net 79.95

STEREO PLAYBACK AMPLIFIER SPEAKER for RK-138




MADE IN U.S.A.

24⁵⁰
NO MONEY DOWN

The attractive speaker/amplifier is style matched and electronically balanced to provide a second stereo channel for the RK-138 Tape Recorder described. Contains 6-watt amplifier, 5" woofer and 4" tweeter. Supplied with 8 ft. hook up cable. Shpg. wt., 6 lbs. RK-139W Net 24.50

LAFAYETTE VALUE COMBINATION



BOTH THE RK-138 TAPE RECORDER AND THE RK-139 AMPLIFIER/SPEAKER COMPLETELY EQUIPPED WITH EVERYTHING YOU NEED FOR FULL TAPE RECORDER ENJOYMENT

WAS 124.45 **104⁴⁵**
SUMMER SPECIAL!

A complete portable tape recorder and stereo playback system which in addition to the regularly supplied equipment contains 3 7" reels of tape, 12 tape storage cans, storage chest plus tape splicer and roll of splicing tape. Shpg. wt., 32 lbs. RKS-16WX Net 104.45

Award-Winning TAPE RECORDER

Lafayette SCOOPS the TAPE RECORDER INDUSTRY

Music at Home at the Office



Never Before Such Exceptional Quality and Value!

Voice Recording parties - dancing




WAS 49.50
NOW! SENSATIONAL LOW PRICE!
44⁵⁰
NO MONEY DOWN

- Completely Portable—Carry it Anywhere!
- Two Speeds—3 3/4 or 7 1/2" Per Second
- Uses Standard 5" Reel
- Frequency Response 60-8,500 C.P.S.

Perfect for home, school or office. At home, the RK-400 proves ideal for parties or recording your favorite musical performance. Handy fool-proof operation has been provided by a single rugged function control (reverse, stop, play and record) and separate on/off volume control. Speeds are adjustable from 3 3/4" to 7 1/2" per second by a simple capstan adjustment. At 3 3/4" ips the RK-400 provides up to one hour of recording time on a standard 600 ft. 5" reel of tape. Special 5" heavy duty permanent magnet speaker furnishes an exceptionally fine tonal quality. Record level indicator light facilitates recording by showing you when volume control is correctly set. Jacks are provided for microphone, phono and extension speaker (special alligator clip cord is supplied). Complete with sensitive crystal microphone. Finished in attractive scuff resistant pyroxylin material. Dimensions: 11 1/4 x 9 1/4 x 7 1/8". For 110 volts 50-60 cycles. Shpg. wt., 20 lbs. RK-400WX Net 44.50

LAFAYETTE ACETATE BASE RECORDING TAPE. Features noise-free reproduction, low abrasion, uniform output. 1 1/2-mil thickness; 5" reel; 600-ft. Shpg. wt., 1/2 lb. RT-17 lots of 1-4, Net ea. .99 lots of 5-24, Net ea. .90 lots of 25 up, Net ea. .85

10 WATT PUSH PULL HI-FI AMPLIFIER KIT



KT-91 LAFAYETTE PUSH-PULL AMPLIFIER

- BUILT-IN PREAMPLIFIER
- SELECTOR SWITCHES PERMIT CHOICE OF THREE INPUTS
- SEPARATE BASS AND TREBLE CONTROLS
- 4, 8 & 16 OHM OUTPUTS
- EASY-TO-FOLLOW INSTRUCTIONS



LAFAYETTE SK-124 ULTRA-COMPLIANCE SPEAKER SYSTEM

TELEFUNKEN AUTOMATIC RECORD CHANGER

10-WATT HI-FI AMPLIFIER KIT
24⁵⁰
NO MONEY DOWN

This new, economy hi-fi amplifier has many deluxe features for exceptional performance. The three inputs are radio/crystal phono pickup, magnetic phono pickup and microphone. A selector switches the input from radio/crystal to microphone or magnetic pickup, depending upon the position of a rear apron slide switch. OUTPUT—Rated 10 watts, peak 18. FREQUENCY RESPONSE—± 1 db 30-15,000 cps. DISTORTION—1.5% harmonic, 4% intermodulation at 8 watts. 4 CONTROLS—Input Selector; Volume; Treble; Power-On-Off-Bass. TREBLE CONTROL—Flat response up to 18 db cut. BASS CONTROL—Flat response up to 15 db boost. OUTPUT IMPEDANCES—4, 8 and 16 ohms. TUBES—6SC7, 6SL7GT, 2-6V6GT and 5Y3GT rectifier. AUXILIARY AC OUTLET—Distinctive Hammertone finish. SIZE—10 1/2 x 6 1/4 x 5 1/4". WEIGHT—8 1/2 lbs. For 110-120 volts. Complete kit with coded wire, highest grade solder and detailed instruction manual. KT-91 Net 24.50

MONAURAL HI-FI PHONO SYSTEM KIT
Have FUN—SAVE MONEY by assembling this top-value system yourself! Features Lafayette KT-91 10-watt amplifier kit, famous Telefunken 4 speed automatic record changer with intermixing, jam proof operation, and automatic shut off feature, crystal turnover cartridge with dual sapphire styli for stereo and monaural records, and 45 rpm automatic spindle adapter plus amazing Lafayette SK-124 Ultra-Compliance 2 way speaker system in mahogany or walnut (specify finish). Tuner can be added at any time for radio program reception. Less changer base. Shpg. wt., 34 lbs.

| | |
|---|-----------|
| PK-600WX | Net 62.50 |
| PK-341W Mahogany base for changer | Net 3.95 |
| PK-342W Walnut base for changer | Net 4.50 |
| Unfinished mounting board cut for changer | Net .95 |
| PK-343W | Net .95 |

4 EXCITING NEW KORDEX™ TRANSISTOR TAPE RECORDER

In Economical Semi-Assembled Kit Form

ONLY **17⁹⁵**

ASSEMBLES
EASILY IN
LESS THAN
AN HOUR



**DUAL TRACK . . . Plays Twice
as long as Full Track**

- Extra Small • Fully portable — Battery Powered • A Mere 2½ lbs. in Weight • Pre-wired • 4 Transistor Printed Circuit Amplifier
- Accepts Standard 3" Tape Reel
- Instant-Action Play/Rewind Lever Control • Record, Rewind, Playback, Erase

INCLUDES: Crystal Lapel Microphone, 3" Reel of Tape, Empty Reel, Batteries, Screwdriver.

Here is a precision, full function miniature tape recorder in money saving semi-assembled kit form. In less than one hour the KorDEX Tape Recorder can be assembled and ready for operation. The amplifier is pre-wired in a rugged printed circuit, thereby eliminating most of the work. Complete it weighs only 2½ lbs. and slips easily into a briefcase or handbag. Designed for ease of operation, all controls are readily accessible. Fast, instant, Rewind-Off-Play functions are provided by a handy lever control. In addition the front panel also includes a Record-Play Slide Switch, Volume Control, plus Earphone and Microphone jacks. The powerful 4 transistor precision wired amplifier drives a specially designed built-in 2" PM speaker. With its attractive carrying case the KorDEX recorder is

equally suitable for home, office or travel—power is supplied by one standard "C" flashlight cell and one inexpensive 9 volt transistor battery. Complete with crystal lapel microphone, batteries, 3 inch, 100 ft. reel of tape, empty reel, earphone and instructions. Measures 8Wx6½Dx3"H. KT-212 Shpg. wt., 6 lbs. Net 17.95

RT-20 3" Reel 300 ft. ½ mil Mylar tape. Shpg. wt., 4 oz. Net .69

BA-2 9 volt transistor battery for above. Shpg. wt., 2 oz. Net .39

BA-156 1.5V Battery for above (1 req.). Shpg. wt., 2 oz. Net .13

NEW SONY MODEL 464-CS STEREO RECORDING and PLAYBACK TAPE SYSTEM



299⁵⁰

NO MONEY DOWN

- Complete Record/Playback Electronics
- Record/Playback 4-Track Stereo and Mono Tapes
- Sound-on-Sound Recording Facilities
- Built-in Monitor Speakers

Completely portable stereo recording and playback system utilizing the famous Sony belt-free idler wheel drive mechanism and dynamically balanced capstan-flywheel assembly for maintaining flutter and wow specifications to less than 0.2% @ 7½ ips. Other specs: freq. resp., 30-18,000 cps; bias freq., 80kc — RK-278WX

push-pull oscillator circuit; signal-to-noise ratio, better than 50 db. Features push-button channel selector switches and 2 high level line inputs for FM stereo recording. Supplied with 2 F-7 dynamic microphones. Net 299.50

WEBCOR MODEL ED 2250 REGENT CORONET STEREO TAPE DECK



Was **249.95**

189⁹⁵ NO MONEY DOWN

A new stereophonic, high fidelity tape deck for 2 and 4 track stereo recording plus monaural. Two built-in pre-amplifiers, one for each channel, with cathode follower output. Exclusive new Webcor "Synchro-Track" provides for simultaneous recording and playback. Three tape speeds: 7½, 3¾ and 1½ ips. Frequency response—Normal voice frequency at 1½ ips. ± 2 db, 50-7,000 cps at 3¾ ips. ± 3 db, 40-14,000 cps at 7½ ips. Wow and flutter 0.2% at 7½ ips. Signal-to-Noise Ratio greater than 50 db per channel. SPECIAL FEATURES: ¼ track stereo record; ½ and ¼ track stereo playback; 4 pole, heavy duty, electronically balanced motor; Belt driven tape transport, editing and cueing key; Record safety lock; Automatic shut-off of amplifier and recorder mechanism; VU meter to indicate correct recording level for each channel; individual volume controls; "Dual Gang" Bass and Treble controls. INPUTS: 2 microphone, high-level input jack. OUTPUT: External amplifier (2 channels). Will take 3, 5, or 7 inch reels of tape. Numerical type tape counter enables desired locations on tapes to be found quickly. Angled steel mounting brackets allow unit to be operated in vertical or horizontal positions. 6 tubes plus a dual selenium rectifier. For 117 volts. 60 cps AC. Size 7½x15Wx15"D. Shpg. wt., 26 lbs. RK-375WX Net 189.95

RK-374W Carrying Case for ED-2250 Net 32.50

NEW! LAFAYETTE Transistorized Professional MINIATURE TAPE RECORDER

- Two Speeds—3¾ & 1½ IPS
- Fully Transistorized—5 Transistors, 1 Thermistor
- Complete With New Dynamic Microphone
- Includes Carrying Case
- Portable—Only 4 lbs.
- Remote Control Mike Switch

Ideal for use everywhere (travel, sales meetings, club functions, parties, etc.)—self-contained with built-in speaker and amplifier. 5 transistors and 1 thermistor with precision printed circuitry and quality PM speaker you would expect from units three and four times this price. Single function lever operation for Rewind, Stop, Play and Record; special safety record button prevents accidental erasure. Built-in level meter shows battery condition and correct recording level. New rugged, sensitive dynamic microphone with desk stand. Convenient volume control adjustment plus jacks for earphones, radio and microphone are accessible from the front. Inputs at rear for AC power supply and remote control foot switch. Microphone equipped with remote control switch for starting and stopping recorder instantly, providing true one-hand operation. Sturdy metal case has snap-open top for easy tape loading and features a calibrated plexiglass insert for viewing tape motion and estimating playing time. Precision heads (1 erase 1 record/playback) are half-track—upper half is recorded first and tape is then turned over to record on lower half . . . records and plays up to 68 minutes at 1½ ips; 34 minutes at 3¾ ips. Powered by 6 inexpensive standard penlight cells (included). Supplied with dynamic microphone with remote control switch, crystal earphone, 3" reel of tape with 300 ft. of tape, empty reel and leather carrying case. Shpg. wt., 8 lbs. Net 69.95

COMPLETE RANGE OF ACCESSORIES

- AC ADAPTOR—Allows switching the RK-135 from battery operation to 115 v, 60 cycle AC. Has on/off switch plus pilot light. Shpg. wt., 2½ lbs. Imported Net 9.95
- RK-136 REMOTE CONTROL FOOT SWITCH—Starts and stops RK-135 instantly. Ideal for dictation. RK-122A Shpg. wt., 1½ lbs. Net 4.75
- TELEPHONE PICK-UP COIL—For recording telephone conversations. RK-121 Shpg. wt., 1 lb. Net 2.95
- PATCH CORD—Allows recording from radio, TV, phono, speaker. RK-124 Shpg. wt., ½ lb. Net .85
- 3" REEL 300 Ft. ½ Mil Mylar Tape. Shpg. wt., ½ lb. Net .69
- RT-20 BATTERIES—The RK-135 requires 6 standard "Z" cells. Shpg. wt., 4 oz. Net ea. .095
- BA-155



BOOK SIZE only 7¾"Wx5¼"H Dx2½"H

REMOTE CONTROL SWITCH

Reg. **79.95**

SALE PRICE

69⁹⁵ NO MONEY DOWN

LAFAYETTE MODEL RK-130

DELUXE DUAL SPEED TAPE RECORDER

- Two Speeds 3¾ and 7½ I.P.S.
- Plays Both 7" and 5" Reels
- Built-in Speaker and Amplifier
- Complete with Dynamic Microphone

PLAYS BOTH
7" and
5" REELS

SENSATIONAL
SUMMER
VALUE!!!

59⁸⁸

WAS
79.95

ACTUALLY BELOW OUR COST!

The perfect companion for language work, voice and instrument study, personal and family use, office work—a worthwhile investment for any classroom. This rugged tape recorder plays both 7" and 5" reels at speeds of 3¾ and 7½ inches per second. Consists of a double track, high frequency bias recording system with a frequency response range of 80 to 10,000 cycles, and a high frequency erase system. Internal amplifier provides 1.5 watts audio output to a built-in 4¾" speaker. An additional speaker may be plugged into the output jack. The RK-130 features simplicity of operation for quick stopping, playing, recording, fast forward winding or rewinding. Two input jacks are provided to permit simultaneous recording from a radio or record player and a microphone. Dynamic microphone is included with the unit. Both volume and tone are adjustable, and a neon tube recording level indicator is provided to facilitate correct settings. A switch allows the user to hear the playback either through the speaker or through a set of headphones (not supplied). A 7" tape reel played on both tracks will last for 120 minutes at 3¾ i.p.s., or for 60 minutes at 7½ i.p.s. A 5" reel will last 60 minutes at 3¾ i.p.s., or 30 minutes at 7½ i.p.s. Internal amplifier tube complement: 1—12A07, 1—6B8, 1—6AR5, plus 1—6X4 rectifier. For 117 VAC, 60 cps. Recorder dimensions: 16.4x12.4x8". Complete with 7" empty reel, dynamic microphone, patch cord, instructions, and large, removable strap. RK-130WX Shpg. wt., 28 lbs. Net 59.88

RT-10 7" reel with 1200 ft. of recording tape. Shpg. wt., 1 lb. Net 1.59



SONY MODEL 101 TRANSISTORIZED DUAL-TRACK TAPE RECORDER

97⁵⁰

NO MONEY DOWN

- 2-Speed 7½ & 3¾ ips
- Fast Forward & Rewind
- Lightweight

An AC powered bantam weight dual track tape recorder which incorporates the latest design in transistor circuitry. Ideal for those who require a low cost, high fidelity reproduction, the model 101 records and plays back monophonic 2-track tape with a frequency response of 50-12,000 cps at 7½ ips and 50-8,000 cps at 3¾ ips. Flutter & wow, less than 0.25% at 7½ ips. Imposing features include: a VU meter and volume control; inputs for mike and auxiliary units; external speaker output, tape lifters and built-in AC power supply. Plugs directly into wall outlet. Complete with 7" reel, dynamic mike, speaker and case. Size 12Wx10Dx 6½"H. RK-288WX Shpg. wt., 20 lbs. Net 97.50

SONY CS-300 STEREO RECORDER

391⁵⁰

NO MONEY DOWN

A complete 4 and 2 track stereophonic tape recording and playback system with built-in stereo preamplifiers and stereo playback monitors. Recording and playback also for 2 and 4 track monophonic tapes. Two speeds 7½ & 3¾ ips. Two built-in VU meters insure accurate playback and record levels for professional sounding tapes. Facilities for record-over-sound recordings. Low impedance outputs to match external pre-amp or power amplifier inputs. An instant Stop Lever insures precise editing and cueing. Specifications: Frequency response—30-18,000 cps at 7½ ips; 30-13,000 cps at 3¾ ips. Signal to Noise Ratio 50 db or more per channel. Flutter and Wow—less than 0.15% at 7½ ips, less than 0.25% at 3¾ ips. Harmonic distortion less than 2% at 3 db below rated output. Tubes: 2-12A07, 2-6AU6, 2-6AQ5, 1-12BH7, 1-6CA4. Size 17x14x8" high. For 117 volts 60 cps. AC. Includes carrying case with 2 built-in speakers and 2 F-7 dynamic microphones. Net 391.50

Model DK-300 Same as CS-300 but without carrying case, speakers, and microphones. Shpg. wt., 35 lbs. Net 342.51

Luxor MP-410A 4-Track Stereo Tape Recorder

- 40-20,000 C.P.S. at 7½ IPS
- Four Track Stereo & Monaural Record & Playback
- Two Track Stereo Playback
- 3 Speeds 7½ - 3¾ - 1½ IPS
- Completely Self Contained With Built-In Speakers and Amplifiers

279⁰⁰ No Money Down

A completely self contained stereo tape unit, the Luxor is equipped with its own built-in speakers and amplifiers for record/playback of both stereo and monaural two and four track tapes. In addition to use as a high performance portable, the Luxor is ideal for utilization with your component stereo system as a tape deck. Fast forward, fast reverse and play are controlled by a single, 3 position, positive shift lever. Separate gain controls for each channel on both playback and record. Additional features include: magic eye recording level indicators for each channel and digital tape counter. Frequency Response: 40-20,000 cps @ 7½ ips; 40-14,000 cps @ 3¾ ips; 80-8,000 cps @ 1½ ips; Flutter & Wow: ± .09% RMS @ 7½ ips; ± .18% RMS @ 3¾ ips; ± .25% RMS @ 1½ ips. Stereo Channel Separation better than 35 db. Supplied with patch cord to assure easy use with all U.S. made components. Size: 14½x11½xW 6½"H. Shpg. wt., 30 lbs. For 117 Volts, 60 cycle AC. RK-477WX Net 279.00



LAFAYETTE TOP QUALITY RECORDING TAPE

LAFAYETTE RECORDING TAPES

LAFAYETTE QUALITY IS BACKED BY OUR MONEY-BACK GUARANTEE



LAFAYETTE'S FAMOUS MONEY-BACK GUARANTEE

Lafayette's tape is made by outstanding nationally known manufacturers. It is first quality, splice free, red oxide coated, with full frequency response, uniform output and no "drop-outs". Resistant to moisture, heat, cold and abrasion. We guarantee absolute satisfaction or your money back. If you do not find it equal to tapes costing up to twice the price, for any reason you are dissatisfied, return the tape in 30 days and we will refund your money. You are the sole judge.

LAFAYETTE MYLAR BASE RECORDING TAPE

AS LOW AS **1.42** RT-19 900 ft. 25 & up

Mylar base is especially strong, durable and break resistant, and is virtually impervious to heat, cold or humidity. All in clear plastic reels, individually boxed.

| Stock No. | Feet | Reel | Mils | Wt. Lbs. | 1-4 | 5-24 | 25 Up |
|-----------|------|------|------|----------|------|------|-------|
| RT-19 | 900 | 5" | 1 | 3/4 | 1.75 | 1.58 | 1.42 |
| RT-12 | 1800 | 7" | 1 | 1 1/4 | 2.50 | 2.25 | 2.13 |
| RT-13 | 2400 | 7" | 1/2 | 1 1/4 | 3.69 | 3.39 | 3.22 |

Tensitized Mylar
Prestretched, super-strong mylar base.
RT-16 2400 7" 3/4 1 1/2 4.95 4.45 4.23

3" REEL 300-ft. 1/2 mil Mylar tape. AS **.63**
Shpg. wt., 1/2 lb.
RT-20 Net ea. 1-4, .69; 5-24, .63

Recording Tape on 3 1/4" Reel 600 Foot 1/2 Mil Mylar Base

1 HR. PLAYING TIME AT 3 3/4 IPS, TWO TRACK FITS ALL TAPE RECORDERS.

INCLUDING MINIATURE AND TRANSISTORIZED TYPES
3 1/4" reel, 600 ft., 1/2 mil Mylar tape. Individually boxed. Shpg. wt., 3/4 lb.

RT-21 Net. ea., 1.35; 5-24 ea., 1.21; 25 up ea., 1.10

CLEAR PLASTIC REELS

AS LOW AS **.23** IN LOTS OF 6

Individually boxed plastic reels for recording tape. Av. shpg. wt., 4 oz. singly.

MS-320 3 1/4" reel. In lots of 6, Ea., .23; Singly, Ea., .26

MS-692 5" reel. In lots of 6, Ea., .26; Singly, Ea., .29

MS-267 7" reel. In lots of 6, Ea., .38; Singly, Ea., .45

LAFAYETTE TAPE HEAD DEMAGNETIZER



Lafayette Tape Head Demagnetizer uses removable pole-pieces. Three complete sets are furnished: straight, 45° and 90° (right angle), permitting quick and easy use with any tape head. Far from being a luxury, a tape head demagnetizer is necessary for best tape recorder performance. Although unmagnetized when new, tape heads gradually become magnetized by sharp switching pulses occurring while switching the recorder from play to record or vice versa. The solution is to use a demagnetizer to remove this permanent magnetism from the head, thus reducing the noise level. Periodic head demagnetization is required for all tape recorders to insure optimum signal-to-noise ratio. Now Lafayette enables anyone with even the most modest budget to perform this necessary demagnetization with a minimum of effort. For 110 volts 60 cycles. Shpg. wt., 1 lb.
PK-23B Tape Head Demagnetizer 3.95

NEW!

NEW! STROB-LOOP RECORDER TEST TAPE

CHECKS: • SPEED • TIMING • WOW • FLUTTER

.98

Accurate within 1/10th of One Percent!

For 7.5 I.P.S. Shpg. wt., 6 oz.

MS-914 Net .98

YOU BE THE JUDGE! LAFAYETTE ACETATE BASE RECORDING TAPE

AS LOW AS **.85** RT-17 600 ft. 25 & up

Acetate base magnetic recording tape with uniform standard red oxide coating provides wide range high fidelity response over the audio spectrum. Features noise free reproduction, low abrasion and uniform output. In 1 mil and 1 1/2 mil thickness.

| Stock No. | Feet | Reel | Mils | Wt. Lbs. | 1-4 | 5-24 | 25 Up |
|-----------|------|------|-------|----------|------|------|-------|
| RT-17 | 600 | 5" | 1 1/2 | 1/2 | .99 | .90 | .85 |
| RT-18 | 900 | 5" | 1 | 3/4 | 1.35 | 1.20 | 1.08 |
| RT-10 | 1200 | 7" | 1 1/2 | 1 | 1.59 | 1.49 | 1.35 |
| RT-11 | 1800 | 7" | 1 | 1 1/4 | 1.98 | 1.88 | 1.79 |

LAFAYETTE MYLAR SPECIAL



THE RECORDING TAPE BUY OF THE YEAR—YOU BE THE JUDGE! 1200 FT. 1 1/2 MIL SPLICE-FREE LIFETIME MYLAR BASE RECORDING TAPE

AS LOW AS **1.25** RT-22 5 and up

Sensational buy by Lafayette brings you this 1 1/2 mil splice-free mylar base lifetime recording tape at an unbelievable low price. This 1 1/2 mil mylar tape features unprecedented recording tape strength as well as exceptional resistance to heat, cold, humidity and abrasion. 7" reel. Shpg. wt., 1 lb.

RT-22 Each Net 1.49

5 and up Each Net 1.25

METAL STORAGE CANS



Your best protection for valuable recorded tapes and movie film. Cans are ribbed for easy storage. Precision fit makes opening and closing easy. Attractively finished in grey. 3 sizes to choose from to fit any size reel. Av. shpg. wt., 8 ozs.


ML-154 3" Can. lots of 6, Ea. .18 Singly, Ea. .20

ML-155 5" Can. lots of 6, Ea. .27 Singly, Ea. .30

ML-61 7" Can. lots of 6, Ea. .36 Singly, Ea. .39

BUY 12 TWIST LOCK TAPE CANS

NEW! FOR ONLY **4.95**



AND GET STORAGE CHEST FREE!

12 dust-free, moisture-proof unbreakable styrene tape cans in storage chest. Can has foolproof twist lock feature and is ribbed for convenient stacking. Center locking stud prevents reel movement on all 7" reels and most 3" and 5" reels. Shpg. wt., 6 lbs.

ML-302 Net 4.95

TWIST LOCK CANS ONLY
ML-151 Lots of 6 ea. .45; Single ea. .49

LAFAYETTE BULK TAPE ERASER AND DEMAGNETIZER

PROFESSIONAL MODEL

- Erases 1/2" Tapes in One Operation—No Reversing
- For 3", 5", 7" or 10 1/2" Reels
- Completely Erases Tapes
- Two Erasing Coils
- Erases up to 1" Tape

1895



STANDARD MODEL

- Takes Reels Up To 10 1/2"
- Reduces Noise Level
- Top Value




1250

A carefully designed and precisely manufactured tape "degausser" for complete erasing of tapes. Just place the tape reel on spindle of demagnetizer, slowly rotate 2 or 3 turns, take off, and that's all. Reduce tape hiss to the level of new "virgin" tape. Two completely separate coils are used for doubly-effective erasures, even of large, 10 1/2" reels. Will erase 1" wide tape. An extra powerful unit for heavy-duty use—draws over 9 amperes. Can be used to demagnetize tape, magnetically stripped film, plus tools and watches. Has a heavy, custom finished case, a rugged non-magnetic top, heavy duty on-off switch and power cord. Has built-in fuse. Pilot light prevents accidentally leaving it turned on. Size 6 1/2 x 7 7/8 x 3 1/2". Shpg. wt., 14 lbs. Imported.

ML-120 Net 18.95

A bulk tape demagnetizer that erases existing recorded signals and noise from magnetic tapes quickly and efficiently. Also capable of demagnetizing metal parts and work tools. Ideal for the recording enthusiast desiring clean, noise-free tapes. Simply rotate reel of tape several turns over unit, turn over and repeat once. Has two spindle positions: inner position for tape reel sizes up to 7" in diameter, and the outer one for 10 1/2" reels. Push button energizes the coil, and a pilot light installed on top of the unit indicates unit in operation. Non-magnetic bakelite plate for tape reel rest. One powerful coil is used for effective erasure of all quarter-inch tapes. Current consumption—5 amps. Heavy duty, rugged gauge metal case. Attractive finish. For 105-125 volts, 60 cycles. Size 7 1/2 x 4 3/4 x 3 1/2". Shpg. wt., 9 lbs.

ML-176 Net 12.50



(A) ROBINS "GIBSON GIRL" SPLICER

Cuts 2 rounded indentations in the tape splice, leaving the edges of the tape which contact parts of the recorder entirely free of adhesive. Adhesive deposited on initial parts of recorder is a frequent cause of wow and flutter. As little as 1/4" tape need be removed. Shpg. wt., 1/2 lb.

MS-288 Net 6.25

MS-473 Replacement Blade .98



(B) EDITALL TAPE EDITING KIT

This kit has all the equipment required to execute a complete editing job on a professional basis. The cutting block supplied is simple to operate but is precise in its application; made of duraluminum precisely machined and polished (makes straight or diagonal cut). All accessories such as grease pencil, blades, splicing tape (66 ft. roll of 3/32") supplied. Comes with instruction booklet—in a smart metal case. Shpg. wt., 1 lb.

MS-474 EDITALL KIT Net 8.82

NEW! Lafayette RECORD, PLAYBACK and ERASE HEADS

3.95 per set

- Ideal for Experimenters
- Half-Track Recording Playback and Erase



A Lafayette special—ideal for the experimenter interested in tape recorders. Recording head has impedance of 9K ohm at 1,000 cps, DC resistance 130 ohms, reproduction level — 40, recording at — 10db. Bias frequency 30KC, bias 10MA. Frequency 60-12,000 cps ± 5db. SN ratio — 40db. Erasing head: DC resistance 10 ohms, erasing current 15-20 milliamp. AC bias, DC erase systems. Record head 7/8 x 3/4"; erase head 3/8 x 1/4". Shpg. wt., 8 oz.

F-687 Net 3.95

LAFAYETTE SPECIAL 3.95 per set

Size: 1/2 W x 3/4 D x 3/4 H.




RECORD PLAYBACK and ERASE HEADS for MINIATURE TRANSISTORIZED TAPE RECORDERS

A two-piece set consisting of one record/playback and one erase tape head. Designed for use in dual track miniature tape recorder. These units will replace the heads in most Japanese-built recorders, and are also excellent for the experimenter. Record/playback head specifications: impedance 2.2K at 1 KC; DC resistance: 160 ohms; reproduction level: — 45db (recording at — 10db); bias frequency: 35KC; bias current: 400ma; voice current: 100ma; response: 100-7000 cps ± 5db; S/N ratio: better than 45db; bias system: AC & DC reproduction: gap: .00024 in. (.006mm); dimensions: approx. 1/2 W x 3/4 D x 3/4 H. Erase head same dimensions. Total shpg. wt., 3 oz.

F-633 Net 3.95

MAGNETIC TAPE SPLICER



1.47

- Cut Both Ends Simultaneously
- Easy to Operate
- Durable & Sturdy

An excellent accessory that splices tapes accurately and eliminates joint noise. Both ends cut simultaneously. Nickel plated brass finish. Shpg. wt., 1 lb.

MS-289 Net 1.47

METAL TAPE STORAGE CHEST



STANDARD CASE: Sturdy all steel carrying case. Holds 12 7" or 5" reels and cans. Twin snap locks for positive closure; perfect portability. Guards against exposure and accidental erase. Platinum gray hammerloid finish. Metal separators between reels. Includes index cards. Shpg. wt., 5 lbs.

ML-60 Net 2.99


REEL LOCKS 59¢ Set of Two



Holds tape recorder reel in place by locking spindle to reel. Especially useful if recorder is in vertical position. Will not interfere with normal operation of reels. Easily removable. Shpg. wt., 6 oz.

MS-564 Set of two .59

TAPE CLEANER 1.49



Simple, unique recorder head cleaner. Tape is impregnated with special formula cleaner. Simply run through like regular roll of tape. Entire job done in 2 minutes. Can be reused many times. 100' roll on plastic reel. Shpg. wt., 8 oz.

PK-283 Net 1.49

RCA SPLICING TAPES

Pressure sensitive for editing and splicing. Shpg. wt., 3 oz.

| | | | |
|--------|------------|-------------|---------|
| RT-266 | Type 515C1 | 3/4" x 100" | Net .17 |
| RT-267 | Type 511C1 | 1/2" x 100" | Net .22 |
| RT-268 | Type 512C1 | 1/2" x 150" | Net .30 |
| RT-269 | Type 513C1 | 3/4" x 100" | Net .32 |
| RT-270 | Type 514C1 | 3/4" x 150" | Net .39 |

ADHESIVE REEL LABELS

Convenient press-on adhesive labels for positive identification of tape reels. Easy to apply or remove. Shpg. wt., 5 oz.

MS-292 Pkg. of 30 .13

ROBINS TAPE THREADER .79

No more awkward fumbling while threading a reel. Just place the tape against the reel, slip your Robins threader over the capstan shaft and over the empty reel. Tip of threader holds the tape firmly against the reel. A few turns on the crank and you're ready to play or record. Saves time and tape. Shpg. wt., 2 oz.

MS-222 .79



NEW TELEPHONE PICKUP COIL 1.89

This telephone pickup coil is designed to feed into the microphone input of either a tape recorder or any high gain amplifier. The pickup can be easily attached to the telephone by the use of a rubber suction type attachment. The coil is electrostatically shielded to minimize hum pickup. When properly positioned or telephone handset, the output of this device is more than adequate for a fully modulated tape recording. Complete with 5' shielded cable. Shpg. wt., 6 ozs.

MS-693 Net 1.89

1¢ SALE!

when you purchase any of these 5 changers

GARRARD • GLASER-STEERS • MIRACORD

PICKERING 380C DIAMOND STEREO CARTRIDGE, SHURE M7D DIAMOND STEREO CARTRIDGE, GE VR-1000-7 DIAMOND STEREO CARTRIDGE OR AUDIO EMPIRE S108 DIAMOND STEREO CARTRIDGE



NEW! GARRARD AUTOSLIM AUTOMATIC INTERMIX CHANGER • 4 Speed
Wired for Stereo and Monaural
3951

PLUS PICKERING, SHURE, GE OR AUDIO EMPIRE OR GE CARTRIDGE

An ultra-compact, automatic-manual changer at a remarkably low price. Only 6 1/4" overall height. Intermixes all records, i.e. records of different sizes can be stacked in any sequence. Separate manual and automatic controls—featuring Garrard's new center-changing mechanism. The Autoslim employs a new type of a turntable and a 4-pole shaded motor, achieving balance and quiet turning. Faun-colored unit plate with white trim. Dimensions: 14 1/2" left to right; 12 1/2" front to rear; 4 1/4" above top of motor board, 2 3/8" below. For 100-130 VAC, 60 cycles. Imported from England.

GR-168W Less Cartridge. Shpg. wt., 9 lbs. Net 39.50
Garrard "Autoslim" plus Pickering 380C Diamond Stereo Cartridge. PK-556W Shpg. wt., 9 lbs. Net 39.51
Garrard "Autoslim" plus Empire 108 Diamond Stereo Cartridge. PK-557W Shpg. wt., 9 lbs. Net 39.51
Garrard "Autoslim" plus Shure M7D Diamond Stereo Cartridge. PK-558W Shpg. wt., 9 lbs. Net 39.51
Garrard "Autoslim" plus GE VR1000-7 Diamond Stereo Cartridge. PK-559W Shpg. wt., 9 lbs. Net 39.51
PK-364W WOOD BASE, WALNUT. SHPG. WT., 5 lbs. Net 4.50



GARRARD AT-6 AUTOMATIC TURNTABLE
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
5451

Combines the convenience of a record changer with the performance of a Turntable. Tubular Tone arm dynamically counter-balanced with adjustable counterweight has built-in gram scale. 4-pole shaded motor. Separate automatic and manual controls. 2 spindles with short spindle for playing records singly. Replaceable plug-in cartridge shell. Rich faun color metal unit plate — Size: 14 1/2" left to right. 12 1/2" front to rear, 1 1/2" above and 2 3/8" below top of motor board. Additional 1 1/2" required at rear of arm and on right side for counterweight clearance. For 100-130 VAC 60 CPS. Shpg. wt., 12 lbs. Imported from England.

GR-167W Net 54.50
Garrard AT-6 plus Pickering 380C Diamond Stereo Cartridge. PK-552W Shpg. wt., 12 lbs. Net 54.51
Garrard AT-6 plus Empire 108 Diamond Stereo Cartridge. PK-553W Shpg. wt., 12 lbs. Net 54.51
Garrard AT-6 Plus Shure M7D Diamond Stereo Cartridge. PK-554 Shpg. wt., 12 lbs. Net 54.51
Garrard AT-6 Plus GE VR-1000-7 Diamond Stereo Cartridge. PK-555W Shpg. wt., 12 lbs. Net 54.51
PK-364W Wood Base, Walnut. Shpg. wt., 5 lbs. Net 4.50

SAVE 40% Special

BUY THESE FAMOUS CHANGERS EQUIPPED WITH THE SHURE M3D HIGH FIDELITY MAGNETIC DIAMOND CARTRIDGE AT A SAVING OF 40.00 OVER THE INDIVIDUAL PRICES.

| | |
|--|--------------------|
| GARRARD MODEL "A" CHANGER ONLY | 79.50 |
| SHURE M3D CARTRIDGE | 44.10 |
| SHPG. WT., 19 lbs. | TOTAL PRICE 123.60 |
| STOCK NO. PK-628WX COMBINATION SPECIAL | 83.60 |
| GARRARD MODEL "AT-6" CHANGER ONLY | 54.50 |
| SHURE M3D CARTRIDGE | 44.10 |
| SHPG. WT., 12 lbs. | TOTAL PRICE 98.60 |
| STOCK NO. PK-629W COMBINATION SPECIAL | 58.60 |
| GLASER STEERS MODEL G7-77 CHANGER ONLY | 59.50 |
| SHURE M3D CARTRIDGE | 44.10 |
| SHPG. WT., 13 lbs. | TOTAL PRICE 103.60 |
| STOCK NO. PK-631W COMBINATION SPECIAL | 63.60 |
| MIRACORD "STUDIO" AUTOMATIC TURNTABLE ONLY | 79.95 |
| SHURE M3D CARTRIDGE | 44.10 |
| SHPG. WT., 12 lbs. | TOTAL PRICE 124.05 |
| STOCK NO. PK-632WX COMBINATION SPECIAL | 84.05 |



GARRARD MODEL "A" AUTOMATIC TURNTABLE
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
ONLY 7951

The Garrard Model "A" is a precision turntable and tone arm with the convenience of automatic record changing. Plays all 4 speeds and is wired for stereo and monaural use. Features a built-in stylus pressure gauge. Complete with line cord, pick-up leads, plug-in shell, mounting hardware, standard and manual spindles, 45 RPM adaptor.

GR-166WX Garrard Model "A" Shpg. wt., 19 lbs. Net 79.50
Garrard Model "A" plus Pickering 380C Diamond Stereo Cartridge. PK-523WX Shpg. wt., 19 lbs. Net 79.51
Garrard Model "A" plus Shure M7D Diamond Stereo Cartridge. PK-524WX Shpg. wt., 19 lbs. Net 79.51
Garrard Model "A" plus GE VR1000-7 Diamond Stereo Cartridge. PK-551WX Shpg. wt., 19 lbs. Net 79.51
GARRARD Model "A" plus Audio Empire S108 Diamond Stereo Cartridge. PK-548WX Shpg. wt., 19 lbs. Net 79.51
PK-358W WOOD BASE, WALNUT. SHPG. WT., 5 lbs. Net 4.50



GLASER-STEERS GS-77 RECORD CHANGER
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
ONLY 5951

Fully automatic, 4-speed stereo record changer. Transcription-type tone arm; inaudible wow, rumble and flutter. 4 pole motor. Shpg. wt., 13 lbs.

GR-50W Changer only, less base, cart. Net 59.50
GS-77 PLUS PICKERING 380C Diamond Stereo Cartridge, less base. PK-540W Shpg. wt., 13 lbs. Net 59.51
GS-77 PLUS Shure M7D Diamond Stereo Cartridge, less base. PK-541W Shpg. wt., 13 lbs. Net 59.51
GS-77 PLUS GE VR1000-7 Diamond Stereo Cartridge, less base. PK-564W Shpg. wt., 13 lbs. Net 59.51
GS-77 plus Audio Empire S108 Diamond Stereo Cartridge. PK-550W Shpg. wt., 13 lbs. Net 59.51
Wood base for changer. Ebony with gold trim. Shpg. wt., 5 lbs. Net 9.60
PK-350W Net 2.95
PK-352 Automatic 45 RPM Spindle. Shpg. wt., 1 1/2 lbs. Net 2.95



MIRACORD "STUDIO" MODEL AUTOMATIC TURNTABLE
Plus PICKERING, SHURE, GE OR AUDIO EMPIRE CARTRIDGE
8996

Pushbuttons select automatic or manual operation at any of 4 speeds. Specially designed, heavy-duty, 4-pole induction motor. Jam-proof, counter-balance tone arm; famous "Magic Wand" spindle.

GR-351WX Less Base and Cartridge Shpg. wt., 20 lbs. Net 89.95
Miracord "Studio" PLUS Pickering 380C Diamond Stereo Cartridge. PK-574WX Net 89.96
Miracord "Studio" PLUS Audio Empire S108 Diamond Stereo Cartridge. PK-573WX Net 89.96
Miracord "Studio" PLUS Shure M7D Diamond Stereo Cartridge. PK-575WX Net 89.96
Miracord "Studio" PLUS GE VR-1000-7 Diamond Stereo Cartridge. PK-576WX Net 89.96
GR-352W Oil Walnut Wood Base Net 9.95
GR-354W Automatic 45 RPM Spindle Net 5.00

PICKERING 380C stereo cartridge with .7 mil diamond stylus with exclusive "V-Guard." Shpg. wt., 5 oz. GD-214L Net 29.85

SHURE M7D moving magnet stereo cartridge with .7 mil diamond stylus. Shpg. wt., 5 oz. GD-273L Net 23.52

GE VR1000-7 magnetic, variable reluctance cartridge with .7 mil diamond stylus. Shpg. wt., 6 oz. GD-144L Net 24.45

AUDIO EMPIRE S108 stereo cartridge with .7 mil diamond stylus. Shpg. wt., 7 oz. GD-315L Net 35.00

NEW! LAFAYETTE AUTOMATIC 4 SPEED RECORD CHANGER

ONLY 2235 NO MONEY

RONETTE CERAMIC CARTRIDGE LESS BASE

• Plays Stereo, LP and 78 RPM
• Quality Ronette Ceramic Cartridge • Automatic 3-Way Shut-Off
• Intermixes Records of Same Speed • Heavy Duty-Constant Speed Motor

Feature for Feature, the Lafayette Automatic record changer matches or exceeds costlier units. Built for compatibility with both stereophonic and monaural records, this changer offers superior performance for budget-sparing music systems. The balanced featherweight tone arm operates at only 5-7 grams of needle pressure to minimize record wear. Flip-type, Ronette ceramic stereo cartridge is unaffected by heat and humidity. Heavy precision-balanced turntable and constant speed motor insure smooth rotation without hum rumble or "wow". Plays all 4 record speeds—automatically changes up to fourteen 7", twelve 10" or 12" records. Intermixes 10" and 12" records of same speed. Plays records manually if desired, 45 r.p.m. spindle optional. Automatic 3-way shut-off after last record (returns tone arm to rest, stops turntable motor, turns set off.) neutral position disengages turntable drive wheel when not in use—prevents rumble producing flat spots. 117 volts AC, 60 cycles. Compact and exceptionally functional, only 13 1/2 x 12 x 7 1/2". 3" below and 5 1/2" above mounting board. Beautiful brown and gold finish. Shpg. wt., 12 lbs.

PK-605W No Money Down Net 22.35
PK-606W Walnut Base Net 4.50
PK-607W Mahogany Base Net 3.95
PK-608W Mounting Board Net 1.10
PK-609 45 R.P.M. Spindle Net 1.49

LAFAYETTE PANASONIC

TURNTABLE WILL TRACK AT ANGLES IN EXCESS OF 45°

SALE PRICE 1995 1962 CATALOG PRICE 32.50

• Distortion Free From 20-16,000 cps • Flat Frequency Response 20-15,000 cps • Feather Light Stylus Pressure—Individually Adjusted For 3-Grams • Hum Free—Entire Arm & Cartridge Case Shielded with Mu Metal

Tone arm resonance is minimized by use of specially designed counter weight, sub weight and lateral damping mechanism. The arm counter balance is floated on a damped suspension bar. Precision bearings assure minimum lateral and vertical friction. Overall height of arm adjusts from 1 1/2" to 2 1/4". Signal to noise level of well over 100 db. Stylus replacement requires only a few seconds, pull out the old stylus and plug in the new. The diamond stylus is capable of supplying up to 2,000 hours of playing time. With .7 mil diamond stylus, mounting instructions, stylus cleaning brush, all hardware. Shpg. wt., 3 lbs. PK-448 Net 19.95
Complete .7 Mil Diamond Stylus Assembly for PK-448 Lafayette Panasonic Tone Arm. Shpg. wt., 1/4 lb. PK-452 Net 7.95

TECHNICAL INFORMATION
Output Voltage . . . 5 millivolts • Channel Separation . . . More than 25 db • S/N Level . . . Over 100 db • Compliance . . . 5x10—6 cm/dyne
• Suggested Load Impedance . . . 50,000 ohms • D. C. Resistance . . . 420 ohms • Tracking Force . . . 3 grams • Stylus . . . 7 mil • Frequency Response . . . Distortion free: 20-16,000 cps Flat. ± 2 db 20-15,000 cps • Overall Length . . . 11 1/4"

Lafayette TRADE 'N SAVE SALE!

Trade-In Your Old Phono Cartridge & Save 4995

united Audio the TOP RATED DUAL 1006 STEREO TURNTABLE/CHANGER with the STEREO CARTRIDGE of your choice

ORDER TODAY—LAFAYETTE WILL SHIP YOUR DUAL 1006 and CARTRIDGE IMMEDIATELY SEND US YOUR TRADE-IN CARTRIDGE LATER

| | | |
|--------------------------------|--------------------------------|--------------------------------|
| PICKERING 380C | SHURE M7D | EMPIRE S-108 |
| Reg Cat Price 29.85 GD-214L | Reg Cat Price 23.52 GD-273L | Reg Cat Price 35.00 GD-315L |

LAFAYETTE'S LOW-LOW TRADE-IN PRICE IS ONLY 65.00
No Money Down

bottom record on the spindle from rest of stack assuring protection of record grooves and centers. Intermix mechanism handles up to 10 records. Complete with 2 cartridge holders, single play spindle, changer spindle and 45 adaptor disc. For 110/120V 60 cycle AC. Chassis 10 3/4 x 13 1" requires 3" clearance below 6" above. Shpg. wt., 20 lbs. Address your orders and cartridge trade-ins to Trade-In Department.

PK-611WX Dual 1006 with Pickering 380C Net 65.00
PK-612WX Dual 1006 with Shure M7D Net 65.00
PK-613WX Dual 1006 with Audio Empire S-108 Net 65.00
Wooden Base for dual 1006. Specify Mahogany or Walnut GR-188W Net 6.95
Dual AS-4 Automatic 45 RPM Record Changer Spindle PK-392 Net 4.80
Dual 1006 Changer without Trade-In & Less Cartridge GR-186WX Net 79.95

Here's one of the top buys LAFAYETTE has ever offered! Send LAFAYETTE your old phono cartridge (regardless of make or condition) and purchase the top-rated Dual stereo record changer with your choice of any one of the famous diamond-needle stereo cartridges shown here, AT AN UNPRECEDENTED TRADE-IN SAVING.

Combining the flexibility of a changer with performance of a transcription turntable, the Dual 1006 features a completely free-floating tone-arm with built-in stylus pressure gauge plus a 3 1/2 lb. turntable, laminated and girded for rigidity. Powerful motor reaches full speed under load in 1/2 sec. "Rigid equiptose" motor suspension, 4-speed control system with separate drive gears for each speed prevents flat-spot thumping. Simplified push button controls. Stereo-Mono switch removes vertical noise often picked up while playing monaural records. "Elevator action" isolates

169

LAFAYETTE DIAMOND NEEDLES

MADE FOR LAFAYETTE BY THE FOREMOST AMERICAN MANUFACTURERS

169

ALL DIAMOND STYLI ARE NOT ALIKE
 • MADE FROM WHOLE DIAMONDS • PRECISION
 GROUND AND POLISHED • VERTICALLY AND EDGE-
 WISE GRAIN ORIENTED • SHADOWGRAPHED



Each Lafayette's diamond stylus is made from individual diamonds, properly oriented and ground to close tolerance; shadowgraph tested to give you less wear per play and long service life.

The synthetic sapphire used in these styli are of the same fine quality used in precision watch bearings.

FULL 1 YEAR REPLACEMENT GUARANTEE AGAINST DEFECTS IN WORKMANSHIP AND MATERIAL ON ALL DIAMOND STYLI

169

ANY DIAMOND or DIAMOND-SAPPHIRE NEEDLE IN THIS LISTING

KEY TO POINT CODES HOW TO ORDER


The symbols in the column headed "PT SIZE" are explained in the table below.

LP = SINGLE 1 MIL MICROGROOVE FOR 33 1/3 AND 45 RPM

COMB = DUAL 1 MIL DIAMOND AND 3 MIL SAPPHIRE


Identify your needle by cartridge number and illustration and order by stock no. Note that all needles listed here are for monaural cartridges.

STEREO DIAMOND 169 NEEDLES



Stylus Stock No. Fig. For Cartridges

- PS-80L G ACOS 73
- PS-80L G .7 mil diamond and 3 mil sapphire styli No. 73-1
- ADMIRAL CARTRIDGES**
- PS-80L C 409B3-1-1(2-1)
- PS-81L B 409C37-1
- ASTATIC CARTRIDGES**
- PS-92L N 17, 17D
- PS-86L 70TS, 74TS, 76TS
- COLUMBIA CARTRIDGES**
- PS-84L J SC-1-2-7-8
- ELECTROVIBRO CARTRIDGES**
- PS-80L C 21 and 26 Series
- EUPHONICS CARTRIDGES**
- PS-93L K E-1-3
- GENERAL ELECTRIC CARTRIDGES**
- PS-87L A GC7
- PS-89L A VR227
- MAGNAVOX CARTRIDGES**
- PS-80L C 560233-3-4
- PS-94L D 560260-1



DIAMOND NEEDLES

| Stock No. | Size Pt. | Fig. | Cartridge | REPLACES JENSEN NO. | Stock No. | Size Pt. | Fig. | Cartridge | REPLACES JENSEN NO. | Stock No. | Size Pt. | Fig. | Cartridge | REPLACES JENSEN NO. | | | | | | | | | | |
|--------------------------------|----------|------|--|---------------------|---------------------------------------|----------|------|----------------------------|---------------------|------------------------------|----------|------|--|---------------------|--|--|--|--|--|--|--|--|--|--|
| FOR ADMIRAL CARTRIDGES | | | | | | | | | | | | | | | | | | | | | | | | |
| PS-10L | LP | 1 | 409A11, 409A300, 98A54-1 | JPS-30LPD | PS-35L | LP | 54 | 560176, 560180 | CRA-55LPD | PS-35L | LP | 53 | TO-200, TO-222, TO-284, or TO-400 series, RA284, 54 (DT60 series). | CRA-55LPD | | | | | | | | | | |
| PS-16L | COMB | 6 | 409B21 | JPS-35SD | PS-70L | COMB | 51 | 560161 | S-66SD | PS-69L | LP | 38 | TX88, A | CRA-56LPD | | | | | | | | | | |
| PS-17L | LP | 7 | 409A30 | A81LPO | FOR PHILCO CARTRIDGES | | | | | | | | | | | | | | | | | | | |
| FOR ASTATIC CARTRIDGES | | | | | | | | | | | | | | | | | | | | | | | | |
| PS-20L | LP | 3 | AC Series, 40T, 41T, 40-1, 41-1, 42-1, 90T series, 10-L-3, 11L-3 | A-75LPD | PS-56L | COMB | 43 | 45-9612, 76-4649, 425-0016 | PH-13SD | PS-56L | COMB | 43 | 45-0009, 425-0011, 425-0014 | PH-13SD | | | | | | | | | | |
| PS-23L | LP | 12 | 408 | M-70LPD | FOR PERPETUUM EBNER CARTRIDGES | | | | | | | | | | | | | | | | | | | |
| PS-25L | COMB | 14 | GCD, 409, 55-T, 55TJ, 55TM | A-71SD | PS-64L | COMB | 47 | P12/RG | RX550SD | PS-65L | COMB | 48 | PE-8, PE10 | RX551SD | | | | | | | | | | |
| PS-23L | LP | 12 | 410 | M-70LPD | PS-66L | LP | 22 | P7000 (MJ, MD) (LP only) | RX552LPD | FOR R.C.A. CARTRIDGES | | | | | | | | | | | | | | |
| PS-17L | LP | 7 | CAC, CQ, CQ-1, LQD, LQD-1, QT, QT-33, 44-T, 46-1, 48-1, 166T Series | A-81LPD | PS-23L | LP | 12 | 74067 | M-70LPD | PS-10L | LP | 1 | S5652, 76257, (988370-1), 75044 | JPS-30LPD | | | | | | | | | | |
| PS-35L | LP | 54 | 118, 120, 124 series, 310T, 312T, 420, 422, 424TS series, 310-1, 310-TB, TS, 312-TB, TS, 414-1 | CRA-55LPD | PS-20L | LP | 3 | 76257, (988370-2) | A-75LPD | PS-70L | COMB | 51 | 78748, 79807, 100653 | S-66SD | | | | | | | | | | |
| FOR MAGNAVOX CARTRIDGES | | | | | | | | | | | | | | | | | | | | | | | | |
| PS-51L | COMB | 37 | 560176, 560180, 560133, 560151, 560169-1, 560170 | M-50SD | PS-25L | COMB | 14 | 100329 | A-71SD | PS-32L | COMB | 51 | 3T, 3TS, 3TO | S-61SD | | | | | | | | | | |

REPLACEMENT STYLI FOR GE CARTRIDGES

FOR GE VR II CARTRIDGES (FIG. 35)
 Direct replacements for clip-in styli in GE VR II series models 4G-050, 4G-052, 4G-053, 4G-040, 4G-041, 4G-063, 4G-061 cartridges. Avg. shpg. wt., 2 oz.
 PS-48L 1 mil diamond LP clip-in stylus. Replaces GE 4G-010 Net 1.69
 PS-546 1 mil sapphire LP clip-in stylus. Replaces GE 4G-01S Net .69
 PS-548 3 mil sapphire 78 clip-in stylus. Replaces GE 4G-03S Net .69

MODERNIZATION ASSEMBLIES (FIG. 33)
 Modernize your old triple-play cartridge. These assemblies replace both the old and new series "A." Once installed, you can replace one point at a time.
 DIAMOND SAPPHIRE. Replaces old RPJ-013 and new RPJ-013A. Avg. wt., 2 oz. Net 1.69
 DUAL DIAMOND. Replaces old GE RPJ-012 and new RPJ-012A. Net 3.90
 DUAL SAPPHIRE. Replaces old GE RPJ-010 and new RPJ-010A. Net .99

STYLI FOR OLD TYPE GE CARTRIDGES (FIG. 32)

Exact replacement for all old type single needle GE cartridges. Avg. wt., 2 oz.
 PS-45L Diamond 1 mil (LP) replaces GE RPJ-004 Net 1.69
 PS-541 Sapphire 1 mil (LP) replaces GE RPJ-005 Net .69
 PS-540 Sapphire 3 mil (78) replaces GE RPJ-001 Net .69

FOR GE SERIES A CARTRIDGES (FIG. 34)

Individual styli replacements that clip in to all GE "A" series. Avg. wt., 2 oz.
 PS-47L Diamond 1 mil (LP) replaces GE RPJ-010 Net 1.69
 PS-543 Sapphire 1 mil (LP) replaces GE RPJ-01S Net .69
 PS-542 Sapphire 3 mil (78) replaces GE RPJ-03S Net .69

DIAMOND STYLI FOR G.E. AS LOW AS 169

LAFAYETTE HI FI STEREO-MONAUURAL TEST RECORD

• TESTS RUMBLE EACH CHANNEL • TESTS LEVEL EACH CHANNEL
 • TESTS RESONANCE • TESTS EQUALIZATION • STYLUS WEAR TEST
 • TESTS BALANCE • INCORPORATES PHASE CHECK

For stereo testing this two-sided 12" L.P. stereo record has on its stereo side two 1000 cycle bands to check the level of each channel separately; balance check to set the level of each channel using special metronome recording; rumble test. There are stylus wear test grooves on both outer and inner edges of each side to check both stereo and monaural styli. Incorporates phase adjusting check to simplify phasing of speakers. For monaural testing it provides an RIAA equalization test in 9 steps from 30 to 15,000 cycles, a continuous glide band from 10 to 35,000 cycles, to test for resonances of tone arm or of cabinet. Also features sections of stereo sound effects of jet planes, boat whistles, etc. A terrific value and a "must" for the Hi-Fi enthusiast. Comes with complete instructions for use. Shpg. wt., 1 lb. Net 2.95



4 SPEED PHONO MOTOR WITH TURNTABLE

Quiet, dependable A-C operation assured by rubber shock-mounted friction drive motor. Speed change control through idler driving an 8" turntable. Mounting centers 4 1/2 x 3 3/4"; 2 1/4" depth below base plate. Shpg. wt., 3 1/2 lbs. Net 5.35
 ML-24 Phono and turntable Net 5.35
 PK-149 Mounting board for motor Net .95



STATI-CLEAN .88

Sprays a fine mist which keeps your record clear of surface noise created by static (common to all vinyl records) and clean of dust attracted by the static charge. Prevents groove and needle wear caused by static-dust and keeps records lustrous. Extends their life. Two applications a year is sufficient. Enough for hundreds of records. Shpg. wt., 8 oz. Net .88




LAFAYETTE RECORD CLEANING KIT EXCELLENT VALUE! 1.29

Clean your valuable records the professional way with this Lafayette Kit. Contains a non-gumming anti-static detergent in polyethylene bottle. Squeeze to apply for complete elimination of static in the record grooves. Supplied with special velvet applicator in plastic pouch. Shpg. wt., 10 oz. Net 1.29



PHONO AMPLIFIERS



THREE TUBE AC-DC PHONO AMPLIFIER

(Fig. A) Equipped with a variable tone control and a separate volume control. Delivers two watts output. Phonograph motor connects to the amplifier. Uses 12AV6, 50C5, and 35W4 rectifier. For 110-120V, 60 cycles AC or 110-120V DC. Supplied with line cord and plug, but less tubes. Shpg. wt., 2 lbs. Net 2.95

2 TUBE AMPLIFIER WITH TUBES

(Fig. B) A two tube phono amplifier using a 50L6 and 35Z5 tube as rectifier. Well-built, good tone and volume. Contains volume control with switch. AT A BIG SAVING! Shpg. wt., 3 lbs. Net 4.50

(Fig. C) Output transformer matches output tube to 3-4 ohm voice coil. Shpg. wt., 1/2 lb. ea. .49

TR-10 Singly In lots of 5, ea. .45


SPECIAL! 1.95 TONE ARM CONTROL

An absolutely essential addition for every Hi-Fi enthusiast. Ends groove and stylus damage caused by accidental dropping of tone arm onto record, greatly extending record life. Accurately and smoothly lowers tone arm into run-in groove and lifts arm off record at end of play. Ideal for "cueing." Designed to fit practically every known turntable arm as well as record changer with manual features. Supplied with adhesive mounting base to keep unit in position and with both wood and metal mounting screws for permanent installation. Shpg. wt., 6 oz. Net 1.95




ELECTROSONIC LAB "DUST BUG"

Automatically removes dirt and dust on each playing. Light plastic arm mounts by suction cup. Can be permanently mounted by rubber cement. The bottle of anti-static cleaning fluid has a built-in wick for application to a brush and pad at the end of arm. Shpg. wt., 6 oz. Net 5.63
 ESL CHANGER DUST BUG (B). The tuft and pad assembly clips onto arm of changer. Performs the same as the standard model. Shpg. wt., 4 oz. Net 4.65
 PK-246 Changer model (B) Net 1.22
 DISPENSER OF ACTIVATING FLUID. For Dust Bugs. PK-247 Net .78
 PK-173 Replacement plush pad .78
 PK-174 Replacement nylon brush .98



MODERN RECORD RACK 1.79

Attractive, brass plated rack carries 60 records of all sizes. Spring steel separators numbered 1 to 60. Heavy carrying handle. Rubber tipped feet. Size 17Lx 5 3/4x7" D. Shpg. wt., 4 lbs. Net 1.79



NEW! .7 MIL DIAMOND STYLUS FOR SHURE M7D STEREO CARTRIDGE

PS-91L Net 4.50




4-SPEED HI-FI TURNOVER PICK-UP 2.75


• ARM TAKES STEREO OR MONAUURAL CARTRIDGES
 • WITH WIDE RANGE MONAUURAL CARTRIDGE • ADJUSTABLE ARM HEIGHT AND STYLUS PRESSURE

Arm is wired for stereo, for future conversion. Has a wide range turnover monaural crystal cartridge with dual sapphire styli. Output is 1 1/2 V. Easy height adjustment at base, 1 1/4" to 1 3/4". Also stylus pressure adjustment. Plastic arm 9 1/2" long overall. Base 1 3/4" with mounting holes on 1 3/4" centers. Shielded leads. Satin smooth light maroon finish.

PK-146 Shpg. wt., 2 lbs. Net 2.75
 PK-158 Sapphire LP replacement Needle Net .49
 PK-159 Sapphire STD replacement Needle Net .49



LAFAYETTE 50-WATT STEREO AMPLIFIER MODEL LA-250A



99⁵⁰
NO MONEY DOWN

MADE IN U.S.A.

... Impressive Performance
... Handsome Styling
... Another Unbeatable Lafayette VALUE!

"Let Your Own Ears be the Judge"

ENGINEERED FOR SUPREMACY

ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE
All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

CLUTCH-TYPE VOLUME-BALANCE CONTROL—Provides precise effective means of controlling volume and balancing stereo channels.



DUAL PREAMPLIFIER SECTION—Inputs have been provided for every stereo-monaural function.



- 50 WATTS MONAURAL — 25 WATTS EACH STEREO CHANNEL
- RESPONSE 15-40,000 CPS ± .5 DB (at normal listening level)
- UNIQUE "BLEND" CONTROL
- PREMIUM EL86 OUTPUT TUBES
- SEPARATE BASS & TREBLE CONTROLS
- CLUTCH-TYPE VOLUME-BALANCE CONTROL
- 3rd CHANNEL OUTPUT

brehtaking performance at a price only LAFAYETTE can offer.

The Stereo 250A... a completely new stereo high fidelity amplifier with a high quality of reproduction, remarkable versatility and new distinctive styling—worthy of a place in the finest stereo hi-fi music system. A full range of controls enables you to enjoy the utmost in listening pleasure in any situation. A unique "blend" control which provides continuously variable channel separation—from full monaural to full stereo—may be used to eliminate the exaggerated channel separation found in some stereo source material. Included is a clutch-type Volume Balance control for independent or simultaneous control of both channels, concentric Bass and Treble controls which provide independent tonal control of each channel and a 4-position switch which selects phono, tuner, auxiliary or tape head stereo inputs. Simple slide switches provide channel reversal and phase reversal—or you can reproduce either channel through both amplifiers. A loudness switch permits the volume balance control to function as a compensated loudness control. The LA-250A also features a 3rd channel output which may be used to feed a 3rd single channel amplifier and speaker to provide a wider sound spread, a Tape Output jack for recording purposes, plus dual terminations for 4, 8 or 16 ohm speakers. Advanced circuitry includes DC operated preamp and tone control tube filaments for hum-free operation, 6CW5/EL86 push-pull output tubes, individual bias and balance adjustments on each channel and a hum balance control.

SPECIFICATIONS:
POWER OUTPUT & DISTORTION: 50 watts—25 per channel ± 1 db at less than 1% Total Harmonic Distortion at 1 KC. Less than 0.25% Total Harmonic Distortion at 1 KC at normal listening level (1 watt); less than 0.5% 1M distortion at normal listening level. FREQUENCY RESPONSE: 15-40,000 cps ± 0.5 db at normal listening level. HUM & NOISE: 70 db below rated output at max. volume (high level inputs). SENSITIVITY: For full output high level inputs 0.5V; Mag. Phono 3.5 MV at 1 KC. CHANNEL SEPARATION: Greater than 55 db at 1 KC; greater than 45 db from 20-20,000 cps. IMPEDANCE: 4, 8 and 16 ohms per channel. POWER: 200 watts; 110-125V AC 50-60 cycles.
Attractive beige vinyl laminated steel case. Handsomely designed three color etched front panel. Sienna brown molded legs and matching knobs with polished brass inserts. Dimensions with legs and knobs, 14½Wx12¼Dx5½"H. Shpg. wt., 28 lbs. LA-250AWX Net 99.50

NATIONALLY ADVERTISED FAMOUS BRAND STEREO MULTIPLEX ADAPTOR

2888



NO MONEY DOWN

This adaptor is designed to operate in conjunction with FM tuners to provide two stereophonic audio channels. Completely self-contained and self-powered, the only required connections are those to the separate inputs of the stereo tuner. Frequency response: ± 3db 50 to 15,000 cycles. Hum and noise down 60 db. Mounting base is 10Lx2¼"W, with mounting holes spaced 2¼". G-336 Shpg. wt., 3 lbs. Net 28.88

SHERWOOD S-3000 IV FM MULTIPLEX TUNER

160⁰⁰



NO MONEY DOWN

The front end of this tuner boasts high sensitivity and wideband selectivity. IF amplifiers, limiters, and discriminator have controlled frequency and phase response—essentially flat to 75Kc. The 19 Kc pilot carrier and 67Kc secondary sub-channel transmissions are filtered out by razor sharp networks. Also featured are FM interchannel hush; smooth, balanced fly-wheel tuning knob; "acro-beam" tuning eye and a 7" expanded FM dial scale. Response 20-15,000 cps ± 0.5 db. OTHER SPECIFICATIONS: Typical sensitivity 0.95 μV @ 20 db quieting; IHFM sensitivity 1.8 μV; selectivity 225 Kc @ -3db; FM discriminator 850 Kc peak to peak. Size: 4x14x10½". For operation from 110-120V, 50-60 cycle AC. Shpg. wt., 15 lbs. G-303WX Less Enclosure Net 160.00 G-289W Brown Flextone Cases Shpg. wt., 6 lbs. Net 5.00 G-290W Black Flextone Cases Shpg. wt., 6 lbs. Net 5.00

THE FISHER 500-B

65 WATT FM MULTIPLEX STEREO RECEIVER

35950



NO MONEY DOWN

The new 500-B receiver has 18 controls and switches for flexible control of its wideband FM multiplex tuner; dual channel preamplifier and dual channel 65 watt power amplifier. FM circuit has 4 IF stages, advanced multiplex design, special switchable noise filter and "Stereo Beam" tuning indicator. SPECIFICATIONS: Amplifier distortion less than 0.5%. Overall frequency response 25-25,000 cps ± 1.5 db; FM sensitivity 0.7 μV into 72 ohm load; IHFM sensitivity 2.2 μV; signal/noise & hum 70 db. IF bandwidth 190 Kc; channel selectivity 52 db; FM response (after deemphasis) 30-15,000 cps. Size: 17½x5¼x12¼" deep. G-403WX Less Cabinet. Shpg. wt., 35 lbs. Net 359.50 FISHER 30-U Oiled Walnut Cabinet for 500-B G-404W Shpg. wt., 6 lbs. Net 24.95

harman kardon

AWARD TA5000X 50 WATT AM/FM STEREO RECEIVER

29995



NO MONEY DOWN

A complete stereo control center consisting of a sensitive, distortion-free AM/FM Tuner with built-in FM multiplex facilities, 50-watt stereo amplifier (25-watts each channel) plus a versatile stereo amplifier. The TA-5000X features a full range of controls for every stereo function including separate Bass and Treble controls for each channel plus Blend, Balance, Loudness and Function controls. Slide switches provide for Stereo Reverse, Equalization, Contour plus Hi-cut and Lo-cut filters. Size: 16Wx10¼Hx13¼"D. Shpg. wt., 40 lbs. G-656WX Net 299.95 G-657WX CX-80 Metal Case. Shpg. wt., 5 lbs. Net 12.95 G-658W WW-80 Walnut Case. Shpg. wt., 5 lbs. Net 29.95

NEW! McIntosh STEREO PHONIC PREAMPLIFIER MODEL C11

19950



The C11 Stereophonic Preamplifier combines excellence in performance with ease of operation. Advanced techniques were used to assure low hum, noise and distortion. Features include: less than 0.2% dist. at rated output, 20-20,000 cycles; hum & noise on high level inputs, 85 db below rated output, 2.5 volts on main output, 8 program inputs, AUX, TAPE, TUNER 1 & 2, phono 1 & 2, MIC and Tape Head + Tape monitor. Mode selector with 7 combinations. Individual Bass & Treble controls, Balance, 7 rocker type switches for equalization, tape, phase, power, rumble and scratch filters, and loudness. 5 AC outlets and variable panel light. Finished in anodized gold and black. Size: 15¾Wx5¼Hx12"D. Shpg. wt., 25 lbs. G-345WX Net 199.50 G-166W oiled walnut cabinet for C11. Shpg. wt., 6 lbs. Net 178.00 G-178W Net 25.00

MARANTZ MODEL 8B DUAL 35-WATT STEREO POWER AMPLIFIER

24900



NO MONEY DOWN

A professional instrument in every respect. Built-in test meters and bias adjustment assure optimum performance. 35 watts Power output per channel (70-watts peak) "Ultra Linear" operation, 18 watts of triode operation possible by altering 2 connections. Response: 0.1 db from 20-20,000 cps at 35 watts. Distortion: harmonic, less than 0.1%, 1M, less than 0.5%. Hum: — 90 db. Input sensitivity 1.3V Heavy duty components throughout. Output impedance: 4, 8 and 16 ohms. Tubes: 2-6BH6, 2-6CH7, 4-EL34/6CA7. Overall size: 13½Wx7¼Hx10½"D. For 117V, 60 cps. AC. Shpg. wt., 57 lbs. G-259WX Marantz Model 8B less cabinet Net 249.00 Model 8G Gold Finish Perforated Snap-on Grille for above. G-257W Shpg. wt., 1 lb. Net 9.00

MODEL 299C 72 WATT STEREO AMPLIFIER

22495



NO MONEY DOWN

A superb unit designed to accommodate every existing signal source. Uses aluminum chassis and D.C. heated preamp filaments for low hum. Specifications: 36 watts per channel; frequency response ± 1db 20-20,000 CPS; harmonic distortion, 0.8% at full output; IM distortion (CCIF), 0.3%; hum and noise 80db. Also features front panel stereo headphone output, derived center channel level control, loudness, tape monitor switch, two low level magnetic inputs for connection of a stereo tape deck. 6 inputs and scratch and rumble filters. Dimensions in accessory case; 15½Wx5¼Hx13¼"D. Shpg. wt., 28 lbs. G-635WX (less case) Net 224.95 G-147W Leather finish steel case for above. Net 12.95

H H SCOTT MODEL 340 60 WATT FM STEREO RECEIVER

37995



NO MONEY DOWN

A no-compromise 60-watt FM Stereo Receiver of outstanding quality. Features unique sonic-monitor which tunes to tone to indicate when stereo FM programs are on the air. Precision meter insures accurate stereo reception. Other features: Separate bass and treble controls, Sub-channel noise filter, sensitivity 2.5 μV (IHFM), silver plated front end, Freq. response 30-15,000 tuner, 20-20,000 amplifier, special stereo filters for clear recordings. Inputs for tape, TV, phono cartridge and tape deck. Conservatively operated 7591 output tubes. Size in optional accessory case: 17½Wx6½Hx16¾"D. Shpg. wt., 35 lbs. G-645WX Net 379.95 G-637W G case for Model 340 Net 17.95

A COMPLETE STEREO SYSTEM BASED ON THE SUPERB LA-250A

brehtaking performance at a price only LAFAYETTE can offer.

THE SMART WAY TO BUY HI-FI!


LAFAYETTE'S MOST POPULAR STEREO PHONO SYSTEM



LAFAYETTE LA-250A
50-WATT STEREO AMPLIFIER



GLASER-STEERS GS-77



2 LAFAYETTE SK-58
FREE EDGE 12"
COAXIAL SPEAKERS



LAFAYETTE
WOOD BASE



NOW! SHURE M3D CARTRIDGE

BUY ANY SYSTEM LISTED BELOW
WITH FAMOUS SHURE M3D
DIAMOND STEREO CARTRIDGE

(Cartridge Reg. Cat. Price 44.10)

In place of the choice of 4 cartridges and

ADD ONLY 4.10 TO SYSTEM PRICE

CHOICE OF CARTRIDGE



Audio Empire
S108

Pickering
380C

Shure
M7D


GE
VR 1000-7

"LISTEN AT HOME GUARANTEE"

Prove to yourself in your own living room, that the hi-fi system you select sounds as good at home as it does in our showroom.

LISTEN at HOME and BE SURE!

With Lafayette's Famous 30 Day FREE Trial if not completely satisfied with your purchase once you get it home, you can return it within 30 days and get your Full Purchase Price returned to you, less only transportation charges.



(OPTIONAL)
2 LAFAYETTE ELIPTOFLEX SERIES
BOOKSHELF ENCLOSURES

ALTERNATE RECORD CHANGER



GARRARD AT6

MATCHED COMPONENTS

| | |
|--|---------------|
| Lafayette LA-250A 50-Watt Stereo Amplifier | 99.50 |
| Glaser-Steers GS-77 4-Speed Record Changer | 59.50 |
| Lafayette Wood Changer Base | 3.95 |
| Audio Empire S108 Diamond Needle Stereo Cartridge | 35.00 |
| 2-Lafayette SK-58 Famous Free Edge 12" Coaxial Speakers @ 29.50 Each | 59.00 |
| REGULAR CATALOG PRICE | 256.95 |

LAFAYETTE SYSTEM PRICE **199.50**
You Save **57.45** NO MONEY DOWN

LAFAYETTE MATCHED STEREPHONIC SYSTEMS


*Make Certain To Indicate Your Choice of either Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Diamond Needle Cartridge.

| System No. | Amplifier | Changer | Cart | Speaker | Shpg. Cabinet** | Shpg. Wt. | Net |
|------------|-----------|---------|----------------|-------------|--------------------------|-----------|-----|
| LS-251WX | LA-250A | GS-77 | CHOICE OF | 2 ea SK-58 | 67 lbs. | 199.50 | |
| LS-252WX | LA-250A | AT-6 | Audio | 2 ea SK-58 | 67 lbs. | 199.50 | |
| LS-253WX | LA-250A | GS-77 | Empire S108 | 2 ea SK-58 | 2 ea Eliptoflex 143 lbs. | 265.50 | |
| LS-254WX | LA-250A | AT-6 | or | 2 ea SK-58 | 67 lbs. | 203.50 | |
| LS-255WX | LA-250A | GS-77 | Pickering 380C | 2 ea SK-180 | 67 lbs. | 203.50 | |
| LS-256WX | LA-250A | AT-6 | or | 2 ea SK-180 | 2 ea Eliptoflex 143 lbs. | 269.50 | |
| LS-257WX | LA-250A | GS-77 | Shure M7D | 2 ea SK-180 | 70 lbs. | 233.50 | |
| LS-258WX | LA-250A | AT-6 | or | 2 ea SK-180 | 70 lbs. | 233.50 | |
| LS-259WX | LA-250A | GS-77 | GE VR 1000-7 | 2 ea SK-210 | 70 lbs. | 233.50 | |
| LS-260WX | LA-250A | AT-6 | | 2 ea SK-210 | 2 ea Eliptoflex 146 lbs. | 299.50 | |
| LS-261WX | LA-250A | GS-77 | | 2 ea SK-210 | 2 ea Eliptoflex 146 lbs. | 299.50 | |
| LS-262WX | LA-250A | AT-6 | | 2 ea SK-210 | 2 ea Eliptoflex 146 lbs. | 299.50 | |
| LS-263WX | LA-250A | Model A | | 2 ea SK-58 | 70 lbs. | 219.50 | |

Any of above systems with addition of Lafayette LT-700 WX Multiplex Stereo Tuner (described on other pages) add \$114.50 to system price. When ordering add the letter T to the prefix.


Example: LS-251WX system with LT-700WX tuner is ordered as LST-251WX.
Eliptoflex—12" shelf type speaker Enclosure.
†—Specify Mahogany, Walnut or Blonde Base.
**—Specify Walnut, Oiled Walnut, Mahogany or Blonde.
AT-6—Garrard 4-Speed Record Changer. Model A—Garrard 4-Speed Record Changer.

ALTERNATE SPEAKER SYSTEMS



LAFAYETTE SK-180
"TRIHELIX" SPEAKERS

NEW LAFAYETTE CRITERION HI-FI CABINETRY.... to decorate your home with music




Lafayette's Criterion Line — the standard of construction and design by which all others are judged.

The Technical Know-How of Lafayette's Audio Engineers Combined with that of America's Finest Furniture Craftsman, bring to you the new Lafayette Criterion Line of Acoustically Correct Hi-Fi Furniture.

Now your high fidelity listening area can look as good as it sounds. Add the elegance, grace and timeless styling of this decorator inspired furniture grouping to your home music center, but lose nothing in performance. Painstaking acoustical design by Lafayette's audio engi-

neers provides the best possible relationship between equipment and furniture. The meticulous custom craftsmanship, rich, matched, natural wood veneers and custom hand-rubbed finishes of these fine cabinets are bound to please the most discerning taste.

THE CRITERION EQUIPMENT CABINET



84.50

"Component Engineered" by Lafayette's audio experts to provide ample, convenient, well-ventilated accommodations for all of your components. When matched with its companion Criterion Eliptoflex speaker enclosure (described on the right) it forms a complete music center. Cabinets employ rigid tongue and groove construction of 3/4" lumber core woods throughout, with matched veneers inside as well as out. Swinging doors with brass pulls and magnetic catches. Smartly styled with tapered legs and gold side trim. Overall Dimensions: 40Wx18Dx32 1/2" H including legs. Shpg. wt., 70 lbs.

| | |
|------------------------|-----------|
| CAB-137WX Walnut | Net 84.50 |
| CAB-138WX Oiled Walnut | Net 84.50 |
| CAB-139WX Mahogany | Net 84.50 |

THE CRITERION ELIPTOFLEX SPEAKER CABINET

The same graceful styling and fine construction as the CRITERION equipment cabinet, which it matches. Designed to accommodate any 12" speaker, this enclosure incorporates the inner construction and acoustic principles of the famous Lafayette "Eliptoflex" enclosure. A specially designed elliptical port with diffracting ring broadens frequency response. This results in natural smoothness and unequalled performance in the low ranges. Constructed of 3/4" lumber core woods with hand-rubbed natural wood veneers. Smartly styled with matching grille cloth, gold trim and tapered legs. Overall Dimensions: 32 1/2 H x 18 D x 16" W. Shpg. wt., 50 lbs.

55.50
NO MONEY DOWN



| | |
|------------------------|-----------|
| CAB-140WX Walnut | Net 55.50 |
| CAB-141WX Oiled Walnut | Net 55.50 |
| CAB-142WX Mahogany | Net 55.50 |

THE OUTSTANDING

"Stereo 250 A" KIT

ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE

All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

50 WATT INTEGRATED STEREO AMPLIFIER KIT

- DC applied to all preamplifier and tone control tube heaters for hum-free operation
- RIAA equalization on phono inputs
- NARTB tape equalization on tape head inputs
- Individual bias and balance controls
- Hum balance Control
- Excellent DC power supply regulation provided by silicon diodes
- Total of 9 tubes, plus 3 silicon diodes—uses premium 6CW5/EL86 output tubes.

Made in U.S.A.

IN EASY-TO-BUILD KIT FORM

74⁵⁰

NO MONEY DOWN



SPECIFICATIONS

POWER OUTPUT: 50 watts (100 watts peak) 25 watts per channel ± 1 db. DISTORTION: Total Harmonic Distortion ± 1 db at less than 1% at 1KC at normal listening level (1 watt); I.M. Distortion less than 0.5% at normal listening level. FREQUENCY RESPONSE: 15-40,000 cps ± 0.5 db at normal listening level. 20-50,000 cps ± 1 db at rated output. HUM & NOISE: Zero volume hum 77 db below rated output; max volume hum high level inputs 70 db below rated output; Mag. phono inputs 50 db below rated output. Sensitivity: For full output high level inputs 0.5V; Mag. phono 3.5 MV at 1KC. CHANNEL SEPARATION: Greater than 55 db at 1KC; greater than 45 db from 20-20,000 cps. SPEAKER AUXILIARY OUTPUT: 1 switched. TUBE COMPLEMENT: 4-6CW5/EL86, 2-7199, 3-12AX7, 3 Silicon diodes. IMPEDANCE: 4, 8 and 16 ohms per channel. POWER: 200 watts; 110-125V AC 50-60 cps. MODEL KT-250AWX Net 74.50

THE new Lafayette KT-250A offers remarkable versatility, high quality of reproduction and new distinctive styling in one convenient low-cost unit. Designed and engineered for ease of assembly, the KT-250A is a fine stereo preamplifier and 50 watt stereo amplifier combined — with all the controls and features to enable you to enjoy the utmost in listening pleasure in any situation. Whether you use it as a stereo amplifier delivering 25 watts per channel or as a powerful 50 watt monophonic amplifier, you are assured of true high fidelity reproduction — free from hum, noise and distortion.

DELUXE FEATURES

- Unique Separation Control**—A new stereo control which provides continuously variable channel separation—from full monophonic to full stereo. Lets you select the amount of separation you want.
- Clutch-Operated Volume Balance Control**—Gives you a choice of independent or simultaneous control of both channels—you can use it as a master volume control without disturbing previously selected settings on each channel.
- 4 Independent Tone Controls**—Independent Bass and Treble adjustment for each channel. Concentric mounting for convenience—
- inner knob controls one channel, outer the other channel.
- Mode Switching**—Two slide switches provide Normal Stereo—Reverse Channel—Mon A (Channel A reproduced through both channels)—Mon B (Channel B reproduced through both channels).
- Input Selector**—4-position switch lets you select instantly any one of your connected monophonic or stereo sources—special non-shorting arrangement on one position permits recording and playback using a permanently connected tape recorder.

Loudness Switch—Provides the frequency response changes required by the ear at low listening levels and permits the Volume-Balance control to function as a compensated loudness control.

Phase Switch—Reverses the phase of one channel electrically—corrects for speakers connected out of phase or for reversed phase recordings sometimes found commercially.

3 Pairs of High Level Inputs—For connection of Crystal or Ceramic phono, Tuner, and auxiliary equipment.

2 Pairs of High Level Inputs—For connection of magnetic phono and Tape Head.

Main Speaker Outputs—Dual 4, 8 and 16 ohm terminals may be paralleled for 4 or 8 ohm operation at 50 watts.

Tape Output—Provides an output for Tape recording—unaffected by Volume and Tone Controls.

Bridged Output—A monophonic blend of both channels which can be fed to a third single channel power amplifier and speaker for a greater sound spread in stereo. May also be used for listening in another room.



NO TECHNICAL SKILL REQUIRED

Designed for ease of construction, the KT-250A can be assembled in a minimum of time. Assembly manual contains detailed step-by-step instructions... guides you every step of the way. Large full-scale pictorials show you where every wire and component goes.



Made in U.S.A.

NO MONEY DOWN

59⁵⁰

Lafayette 36 watt stereo amplifier


THE AMAZING "STEREO 236" KIT

A NEW LOW-COST STEREO AMPLIFIER ANYONE CAN BUILD



Easy to Build!

Anyone can build these superb Lafayette stereo kits—no special skill is needed. Assembly manuals contain clearly-warded step-by-step instructions which guide you all the way. Large full-scale pictorials illustrate every stage of assembly—show you exactly where every part goes. Join the thousands who have already discovered this easy low-cost way of owning the finest audio equipment.



Deluxe Stereo Controls

- 1 3-position Selector switch
- 2 Dual concentric Bass control
- 3 Dual concentric Treble control
- 4 Concentric clutch-operated Volume control
- 5 Unique "Blend" control
- 6 Phase reverse switch
- 7 Mode switches

Fine wide-range stereo reproduction can be yours when you build this easily constructed 36 watt stereo amplifier (18 watts each channel). The KT-236A provides all the necessary inputs—lets you connect your stereo or monophonic sources permanently, with instant selection provided by the turn of a switch. Has built-in dual preamps for low level phono inputs—RIAA equalized for flat response. It includes a unique "Blend" control which provides continuously variable channel separation from full monophonic to full stereo—you select the exact degree of separation you want. Other features are: Concentric clutch-operated Volume control for independent or simultaneous level adjustment of both channels; Dual concentric Bass and Treble controls—give you 4 independent tonal adjustments; 3-position Selector Switch—Aux-Tuner-Phono; Mode (2 Slide Switches) provide Normal Stereo, Reverse channel, Mon A and Mon B; Phase switch—makes up for reversed-phase recordings sometimes found commercially and also corrects for speakers connected out of phase.

SPECIFICATIONS: POWER OUTPUT: 36 watts—18 watts per channel ± 1 db. Institute of High Fidelity Manufacturers Rating (72 watt peak). FREQUENCY RESPONSE: 15-30,000 cps ± 1 db at normal listening levels. SENSITIVITY: For full output; High level inputs 0.5V; Mag. Phono 3 mv. DISTORTION: Harmonic, less than 0.15% at normal listening level; IM, less than 3%. HUM AND NOISE: (At full volume) High level inputs 70 db below rated output; Mag. phono 53 db below rated output. CHANNEL SEPARATION: Better than 50 db. SPEAKER OUTPUT IMPEDANCE: 8 and 16 ohms. INPUTS: (Total 8) Dual Aux, dual Tuner, dual Tuner, dual Crystal Phono, dual Mag. Phono. OUTPUTS: (Total 4) Dual main speaker output, dual Tape Out jacks. TUBE COMPLEMENT: 4-EL84, 2-7199, 3-12AX7 plus 2 silicon diodes. Attractive beige vinyl laminated steel cabinet. Handsomely designed brass anodized aluminum front panel. Sienna brown molded legs, matching knobs with polished brass inserts. 14 1/2" wide x 11 1/2" deep x 5 3/4" high (with legs and knobs). Shpg. wt. 24 lbs. 36 watt integrated Stereo Amplifier Kit, complete with deluxe cabinet and legs, all necessary parts and detailed assembly MODEL KT-236AWX Net 59.50

DO-IT-YOURSELF and SAVE with LAFAYETTE HI-FI STEREO KIT SYSTEMS

BUILD THIS 36-WATT STEREO KIT SYSTEM

| COMPONENTS | |
|--|-------|
| Lafayette KT-236A 36 Watt Stereo Amplifier Kit | 59.50 |
| Lesa CD2/21 4-Speed Stereo Record Changer (less base) | 44.50 |
| Base for Record Changer (Specify Finish) | 4.50 |
| Audio Empire S108 Diamond Needle Stereo Cartridge | 35.00 |
| 2 Lafayette SK-128 8" Ultra-Linear Bixial Speakers @ 19.50 | 39.00 |
| Regular Catalog Price 182.90 | |

ONLY 142.50

YOU SAVE 40.00



| CHOICE OF ONE | |
|-------------------|-------------|
| AUDIO EMPIRE S108 | SHURE M7D |
| PICKERING 380C | GE VR1000-7 |

OPTIONAL



| CHOICE OF ONE | |
|-------------------|-------------|
| AUDIO EMPIRE S108 | SHURE M7D |
| PICKERING 380C | GE VR1000-7 |

OPTIONAL



Deluxe 50-WATT DO-IT-YOURSELF STEREO KIT SYSTEM

| MATCHED COMPONENTS | |
|--|-------|
| Lafayette KT-250A 50 Watt Stereo Amplifier | 74.50 |
| Glaser-Steers GS-77 4-Speed Record Changer (less base) | 59.50 |
| Base for Changer (Specify Finish) | 3.95 |
| Audio Empire S108 Diamond Stereo Cartridge | 35.00 |
| 2-Lafayette SK-58 12" Coaxial Speakers @ 29.50 | 59.00 |
| REGULAR CATALOG PRICE 234.95 | |

ONLY 184.75

YOU SAVE 47.20

| LAFAYETTE MATCHED 36-WATT STEREO KIT SYSTEMS | | | | | | |
|---|----------|---------------------|---|------------------------|---------------------|-----------------|
| *Be sure to Specify Choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Diamond Needle Cartridges. | | | | | | |
| System | Amp. Kit | Changer | Cartridge* | Changer Base† Speakers | Spkr. Cab. or Tuner | Shpg. Net |
| LSK-231WX | KT-236A | Lesa CD2/21 Garrard | Choice of Audio Empire S108, Pickering 380C, Shure M7D, or GE VR-1000-7 | Lesa† 2 SK-128 | — | 50 lbs. 142.50 |
| LSK-232WX | KT-236A | Autoslym | — | Laf† 2 SK-128 | — | 48 lbs. 142.50 |
| LSK-233WX | KT-236A | Lesa CD2/21 Garrard | — | Lesa† 2 SK-128 | 2 Mini-Duct† | 93 lbs. 185.50 |
| LSK-234WX | KT-236A | Autoslym | — | Laf† 2 SK-128 | 2 Mini-Duct† | 91 lbs. 185.50 |
| LSK-235WX | KT-236A | Lesa CD2/21 Garrard | — | Lesa† 2 SK-58 | — | 61 lbs. 162.50 |
| LSK-236WX | KT-236A | Autoslym | — | Laf† 2 SK-58 | — | 61 lbs. 162.50 |
| LSK-237WX | KT-236A | Lesa CD2/21 Garrard | — | Lesa† 2 SK-58 | 2 CK-14 | 109 lbs. 203.50 |
| LSK-238WX | KT-236A | Autoslym | — | Laf† 2 SK-58 | 2 CK-14 | 107 lbs. 203.50 |
| LSK-239WX | KT-236A | Lesa CD2/21 Garrard | — | Lesa† 2 SK-128 | KT-650 | 64 lbs. 192.00 |
| LSK-240WX | KT-236A | Autoslym | — | Laf† 2 SK-128 | KT-650 | 62 lbs. 192.00 |

Any of above systems with addition of Lafayette LT-700WX, Multiplex Stereo Tuner, add \$114.50 to system price. When ordering add T to prefix. Example: LSK-231WX system with LT-700WX tuner is ordered as LSKT-231WX.

†: Specify Mahogany, Walnut or Blonde Base. Mini-Duct: 8" Speaker Bookshelf Enclosure. CK-14: Eliptoflex 12" Speaker Enclosure Kit, Unfinished. KT-650: FM Tuner Kit.

| LAFAYETTE MATCHED 50-WATT STEREO KIT SYSTEMS | | | | | | |
|---|----------|---------------------|---|------------------------|---------------------|------------|
| *Be Sure to Specify Choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Stereo Cartridges. | | | | | | |
| System | Amp. Kit | Changer | Cartridge* | Changer Base† Speakers | Spkr. Cab. or Tuner | Shpg. Net |
| LSK-351WX | KT-250A | Glaser-Steers GS-77 | Choice of Audio Empire S108, Pickering 380C, Shure M7D, or GE VR-1000-7 | Laf† 2 SK-58 | — | 80 184.75 |
| LSK-352WX | KT-250A | AT-6 | — | Laf† 2 SK-58 | — | 80 184.75 |
| LSK-353WX | KT-250A | Glaser-Steers GS-77 | — | Laf† 2 SK-58 | 2 CK-14 | 128 225.75 |
| LSK-354WX | KT-250A | AT-6 | — | Laf† 2 SK-58 | 2 CK-14 | 128 225.75 |
| LSK-355WX | KT-250A | Glaser-Steers GS-77 | — | Laf† 2 SK-180 | — | 74 188.75 |
| LSK-356WX | KT-250A | AT-6 | — | Laf† 2 SK-180 | — | 74 188.75 |
| LSK-357WX | KT-250A | Glaser-Steers GS-77 | — | Laf† 2 SK-180 | 2 CK-14 | 122 229.75 |
| LSK-358WX | KT-250A | AT-6 | — | Laf† 2 SK-180 | 2 CK-14 | 122 229.75 |

Any of above systems with addition of Lafayette LT-700WX, Multiplex Stereo Tuner, add \$114.50 to system price. When ordering add T to prefix. Example: LSK-351WX system with LT-700WX tuner is ordered as LSKT-351WX.

†: Specify Mahogany, Walnut or Blonde Base. SK-180: "Trihelix" 10" 3-way speakers. AT-6: GARRARD 4-Speed Record Changer. CK-14: Eliptoflex Bookshelf Speaker Enclosure in Kit form, unfinished.


LAFAYETTE Criterion STEREO COMPONENTS

LAFAYETTE KT-600A STEREO PRE-AMPLIFIER MASTER CONTROL CENTER

MODEL KT-600A
79.50
IN EASY-TO-BUILD KIT FORM
COMPLETELY WIRED AND TESTED
LA-600A
134.50
NO MONEY DOWN!



MADE IN U.S.A.



PATENTS APPLIED FOR ON BRIDGE AND NULL BALANCE CIRCUITRY.

The KT-600A Solves every Stereo-Monaural problem

- RESPONSE 5-40,000 CPS • AMAZING BRIDGE CONTROL PROVIDES VARIABLE 3rd CHANNEL OUTPUT FOR 3-SPEAKER STEREO
- HIGHLY PRECISE "NULL" BALANCING & CALIBRATION—MORE ACCURATE THAN METERS • TAPE HEAD PLAYBACK EQUALIZATION FOR NEW 4-TRACK STEREO • 4-AUXILIARY AC OUTLETS

The KT-600A represents a brilliant stereo achievement. This "no-compromise" stereo pre-amplifier and control unit offers unlimited versatility, includes every feature necessary for the finest reproduction. It has a total of 12 input jacks (6 stereo pairs) for program sources of any type and level—all of which may be selected by front panel control. Separate turnover and roll-off switches provide 24 positions of correct equalization—independent for each channel. Dual concentric stereo function selector for maximum flexibility in controlling selected program sources. A unique Bridge Control provides continuously variable channel separation from full mono to full stereo or it can optionally be used to regulate the 3rd channel output. A clutch-operated Volume Balance Control provides independent or simultaneous level adjustment of channels. Low impedance Plate Follower outputs are used, and a host of many other professional type features.


KT-600AWX Stereo Pre-amplifier Kit No Money Down Net 79.50
LA-600AWX Stereo Pre-amplifier, wired and tested No Money Down Net 134.50

SPECIFICATIONS

FREQUENCY RESPONSE: 5-40,000 cps \pm 1 db. DISTORTION: Less than 0.05% IM at 2 volts out; Less than 0.1% Harmonic at 2 volts out. SENSITIVITY: Low Level 2.2 mv for 1 volt out; high level 94 mv for 1 volt out; Tape Head inputs 1.8 mv for 1 volt out. HUM AND NOISE: High level inputs better than 80 db below 2.0 volts; low inputs better than 62 db below 2.0 volts. INPUT IMPEDANCES: High level—250K ohms; Mag—96K ohms; Ceramic—96K ohms in series with 68 ohms; Tape Head—470K ohms. OUTPUT IMPEDANCES: Main Outputs—1500 ohms; Tape Outputs—2700 ohms; Bridged Output—1100 ohms. TONE CONTROL RANGE: Bass \pm 15 db at 30 cps; Treble \pm 15 db at 10Kc. RUMBLE FILTER: 12 db/octave slope, down 15 db at 30 cps. SCRATCH FILTER: 12 db/octave slope, down 15 db at 15 Kc. CROSSTALK: Greater than 55 db separation between channels. AUXILIARY AC OUTLETS: 4, 1 unswitched. TUBES: 7-7025, 2-Selenium Rectifiers. POWER REQUIREMENTS: 35 Watts, 105-125 volts AC, 50/60 cycles. SIZE: 14Wx4 1/2"Hx11 1/2"D, not including projections. Shpg. wt., 16 lbs.

"LABORATORY STANDARD"

IN EASY TO BUILD KIT FORM
MODEL KT-550
134.50
MODEL LA-550
184.50
COMPLETELY WIRED AND TESTED
NO MONEY DOWN



the KT-550 100 WATT BASIC STEREO AMPLIFIER KIT

- 50 Watts—per channel—100 watts for monophonic use. Frequency response from 2-100,000 cps, \pm 0, \pm 1 db at 1 watt • Unmeasurable Distortion • Hum and Noise Better Than 90 db Below 50 watts • Multiple Feedback Loop Design (over 50 db) Lowers Distortion Without Sacrificing Stability • Metered Control Panel With D.C. Bias and AC Balance Potentiometer • High Power 7027A Output Tubes • Massive Grain oriented steel transformers.

TECHNICAL SPECIFICATIONS

Power Output: 50-watts per channel continuous RMS from 20-20,000 cps; 100-watts monophonic operation. Total Harmonic Distortion: Less than .15% at 1,000 cycles at 50 watts each channel, 0.75% from 20-20,000 cps at 50 watts each channel. Intermodulation Distortion: Less than 0.5% at 50-watts equivalent sine wave power, 60 & 7,000 cps 4:1 ratio, 0.15% at 10-watts equivalent sine wave. Frequency Response: 12-45,000 cps, 0 \pm 1db at 50-watts; 2-100,000 cps, \pm 0 \pm 1db at 1 watt. Sensitivity: 1.0 volt RMS input for 50-watts output. Damping Factor: 15 at 1 kc—16 ohms. Feedback: Over 50db in six multiple loops. Hum and Noise: Better than 90 db below 50-watts. Output Impedance: 4, 8 and 16-ohms. Convenience Outlet: Single A.C. convenience outlet. Fuse: Externally accessible fuse. Controls: 4 Bias Controls, 2 AC Balance Controls, Meter Selector Switch and Power On/Off Switch. Tube Complement: (Total of 10) 4-7027A, 4-6CL6, 2-6BR8A plus 5 Silicon Diodes. Power Consumption: 350-watts.

Lafayette introduces the KT-550 "Laboratory Standard" Dual 50-watt Stereo Amplifier Kit—the finest instrument possible to design and produce regardless of price. Advanced engineering concepts in audio design were used to achieve flawless performance at an output of up to 50 watts per channel for stereo operation or 100 watts combined for monaural. The sound reproducing capabilities of the KT-550 are in excess of the audible range... \pm 0, \pm 1 db from 2 to 100,000 cps without evidence of ringing or instability. Perfect for low efficiency speaker systems. "Multiple loop" feedback design achieves very low distortion and high stability, with an absence of listening fatigue. Highest quality components were used throughout such as special massively designed output transformers, telephone grade electrolytics, and Corn-

ing deposited metal film glass case resistors. The 7027A output tubes are conservatively rated in the KT-550 to insure long life at lowest distortion levels. A well regulated power supply employing 4 silicon diode rectifiers is used. Engineered for the kit builder, two printed circuit boards virtually eliminate any possibility of error. Lafayette's famous step-by-step instruction manuals plus large pictorials provide ease of assembly equal to factory built units. Handsomely finished in contrasting brown and beige; control panel finished in brass. Complete with cover. Size: 17Wx12 1/2"Dx8 1/2"H 105-120 V. AC 50-60 cycles Shpg. wt., 60 lbs.
KT-550WX No Money Down Net 134.50
Dual 50-watt stereo amplifier as above wired and tested.
LA-550WX No Money Down Net 184.50

AUDIO

"The published specifications for the '550' are unusually fine, well up amongst the top quality amplifiers available. This amplifier met every one of its published specifications. "In view of the excellent performance and easy construction, we would recommend this amplifier to any audiophile."

high fidelity

"The listening quality of the '550' was superb. It has proven to be an amplifier capable of performing well under the most exacting applications and suitable for use in the finest of music-reproducing systems. United States Testing Company feels the '550' not only is an exceptionally good value, but is one of the finest amplifiers it has seen."

ELECTRONICS WORLD

"One of the best hi-fi amplifiers on the market. "From the test results obtained, we would rate this amplifier along with the very best in the field. It will provide excellent hi-fi performance whose quality would be limited only by that obtained from the other components in the system."

NOW YOU CAN AFFORD The Very Finest LAFAYETTE BUILD-IT-YOURSELF PROFESSIONAL 100 WATT STEREO SYSTEM



| MATCHED COMPONENTS | | |
|---|--|--------|
| Lafayette KT600A Stereo Pre-amplifier Kit | | 79.50 |
| Lafayette KT-550 Dual 50-Watt Basic Stereo Amplifier Kit (with enclosure) | | 134.50 |
| 2-Lafayette SK-115A 15" 3 Way Speakers @ 79.50 | | 159.00 |
| Garrard Model A Record Changer (less base) | | 79.50 |
| Base for Model A Changer (Specify Finish) | | 3.95 |
| Audio Empire S108 Diamond Needle Stereo Cartridge | | 35.00 |
| Regular Catalog Price | | 491.45 |

LAFAYETTE KIT SYSTEM PRICE
437.75 NO MONEY DOWN
YOU SAVE **53.70**

LAFAYETTE 100 WATT MATCHED DE LUXE STEREO KIT SYSTEMS

*Be sure to specify Audio Empire S108, Pickering 380C, Shure M7D or GE VR-1000-7 Cartridge.

| System | Amp. Kit | Preamp Kit | Changer | Cartridge* | Changer Tuner Base† | Kit | Spkr. | Cabinet Kit | Shpg. Wt. | Net |
|-----------|----------|------------|-----------------|-----------------|---------------------|---------|-----------|-------------|-----------|--------|
| LSK-551WX | KT-550 | KT-600A | Garrard Model A | Choice of | Laff | — | 2 SK-115A | — | 175 lbs. | 437.75 |
| LSK-552WX | KT-550 | KT-600A | Garrard Model A | Empire S108, | Laff | — | 2 SK-115A | 2 CK-10 | 283 lbs. | 491.75 |
| LSK-553WX | KT-550 | KT-600A | Garrard Model A | Pickering 380C, | Laff | — | 2 SK-210 | CK-14A | 183 lbs. | 422.75 |
| LSK-554WX | KT-550 | KT-600A | Garrard Model A | Shure M7D, | Laff | KT-500A | 2 SK-115A | — | 193 lbs. | 512.25 |
| LSK-555WX | KT-550 | KT-600A | Garrard Model A | Or GE VR-1000-7 | Laff | KT-500A | 2 SK-115A | 2 CK-10 | 301 lbs. | 566.25 |
| LSK-556WX | KT-550 | KT-600A | Garrard Model A | | Laff | KT-500A | 2 SK-210 | — | 153 lbs. | 456.25 |
| LSK-557WX | KT-550 | KT-600A | Garrard Model A | | Laff | KT-500A | 2 SK-210 | CK-14A | 201 lbs. | 497.25 |
| LSK-558WX | KT-550 | KT-600A | Garrard Model A | | Laff | KT-500A | 2 SK-210 | — | 153 lbs. | 456.25 |

Any of above systems with addition of Lafayette LT-700WX Multiplex Stereo Tuner add \$114.50 to system price. When ordering add T to prefix. Example: LSK-551WX system with LT-700WX tuner is ordered as LSKT-551WX. † Specify Mahogany, Walnut or Blonde Base.
KT-500A AM-FM Stereo Tuner Kit. SK-210 12" 3 Way Speaker. CK-10 Base Reflex Unfinished Speaker Enclosure Kit for 12" or 15" Speakers. CK-14A Famous Lafayette Bookshelf Enclosure Kit for 12" Speaker.

NOW! For any of above systems with Shure M3D Diamond Stylus Stereo Cartridge in place of choice of above cartridges add only \$4.10 to System Net Price.

THE ULTIMATE FM MULTIPLEX STEREO TUNER

Now! from the
LAFAYETTE
HIGH-FIDELITY
RESEARCH
LABORATORIES



124⁵⁰ NO
MONEY
DOWN!

THE
NEW

Criterion™
LT-700



MADE IN U.S.A.



- Virtually Distortionless Performance — Less than 0.15% Distortion at 100% Modulation, Monaurally • Low Noise Front End With Triode Grounded Grid Amplifier and Triode Mixer • Electronic Bar Tuning Indicator
- Double-Tuned Dual Limiters and Foster Seeley Discriminator • Stereo Separation: 35 db at 400 cps. • Frequency Response $\pm 1/2$ db 15-35,000 cps, Monaurally • Variable AFC Literally "Locks In" Stations • Sensitivity 1.25 μ v for 20 db of Quieting • 3 Gang Tuning Condenser

FREE! LAFAYETTE FM STEREO MULTIPLEX BROCHURE

Lafayette has prepared an informative, fact-filled brochure describing FM stereo Multiplex Broadcasting. Write for your free copy of brochure BK-50, "Facts About FM Stereo Broadcasting."

The LT-700 is another impressive example of Lafayette's engineering leadership. For here is a tuner that achieves a level of distortionless performance and flexibility that sets the standard for professional FM multiplex reception. Its superb circuitry features a low noise front end with triode mixer, double-tuned dual limiters and wide band Foster Seeley discriminator. Distortion has virtually been eliminated with less than 0.15% distortion at 100% modulation (monaurally). Sensitivity of the LT-700 is such that in many areas the only antenna needed will be a short piece of wire, except of course in remote locations. Plate follower outputs permit using the tuner up to 50 feet from the amplifier. Designed for maximum versatility, the LT-700 features a convenient front panel volume control for precision adjustment of tuner output level. In addition a

variable AFC (automatic frequency control) is provided. Once properly tuned, the AFC literally "locks in" the station and is adjustable for tuning weak stations adjacent to strong stations. Pinpoint tuning accuracy is assured by a special electronic bar tuning indicator that indicates maximum closure at the point of best tuning. Multiplex operation is achieved by a simple front panel switch. This also activates a stereo light when the station tuned to starts broadcasting stereo. Every LT-700 is individually aligned and tested to meet or exceed Lafayette's specifications. Attractively styled with a cream and brushed brass front panel set in a beige finished vinyl enclosure. Size 13 $\frac{1}{2}$ "x10 $\frac{1}{2}$ "x4 $\frac{1}{2}$ " H. For 117V. 50-60 cycle AC. LT-700WX Shpg. wt., 16 lbs. Net 124.50


LOOK at THESE
QUALITY LT-700 FEATURES!

- 1 Simple Front Panel Switch for Mono or Stereo Multiplex or Stereo Multiplex "Locks In" Stations
- 2 Variable AFC

TECHNICAL SPECIFICATIONS

Sensitivity: 1.25 μ v for 20 db of quieting. Variable AFC. Harmonic Distortion: 0.15% at 1Kc 100% modulation. Signal-to-Noise Ratio: Better than 57 db. Freq. Response: $\pm 1/2$ db 15-35,000 cps monaurally. Image Rejection: -50db. Stereo Separation: Built-in MPX section provides 35db separation at 400 cps. Discriminator Linearity: 600 Kc. Audio output: 1.75v at 75 Kc deviation (100% modulation). Tubes: Simple manual switching for FM multiplex operation. Anode Follower for low impedance wide-band distortion-free output. Automatic FM stereo indicator light. 2—No. 47 Pilot Lights. Tubes: 12AX7, 6C4, 12BZ7, ECC85/6AQ8, 6BK7, 2-6BA6, 2-7543, 6AL5, EZ-80 rectifier, 2 matched diodes plus EM-84 tuning eye.

LAFAYETTE STEREO TRIUMPH! 24-WATT STEREO AMPLIFIER!



DELIVERY, JULY 25, 1962

Dual 12-Watt Stereo Amplifier Coupled With a Versatile Stereo Preamplifier . . . Performance The Equal of Units 2 & 3 Times Its Power & Price.



49⁹⁵ NO MONEY
DOWN

SPECIFICATIONS
Power Output: 12 watts per channel stereo. 24-watts monaural operation. Frequency Response: 20-25,000 CPS ± 1 db at 1 watt; 50-50,000 CPS ± 2 db at 12 watts. Hum and Noise: Mag Phone — 56 db below rated output, Tuner — 73 db below rated output. Distortion: less than 1% total harmonic distortion at 12 watts (1KC), less than .25% total harmonic distortion at 1 watt (1KC). Sensitivity: Low Level (Mag Input) 5mv at full output, High Level .6v at full output. Outputs: Dual 8 and 16 ohm impedance speaker outputs. Dual Tape outputs, Tube Complement: Total of 8, 3-12AX7, 4-6GW8, 1-5AR4.

CHECK THESE QUALITY FEATURES

- ✓ Stereo Headphone Jack
- ✓ Independent Concentric Bass & Treble Controls For Each Channel
- ✓ Concentric Volume Balance Control
- ✓ Frequency Response: 20-25,000 CPS ± 1 db at 1 Watt
- ✓ Hum & Noise—73 db Below Rated Output
- ✓ High Sensitivity Allows Use With All Stereo Cartridges

FIRST RATE—make no mistake, don't be misled by Lafayette's low price. This is a Brilliant Stereo Performer . . . an amplifier with the wide-range frequency response, low distortion, low hum and noise characteristics you'd expect of amplifiers 2, even 3 times its power rating and many times its price. A full range of control facilities have been provided to assure complete Stereo capability and flexibility. Two dual concentric Bass and Treble controls provide separate and individual tone controls for each channel. A dual concentric volume Control acts as an independent level control for each channel and allows precise channel balancing. Fast, easy operation between Stereo, Reverse Stereo, Monophonic Left channel and Monophonic Right channel is furnished by a Mode switch. A selector Switch furnishes switching from Aux, Tuner or Phono music

sources. In addition slide switches are included for: Rumble Filter (off-on) Phase (normal-reverse) and to take full advantage of the front panel Headphone jack a switch is provided for speaker or phone operation. Paired inputs located on the rear panel accommodate any of the ordinary stereo sound sources—inputs are included for magnetic, crystal or ceramic cartridges; Tuner, tape or auxiliary (high output) plus Tape Out jacks for recording through your tape recorder. Beautifully styled in a low silhouette enclosure, color keyed to do justice to any decor. Ivory and gold front panel is contrasted by gold metal knobs and enclosure. Complete with cage and legs. Size: 5 $\frac{1}{2}$ "x13 $\frac{1}{2}$ "x4 $\frac{1}{2}$ " D. For 115V 60 cycle AC operation. Shpg. wt., 20 lbs. LA-224WX Net 49.95



NEW KORDEX AM-FM STEREO MULTIPLEX TUNER

79⁹⁵ NO MONEY
DOWN
Made in U.S.A.

SPECIFICATIONS: Sensitivity: FM 4 microvolts for 30db quieting, AM 75 Microvolts loop sensitivity; Frequency Response: FM—1db 20-20,000 CPS; AM—2db 20-5000 CPS; Selectivity—FM 250 KC bandwidth, 6db down, AM 7KC Bandwidth 6db down; Hum Level—70db below 1 volt. Tubes: Total of Ten—6U8, 12AT7, 6BE6, 6BAG, 2-6AUG, 6A15, 6C4, 2-12AU7, plus 2 matched diode detectors.

An excellent performer with outstanding features and at Lafayette's low price a truly fabulous buy. Engineered to provide the widest possible range of tuner flexibility it's capabilities include—Sparkling clear AM reception, highest fidelity FM reception and most important FM multiplex stereo reception. Front panel controls provide complete tuner flexibility with smooth action AM-FM flywheel tuning, Selector Switch (Off-On, FM, FM with AFC, AM), Monaural-Stereo Multiplex Switch, and a Calibrated Stereo Separation Control. The Automatic Frequency Control virtually locks in stations and prevents drift while the AFC defeat position allows easy tuning of weaker or distant FM station adjacent to stronger stations on the tuning dial. A Stereo Separation Control allow precise channel separation according to individual acoustic requirements during FM stereo multiplex

- Foster Seeley discriminator
- AFC (plus AFC Defeat Switch) Locks In Stations—Prevents Drifting
- Stereo Separation Control
- Four FM IF Stages plus 2 AM IF Stages
- Flywheel Tuning
- 4 μ v Sensitivity For 30db Quieting
- Dual Channel Cathode Follower Output
- FM Frequency Response—1db 20-20,000

operation. Quality FM circuitry features a Foster Seeley Discriminator with 4 IF stages including discriminator, an R.F. Input stage plus Dual Channel Cathode follower output. The FM stereo MPX section utilizes an ASC-Doubler with 2 Diode Detectors plus a Dual Channel Cathode Follower Output. AM circuit feature two IF Stages plus OSC/Mixer and Diode Detector with a Dual Channel Cathode Follower Output. In addition an Automatic Volume Control (AVC) insures a constant output in tuning from station to station. Attractive low silhouette styling features brushed brass from panel with contrasting ebony finished steel enclosure. Size: 13 $\frac{1}{2}$ "x4 $\frac{1}{2}$ "x11 $\frac{1}{2}$ " D. Equipped with AM ferrite rod antenna plus FM line cord antenna. For 110-120V 60 cycle AC. G-542WX Shpg. wt., 10 lbs. Net 79.95


JUST OUT! FM-AM TUNER Superior Quality and VALUE!

49⁹⁵ NO MONEY
DOWN

Receive FM and AM broadcasts with this "best value" tuner. Delivers the same fine performance and value as the (G-542WX) KorDEX Tuner described above, but it is equipped with a multiplex output jack that will allow you to add multiplex later at your convenience with one of Lafayette's Kit or factory wired low cost multiplex adaptors. Front panel controls include: Selector Switch for OFF, FM and FM AFC positions plus flywheel tuning control for velvet smooth tuning. For 110-120V 60 cycle AC operation. Finished in attractive brushed brass with matching ebony enclosure. Size 13x4 $\frac{1}{2}$ x9". G-541WX Shpg. wt., 10 lbs. Net 49.95



Only At Lafayette!! The Superb Stereo Multiplex Components



MODEL LT-78

Brilliant Stereo Performance... LAFAYETTE FM-AM STEREO MULTIPLEX TUNER

Two 3-Gang Tuning Condensers with Added Tuned RF Stage for Exceptional Sensitivity & Selectivity

- 16 Tube Performance—12 Tubes & 5 Diodes & Tuning Meter • MPX Separation 30 db @ 400 CPS. Less than 1% Distortion • Armstrong Circuit with Dual Tuned Limiters and Foster-Seeley Discriminator • Automatic Frequency Response
- Tuned Grounded Grid R.F. Stage on AM & FM
- Flywheel Tuning • Broadband I.F. for AM
- Noise Filter Slide Switch • AM Level Control
- Stereo Dimension Control • Illuminated Multiplex Indicator

89⁵⁰
NO MONEY DOWN

No Multiplex Adapter Required!

SIMPLICITY, FLEXIBILITY AND SUPERB STYLING have been carefully integrated in this quality instrument. Offering unlimited versatility, the LT-78 features separate AM, FM and FM MULTIPLEX Reception for your listening pleasure. A complete set of controls provide for every tuner function on the front panel there is a mode selection switch with a choice of AM, FM or FM stereo, a power on/off slide switch; Variable AFC adjustable for tuning in weak stations adjacent to strong stations; Flywheel tuning for smooth rapid station selection, tuning meter for pinpointing your station to the strongest signal; a noise filter slide switch for weak stations and an illuminated multiplex indicator which shows you are in the FM stereo mode. On the rear panel there is an AM level control and a stereo dimension control to provide the right separation for your systems. Plate follower output permits using the tuner up to 50 ft. from an amplifier. FM circuitry features armstrong grounded grid low noise front end and Foster-Seeley discriminator. Superheterodyne AM circuit

with 3 stages, AVC and ferrite loopstick antenna. Specifications: Selectivity FM 200 KC band width, 6db down; AM 8 KC bandwidth, 6db down; Frequency Response: FM 20-20,000 CPS \pm 2db; Stereo Separation 30 db @ 400 cycles less than 1% distortion; Harmonic distortion less than 1% on AM to 80% modulation; HUM Level—60db; Image rejection, FM Better than 40 db, AM 70 db; I.F. Rejection, FM 70 db AM 50 db; FM Sensitivity: 2 μ v @ 20 db S/N. Meets FCC RF Radiation requirements. Tubes: 12 AX7, 12AU7, 6BE6, (3) 6AU6, (3) 6BA6, (2) 6AQ8. 6x4 plus 5 germanium diodes. Antenna Input: 300 ohms, dual stereo outlets. Each unit has been hand wired and individually tested at the factory. Superbly styled low silhouette enclosure finished in gold and white with an easy to read black dial face. Complete with case and legs. Dimensions: 15Wx9 $\frac{1}{2}$ Dx5 $\frac{1}{4}$ H. Legs add $\frac{3}{4}$ " to height. Shpg. wt., 16 $\frac{1}{2}$ lbs. LT-78WX AM-FM MULTIPLEX TUNER Net 89.50

NEW! LAFAYETTE 40 WATT STEREO FM MULTIPLEX RECEIVER AN OUTSTANDING VALUE!



Delivery July 25, 1962

A MATCHED AM-FM TUNER PLUS BUILT-IN MULTIPLEX PLUS A 40-WATT STEREO AMPLIFIER (20-WATTS EACH CHANNEL) AT LAFAYETTE'S AMAZING LOW PRICE!

- AM FM Tuner with Multiplex
- 20 Tubes—7 Diodes
- Complete Stereo Preamp Facilities
- 15 Front Panel Controls
- JUST ADD A TURNTABLE AND SPEAKERS FOR A COMPLETE STEREO SYSTEM

189⁹⁵
NO MONEY DOWN

Two 3-Gang Tuning Condensers with Added Tuned RF Stage for Superior Sensitivity & Selectivity

The Lafayette LA-226 is a self-contained instrument designed for the control and reproduction of all stereophonic and monophonic sources featuring a new built-in FM multiplex circuit. The receiver section consists of an AM/FM tuner with built-in multiplex which provides more than 30 db separation @ 400 cycles; Precision tuning meter and flywheel tuning for precise station selection. Multiplex pilot light indicates set is tuned to MPX. A sensitivity of 2 μ V for 20 db of quieting is achieved by the FM circuit with AFC and AFC defeat assuring reception of even the weakest signals. FM noise & filter slide switch cuts out unwanted station noise. The AM section features a superheterodyne circuit with AVC, and built-in ferrite loop antenna. The 40-watt amplifier section features large power transformers and a frequency response of 20-20,000 CPS \pm 2 db. Less than 1.5% harmonic distortion on all modes. Complete stereo preamp facilities provide dual concentric front panel controls for bass and treble, Volume control balance, blend for variable channel separation from 5-position selection stereo to mono, switch (AM, FM, FM Stereo, phono, AUX) 4-Position Amplifier mode switch (A, B, AB, REV), rumble filter slide switch, loudness slide switch, and on-off power switch. Rear controls include: Speaker phase switch, 8-16 ohm impedance selector switch, dimension control adjustment, speaker on/off switch, jack for stereo headphones, AC outlet, fuse and stereo tape outputs. Complete with a handsome enclosure in contrasting brown and brass—overall size: 17 $\frac{1}{2}$ Wx15Dx5 $\frac{1}{4}$ H. LA-226WX Shpg. wt., 45 lbs. Net 189.95

SPECIFICATIONS

TUNER: HARMONIC DISTORTION: .7 on FM for 100% modulation; FM Freq.-response: 20-20,000 CPS \pm $\frac{1}{2}$ db FM Sensitivity: 2 μ V for 20 db quieting; MPX Separation: 30 db @ 400 CPS. Hum level: 60 db. Image rejection: FM—50 db. AMPLIFIER: 65 db below full output for low level—75 db for high level. Power Output: 20 watts per channel. Sensitivity: mag phono 2 mv at full output, crystal input 30 mv at full output. Tone Control: \pm 12 db @ 50 CPS (bass), \pm 9 db @ 10 KC (treble) 20-20,000 CPS \pm 2 db. Output Impedance: 8 & 16 ohm, switch selected. Input Impedance: 47 K phono; .22 meg (high level) Rumble Filter —8 db @ 50 db. Phono Equalization: RIAA.

MODEL LT-80B FM TUNER READY FOR MULTIPLEX!

COMPARE FEATURE FOR FEATURE
WITH THE MOST EXPENSIVE TUNERS



NO MONEY DOWN!

49⁵⁰

• 3 GANG TUNING CONDENSER

- ARMSTRONG CIRCUIT FOSTER-SEELEY DISCRIMINATOR AND DUAL TUNED LIMITERS • AFC • AFC DEFEAT • EXTREMELY SENSITIVE — 1.5 UV FOR 20 DB QUIETING • 10-TUBE PERFORMANCE — 8 TUBES (2-DUAL PURPOSE) • 20-20,000 CYCLES \pm $\frac{1}{2}$ DB • SUPERB LOW SILHOUETTE STYLING
- TUNED GROUNDING GRID RF STAGE

Remarkable . . . Quality, performance and styling that is in every respect the equal and in many instances superior to tuners priced far above the modest cost of this instrument. Designed and constructed of the finest components, with jewel like precision (each unit is hand wired). Engineered to provide maximum FM versatility, the LT-80B is provided with a multiplex output, designed to accept a stereo FM multiplex adapter. Flywheel action tuning control. Tube complement consists

of 2-6AQ8, 2-6BA6, 2-6AU6, 1 each 6AL5 and 6X4. Handsome low silhouette enclosure will do justice to any decor. Beautifully finished in gold and white with contrasting black dial face. Complete with cage and legs. Dimensions: 11 $\frac{3}{8}$ Wx8Dx4 $\frac{1}{8}$ H. LT-80B FM Stereo Tuner Net 49.50 HTA-11WX Combination of LT-80B and LT-200 FM Multiplex Adapter. You Save 5.00 Net 99.00

NEW EASY-PAY-PLAN—SEE PAGE 54 FOR FULL DETAILS

build your own HI-FI KITS

H.H. SCOTT

NEW FISHER HI-FI KITS

CITATION STEREO KITS



NEW MODEL LT-110
WIDE-BAND FM
STEREO MULTIPLEX
TUNER KIT

- First Kit With Built-In Multiplex
- Prealigned Multiplex Section

FM multiplex tuner in kit form. Both the multiplex section and silver plated front end are factory preassembled and prealigned. You need only align the tuner's wide-bandpass IF's and detector using the meter on the tuner itself. Special shielding protects against interaction of tuner and multiplex sections. Unique circuitry eliminates multiplex interference with bias oscillator of any stereo tape recorder. Features stereo Noise Filter, Vernier Tuning, Front panel tuning meter; and Stereo Tape recorder output. IHFM usable sensitivity 2.2 microvolts. 10 Tubes, 11 diodes. Shpg. wt., 20 lbs. 15 1/2 Wx5 1/4 Hx13 1/4 D.

G-633WX (less case) Net 159.95
Leatherette metal case C for LT-110. Shpg. wt., 5 lbs. G-147W Net 13.95



MODEL LK-72
72-WATT STEREO
AMPLIFIER KIT

The LK-72 has the same output circuitry as the 299C wired stereo amplifier. Aluminum chassis and D.C. heated preamp filaments give low 80 db hum and noise. Frequency response 20 to 20Kc ± 1 db; harmonic distortion at full output 0.8%. IM distortion 9.3% (CCIF); IHFM power bandwidth 21 to 20 Kc; speaker output impedances 4, 8, 16 ohms. Front panel controls: Input selector (phono or tape head, Tuner, Extra); Equalization (NAB tape head or RIAA record equalization), Stereo Selector Switch; separate tone controls for channels A & B Stereo Balance; Derived Center Channel Level Control; Loudness On-Off; Scratch Filter; Tape Monitor; Loudness Compensation. 15 1/2 Wx5 1/2 Hx13 1/4 D.

G-625WX (less case) Shpg. wt., 35 lbs. Net 159.95
Leatherette metal case for LK-72 kit. G-147W Shpg. wt., 5 lbs. Net 13.95



THE FISHER KX-200 80
WATT STEREO CONTROL
AMPLIFIER KIT
169.50

Fisher engineers have developed a new concept of kit design known as Stratakit. Major components are premounted and wires are pre-cut. The KX-200 amplifier/preamp specifications are: 80 watts IHFM music power output; (35 watts RMS each channel) Harmonic distortion (at rated output) 0.4%; IM Distortion (SMPT, at rated output) 0.8%; Frequency response (overall 20-20,000 cps ± 1 db—total hum and noise 80 db (450mv rep); Channel Separation at 1 KC better than 50 db. Tubes: 6 ECC83, 4-7591, 2-SD95A, 2-SD91A. Built-in D'Arsonval calibration meter. For 117V, 60 cycles AC. Size: 15 1/2 Wx12 1/2 Dx5 1/4 H. Shpg. wt., 30 lbs.

G-666WX KX-200 Amplifier, less case Net 169.50
G-109W MC-2 Metal Cabinet for KX-200. Shpg. wt., 9 lbs. Net 15.95



NEW FISHER KM-60
FM STEREO TUNER KIT

A high quality FM Stereo multiplex tuner kit with famous Fisher features. Ultra-Sensitive Golden Cascade Front-End provides clear reception even from distant stations, exclusive Stereo Beam instantly indicates whether or not a station is broadcasting in stereo, precision D'Arsonval tuning meter which is also used in alignment of IF and ratio detector sections; pre-aligned front-end and multiplex section. 4 IF stages and 2 limiters. SPECS: Sensitivity 0.6 microvolts at 20db quieting, Signal-to-noise ratio 70db at 100% mod., Freq. response — 1db 20-15,000 CPS. 11 Tubes 12 Diodes, Selenium rectifier. Complete with illustrated manual. Size: 15 1/2 Wx12 1/2 Hx13 1/4 D. Shpg. wt., 18 lbs. Less cabinet.

G-667WX Net 169.50
MC-2 Metal cabinet for KM-60 Net 15.95
G-109W Shpg. wt., 9 lbs.



FISHER SLIM-LINE SPEAKER
SYSTEM KITS MODEL KS-1

The Fisher KS-1 Slim-line Loudspeaker System lends itself to virtually any type of installation. It can be wall mounted, placed on the floor or in a bookshelf. Composed of a 10-inch free-piston woofer with 30 CPS free-air resonance and 4-lb. magnet; 5-inch AcoustiGlas packed midrange unit, LC type B-way crossover network, 8-ohm impedance. Supplied complete with cabinet, grille cloth, AcoustiGlas padding and instructions. Size: 18Wx24Hx5 1/4 D. Shpg. wt., 26 lbs.

GB-464WX KS-1B Speaker System Kit, Unfinished Net 59.50
GB-465WX KS-1W Speaker System Kit, Walnut Net 64.50
GB-462WX KS-1AB As above, Factory Assembled, Unfinished Net 84.50
GB-463WX KS-1AW As above, Factory Assembled, Walnut Net 89.50



CITATION III
FM STEREO TUNER KIT

Famous Citation tuner III now has built-in multiplex. Outstanding sensitivity is featured with a completely assembled and prealigned front end and converting IF sections. Maximum selectivity is assured by Nuvistor Front end followed by three wide band IF stages. Sensitivity 0.65 microvolts for 20db quieting. Frequency response ± 0.5db, 1-52,000 CPS, (mono) 10-15,000 CPS (stereo); Dual cascaded gated beam limiters; Foster-Seeley discriminator. Hum: 65db below 100% modulation. Stereo Separation, —30db at 10-15,000 CPS. 6x14 1/2 Wx12 1/4 H. For 110-120V AC. Shpg. wt., 33 lbs.

G-364WX Citation III Stereo Tuner Kit Net 219.95
G-374WX Citation III Stereo Tuner wired Net 299.95
G-365WX Citation III FM Tuner Kit with multiplex output jack. Shpg. wt., 32 lbs. Net 149.95
G-366WX Citation III wired with Multiplex output jack Net 229.95
G-232W WC1 walnut enclosure for Citation III and III Net 29.95
G-373WX Citation III MA FM Stereo Adapter wired. Shpg. wt., 3 lbs. Net 79.95



CITATION HI-FI EQUIPMENT
CITATION I KIT
Stereo Preamp Control Center

A high quality stereo-monaural preamp-control unit. Inputs: 12 (six pairs) — Aux, Tape Amp, Tuner, low-level phono, high-level phono. Outputs: 5-Two main preamp outputs plus a third channel output, two tape outputs for recording. Mode selector chooses output types: stereo, 0.05% at 2 volts. RESPONSE: to ± 5 db 5-80,000 cps. Tubes: 9-ECC83/12AX7 plus silicon rect. POWER REQUIREMENTS: 110V AC, SIZE: 14 1/2 Wx12 1/4 Dx6 1/2 H. Shpg. wt., 20 lbs. Gold & Charcoal brown finish.

G-230WX Kit Net 159.95
G-231WX Wired Net 249.95
G-232W Walnut Enclosure Net 29.95



CITATION II KIT
120 Watt Stereophonic Hi-Fi Power Amplifier

Two ultra-linear type amplifiers deliver 60 watts each channel or a total of 120 monaural. Frequency Response: 18-40,000 cps ± 0 to —1.0 db @ 60 watts, 2-80,000 cps ± 0 —1.0 db @ 1 watt; IM Distortion: Less than .5% @ 60 watts. Harmonic Distortion: Less than 0.5%. Output 4, 8, 16 ohms. Tubes: 6-12BV7, 4-KT88, plus 4-Silicon Diodes & 1 Selenium rect. Dimensions: 16 1/2 Wx9 1/2 Hx11 1/2 D. Charcoal Brown & Gold Finish. Shpg. wt., 60 lbs.

G-233WX Kit Net 159.95
G-234WX Wired Net 229.95
G-235W Charcoal Brown Metal Enclosure Net 7.95

NEW! harman kardon AWARD SERIES KITS



MODEL F 50XK
12995 NO MONEY DOWN



MODEL A 50K
11995 NO MONEY DOWN



MODEL A 30K
7995 NO MONEY DOWN

MODEL F-50XK FM Stereo Multiplex Tuner Kit. Special wide-band audio output circuitry, 3 IF stages, and triode grounded grid RF stage provide extended sensitivity and Freq. Response. Sensitivity: IHFM 2.8 MV @ 20 db S/N. Freq. Response 10-52,000 cps ± 1 db. Built-in multiplex and tuning meter. Brushed gold panel. Size: 15 1/4 Wx5 1/4 Hx12 D. Shpg. wt., 22 lbs.

G-659WX No Money Down Net 129.95

MODEL A50K 50 Watt Integrated Stereo Amplifier Kit. 25 watts per channel music power output. Features center channel gain control, blend control with lamps and front panel stereo headphone jacks. 9 tubes. Freq. Response 12-70,000 cps ± 1 db. Hum — 85 db. High level input sensitivity, 200 mv. for rated output; phono input 2 mv., 12 Stereo Inputs, 2 Mag. phono, 2 tape head, 2 crystal phono, 2 tuner 2 tape amp., 2 aux., 2 tape monitor. Brushed gold front panel. Size: 15 1/4 Wx5 1/4 Hx12 D. Shpg. wt., 32 lbs.

G-660WX No Money Down Net 119.95

MODEL A30K 30 Watt Integrated Stereo Amplifier Kit. Features continuously variable blend control to fill the "hole in the middle," gauged bass and treble controls. Freq. Response: 15-70,000 cps ± 1 db. Hum — 80 db. Excellent B+ regulation by silicon diode power supply. 8 Stereo inputs. Brushed gold front panel. Size: 15 1/4 Wx5 1/4 Hx11 1/2 D. Shpg. wt., 25 lbs.

G-661WX Net 79.95

FAIRCHILD RECORDING EQUIPMENT



2-SPEED
MODEL 440
TURNTABLE KIT

A high fidelity turntable kit. 2-speed operation (33 1/3 and 45 rpm), single belt drive, Speed Sentinel control varies turntable speed ± 1 1/2%, highly styled and precision turntable platter. Strobe disc included to determine correct speed. Size: 19x16x10". Complete with unfinished mounting board, but less base, 19x16". For 110V, 60 cycle, AC. Requires 1 1/2" clearance above turntable, 3/2" below. GR-276W Shpg. wt., 21 lbs. Net 58.00

GR-274WX Net 69.95

MODEL 440CBW. Base for above. Includes walnut mounting board, walnut wraparound. 19x16x8". Shpg. wt., 12 lbs. Net 19.95

GR-275W Net 19.95

Jensen 57.75 KTF-3 SPEAKER KIT

Provides the necessary speaker components for TF-3 performance in a home-built or separately bought cabinet. Kit includes the woofer, two midrange units and tweeter of the TF-3 system. Includes M-1/H-F balance control, crossover network, wiring cable, enclosure vent tube and full instructions for enclosure construction. SPECIFICATIONS: Frequency Range: 25 cps to beyond audibility. Crossovers: 2,000 and 10,000 cps. Speaker System Power Rating: 25 watts. Impedance 8 ohms. GS-313 Shpg. wt., 11 1/2 lbs. Net 57.75

FAIRCHILD COMPANDER KIT

Automatic Sensing Device
The Fairchild Compander is a deluxe automatic sensing device that allows recreation of original performance dynamics in existing playback equipment for discs, tape or FM. The Compander is not an amplifier. It does not introduce distortion or require a 110 V AC power supply. The Compander is inserted between the output program source: pickup, tape unit, or FM and the input of preamp, or integrated amp. By deriving and analyzing a signal from the existing amplifier — the Compander automatically increases your amplifier gain to allow dynamic expansion of high level signals to compensate for the controls placed on the original recording. Surface noise; turnable and system noises are minimized. Right or left information is displayed giving insight into original studio mike placement. Dynamically expands signals—increases separation effects of signal. Also can be used as signal compressor for background music control. Specifications: Input Imp. 47 K ohms both channels. Output Imp. 47 K ohms. Control circuit imp. 4-16 ohms; Min. Control Circuit volt. 25V AC. Expansion 8 db max/channel. Compression 20 db max/channel. Distortion—none. Freq. Response — Flat through entire audio range. AC Power Requirements — none. Dim.: 8 1/2 Wx5 1/2 Hx2 1/2 D. Shpg. wt., 6 lbs.

G-676WX Compander kit Net 59.95
G-675WX Compander Factory Wired and Assembled Net 75.00



TEICO HI-FIDELITY COMPONENTS • Kits and Wired



NEW! EICO ST-84
STEREO PREAMPLIFIER

A comprehensive self-powered stereo preamplifier which features 0.05% distortion or less on all basic functions (mag phono, tuner, tape). Input and mode selectors each have seven positions each for maximum flexibility. Independent bass and treble controls provide true variable crossover control to boost or cut. Tape recorder outputs are not affected by controls. Has high and low frequency filtering, Tape Speed equalization and monitor switches for top tape control flexibility. Also includes level, and balance controls and a loudness switch. Frequency Response is 0.3 db from 5 to 25,000 CPS. Hum and noise is a 65db for low level inputs and —75db for high level inputs. RIAA phono equalization and NARTB for Tape. Tube Complement five 12AX7/ECC83 plus one 6X4. Metal cover is included. Finished in brush gold aluminum faceplate with brown accenting band. Size: 5 1/2 Wx15 1/2 Hx8 3/4 D.

G-523WX ST-84 Kit Net 59.95
G-524WX ST-84 Wired Net 89.95



EICO 12-WATT HI-FI AMPLIFIER... PREAMP

Compact, attractively styled amplifier with complete front end facilities and true high fidelity performance. Direct tape head and magnetic phono inputs with NARTB (tape) and RIAA (phono) feedback equalizations. Power output: 12 watts continuous, 25 watts peak. Intermodulation distortion 1.5% at 12 watts, db at 1 watt; 25,000 cps ± 0.5 db at 12 watts. Controls: Selector switch, level control, bass and treble controls. Speaker connections for 16, 8, and 4 ohms. Tubes (2) ECC83/12AX7, ECC82/12AU7, (2) EL84, E281. Size: 3 1/2 Wx8 1/2 Hx4 1/2 D.

G-424 Kit — Shpg. wt., 13 lbs. With instructions. Net 34.95
HF12 As above, but factory wired. Net 57.95
G-425



EICO MODEL HFT 90K FM TUNER KIT

Factory pre-wired and pre-aligned front end. Pre-wired tuning eye assembly. Stereo FM multiplex reception with adaptor, "traveling" tuning indicator, fly-wheel tuning and AGC. SENSITIVITY: 1.5 uv for 20 db quieting; 2.5 uv for 30db quieting; full limiting from 25 uv. INPUT: 300 ohm balanced. OUTPUTS: Cathode follower and multiplier. TUBES: 1-ECC85/40 watts at 110-120 volts AC, 50-60 cycles. Complete with instructions. 12x8 1/4 Wx3 1/2 H. Shpg. wt., 10 lbs.

G-422 Kit Net 39.95
G-423 HFT-90 Same as above, but factory wired Net 65.95
G-431 E-3 Cover for HFT-90. Shpg. wt., 3 lbs. Net 3.95



EICO ST-40K 40-WATT STEREO
INTEGRATED AMPLIFIER KIT

The ST-40 contains 2 twenty watt amplifiers and a complete stereophonic hi-fi control center on one chassis. FEATURES: Switched sets of stereo inputs including magnetic phono (2), tape head, preamplified tape, FM-AM stereo tuner, FM-FM multiplex, and Auxiliary. Balance Check switch. Loudness/level switch. Bass and treble controls. Other controls include: Six position mode selector, tape monitor, scratch and rumble. Output 4, 8, and 16 ohm. Third channel speaker connection. Specifications: IM distortion — 2% at 40 watts; Harmonic Distortion — 1/2% at 40 watts; Frequency response — ± 1/2 db. 20-20,000 cps. Shpg. wt., 27 lbs.

G-520WX Net 79.95
G-521WX Same as above, but wired. Net 129.95



EICO ST-70K 70 WATT STEREO
INTEGRATED AMPLIFIER KIT

Consists of 2-35 watt amplifiers and a complete stereophonic hi-fi control center on one chassis. Stereo inputs in switched sets including: 2 magnetic phono (one for turntable, one for changer); tape head, preamplified tape, FM-AM stereo tuner, FM-FM Multiplex, and Auxiliary. Controls: Level with balance check switch and loudness/level switch; bass, treble, six-position mode selector, blend, tape speed, tape monitor, scratch, and rumble. Output: 4, 8, and 16 ohm speaker. Third channel output available. Specifications: IM distortion — 2% at 70-watts. Harmonic Distortion — 1/2% at 70 watts. Frequency response — ± 1/2 db, 20-20,000 cps. Shpg. wt., 35 lbs.

G-518WX Net 94.95
G-519WX As above, but factory wired. Net 149.95



NEW! EICO RP-100K
TAPE DECK KIT

A new, precision stereo/monaural tape deck, the RP-100 provides stereo/mono 1/4 track erase, record, and playback; plus 1/2 track stereo/mono playback. Separate record and playback heads and preamps permit simultaneous stereo playback from tape while recording. Sound-on-Sound recordings can be obtained without changing any connections. Features: Dual meters for monitoring stereo recording levels and separate line and mic. (dynamic) mixing controls for each channel; SPECIFICATIONS: Tape speed — 7 1/2 or 3 1/4 ips; up to 7" reel size; Flutter and Wow — 0.2% at 7 1/2 ips, 0.25% at 3 1/4 ips; Frequency response: 30-17,000 cps at 7 1/2 ips, 40-15,000 cps at 3 1/4 ips; Signal-to-Noise ratio — 53 db, or better. Timing accuracy — 0.3%. Dimensions: 15 1/4 Wx13 1/4 Hx7 1/2 D. Shpg. wt., 28 lbs.

RP-100K semikit; includes transport completely assembled and tested with 3 heads: stereo record, and stereo playback preamps in kit form. Net 299.95
RK-275WX Net 299.95
RP-100W wired and tested with 3 heads, stereo record, playback preamplifiers. Net 399.95
RK-276WX Net 65.95
Model CC-2 Luggage Type Carrying Case with detachable cover. For RP-100 Net 29.95
RK-277W Shpg. wt., 13 lbs.

NEW! LAFAYETTE MULTIPLEX ADAPTER KIT MODEL KT-220

Amazing!

- Separation 30db at 400 cycles
- Self-powered
- Ideal for Lafayette tuners equipped with MPX output Jacks

Quality Stereo FM Multiplex
At minimum cost

ONLY **19⁵⁰**



Enjoy thrilling FM Stereophonic sound from any recent Lafayette Tuner or any other quality wide-band FM or FM-AM tuner equipped with multiplex jacks. Hear the full range of audio frequencies in all the realism and magnificence of stereo sound by simply adding this low-cost Lafayette Multiplex adaptor kit. Engineered for anyone to build and operate, the KT-220 is easily connected to your tuners built-in multiplex output and special instructions are provided for connection to tuners without MPX output jacks. Coils are pre-aligned and only minimum adjustments are necessary. Self-powered, the unit may be hidden out of sight or installed remotely from your tuner.


The specifications speak for themselves: Separation—30db at 400CPS; Distortion—below 1%, noise filter controls: on-off with pilot light, Separation control, Tubes: 12AU7, 6BN8, 12AX7 plus a silicon rectifier.

The KT-220 Multiplex adapter is supplied complete with shielded cable for input and output connections; metal case and all parts plus the famous Lafayette detailed kit instruction manual. Front panel is finished in beige and ivory trim with contrasting beige and brown cabinet. Size 8 1/2" x 4 3/4" x 4 1/2" H for 110-125 volts, 60 cycle AC.

KT-220 Shpg. wt., 4 lbs.

Net 19.50

NEW! TruTest™ STEREO/5 AMPLIFIER




- Individual Stereo Volume-Balance Controls
- For Both Stereo and Monaural
- Fully Wired—Ready For Stereo

Only **9⁹⁵**

One of the finest stereo values we have ever offered. This rugged, precision made dual channel stereo amplifier will amaze you with its fine quality. . . . Ideal for that low cost stereo system you're planning for your home or business. Perfect for converting your present console or portable to stereo. Controls include separate left channel and right channel volume controls, stereo-monaural mode switch, tone control switch and on-off switch. Provision for crystal or ceramic cartridge. 4 ohm output terminals accept most speakers. Tube complement: 2-35C5, 1-35W4 and 1-12AX4. Size: 4 1/2" x 5 1/2" x 4 1/2" D. 115 volt 60 cycles. Shpg. wt., 5 lbs.

Net 9.95

COMPLETE STEREO PHONO SYSTEM TruTest™



44⁵⁰

NO MONEY DOWN

SK-228

PK-605W


Now you can have genuine component stereophonic sound at the lowest price ever. Complete in every detail this system consists of:

The TruTest Stereo/5 Amplifier. Lafayette AUTOMATIC 4 Speed Stereo Record Changer that plays Stereo, LP and 78 RPM records and features quality Ronette Ceramic Stereo Cartridge. Automatic 3-way Shut-off, Record Intermitter, heavy precision balanced turntable and constant speed motor; and 2 Lafayette SK-228 "Music Mite" Speakers in attractive Mahogany. Each speaker system is supplied with 25 feet of hook-up cable and measures only 9 1/4" x 5 3/4" x 4 1/4" D. Shpg. wt., 20 lbs. Less Changer Base.

PK-627WX
PK-607W Mahogany Base for Changer
PK-609 45 RPM Spindle for Changer

Net 44.50
Net 3.95
Net 1.49

JUST OUT!! LAFAYETTE SK-228 "MUSIC MITE" SPEAKER



- AMAZING TONAL QUALITY
- CONTAINS SPECIAL 6x4" OVAL SPEAKER
- HANDSOME MAHOGANY FINISHED WOOD ENCLOSURE
- EQUIPPED WITH 25 FT. OF EXTENSION CABLE

Only **8²⁵**

Truly amazing tonal quality—Utilizing a specially designed 6x4" oval Speaker in a rigid rear vented wood enclosure this new speaker unit delivers a quality of reproduction out of all proportion to its small size. It measures only 9 1/4" x 5 3/4" x 4 1/4" D. Ideal for that inexpensive music and/or paging installation you've wanted for your store, office, den or kitchen. Use two for stereo. May be connected to either 8 or 4 ohm amplifier outputs. Supplied with 25 ft. of extension cable. Cabinet is attractively finished in mahogany.

Net 8.25

NEW! pioneer MODEL SE-1 STEREO HEADPHONES



19⁹⁵

- Actually 2 High Fidelity Dynamic Speakers
- Frequency Response 25 to 15,000 Cycles
- Soft Foam Rubber Ear Pads
- Frequency Response 25 to 15,000 Cycles
- Actually 2 High Fidelity Dynamic Speakers
- Soft Foam Rubber Ear Pads

For the audio connoisseur who demands the finest in stereophonic headphone performance, the Pioneer Stereophones combine broad frequency response and faithful reproduction with comfort-oriented design, to fulfill the most exacting requirements. The Stereophones are actually two 2 1/2" high fidelity dynamic speakers with a frequency response range of 25 to 15,000 cycles. Perfect for stereo and monaural operation, the headphones are rated at 1/2 watt maximum input; impedance, 8 ohms per phone. The soft foam rubber ear pads provide extremely comfortable listening, help to keep out noise and maintain an excellent bass response. Imported.

F-770 Shpg. wt., 2 lbs. Net 19.95
Model SE-2 resistor box for SE-1. Permits flexible one-switch changeover from speakers to Stereophones. Net 4.95
F-800 Model SE-3 "Y" connector for connecting 2 or more sets of headphones to a single source. Net 2.45
F-801 Model SE-4 12' extension cord for SE-1 phones. Net 2.95
F-802

NEW! REVOLUTIONARY pioneer STEREOSCOPE! NOW! PLAY YOUR STEREO RECORDS ON ANY TURNTABLE WITHOUT AN AMPLIFIER OR SPEAKERS.




- Attaches in Minutes
- Frequency Response—30-15,000 CPS
- Comes complete with one head set—up to 4 people can listen by adding accessory earphones!

Original Price 29.95
Only **9⁹⁵**

Listen to your stereo records as you've never heard them before—without amplifier or speaker—no electronic devices of any sort between your ear and the record. . . . a range of distortion free, full-bodied sound that will amaze you. These headphones are driven by variations in pressure transmitted by the specially designed pickup arm. The sound is then transmitted by a set of pipes to the specially designed earphones. A handy, easily adjusted control unit inserted in the pipe provides a separate volume control for each channel and a mixing control to govern channel separation (from full stereo to monaural operation). Frequency Response 30 to 15,000 CPS. Tracking force for pickup, 3-6 grams. Accessory earphone kits permit as many as 4 persons to enjoy the same recording. Easily mounted on virtually any turntable. Complete with special pick-up-arm, sapphire needle, mounting base, suction base, volume control unit, connecting tubes, earphones and mounting hardware. Shpg. wt., 4 lbs.

PK-596 SH-100 Stereoscope Net 9.95
PK-597 SH-101 Additional earphone kit Net 2.95
PS-97L NSH Diamond replacement needle Net 3.49

NEW OUTDOOR WEATHER-PROOF SPEAKER



The Same Indestructible Speaker Specified By The Navy For Our Atomic Submarines!!

- Frequency Response: 100 to 10,000 CPS
- Compact — Measures Only 3 3/4" x 3 3/4" x 2 1/2" D
- Completely Weatherproof & Dustproof
- Specially Designed Plastic Impregnated Cloth Speaker Cone
- 3.2 Ohm Imp.


4⁷⁹

Compact, Weatherproof, Dustproof. . . . virtually indestructible. What's more you'll be amazed at it's sound. So rugged it will withstand immersion in boiling water, and is impervious to salt spray. The Speaker utilizes a plastic impregnated cloth cone, spider and dust cap material with an aluminum voice coil and zinc plated frame. The rugged enclosure is constructed of 20 gauge cadmium plated steel. Enclosure is equipped with an RCA Type Phone Jack, Key slot mounting hole plus a mounting cutout to accept a volume control, on-off or push-to-talk switch. Ideal for outdoor extensions, patios, pools, skating rinks, barns, grain elevators, open fields, paging. Use in industrial plants where corrosive atmosphere destroys other speakers. SPECIFICATIONS: Response: 100 to 10,000 CPS. Shock Test: withstands up to 50 G's. Voltage: withstands up to 100 volts RMS. Temperature Extremes: from -80°F to 160°F. Size: 3 3/4" x 3 3/4" x 2 1/2" D.

SK-209 Shpg. wt., 5 lbs.

Net 4.79

STEREO AUDIO ANALYST™



Single Needle Dual Channel VU Balance METER

- UNIQUE TWO COIL GALVANOMETER TYPE PRECISION METER MOVEMENT
- SEVEN RANGES OF METER SENSITIVITY
- PROVISION FOR USE AS VU METER AND TAPE RECORDER LEVEL INDICATOR
- MAXIMUM METER SENSITIVITY 120 ua

11⁹⁵

Provides the solution to all stereo balancing problems. When both signals are equal and balanced the resultant deflection on the scale will measure 0. Individual channels may be measured by two slide switches. Stable meter action and protection from peak voltages is provided by special damping networks. Single seven-step range control serves for both channels and facilitates use of meter with all amplifier power levels. By properly positioning this control the movements may be used as VU meters when terminated across the 600-ohm load. The scales are calibrated in "Volume Units". Sensitivity is 1.2 volts for 0 vu for 100 percent indication. Finished in a rich satin gold. Overall size is 4 3/8" x 5 1/2" x 4 3/8" W. Shpg. wt., 2 lbs.


TM-66 Audio Analyst

Net 11.95

LAFAYETTE MINIATURE HI-FI SPEAKER and ENCLOSURE

- ATTRACTIVE MAHOGANY FINISHED WOOD CABINET
- COMPLETE WITH 25 FEET OF CABLE

6⁹⁵



Enjoy music everywhere in your home with this amazing Lafayette miniature speaker system. Perfect as an extensor speaker for your den, basement, kitchen or bedroom. Use two as extension speaker units for stereo or with your TV and Radio. Housed in a beautiful mahogany—finished wood cabinet with ventilated back cover, the 5-watt 4x6" speaker is designed to work from either 4 or 8 ohm outputs. System is supplied with 25 feet of cable which should meet any hook up requirement. Over-all size: 9 1/2" x 7 3/4" (inc. feet) x 3 3/8" D.

SK-109 Miniature Speaker System. Shpg. wt., 5 lbs.

Net 6.95

LAFAYETTE BREAKS THROUGH THE STEREO PRICE BARRIER



A COMPLETE MATCHED STEREO PHONO SYSTEM FEATURING THE PHENOMENAL NEW LAFAYETTE LA-210 STEREO AMPLIFIER

94⁹⁵
NO MONEY DOWN

Outstanding Stereophonic Performance at a Budget Price


● LAFAYETTE LA-210 10-WATT STEREO AMPLIFIER, A superb stereo performer providing 10-watts each stereo channel . . . more than enough power for room filling stereophonic sound. Frequency Response is 30-20,000 cps with Hum & Noise 65 db below rated output. Contains a full range of inputs and controls.

● LAFAYETTE PK-605 4-SPEED STEREO RECORD CHANGER. Contains famous Ronette Stereo Cartridge and is complete with your choice of Mahogany or Walnut base. Superior performance without rumble or wow provided by a heavy precision balanced turntable and

constant speed motor. Features include full automatic operation with Intermix and automatic shut-off after last record.

● 2-LAFAYETTE SK-124 2-WAY BOOKSHELF SPEAKER SYSTEMS (Choice of Mahogany or Walnut). These famous Lafayette speakers feature a unique dual cone construction to provide smooth distortion-free response with deep fundamental bass and clear pure highs.

Complete stereo system as listed above. Shpg. wt., 67 lbs. LS-210WX Net 94.95



SK-124



PK-605

LAFAYETTE LA-210 STEREO AMPLIFIER **37⁵⁰**
No Money Down

Same "best value" stereo amplifier as featured in above stereo system. Styled in contrasting gold and white. For 117V 60 cycle operation. Shpg. wt., 15 lbs. LA-210 Net 37.50

LOW COST HIGH VALUE



LA-212 24 Watt Stereo Amplifier

COMPLETE 24-WATT MATCHED COMPONENT STEREO PHONO MUSIC SYSTEM

COMPONENTS

| | |
|--|--------|
| LAFAYETTE LA-212 24-Watt Stereo Amplifier | 49.95 |
| GARRARD AUTOSLIM 4 Speed Stereo Record Changer | 39.50 |
| WOODBASE FOR CHANGER (Specify Walnut, Mahogany or Blonde) | 3.95 |
| AUDIO EMPIRE S108 Diamond Needle Stereo Cartridge | 35.00 |
| 2-LAFAYETTE SK-124 Ultra-Compliance 2-Way Speaker Systems (Specify Walnut or Mahogany) | 34.00 |
| REGULAR CATALOG PRICE | 162.40 |

INCREDIBLY PRICED AT ONLY

128⁴⁵ NO MONEY DOWN



SK-124



GARRARD AUTOSLIM



CHANGER BASE



G-542WX

LAFAYETTE LA-212-WATT STEREO AMPLIFIER

49⁹⁵ NO MONEY DOWN

- Power Output 24 Watts RMS (12 Watts Each Channel)
- Frequency Response 20-20,000 CPS ± 1 db
- Harmonic Distortion Less Than .5% (at 1000 cps)
- IM Distortion Less Than 2%
- Hum & Noise —72 db Tuner input, —52 db Phono/ Input

- Individual Bass & Treble Controls For Each Channel
 - Variable Balance Control
 - Attractively Styled With Rich Brown Low Silhouette Enclosure & Contrasting Brushed Aluminum Front Panel
 - Size 4½Hx9Dx14"W
 - For 110-120V 60 Cycles AC
- LA-212 Shpg. wt., 21 lbs. Net 49.95

CHOICE OF ONE



THE FAMOUS SHURE M3D CARTRIDGE

Substitute this famous Shure M3D Diamond Stereo Cartridge in place of any of above 4 cartridges. Add \$4.10 to system price.

Incredible Price—Incredible Value—Incredible Performance . . . A complete stereo phono system selected and matched by Lafayette's audio experts for outstanding value and performance.


Complete stereo system as listed above with your choice of either the Audio Empire S108, Pickering 380C, Shure M7D or GE VR1000-7 diamond needle stereo cartridges.

LS-312WX Shpg. wt., 65 lbs. Net 128.45
Same as LS-312WX listed above plus the G-542WX FM-AM Stereo Multiplex Tuner. Net 202.95
LS-313WX Shpg. wt., 75 lbs.

LAFAYETTE 40 WATT RECOMMENDED MATCHED STEREO SYSTEM

COMPONENTS

| | |
|---|--------|
| LAFAYETTE LA-240 40-watt Stereo Amplifier | 79.95 |
| GARRARD AUTOSLIM 4-Speed Record Changer | 39.50 |
| WOOD BASE FOR CHANGER (Specify Walnut, Mahog. or Blonde) | 3.95 |
| AUDIO EMPIRE S108 Diamond Needle Cartridge | 35.00 |
| 2-LAFAYETTE SK-58 Free Edge 12" Coaxial Speakers @ 29.50 each | 59.00 |
| REGULAR CATALOG PRICE | 217.40 |



2 Lafayette Eliptoflex Bookshelf Enclosures

CHOICE OF ONE




LAFAYETTE SPECIAL SYSTEM PRICE

182⁹⁵
NO MONEY DOWN

YOU SAVE 34.45

Choice of Speakers



LAFAYETTE LA-240 40-WATT STEREO AMPLIFIER

79⁹⁵
No Money Down

- Total Harmonic Distortion at 1 KC.
 - Frequency Response 12-100,000 cps 1 db at 1 watt
 - Hum & Noise: 80 db Below Rated Output
 - Dual Concentric Bass & Treble Controls
 - Variable Separation Control Eliminates Exaggerated Channel Separation
 - Superb Low Silhouette Styling with Gold Finish Enclosure Set Off By An Ivory & Gold Front Panel
 - 14½Wx10½Dx5¾"H
 - For 115V 60 Cycles AC Operation
- LA-240WX Shpg. wt., 25 lbs. Net 79.95



SK-58 SPEAKERS



"TRIHELIX" SPEAKERS SK-180



GARRARD AUTOSLIM



LAFAYETTE LA-55

LAFAYETTE LA-55 15-WATT MONAURAL AMPLIFIER

The most extraordinary Hi-Fi value ever offered

44⁵⁰
NO MONEY DOWN

- Frequency Response: 15-30,000 CPS
 - Hum 65 Db Below Rated Output
 - Power Output 15 Watts
 - Harmonic Distortion Less Than .3%
 - Sensitivity: 3 MV Mag. Phono
 - 5 Input Channels
 - Rumble Filter
 - Beautifully Styled
 - EL84 Output Tubes in Push-Pull
- LA-55WX Shpg. wt., 20 lbs. Net 44.50

LAFAYETTE SUPER-VALUE Hi-Fi PHONO SYSTEM

PLAY STEREO & MONAURAL RECORDS MONAURALLY NOW—ADD COMPLETE STEREO LATER. This economical high-fidelity system is the performance value of the year. Designed for ruggedness as well as beauty, these components will satisfy even the most critical music listener.

COMPONENTS

| | |
|--|--------|
| LAFAYETTE LA-55 15 Watt Complete Amp. | 44.50 |
| LESA CD 2/21 4 Speed Record Changer | 44.50 |
| WOOD BASE FOR CHANGER (Specify Walnut, Mahog. or Blonde) | 4.75 |
| AUDIO EMPIRE S108 Diamond Needle Cartridge | 35.00 |
| LAFAYETTE SK-124 Ultra Compliance 2 Way Speaker System | 17.50 |
| REGULAR CATALOG PRICE | 146.25 |

Complete System as above with choice of Audio Empire S108, Pickering 380C, Shure M7D or GE VR1000-7 Diamond Needle Stereo Cartridge. Net 107.50

SPECIAL LAFAYETTE SYSTEM PRICE

107⁵⁰
No Money Down

YOU SAVE 38.75



SK-124



CHANGER BASE



LESA CD2/21

CHOICE OF ONE



LAFAYETTE UNIVERSAL MULTIPLEX ADAPTER



New!

Now Enjoy All The Quality & Dynamic Brilliance of Stereo Through Your FM Tuner

COMPARE THESE QUALITY FEATURES

- 35 DB STEREO SEPARATION (AT 400 CPS)
- MATCHES WITH VIRTUALLY ALL RECENT MODEL WIDE BAND TUNERS EQUIPPED WITH MPX OUTPUT JACKS
- LESS THAN 1% DISTORTION FROM 50-15,000 CPS
- PLATE FOLLOWER OUTPUT PROVIDES FOR REMOTE AMPLIFIER CONNECTION
- SELF POWERED
- COMPLETE WITH ENCLOSURE & ALL NECESSARY CONNECTING CABLES

ONLY **54⁵⁰**
No Money Down

• 35 DB Stereo Separation (at 400 cps)

Here's the easiest, most inexpensive way for you to enjoy stereo—not records, not tapes, but stereo with all the fidelity and convenience that only FM can provide. Add this exciting new method of stereo reproduction to your component High-Fidelity system with this brilliant new stereo multiplex adapter. Performs beautifully with virtually any late model, wide band tuner equipped with a multiplex output jack and delivering a mpx output signal from 1.5 to 2 volts. Requires no special knowledge or tools to hook up—as simple and easy to connect as were your original components. Supplied with all necessary audio cables. All that's required is to merely plug the unit into your tuner, amplifier and AC outlet. Engineered for simplicity of operation, a selector switch conveniently located on the front panel provides for ON-OFF, Mono-FM and Stereo-FM. Individual pilot lights indicate when power is on and when adapter is

operating stereophonically. Beautifully styled to match any decor in textured beige finish cover and smart brushed brass anodized aluminum front panel. TECHNICAL SPECIFICATIONS: Separation: (at 400 cps) 35db; Harmonic Distortion: Less than 1% from 50 to 15,000 cps; Frequency Response: ± 1 db 50-15,000 cps. Multiplex Input Signal: .15 volts to 2V; Gain: 15 db; Output Impedance: 8000 ohms; Hum: at 60 cps for 1 volt signal input better than 60db; Rejection to 67KC; at least 50db; Rejection to 38 KC; at least 40 db. Four tubes (2 dual purpose) 12AX7, 6C4, 12BZ7, EZ80. Features notch filter for 38KC; low impedance plate follower output (for remote amplifier connection); matched diodes for optimum separation. Supplied with a special low capacitance input cable for optimum separation. Measures 4 $\frac{3}{4}$ x 5 $\frac{3}{4}$ x 10 $\frac{1}{2}$ " D. For 110-120V, 60 cycle AC. LT-200WX Shpg. wt., 8 lbs. Net 54.50

KT-650 FM TUNER KIT



ASSURANCE OF COMPONENT QUALITY
ONE YEAR PARTS GUARANTEE
All components in this unit are conservatively engineered to operate well within their performance capabilities. As assurance of this quality, Lafayette guarantees all parts including tubes for one year.

LT-650 Factory Wired & Tested **79⁹⁵**

54⁵⁰ in KIT FORM

• Low Noise Front End With Triode Grounded Grid Amplifier and Triode Mixer • Double Tuned Dual Limiters and Foster Seeley Discriminator • Sensitivity 1.25uv For 20 db of Quieting • Variable AFC Literally "Lock In" Stations • Frequency Response $\pm \frac{1}{2}$ db 15-35,000 cps • Multiplex Output For Stereo FM • Easy-to-Build Printed Circuits • Electronic Bar Tuning Indicator Tube • Pre-Aligned IF and Discriminator Coils • 3 Gang Tuning Condenser • Virtually Distortionless Performance—Less than .15% Distortion at 100% Modulation

READY FOR MULTIPLEX!

The KT-650 incorporates every desirable FM Tuner feature. A Multiplex jack provides for addition of a Multiplex Adapter for FM Stereo Reception. Flywheel weighted tuning enables effortless station-to-station tuning. Pinpoint tuning accuracy by a special electronic bar tuning indicator tube. A variable AFC (Automatic Frequency Control) is featured—literally "locks in" the station and is adjustable for tuning weak stations adjacent to strong stations. The Tuner Level Control allows precise adjustment of the Tuner output level. Superb circuitry features a low noise front end with triode mixer plus double tuned dual limiters and wide band Foster-Seeley discriminator. Sensitivity is such that in many areas the only antenna needed will be a short piece of wire, except in remote locations. Plate follower outputs permit using the tuner up to 50 feet from the amplifier. Time-saving printed circuit boards are utilized to make wiring errors almost nonexistent.

"I congratulate you people on the tremendous job you have done with this FM tuner."
Donald MacKenzie
Marlboro, Mass.

"The KT-650 performed as beautifully as it went together."
Curtis Fretz
Ontario, Calif.

"In this era of loose claims by many reputable manufacturers, you may feel a deep sense of pride in producing this kit. Every claim you made is true."
George F. Schaefer
Ramsey, N. J.

"A pleasure to build."
Francis J. Crowley
Hempstead, N. Y.

Some Letters Out of THOUSANDS

IF and discriminator coils have been carefully factory prealigned—permits you to play the tuner as soon as assembled.

The superbly styled low silhouette enclosure will do justice to any decor. Beige cover is set off by a Cream and Sienna Brown etched panel and knobs with contrasting Black Dial Face. Complete with cage, legs, interconnecting cables with plugs, indoor folded dipole antenna and alignment tool. Overall Dimensions: 14x5 $\frac{1}{2}$ x 11" D. For 117V, 50-60 cycle AC. Power consumption 40 watts. Shpg. wt., 13 $\frac{1}{2}$ lbs.

KT-650WX FM Tuner Kit Net 54.50
HTA-14WX Combination of KT-650 and LT-200 FM Multiplex Adapter. You Save 5.00 Net 104.00
LT-650WX Factory Wired & Tested Net 79.95
HTA-15WX Combination of LT-650 and LT-200 FM Multiplex Adapter. You Save 5.00 Net 129.45

COMPARE THESE SPECIFICATIONS:

Sensitivity: 1.25 microvolts for 20 db of quieting. Image Rejection: 66 db. AM Suppression: 48 db. Discriminator Linearity 600 kc. Distortion and Noise: Better than 57 db below 1.5 volts at 100% modulation. Frequency Response: $\pm \frac{1}{2}$ db from 15 to 35,000 cps with a standard 75 microsecond de-emphasis network. Audio Output: 1.75 volts at 75 KC deviation (100% modulation). Antenna Input: 300 ohm. Controls: Tuning, Level; AFC Control and Power Switch. Outputs: (2) Multiplex Adapter; Amplifier. Tube Complement: ECC85, 6BK7B, 6AL5, 2-7543, 2-6BA6, 6AV6, EM84 Electronic Bar Tuning Indicator Tube and a silicon diode rectifier.

KT-500A STEREO TUNER KIT

MADE IN U.S.A.



KT-500A **74⁵⁰**
NO MONEY DOWN IN KIT FORM

LT-50A **124⁵⁰**
NO MONEY DOWN COMPLETELY WIRED AND TESTED

• MULTIPLEX OUTPUT FOR NEW STEREO FM • TWO PRINTED CIRCUIT BOARDS AND PREALIGNED IF'S • FM AFC AND AFC DEFEAT • 17 TUBE PERFORMANCE—11 Tubes (4 dual-purpose) + Tuning Eye & Selenium Rectifier • ARMSTRONG CIRCUIT WITH DUAL LIMITERS AND FOSTER-SEELEY DISCRIMINATOR • 12 TUNED CIRCUITS AND DUAL CATHODE FOLLOWER OUTPUTS • EXTREME SENSITIVITY AND WIDE FREQUENCY RESPONSE


The KT-500A will receive simultaneous FM and AM stereo broadcasts or may be utilized for normal FM or AM reception. Provides an output for the new multiplex FM stereophonic reception. Apart from its unique flexibility, the KT-500A offers noise-free, drift-free, distortion-free performance. Each FM & AM section is tuned with its own 3-gang tuning capacitor and is provided with individual cathode follower outputs. Also, separate volume controls are provided for each channel so that when used for stereophonic reception, a proper balance between channels can be achieved. Convenient front panel switch changes from stereo to monaural use. Simplified accurate knife-edge tuning is provided by magic eye which operates independently on FM and AM. Automatic frequency control "locks in" FM signal permanently. Ferrite rod antenna with loading ring is supplied to bring in weak AM stations. Designed for easy assembly, the kit is built around two printed circuit boards and prealigned IF's insuring fast accurate construction even for the beginner. Employs a cream and brushed brass front panel plus matching brown knobs with copper inserts set in a beige finished vinyl enclosure.

KT-500AWX Stereo Tuner Kit Net 74.50
HTA-12WX Combination of KT-500A and LT-200 Multiplex Adaptor You Save 5.00 Net 124.00
LT-50AWX Same as KT-500AWX, completely wired and tested Net 124.50
HTA-13WX Combination of LT-50A and LT-200 Multiplex Adaptor You Save 5.00 Net 174.00

SPECIFICATIONS

FM CIRCUIT: Armstrong, low noise front end with triode grounded grid amplifier and triode mixer. Double tuned dual limiters, Foster-Seeley discriminator, AFC and AFC defeat. AM CIRCUIT: Superhet with 3 stages AVC, 10kc whistle filter, ferrite antenna. DISTORTION: Under 1% harmonic on FM; under 1% on AM for up to 80% modulation. HUM LEVEL: 60 db below 100% modulation. SENSITIVITY: FM—full limiting on signals as low as 1 uv, 2 uv for 30 db quieting; AM Terminal Sensitivity 5 uv. SELECTIVITY: FM 200 kc bandwidth; 6 db down, AM 8kc BW; 6 db down. FREQUENCY RESPONSE: FM 20-20,000 cps $\pm \frac{1}{2}$ db. AM 20-5,000 ± 3 db. IMAGE REJECTION: FM 40 db; AM 30 db. I. F. REJECTION: FM 70 db, AM 50 db. CONTROLS: 5 controls: FM VOL, AM VOL, FM Tuning, AM Tuning, and five position function selector switch. TUBES: 3-6BA6, 2-6AU6, 1 each 6BK7B, ECC85, 6AL5, 6BE6, 12AU7 and 6U5 tuning eye. Selenium rectifier. OUTPUT IMPEDANCE: Low impedances cathode follower. Output jacks for FM, AM or Stereo. ANTENNA INPUT: 300 ohms. Size 13 $\frac{3}{4}$ x 10 $\frac{3}{4}$ x 4 $\frac{1}{2}$ " H. Shpg. wt., 18 lbs. Kit comes complete with all parts and metal cover, a step-by-step instruction manual, schematic and pictorial diagrams.

READY FOR MULTIPLEX!
USE AS TWO INDIVIDUAL TUNERS
Use as a FM-AM Stereophonic Tuner for simulcast stereo or with a multiplex adapter for FM stereo reception
FM IN ONE ROOM . . . AM IN THE OTHER




"... this kit is excellent all the way around. It would be difficult to improve upon."
Robert Meier
Washington, D.C.

"Instructions were very good. Performance is wonderful. Best all around design."
S. B. Heberlig
Glendora, New Jersey

NEW SENSATIONAL "SLENDERETTE" SPEAKER SYSTEM

Jensen SPEAKERS and UNIVERSAL WOODCRAFTERS CABINETS



JUST 5" IN WIDTH

ONLY **39⁹⁵** each

- Low Lafayette Price
- Superb Custom Styling
- 7 Ply with Genuine Walnut Veneer
- Oil Walnut Finish

• 5-Speaker 3-Way System • 1 Jensen 8" Woofer, 2 Jensen 6" Midrange Drivers, 2 Jensen 3 $\frac{1}{2}$ " Tweeters

A new concept in the design of speaker systems enables you to place each system in almost any desired location of your choice—floor, wall, or top of bookshelf. A hermetically sealed cabinet, by Universal Woodcrafters, measuring only 5" deep, 24" in height, and 20" in length, represents an outstanding achievement in speaker system development. A beautifully styled grill harmonizes with all home interiors. Provides unbelievably fine speaker performance at a low, low Lafayette price. Contains a carefully integrated pneumatically dampened 5-speaker 3-way system engineered by Jensen with specially developed Jensen speaker components. Contains 2 special 6" woofer driver elements, one 8" midrange driver enclosed in its own sealed acoustic surroundings, completely separated from the woofer cavity, and 2 3 $\frac{1}{2}$ " fully enclosed tweeters. Woofer has an electric crossover at 400 cps. Midrange crossover at 2,000 cps. Frequency response 50-15,000 cps. 20 watt capacity. Impedance 8 ohms. Comes equipped with hangers for wall mounting. Oil walnut finish. Shpg. wt., 24 lbs. Net 39.95



SAVE WITH EXCLUSIVE LAFAYETTE HI-FI

now from Great Britain... **LAFAYETTE PERFORMANCE, DESIGN & VALUE**

THE LAFAYETTE SOVEREIGN 12 . . .

3-Way High Performance

High-Fidelity Speaker



- 2 1/4 lb. Ceramic Magnet
- "Rigidflex" Free-Edge Cone Suspension — No Standing Waves Or Surround Resonances
- 3-Way Triaxial Design Provides Unequaled Smooth Low, Mid & High Frequency Coverage
- Special Low-Resonance Woofer Cone, Stiff Mid-Range Radiator.
- Compressor-Driver Tweeter
- Frequency response: 30-20,000 C.P.S.
- Fundamental Resonance: 35 Cycles
- Power Handling Capacity: 30 Watts
- Voice Coil: 3 Inches
- Wide Dispersion Tweeter, Self Aligning Aluminum Voice Coil & Diaphragm
- High Efficiency With Low Distortion
- Superb Transient Response
- Impedance: 16 ohms
- Entirely New Unitized Die-Cast Frame

the Revolutionary LAFAYETTE



SK-146


22⁵⁰

HIGH FREQUENCY SUPER TWEETER

- Frequency response from 3,000 cps to beyond 40,000 cps
- Uniform dispersion over 120 degrees in all directions
- High-sensitivity allows use with any 4-16 ohm speaker
- Requires no high voltage or power supply
- Built-in 3,000 cycle crossover network

Achieve unequalled brilliance and musical warmth from your present speaker system or the system you're now planning. The Lafayette's Sphericon is an entirely new concept in tweeter design. Equipped with a built-in 3,000 cycle crossover network and featuring a specially designed domed phenolic diaphragm with spherical diffractor. The Sphericon produces a virtually linear response from 3,000 cps to beyond 40,000 cps, ± 2 db. to 22,000 cps. High frequencies are radiated in a 120° pattern in all directions, vertically as well as horizontally—with absolutely no trace of stridency or harshness. Unlike electrostatic tweeters the "Sphericon" is highly efficient and may easily be matched with any speaker or speaker systems . . . especially the low efficiency high compliance type. Precise matching of the "Sphericon" with today's low and medium efficiency speaker is accomplished by means of a special built-in attenuator designed not to affect or lower the efficiency of the woofer. As a result less amplification is needed assuring lower distortion. Power capacity is 30 watts. May be employed with any 4-16 ohm speaker. Beautifully styled with an acoustically designed gold anodized grill set in a sturdy satin black plastic case. Dimensions: 9x4x2 1/2"D. SK-146 Shpg. wt., 4 lbs. Net 22.50

49⁵⁰
NO MONEY DOWN



LAFAYETTE'S FINEST 12" SPEAKER

Constructed by master English craftsmen to Lafayette's rigid specifications, the Lafayette SK-210 Sovereign 12" must be considered among the very finest 12" speakers available. Engineered to satisfy the most discriminating listener, the SK-210 achieves full 3 speaker performance through its advanced triaxial design. Woofer, midrange radiator and tweeter are all axially mounted within a single rigid, unitized die cast frame, to provide an integrated, efficient wide range speaker system. Construction features incorporate a 3 inch voice coil with an exclusive "Rigidflex" cone-bonding and cone-edge treatment process to form a virtually free-edged cone suspension.

All irregularities of the audible frequency spectrum are smoothed out with standing waves and surround resonances eliminated. High efficiency and low distortion are further assured by use of a specially designed 2 1/4 lb. ceramic magnet. The quality of the Sovereign 12" is immediately evident in its uncompromising performance. Frequency response is 30-20,000 cps with a free-air woofer cone resonance of 35 cps. Bass response is tight and solid without boom or hangover to achieve a phenomenal realism. At 2000 cps, frequencies are channeled into a stiff-coned mid-frequency radiator by means of a smooth mechanical

crossover. High frequencies are reproduced with a silkiness and naturalness to beyond the limits of human hearing by means of a compression driver tweeter. This superb new tweeter incorporates a rigid, die cast, flared, hyperelliptical horn, a 1" diameter aluminum voice coil and diaphragm in a self-aligning assembly with air chamber and phase equalizer. A built in crossover allows the tweeter to take over at 5,000 cps and is provided with a high-frequency L-pad level control with attractive escutcheon and knob. Shpg. wt., 15 lbs. Recommended with Eliptoflex enclosures. SK-210 Net 49.50




ROYAL DANISH 12" DUAL CONE SPEAKER

- HIGH FLUX DENSITY

795

Lafayette brings you this fine imported high fidelity speaker at a fraction of the price you would expect to pay for so much quality. Two cones are mounted on a single axis, and provide remarkable wide range frequency response from 45 to 14,000 cps. Reproduction of program material is exceptionally lifelike throughout the entire range. An exclusive, special formula cone treatment eliminates cone rim resonance and distortion. Also, the damping effect improves transient response and prevents "hangover." Overall depth, 5 3/4". Completely enclosed. 1" diameter voice coil with an impedance of 6 ohms. Shpg. wt., 6 lbs. SK-86. 12" Dual Cone Hi-Fi Speaker Net 7.95

NOW FROM LAFAYETTE... THE "BIG 8"



34⁹⁵

NO MONEY DOWN

ONLY 8" SPEAKER WITH 1 3/4 LB. MAGNET

THE LAFAYETTE SK-212... A new 8-Inch 3-Way High-Fidelity Speaker with Performance and Capabilities of a 12-Inch Speaker

ONLY 8", BUT LOOK AT THESE SPECIFICATIONS AND PERFORMANCE:

- FREQUENCY RESPONSE: 35-20,000 CPS
- CONE RESONANCE: 45 CPS
- MAGNET: 1 3/4 LB. ALCOMAX
- VOICE COIL: 3" DIAM.
- FLUX DENSITY: 175,000 GAUSS
- IMPEDANCE: 16-OHMS
- POWER HANDLING CAPACITY: 25-WATTS
- 2,000 CPS MECHANICAL CROSSOVER 5000 CPS ELECTRONIC
- CROSSOVER WITH BUILT-IN BRILLIANCE CONTROL
- SPECIALLY DEVELOPED "RIGIDFLEX" FREE EDGE CONE SUSPENSION
- DIE-CAST FRAME
- NEW COMPRESSION-DRIVER TWEETER

LAFAYETTE'S "BIG 8"—The remarkable quality and performance of this new speaker provide it with the largest 8" of sound we've ever heard! With almost uncanny ability the SK-212 easily re-creates the entire musical spectrum from 35 to 40,000 cps; achieving a standard of natural balance distortionless performance and superb transient response normally associated with larger costlier speakers. Every musical tone is there—from powerful orchestral passages and deepest organ tones to the most delicate of solos. Precision engineered to meet Lafayette's uncompromising specifications and constructed by master English craftsmen, the SK-212 incorporates the design and construction features you'd expect to find in the finest speakers. This excellence of design is best demonstrated by its 3 inch voice coil, 1 3/4 lb. Alcomax magnet, and special "rigidflex" free edge cone suspension. Woofer, midrange radiator and tweeter are axially mounted to provide wide range speaker performance. A mechanical crossover separates bass and midrange frequencies at 2,000 cycles while 5,000 cycle electrical crossover provides a smooth transition from midrange to a newly developed compression driver tweeter. A high frequency level control allows matching of sound to individual taste and room acoustics. Recommended with Eliptoflex enclosures. SK-212WX Shpg. wt., 11 1/2 lbs. Net 34.95

LAFAYETTE SK-130 8" WIDE-RANGE HI-FI SPEAKER



NEW!

12⁹⁵

Check These Phenomenal Specifications

- ✓ Frequency Response: 40-18,000 cps
- ✓ Magnet Weight: 1 lb. High Efficiency Alcomax Magnet
- ✓ Flux Density: 13,500 Maxwells
- ✓ Power Handling Capacity: 15 Watts
- ✓ Cone Resonance: 55 cps
- ✓ Voice Coil: 1 Inch
- ✓ Impedance: 16 Ohms

ASTONISHING FIDELITY from a speaker of this size and modest price. Designed and finished with typical British craftsmanship, the SK-130 features an especially designed hyperbolic cone with a plastic surround suspension for wide compliance performance. Bass response is robust and full bodied, while the mid-range and highs are virtually transparent, with never a trace of shrillness or harshness.

The excellent wide-range response of the SK-130 make it ideal for stereo when used in pairs or perfect for use as a high quality extension speaker. Overall Diam. 8 1/2" x 4" Deep. Baffle cut-out 7 1/2". Rigid vibration-free frame is equipped with screw type terminals. See Eliptoflex enclosures recommended for this speaker elsewhere in catalog. SK-130 Shpg. wt., 3 lbs. Net 12.95

LAFAYETTE-GOODMANS SK-111 1 3/4 LB. 15" MAGNET SPEAKER



Reg. 1961
Catalog Price 54.50
NO MONEY DOWN 39⁵⁰

- Frequency Response: 30-20,000 cps.
- Cone Resonance: 25 cps.
- Power Rating: 35 watts

15" speaker with power rating of 35 watts and cone resonance of 25 cps. Employs 1 3/4 lb. Alcomax magnet and 1 3/4" voice coil, 7" deep, 15 3/8" diam. Shpg. wt., 25 lbs. SK-111WX Net 39.50

CONE TYPE METAL-CASED HI-FI TWEETER



5⁹⁵

- FREQUENCY RESPONSE 2,000-16,000 CPS
- HANDLES 20 WATTS • IMPORTED TO SAVE YOU MONEY

Without doubt one of the finest cone type high frequency tweeters we have ever tested, and is exceeded in performance only by diaphragm type tweeters. It is particularly efficient in the higher end of the audio spectrum where ordinary cone tweeters tend to lose clarity and volume. With this tweeter added to your present system, you will be able to hear all the fine transients and high notes of the upper register as they were actually recorded. Entirely enclosed in metal case with base for standing by itself, or mounting on a flat surface. Bracket is supplied for mounting on panel or in cabinet. Requires crossover network such as Lafayette LN-2. Diameter 3". Depth 2 1/8". Voice coil impedance 8-16 ohms. HK-3 Hi-Fi Tweeter—Shpg. wt., 4 lbs. Net 5.95

THE LAFAYETTE TRIHELIX[®]

3 COMPLETELY INDEPENDENT SPEAKERS WITH 3 SEPARATE VOICE COILS IN A SINGLE COMPACT UNIT

- Frequency Response 20 to 20,000 cps (30-18,000 cps \pm 3 db) • Revolutionary "Conical Stiffener" • Eccentric Baffle Mounting of Midrange & Tweeter Eliminates Interaction Between Speaker Cones
- Built-in Crossover Network and Brilliance Control • Extremely Efficient • High Excursion Woofer • Ideal For Stereo


3250
NO MONEY DOWN

Recreates The Entire Audio Spectrum With Concert Hall Faithfulness—The Lafayette "Trihelix" represents a major breakthrough in three way speaker design. Fresh engineering concepts have resulted in a single 10-inch speaker designed expressly for use in bookshelf size enclosures, that delivers a quality of performance with the unmistakable feel, presence and clarity of a 3-way speaker system. The "Trihelix" is in effect a complete three-way high-fidelity speaker system, with three mechanically and electronically independent speakers mounted within a single 10-inch frame.

Although they are individual units the 2-inch tweeter and 5-inch midrange speakers have been especially designed to compliment the woofer. Special treatment of the cones and cone edges with polyester resins provides an even distribution of mid and high frequencies without peaks or resonances. To minimize interaction between the three cones both the midrange and tweeter units are mounted eccentrically or off center in relation to the woofer. In addition the midrange and tweeter are completely enclosed by a specially designed baffle. These unusual design features result in effectively eliminating intermodulation distortion due to interaction between woofer, midrange and tweeter cones—a

common fault in conventionally designed 3-way speakers. The specially treated woofer cone employs a revolutionary "conical stiffener" located at the apex of the cone in order to stiffen the diaphragm and eliminate "break-up," thus providing a true piston action. This carefully designed cone-stiffening procedure, in addition to its very high compliance, enables the woofer to deliver a smooth, crisp, solid bass that balances naturally against a crystal clear midrange and natural treble. A built-in electrical crossover network with crossover points at 1500 cps and 5000 cps, allows each speaker to reproduce its portion of the audio range smoothly and efficiently. An adjustable brilliance control permits matching of sound to room acoustics. SPECIFICATIONS: Overall Response 20-20,000 cps (30 to 18,000 cps \pm 3 db). Free Air Resonance 35-55 cps. Impedance 16 ohms. Power Rating: 20 watts Average Program Material. Crossover Points: 1500 & 5000 cps. Overall Diam: 10". Overall Depth: 7". Baffle cut-out: 8 $\frac{1}{2}$ ". Screw type terminals are color coded for quick easy connection of amplifier leads. Shpg. wt., 8 lbs.

| | |
|--|-----------|
| SK-180 10" Lafayette "Trihelix" | Net 32.50 |
| SB-62W Adaptor Board To Fit SK-180 To 12" Cutout | Net .89 |



THE WIDELY ACCLAIMED LAFAYETTE SK-58 12" COAXIAL SPEAKER

Now!

OFFERED EXCLUSIVELY BY LAFAYETTE AT

Tremendous Savings

SUPERB PERFORMANCE GUARANTEED—OR YOUR MONEY BACK!

- RESPONSE 30-15,000 CPS
- SHEEPSKIN "FREE EDGE" CONE MOUNTING
- 1 $\frac{1}{4}$ LB. MAGNET WEIGHT
- 3" COAXIALLY MOUNTED TWEETER
- BUILT-IN LC NETWORK
- RATED AT 20 WATTS CONTINUOUS POWER


2950
NO MONEY DOWN

The World Renowned Original Lafayette SK 58[®]

Lafayette's exclusive 12" coaxial is a precision-made high fidelity loudspeaker, universally acclaimed by music lovers, hi-fi enthusiasts and professional experts alike as the greatest performance-value on the hi-fi market. It provides a truly faithful reproduction of sound without any "coloration" or distortion, its excellence being responsible for its use in innumerable high fidelity music systems today. The SK-58 incorporates such features as heavy, high flux density TSK-5 magnets for high efficiency; $\frac{3}{4}$ " wide sheepskin cone-edge suspension and special composition fibre cone material, specially treated for ultra-linear, distortion-free response; heavy rugged cast metal frame for freedom from resonances and for greater rigidity. The coaxially-

mounted 3" cone-type tweeter has a bell shaped mounting for maximum dispersion of high frequencies with no back radiation. With the built-in 3000 cps crossover network it contributes its share to the smooth delivery of the overall wide range response of 30-15,000 cps. Woofer resonance in free air is 40 cps. Speaker power handling capacity is 20 watts continuous sine wave, 35 watts peak program material. Impedance of the voice coil is 8 ohms, connections being made to chrome-plated screw terminals. Finished in gray-brown opalescent enamel, the speaker is supplied complete with "brilliance" level control. Shpg. wt., 11 lbs.

SK-58W 12" COAXIAL SPEAKER Net 29.50



LAFAYETTE SK-115A 3-WAY 15" HIGH FIDELITY SPEAKER

- Massive 5 lb. Magloy Magnet—The Most Efficient Magnetic Material Available
- Free-Edged Cone Suspension • 3 Inch Long Main Voice Coil • 12 DB/Octave Crossover Network with High Frequency Level Control • Precision Pressure Driven Horn Loaded Tweeter with Aluminum Diaphragm & Coil

Custom Built in England to Lafayette's Rigid Specifications

SUPERB PERFORMANCE—The finest British craftsmanship and advanced acoustic design, combined by Lafayette to bring you this outstanding 3-way 15" speaker. Designed and constructed to the most exacting laboratory standards, the SK-115A features a patented concentric twin gap magnetic system with a massive 5 lb. Magloy magnet. Woofer, mid-range radiator and speaker are axially mounted to achieve unexcelled, efficient, wide-range speaker performance. The woofer section with a cone resonance of 25 cps is vacuum constructed by an exclusive process. The cone rolls and edges are bombarded with minute particles of specially-blended plastic materials, to form a virtually free-edged cone suspension that eliminates standing waves and surround resonances. An automatic mechanical crossover separates bass and mid-range frequencies at 2,000 cps to a high stability mid-range radiator. A 12 db per octave LC crossover network provides smooth transition at 5,000 cps from mid-range to a precision pressure driven horn loaded tweeter employing an aluminum diaphragm and

coil in a self aligning assembly with air chamber and phase equalizer. This crossover is provided with a high frequency level control for matching of sound to room acoustics and individual listening tastes. Dimensions: 8 $\frac{3}{4}$ " Overall depth; 15 $\frac{3}{8}$ " diam. Shpg. wt., 40 lbs.

SK-115AWX Net 79.50

* Repairs which become necessary due to manufacturing defects will be made by Lafayette at no charge during the Guarantee period.

COMPARE THESE SPECIFICATIONS

• Cone Resonance: 25 cps. • Overall Frequency Response: 20-20,000 cps. • Magnet: 5 lb. Magloy Permanent Magnet • Magnetic Flux Density: 306,000 Maxwells • Crossover: 12db/Octave Twin $\frac{1}{2}$ Section LC Network • Power Capacity: 50-watts • Woofer Voice Coil Diameter: 3 inches • Tweeter Voice Coil Diameter: 1 inch • Impedance: 16 ohms.

7950
NO MONEY DOWN

MONEY BACK GUARANTEE
YOU BE THE JUDGE

Try the SK-115A for 30 days. If not completely satisfied, return it for full refund. * 1 Year Service Guarantee



LAFAYETTE "MINUETTE"[™] HIGH-FIDELITY SPEAKER SYSTEM



Room Filling Music Everywhere in Your Home!

1250
SINGLY

TWO FOR STEREO 2350

- Shelf Size — 8 $\frac{1}{4}$ Dx15 $\frac{3}{4}$ Lx5 $\frac{7}{8}$ "H
- Genuine Walnut Finish on 4 Sides
- Complete with 6' Extension Cable and Phone Plug

An exceptional speaker value... the Lafayette "Minuette" Hi-Fi Speaker System will bring music to any room in your home — and for a remarkably low cost. Designed for use where space is at a premium — ideal for the small apartment or listening area. Expand your stereo system to other areas of your home... easily used in the den, kitchen, patio or bedroom. Employs a specially designed 5x7" speaker in a rear loaded reflex type enclosure. Provides an exceptionally fine musical quality yet measures only 8 $\frac{1}{4}$ Dx15 $\frac{3}{4}$ Lx5 $\frac{7}{8}$ "H — small enough to fit anywhere. Superb Walnut finish on 4 sides allows placing speaker horizontally or vertically. Frequency Response 100-12,000 cps. Impedance 8 ohms. Rated at 10 watts. Supplied with 6 ft. of extension cable and phone plug.

SK-181 Shpg. wt., 5 $\frac{1}{2}$ lbs. Net 12.50
Save — Buy two for stereo. Shpg. wt., 11 lbs. Net 23.50
Set of two

THE LAFAYETTE CAVALIER 12" HIGH-FIDELITY 3-WAY SPEAKER

- 1 $\frac{3}{4}$ lb. High-Efficiency "Alcomax" Magnet
- Special Design For Distortionless Performance From 30-20,000 cps.
- 1 $\frac{3}{4}$ " Voice Coil
- Handles 25 Watts of Power
- Non-Resonant Rigid Frame Construction
- Crossover Complete With Brilliance Control



AN OUTSTANDING PERFORMANCE VALUE . . .

This new Lafayette Cavalier 12 integrates the finest acoustic design with precise British craftsmanship. It's advanced 3-way design with woofer, mid-range radiator and tweeter axially mounted within a specially engineered non-resonant rigid frame is capable of faithfully reproducing the complete audio spectrum from 30-20,000 cps. The most violent crescendos are easily handled without tone coloration or distortion, with superior bass response achieved even at the lowest volumes. Construction features include a 1 $\frac{3}{4}$ lb. high efficiency "Alcomax" magnet, an especially engineered "Rigidflex" cone-bonding and cone edge treatment process for a virtually free-edged cone suspension, 1 $\frac{3}{4}$ inch voice coil plus a stiff-coned midrange radiator with a 2,000 cps


mechanical crossover. A 5,000 cps LC crossover equipped with brilliance control channels high frequencies into a compression-driver tweeter; incorporating a rigid die cast flared hyperelliptical horn, a 1" diameter aluminum voice coil and diaphragm in a self-aligning assembly with air chamber and phase equalizer.

SPECIFICATIONS: Frequency Response: 30-20,000 cps, Fundamental Cone Resonance: 35 cps, Power Handling Capability: 25 watts. Magnet 1 $\frac{3}{4}$ " lb. "Alcomax," Voice Coil: 1 $\frac{3}{4}$ " diameter; Crossover: Mechanical at 2,000 cps. Electrical at 5,000 cps; Impedance: 16 ohms. Shpg. wt., 10 lbs.

SK-211 Lafayette Cavalier 12 Net 39.95



THE FAMOUS LAFAYETTE ELIPTOFLEX



ELIPTOFLEX®

COMPLETE SPEAKER SYSTEM with ENCLOSURE

NOW IT IS POSSIBLE TO HAVE THE ADVANTAGES OF A HIGH EFFICIENCY 12" SPEAKER IN A BOOKSHELF SIZE ENCLOSURE.

SPECIALLY DESIGNED 12" COAXIAL SPEAKER WITH SHEEPSKIN CONE EDGE SUSPENSION AND 1 1/4 LB. MAGNET PROVIDE A RESPONSE FROM BELOW 30 TO 15,000 CPS.

ENCLOSURE BEAUTIFULLY FINISHED ON FOUR SIDES IN HAND RUBBED VENEERS.

The "Eliptoflex" is the result of an intensive research program whose 3-fold purpose was to:

Develop a speaker system that would meet space requirements of stereo.

Utilize the full advantages of efficient 12" speaker performance.

Provide optimum performance without use of large wattage expensive amplifiers.

64⁵⁰

NO MONEY DOWN

FINISHED ON 4 SIDES

Adapts to any room arrangement. Place horizontally on shelves or vertically on the floor.

PHENOMENAL ELIPTOFLEX PERFORMANCE



PERFORMANCE EXPLANATION

The loudspeaker is mounted on a baffle recessed in the cabinet shell with the front-plate extending partially across the front surface of the baffle forming ducts or tubes from the port openings to the outside air. The elliptical cutout changes the effective length of the duct across its area. This variation in path lengths provide an extremely smooth transition from duct to free air; broadens the frequency response and provide better transient response. A triangular shaped diffracting ring mounted on the front of the baffle board virtually eliminates undesirable cancellation effects normally produced by close coupling of front and rear cone radiation. This results in a "lens" effect, changing relative particle velocities and consequently, phase relationships so as to produce a smooth transition from front to rear radiation. Comparative laboratory and listening tests indicate that "Eliptoflex" performance is demonstratively superior throughout the audio spectrum.

Patents applied for in United States, England and Canada

The Results Were Remarkable... The Eliptoflex utilizes a unique elliptical port which broadens frequency response and provides better transient response. A specially engineered diffracting ring eliminates cancellation effects between front and rear radiation. These engineering advances are coupled with the famous Lafayette free edge SK-58 12" coaxial speaker 3" cone type tweeter, 1 1/4 lb. TSK-5 high flux density magnet and special 3/4" wide sheepskin cone-edge suspension and built-in crossover network level control.


"Eliptoflex" achieves a degree of natural smoothness, low-distortion and rich robust bass hitherto found only in large enclosure speaker systems or inefficient bookshelf speakers many times its price requiring high powered amplifiers. Due to its highly efficient design characteristics the "Eliptoflex" does not require costly high wattage amplification.

The "Eliptoflex" speaker system is beautifully finished on 4 sides in a variety of hardwood veneers for attractive room placement either horizontally or vertically. Dimensions are 14"Hx23-7/16"Wx13-5/16"D. Shpg. wt., 35 lbs.

| | |
|---|-----------|
| SY-381WX "Eliptoflex" Speaker System Mahogany | Net 64.50 |
| SY-382WX "Eliptoflex" Speaker System Walnut | Net 64.50 |
| SY-383WX "Eliptoflex" Speaker System Blonde | Net 64.50 |
| SY-384WX "Eliptoflex" Speaker System Oiled Walnut | Net 64.50 |
| SY-392WX "Eliptoflex" Speaker System Unfinished furniture grade birch | Net 59.50 |

| | |
|---|-----------|
| ELIPTOFLEX ENCLOSURE LESS SPEAKER—FINISHED ON 4 SIDES | |
| CAB-83WX "Eliptoflex" Enclosure—Mahogany | Net 36.50 |
| CAB-84WX "Eliptoflex" Enclosure—Walnut | Net 36.50 |
| CAB-85WX "Eliptoflex" Enclosure—Blonde | Net 36.50 |
| CAB-86WX "Eliptoflex" Enclosure—Oiled Walnut | Net 36.50 |
| CAB-124WX "Eliptoflex" Enclosure—Unfinished Birch | Net 29.50 |

HI-FIDELITY WOOFERS



SK-67W*

SK-68

2395

1550

15" HI-FI WOOFER

- 2 LB. ALNICO MAGNET
- 20 TO 5000 CYCLES—35 WATTS

This efficient 15" low frequency woofer incorporates many exclusive features. For original equipment or replacement, it provides highly efficient extended low-frequency response. Ideal for assembling 2- and 3-way speaker systems. Handles 35 watts of audio power. Frequency response ± 2 db 20 CPS to 1000 CPS, and ± 5 db from 20 CPS to 5,000 CPS with proper baffling. Voice coil dia. 2", impedance 8 ohms, 31.5 oz. Alnico V magnet. Finished in beautiful brown enamel. Cone is seamless type, permanently bound to voice coil. Has 4-way binding posts. Shpg. wt., 13 1/4 lbs. Cone Resonance 45 cycles. Net 23.95

12" HI-FI WOOFER

21.5 OZ. ALNICO V MAGNET—25 WATT

Provides efficient, extended low-frequency response of ± 5 db from 35 to 8000 CPS, and features 25 watts of power handling capacity. Perfect for high-fidelity installations or for modernization of older equipment. Ideal for assembling 2- and 3-way speaker systems at a budget price. Enclosed magnet structure—completely dust-proof. Placement of outer cone and inner spider carefully calculated for best bass response. 21.5 oz. Alnico V magnet, 1 1/2" dia. voice coil, 8 ohm impedance. All exposed surfaces are finished in beautiful brown enamel. Has 4-way binding posts. Cone Resonance 50 cycles. Shpg. wt., 8 lbs. Net 15.50

HIGH FREQUENCY TWEETER WITH ACOUSTIC LENS

DIRECT IMPORTATION MAKES THIS PRICE POSSIBLE!

- FREQUENCY RESPONSE FROM 2000 CPS TO BEYOND AUDIBILITY
- LOUVERED ACOUSTIC LENS FOR UNIFORM SOUND DISPERSION
- HANDLES 25 WATTS OF POWER
- PRICED EXCEPTIONALLY LOW

New high frequency tweeter featuring a louvered acoustic lens for uniform sound dispersion and capable of handling up to 25 watts of distortion-free power. The directional tendency of high frequency notes is overcome by the natural wide dispersion angle of the short horn and acoustic lens which disperses and radiates the high notes smoothly throughout the entire listening area. The lens is detachable for panel mounting, with a separate base for the tweeter furnished for external mounting where desired. Aluminum voice coil has 16 ohms impedance. Size 4 1/4" long x 3" diameter, lens extends 2 1/2". Requires a crossover network, preferably one with a level control, such as the LN-2. With full instructions. Shpg. wt., 5 lbs. Net 14.95



14⁹⁵

SPECIAL KIT VALUE Lafayette ELIPTOFLEX in KIT FORM



- Easy To Assemble
- 3 Sides Ready To Finish For Horizontal Placement
- 3/4" Furniture Quality Birch
- Decorative Acoustic Grille
- Interior Acoustic Padding


21⁵⁰

NO MONEY DOWN

PRICED EXTRA LOW!
COMPARE FOR VALUE

| | |
|--|-----------|
| CK-14AWX Ready-To-Finish "Eliptoflex" Speaker Cabinet Kit in Birch | Net 21.50 |
| CK-34WX Ready-To-Finish Kit with Walnut veneer | Net 24.50 |

LAFAYETTE ELIPTOFLEX® BOOKSHELF ENCLOSURE with SK-180 10" TRIHELIX 3-WAY SPEAKER




66⁵⁰

NO MONEY DOWN

An ideal combination of speaker and enclosure that furnishes optimum 3-way speaker performance. Eliptoflex enclosures are finished on all four sides for vertical or horizontal placement. Shpg. wt., 32 lbs.

| | |
|-----------------------|-----------|
| SY-398WX Mahogany | Net 66.50 |
| SY-399WX Walnut | Net 66.50 |
| SY-400WX Blond | Net 66.50 |
| SY-401WX Oiled Walnut | Net 66.50 |

VALUE COMBINATION! LAFAYETTE SK-211 CAVALIER SPEAKER with 1 3/4 LB. MAGNET & FAMOUS ELIPTOFLEX ENCLOSURE



74⁵⁰

NO MONEY DOWN

Get the most in both value and performance with this speaker/cabinet combination. Lafayette's famous Eliptoflex bookshef enclosure assures you of top performance for your SK-211 "Cavalier" 12" speaker. Enclosures finished on all four sides for vertical or horizontal placement. Your choice of fine finishes. Size 14Hx23 7/16"Wx 13-5/16"D. Shpg. wt., 34 lbs.

| | |
|--|-----------|
| SY-410WX SK-211 & Eliptoflex in Mahogany | Net 74.50 |
| SY-411WX SK-211 & Eliptoflex in Walnut | Net 74.50 |
| SY-412WX SK-211 & Eliptoflex in Blonde | Net 74.50 |
| SY-413WX SK-211 & Eliptoflex in Oiled Walnut | Net 74.50 |
| SY-414WX SK-211 & Eliptoflex in Unfinished furniture grade birch | Net 67.50 |

FAMOUS LAFAYETTE ELIPTOFLEX ENCLOSURE & SK-210 SOVEREIGN 12" 3-WAY SPEAKER with 2 1/4 LB. MAGNET



82⁵⁰

NO MONEY DOWN

PERFORMANCE MATCHED—Lafayette's famous Eliptoflex bookshef enclosure matched with the exceptional SK-210 Sovereign 12" 3-way speaker. Finished on four sides in your choice of decorator finishes. Size: 14Hx 23 7/16"Wx 13 5/16"D. Shpg. wt., 39 lbs.

| | |
|--|-----------|
| SY-405WX SK-210 & Eliptoflex in Mhg. | Net 82.50 |
| SY-406WX SK-210 & Eliptoflex in Walnut | Net 82.50 |
| SY-407WX SK-210 & Eliptoflex in Blonde | Net 82.50 |
| SY-408WX SK-210 & Eliptoflex in Oiled Wal. | Net 82.50 |
| SY-409WX SK-210 & Eliptoflex in Unfinished furniture grade birch | Net 75.50 |

2 OR 3 WAY CROSSOVER NETWORK



875

- 4 CROSSOVER FREQUENCIES
- 1 PAD BALANCE CONTROLS
- EASY TO USE
- IMPEDANCE 16-OHMS

The LN-7 Crossover Network combines quality performance, beauty and versatility at an unbeatable price. It can be used in a two-way system by crossing over at 500 cps or 3300 cps, and in a three-way system by utilizing the two simultaneously. The change from a two-way to a 3-way 6 db per octave network may be accomplished easily. Two level balance controls. Size 5 7/8"x2 7/8"x2 3/8". Shpg. wt., 2 1/2 lbs. Net 8.75

LN-7 Net 8.75

2- and 3-way L C CROSSOVER NETWORK



14⁹⁵

- 4 CROSSOVER FREQUENCIES: 350, 700, 2000-3000, 5000 CYCLES
- 6 CROSSOVER COMBINATIONS
- 2 OR 3 WAY CROSSOVER
- ATTRACTIVE METAL CASE
- BUILT-IN BRILLIANCE & PRESENCE CONTROLS

This versatile unit can be used either as a 2-way or 3-way 6 db per octave network. You can use this network for a 2-way system now, easily and quickly convert to 3-way later. Six crossover combinations are available—2-way crossover with 2000-3000 cycle or 5000 cycle crossover, and 3-way with crossover frequencies of 350 and 5000, 350 and 2000-3000, 700 and 2000-3000 or 700 and 5000 cycles—a total of four different crossover frequencies! Suitable for 8-16 ohm speakers. The network is housed in an attractive metal case, suitable for mounting inside enclosure or leaving out in the open. Two level controls—Brilliance and Presence controls—are mounted on the front panel. If desired, these level controls may be removed, along with the beautiful gleaming copper escutcheon plate, for external mounting; controls are wired with 3-foot long leads. High quality components are used for long life and top performance. Shpg. wt., 6 lbs. Net 14.95

LN-5 Lafayette L/C Crossover Net 14.95

SPEAKER AND ENCLOSURE COMBINATIONS

**NEW! 12" WIDE-RANGE
HI-POWER
HI-FI SPEAKER**


- 21.5 OZ. ALNICO 5 MAGNET • RATED AT 30 WATTS • RESPONSE 20-14,000 CPS • SEAMLESS CONE • SPECIAL HEAVY-DUTY CONSTRUCTION

ONLY 14⁹⁵



Incorporating a full 21.5 oz. magnet of high-flux density Alnico 5, this new wide-range 12" PM high fidelity speaker is rated at 30 watts and is excellent for use with any hi-fi system. With proper baffling, frequency response is 20 to 14,000 cps. Special constructional features include a 1½" voice coil; epoxy bonding of the voice coil to the seamless cone; completely dust-proof enclosed magnet structure; fibre-to-metal bonds made with heat under extreme pressure; heavy cast-metal frame; metal parts heavily cadmium-plated, with exposed surfaces covered with a handsome mar-resistant hammerloid finish. Voice coil impedance 8 ohms. Outside diameter 12½", mounting diameter 11½", depth 6¾". Color-coded 4-way binding-post terminals.
SK-137 Shpg. wt., 7 lbs. Net 14.95

**NOW FROM LAFAYETTE
ADD-ON REVERBERATION**



**Works With Phono, TV
Radio or Tape Recorder**

Converts Your
Living Room Sound
to that of Concert
Hall Grandeur

69⁹⁵
NO MONEY DOWN!

- Marvelous For Existing Monaural Systems
- Enriches Your Present Stereo Systems
- Adds A Delightful Dimension to Sound Without Effecting Fidelity
- Completely Self-Contained, Has Own Amplifier and Speaker

Changes the acoustic dimensions of your room. A self-contained reverberation speaker-and-amplifier with its own internal power supply, that hooks into any existing stereo or monophone component sound system, FM and AM radio, Tape Recorder, T.V. set, or Electric Organ. More than just a simple "echo device," the "Reverb-Control" takes part of the original signal from a speaker system and feeds this signal through a carefully tuned device which delays the sound for 1/30th of a second. This delayed sound blends with the original sound to add acoustic dimension to your room. Uses 8" Dual diameter speaker. Power output of amplifier 3 watts R.M.S. (will work excellently with systems having up to 60 watt amplifiers). 2 sets of inputs—high level and low level (left and right)—use only one input for monaural. Comes supplied with 2 cables, 15' each with standard phono plugs on one end. Power requirement 110V to 120V AC. Cabinet size 10x20x10¾" deep. Available in walnut and mahogany. Shpg. wt., 22 lbs.
SK-204WX Walnut Finish Net 69.95
SK-205WX Mahogany Finish Net 69.95

SENSATIONAL SPEAKER SYSTEM

**JENSEN speakers + UNIVERSAL
WOODCRAFTERS cabinets +
LAFAYETTE low prices**



38⁹⁵

NO MONEY DOWN!

- Heavy 7-Ply Furniture Veneer Cabinets
- Fiberglass-loaded Cabinet for Better Bass Response
- Jensen 12" Woofer, 8" Midrange Driver, 3½" Enclosed Tweeter


Now you can get unparalleled speaker performance at a low, low Lafayette price—the most outstanding value of its kind in the industry. The Uni-Voice hi-fi speaker system is a thrilling blend of fully integrated, unified 3-speaker systems engineered by Jensen with specially developed Jensen components, with cabinetry by Universal Woodcrafters. Contains special 12" woofer, 8" midrange driver independently pneumatically damped in its own hermetically enclosed acoustic surroundings, completely separated from woofer cavity; 3½" fully enclosed, independently baffled tweeter. Woofer electric crossover at 600 cycles, midrange electric crossover at 2000 cycles. Impedance 8 ohms. Response: 35-18,000 cycles.
MODEL UV-30. Bookshelf enclosure finished on 4 sides. Speaker grille completely framed with brass inlay. 24Wx14¼Hx13"D.
SK-185WX Walnut finish. Shpg. wt. 32 lbs. Net 38.95



Tweeter with baffle



Polyester resin treated tweeter edge



TWEETER BAFFLE

CONICAL STIFFENER

CROSSOVER NETWORK


Lafayette presents

**THE NEW ULTRA-LINEAR SK-128™ full range 8 inch
biaxial speaker with newly developed
tweeter baffle design.**

19⁵⁰

- 20 TO 20,000 CPS (40 TO 16,000 CPS ± 3 DB) ■ HIGH EFFICIENCY
- HIGH EXCURSION WOOFER WITH UNIQUE "CONICAL STIFFENER"
- HANDLES HEAVY BASS PASSAGES WITHOUT "DOUBLING"

*Eccentric Tweeter Mounting & Unique Elliptical Baffle
Completely Eliminates Interaction Between Woofer & Tweeter*



The SK-128 combines the best features of a multiple speaker system in one compact and economical unit. It offers full, even coverage of the entire audible range, with no distortion or coloration to mar your listening pleasure. The specially treated woofer cone has a unique "Conical Stiffener" at the apex which, coupled with its high compliance, enables the cone to operate in a piston-like manner—delivering a clean, powerful bass response. The 2-inch tweeter has its own voice coil and magnetic field. Special treatment of cone and cone edge provides even distribution of the high frequencies, with no peaks or resonances. The unusual off-center mounting of the tweeter and its elliptical baffle minimizes interaction between tweeter and woofer and insures an overall response free of intermodulation distortion. Electrical crossover from the woofer cone to the tweeter unit is provided by a built-in network. An adjustable brilliance control permits matching of sound to room acoustics. Efficiency of the speaker is such that it will operate from any amplifier with an output of 1 watt or more. Installed in a bass-reflex type of enclosure, it performs outstandingly, and is recommended for all high-quality music systems—whether monaural or stereophonic. SPECIFICATIONS: Overall Response: 20-20,000 cps (40-16,000 cps ± 3 db). Free air Resonance: 45-65 cps. Impedance: 8 ohms. Power Rating: 20 watts Integrated Program Material. Crossover: 2,500 cps. Overall Diam. 8½". Overall Depth: 5½". Baffle cut-out: 7½". Rugged, vibration-free speaker frame with color-coded screw-type terminals for quick, easy connection of amplifier leads. Shpg. wt., 5 lbs.
SK-128 Full Range 8" Biaxial Speaker.....Net 19.50

**LAFAYETTE MINI-DUCT BOOKSHELF ENCLOSURE
WITH SK-128 8" ULTRA-LINEAR SPEAKER**

The perfect answer for those who demand realistic sound reproduction even where space is limited. Two of these systems are ideal for stereo. Shpg. wt., 28 lbs.

| | |
|---|-----------|
| SY-343WX Speaker System in Walnut | Net 39.50 |
| SY-344WX Speaker System in Mahogany | Net 39.50 |
| SY-345WX Speaker System in Blonde | Net 39.50 |
| SY-346WX Speaker System in Oiled Walnut | Net 39.50 |
| SY-347WX Speaker System in Unfinished Birch | Net 37.50 |

SK-128 SPEAKER & MINI-DUCT FINISHED ON 4 SIDES

| | |
|-------------------|-----------|
| SY-403WX MAHOGANY | NET 41.95 |
| SY-404WX WALNUT | NET 41.95 |




**LAFAYETTE MINI-DUCT™ BOOKSHELF ENCLOSURE
WITH SK-212 3-WAY SPEAKER**

A perfect match: The "Mini-Duct" enclosure and the remarkable Lafayette SK-212 3-way High Fidelity speaker. Reproduces the entire audio spectrum with a marvelous smoothness. Styled in attractive furniture finishes. Shpg. wt., 35¼ lbs.

| | |
|--|-----------|
| SK-212 SPEAKER AND MINI-DUCT ENCLOSURE FINISHED ON 3 SIDES | |
| SY-431WX UNFINISHED | Net 52.45 |
| SY-432WX MAHOGANY | Net 54.95 |
| SY-433WX WALNUT | Net 54.95 |
| SY-434WX OILED WALNUT | Net 54.95 |
| SY-435WX BLONDE | Net 54.95 |

SK-212 SPEAKER AND MINI-DUCT FINISHED ON ALL 4 SIDES

| | |
|-------------------|-----------|
| SY-436WX MAHOGANY | Net 56.40 |
| SY-437WX WALNUT | Net 56.40 |



**FAMOUS LAFAYETTE MINI-DUCT™ BOOKSHELF ENCLOSURE
WITH SK-130 8" WIDE-RANGE SPEAKER**


As Low As **33⁹⁵** NO MONEY DOWN!

A combination that rivals the performance of much larger speaker systems. This fine enclosure assures optimum performance from the SK-130. Only 23" W x 11½" H x 11½" D—ideal for mounting in a bookcase or record shelf. Finished on 3 sides in a variety of fine furniture finishes. Shpg. wt., 27 lbs.

| | |
|---|-----------|
| SK-130 SPEAKER & MINI-DUCT ENCLOSURE COMBINATIONS | |
| SY-415WX Unfinished | Net 33.95 |
| SY-416WX Mahogany | Net 35.95 |
| SY-417WX Walnut | Net 35.95 |
| SY-418WX Oiled Walnut | Net 35.95 |
| SY-419WX Blonde | Net 35.95 |

SK-130 SPEAKER & MINI-DUCT FINISHED ON 4 SIDES

| | |
|-------------------|-----------|
| SY-420WX Mahogany | Net 36.95 |
| SY-421WX Walnut | Net 36.95 |




MINIDUCT

SK-130

BUILD-YOUR-OWN LAFAYETTE SPEAKER ENCLOSURES

**EASY-TO-ASSEMBLE
HI-FI
ENCLOSURE KITS**

LAFAYETTE UNIVERSAL HI-FI BASS REFLEX ENCLOSURE KITS



At Tremendous Savings To You!

A LAFAYETTE BEST BUY!

At Only **29⁹⁵**

NO MONEY DOWN

- EASIEST TO ASSEMBLE — ALL YOU NEED IS A SCREWDRIVER!
- PRECISION-CUT — FITS TOGETHER SMOOTHLY
- PERFECT FOR SINGLE WIDE RANGE, 2-WAY OR 3-WAY SPEAKER SYSTEMS
- HIGHBOY OR LOWBOY STYLE

All pieces of these carefully designed bass reflex high fidelity speaker enclosures are accurately precut of 3/4" Plywood to fit snugly together and eliminate spurious resonances. Surface is white birch veneer. Front panels have picture-frame moulding and plastic acoustic grilles to blend with any finish and room decor. Tapered offset legs are protected by brass ferrules. Acoustic lining material prevents reverberation and cabinet resonance. Cutouts are provided for 15" speaker plus adapter for 12" 8 1/2" or 8" midrange plus adapter for 5" and blank wood block if no midrange speaker is used; cutout with adapter boards for 2 sizes of rectangular and 3 sizes of round compression horn tweeters plus blank block if no tweeter used. Thus, any single wide-range 12" or 15" speaker may be used, or any Lafayette 2- or 3-way speaker system, or almost any other combination of speakers. Kits are supplied unfinished, smoothly sanded and ready for finishing. The lowboy-style cabinet dimensions are (less legs) 28 7/8" x 23 1/2" x 16 3/4" D; legs are 7" high. Highboy has same dimensions with height and width interchanged. Instructions, all parts, hardware, and grille are included. Shpg. wt., 5 1/2 lbs.
CK-10WX Unfinished Highboy Enclosure Kit Net 29.95
CK-11WX Unfinished Lowboy Enclosure Kit Net 29.95


LAFAYETTE OILED WALNUT FINISHING KIT

2⁶⁹

At Tremendous Savings To You!

Use this professional walnut oiling kit to achieve a beautiful oil finish on all unfinished walnut furniture. Materials are identical to those used by professional finishers; kit contains walnut oiling mixture, walnut paste wax, sandpaper and instructions. Shpg. wt., 2 lbs.
MS-592 Net 2.69

LAFAYETTE HI-FI SPEAKERS AT POCKETBOOK PRICES




12" THREE-WAY HI-FI SPEAKER

This new 3-way speaker answers the needs of many hi-fi enthusiasts. Featuring an 8 oz. dual-diameter magnet it has a frequency response of 35-17,500 cps. The elliptical tweeter gives improved sound dispersion over cylindrical types. Voice coil: diam-1 1/4", impedance-8 ohms. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 6 1/2 lbs.
SK-183 Net 11.95

6" MID-RANGE SPEAKER

An excellent mid-range direct-radiator type speaker for installation in 3-way or 4-way speaker systems. Gives clean, distortion-free reproduction at rated power. Features closed back to eliminate interaction with sound waves generated from other speakers in the same enclosure. Rated power handling capacity: 10 watts. Frequency response from 700 to 7000 cps. Magnet weight: 3.16 oz. Voice coil impedance: 8 ohms. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 3 lbs.
SK-138 Net 5.25




LAFAYETTE 8" EXTENDED RANGE SPEAKER

- 45 to 13,000 cps
- SKIVER ROLLED CONE FOR SMOOTH RESPONSE
- 3.16 OZ. NEW TYPE MAGNET

Here is a price buster for the budget-wise hi-fi music lover. This is an extended range domestic speaker whose high sensitivity is achieved through a new hi-efficiency magnetic circuit. Ideally suited for medium and low level monaural or stereo reproduction. It has a 1" voice coil with 8 ohms impedance and will handle musical peaks of 10 watts. Size: O.D. 8 1/2"; Mtg. hole dimensions 7 1/4"; 3 1/2" deep; Brown enamel over heavily plated steel. 4-way binding posts. Shpg. wt., 2 lbs.
SK-106 Net 4.95

12" COAXIAL HI-FI SPEAKER

12" Alnico V PM with 1" voice coil and heavy one-piece cone. Specially designed 3" Alnico V PM tweeter completes this combination speaker. Range 40 to 15,000 cps. Built-in high pass filter. Power rating: 12 watts. 6.8 oz. Alnico V magnet. Impedance 8 ohms. Shpg. wt., 8 lbs.
SK-93W Net 8.75



8" HI-FI WIDE RANGE SPEAKER

50-13,000 CPS

Answers the need for a good quality but moderately priced speaker with a range of 50-13,000 cycles. An extremely smooth single cone reproducer — ideally suited for Hi-Fi systems. Excellent for limited space—good overall balance—power handling capacity: 10 watts—6.8 oz. Alnico V magnet—frequency response: 50-13,000 CPS when properly baffled. Rim treatment on cone minimizes possibility of diaphragm distortion. Voice coil impedance: 8 ohms. Cone Resonance 85 cycles. Plated steel frame finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 4 lbs.
SK-69 Net 6.25

LAFAYETTE 8" WOOFER

- Rated 20 Watts • Free edge cone
- 14.7 oz. alnico V magnet
- High Compliance • 35 to 7500 cps

Ideal for 2 or 3 way systems where space is at a premium, this 8" woofer provides coverage from 35 to 7500 cps. The 14.7 oz. magnet is extraordinarily heavy for this size speaker insuring the efficiency needed for good clean response. Other features include free edge, high compliance cone, 20 watt power dissipation, voice coil dust cover. Cone resonance 50 cycles, 8 ohm V.C. Has 4-way binding posts.
SK-164 Shpg. wt., 4 1/2 lbs. Net 10.95

8" MID-RANGE SPEAKER

Ideal for use with tweeter and crossover networks to make up a 2- or 3-way system. This 8" mid-range speaker is capable of producing undistorted response down to 350 cps, the crossover frequency. Back is enclosed. Power handling capacity: 25 watts. Frequency response 350-13,500 cycles. Recommended to crossover at 5000 cycles to a tweeter. Cone resonance 150 cycles. Impedance: 8 ohms. Plated steel framed finished in brown baked enamel. Has 4-way binding posts. Shpg. wt., 4 lbs.
SK-74 Net 6.50

NEW!

LAFAYETTE 8" 3-WAY HI-FI SPEAKER

PAY LESS FOR HIGHER QUALITY-PERFORMANCE

24⁵⁰
NO MONEY DOWN

- Frequency Range: 40-20,000 cps • Magnet System: 1 lb. • Voice Coil: Aluminum • Impedance 16 Ohms • Power Handling Capacity: 20 Watts • 3-Concentric Radiators • Unique Wide-Angle Compression Lens Tweeter • Special "Rigidflex" Free Edge Woofer Cone • Built-in Brilliance Control • Die-Cast Frame

MADE IN ENGLAND TO OUR SPECS!

For Stereophonic and Monophonic Systems

The Lafayette SK-213 has been specially designed for us in England to reproduce sound with true fidelity without compromise. It is a complete 3-way system, composed of 3 concentric radiators. The "Rigidflex" bass and midrange radiators accurately reproduce frequencies of from 40 to 5,000 cps. The new wide-angle compressor lens tweeter extends the frequency range from 5,000 on up to 20,000 cycles. Here is a speaker capable of a standard of performance previously associated with much larger and more elaborate loudspeaker equipment. Deluxe features such as an aluminum voice coil, heavy 1 lb ceramic magnet system and rigid nonresonant die-cast frame demonstrate the unique marriage of Lafayette custom specifications

and quality English craftsmanship. Small size makes it an ideal choice for mounting in the famous Lafayette "Mini-duct" bookshelf enclosure. Use it in pairs for finer stereo reproduction anywhere in your home. A built-in bass-treble attenuator makes it possible to "customize" the SK-213's sound to your individual requirements. Baffle Hole dia., 7"; Front to back dimension, 3 3/4".
SK-213 Shpg. wt., 6 lbs. Net 24.50
SK-213 3-WAY SYSTEM with MATCHING "MINI-DUCT" ENCLOSURES FINISHED ON ALL 4-SIDES
SY-438WX Mahogany Net 46.95
SY-439WX Walnut Net 46.95

NEW! Lafayette BASS REFLEX SPEAKER BOOKSHELF ENCLOSURE KIT FOR 8" or 6" SPEAKERS

COMPARES TO CABINETS PRICED AT \$35


AS LOW AS **10⁹⁵**

Assembles In Less Than 30 Minutes!

Not 1/2", But 3/4" Furniture Grade White Birch Or Walnut Veneer

- Precision Cut — Fits Together Smoothly
- Adapts For 8" or 6" Speakers
- Easy To Follow Pictorial Instructions
- Versatile — Use As Floor or Bookshelf Enclosure

BUILD IT YOURSELF . . . All that's required to construct this excellent bookshelf speaker enclosure is a screwdriver and thirty minutes of your time. Expensive woodworking equipment isn't needed—each cabinet component has been precision cut and fits together perfectly. There's nothing else to buy . . . acoustic padding, grill cloth and hardware are provided. Use any 8" or 6" speaker; the mounting board has been precut for 8" speakers and an adapter is supplied for 6" speakers. Designed for horizontal placement in a bookshelf, along a wall etc. Constructed of 3/4" veneers on 3 sides with handsome picture frame moulding. You save even more by finishing this kit yourself—the 3 sides are smoothly sanded furniture grade wood, ready for a finish you'll be proud of. (See Lafayette's professional finishing kits). Dimensions: 23x9 1/2 x 11". Available in either birch or walnut unfinished veneers.
CK-31WX Birch Kit Shpg. wt., 15 lbs. Net 10.95
CK-35WX Walnut Kit Net 13.95
Speakers for Lafayette CK-31 Cabinet Kit Lafayette 8" Duo-Cone Speaker: 40-16,000 cps response. Net 9.95
SK-98 Shpg. wt., 5 1/2 lbs. Net 9.95
Lafayette 6 1/2" Coaxial Speaker: 50-16,000 cps response. Net 6.95
SK-97 Shpg. wt., 3 1/2 lbs. Net 6.95



LAFAYETTE


SPEAKERS, SYSTEMS, AUDIO & PHONO ACCESSORIES

LAFAYETTE'S Amazing New! MINI-DUCT

A universal ducted-port bookshelf enclosure engineered for use with 1, 2 or 3-way speaker systems.

SOLIDLY CONSTRUCTED OF 3/4" WOODS START WITH A SINGLE SPEAKER AND BUILD INTO A 2- OR 3-WAY SYSTEM LATER ACOUSTICALLY LINED THROUGHOUT AVAILABLE IN A VARIETY OF FINISHES

23⁵⁰
NO MONEY DOWN



MINI-DUCT BOOKSHELF ENCLOSURE

Mounting boards accept all types of tweeters



33²⁵
NO MONEY DOWN

SK-98

Now limited space need not necessarily mean limited sound. The Lafayette Mini-Duct is acoustically designed to achieve smooth, distortion-free reproduction with a remarkably full, clean extended bass response that gives no indication as to its small size. Reducing boards are supplied so that the Mini-Duct will accept an 8" Woofer, 6" Mid-Range and a variety of tweeters. This versatility makes it possible to start with an 8" speaker and eventually build into a 2-way or 3-way speaker system. Solidly constructed of 3/4" woods the Mini-Duct is beautifully finished in a variety of fine veneers on 3 sides. Designed for attractive placement anywhere in your home with dimensions 23Wx11 1/2Hx11 1/8"D. Shpg. wt., 23 3/4 lbs.

| | |
|--|-----------|
| CAB-47WX MINI-DUCT IN WALNUT | Net 23.50 |
| CAB-48WX MINI-DUCT IN MAHOGANY | Net 23.50 |
| CAB-49WX MINI-DUCT IN BLONDE | Net 23.50 |
| CAB-50WX MINI-DUCT IN OILED WALNUT | Net 23.50 |
| CAB-51WX MINI-DUCT UNFINISHED BIRCH | Net 21.50 |
| Mini-Duct Enclosure finished on 4 sides for attractive horizontal or vertical placement. Choice of mahogany or walnut. | |
| CAB-105WX Mahogany | Net 24.95 |
| CAB-106WX Walnut | Net 24.95 |

SPEAKER AND ENCLOSURE COMBINATIONS

A PERFECT COMBINATION: The "Mini-Duct" enclosure and the famous Lafayette SK-98 8" mechanical 2-way speaker with patented dual cone construction. This speaker combined with the Lafayette "Mini-Duct" enclosure will give the same wide-range frequency response (40-16,000 cps) normally found only in the coaxial speakers or multiple speaker systems. Shpg. wt., 29 1/2 lbs.

| | |
|--|-----------|
| COMBINATION UNFINISHED "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-348WX | Net 31.25 |
| COMBINATION MAHOGANY "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-349WX | Net 33.25 |
| COMBINATION WALNUT "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-350WX | Net 33.25 |
| COMBINATION OILED WALNUT "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-351WX | Net 33.25 |
| COMBINATION BLONDE "MINI-DUCT" ENCLOSURE WITH SK-98 SPEAKER SY-352WX | Net 33.25 |

SK-98 SPEAKER AND MINI-DUCT FINISHED ON 4 SIDES

| | |
|-------------------|-----------|
| SY-377WX MAHOGANY | Net 34.25 |
| SY-378WX WALNUT | Net 34.25 |

LAFAYETTE L PADS

139



New L pads for use as "brilliance" controls to vary tweeter level, or as "presence" controls to vary mid-range speaker level. Both wirewound elements are concentrically mounted

within one plastic housing. With gold-finished metal escutcheon plate, mtg screws, and attractive black knob. Size: 1 1/4" dia., 7/8" deep (less shaft), 2 1/2" deep overall. Shpg. wt., 6 oz.
VC-49—L pad for 8 ohm circuits Net 1.39
VC-50—L pad for 16 ohm circuits Net 1.39

STEREO LEVEL BALANCE CONTROL

- Dual Concentric 8 ohm L Pads
- Logarithmic Curve

289



Provides individual level control for stereo speakers. Varies "brilliance" or "presence" Controls stereo extensions without mismatching. Dual control mounted on concentric shaft. Gold-finished brass plate and attractive black knobs, with gold trimming. L pad for 8 ohm circuits. Plate is 2 1/4" across; overall depth 3 1/4". Shpg. wt., 10 oz. Imported
VC-55 Level Control Net 2.89

STEREO RUMBLE FILTER

249



Filters out turntable vibration and rumble—makes every low-priced turntable and changer quiet and rumble-free. Designed for use with ceramic or magnetic cartridges. 3-position selector switch—ceramic, magnetic cartridge, off. Just plug it in between cartridge and amplifier inputs. Overall size: 5x2 1/2x3/4". Shpg. wt., 14 oz. Imported
PK-44 Stereo Rumble Filter Net 2.49

NEW! LAFAYETTE SK-98® 8" DUO-CONE HI-FI SPEAKER

- MECHANICAL 2-WAY DESIGN
- OVERALL RESPONSE 40-16,000 CPS.
- LARGE MAGNET STRUCTURE
- PATENTED CONE CONSTRUCTION AND MATERIAL HIGH EXCURSION WOOFER



9⁹⁵

The dual-cone construction used in these high quality 8" speakers, provides the same type of wide-range response normally found only in true coaxial speakers or multiple speaker systems. Two separate cones act through a common voice coil. The outer edge of the tweeter cone is attached to the mid-section of the woofer cone; both cones "float" on flexible corrugated edges. This mounting results in true mechanical cross-over, so that both cones operate at low frequencies, but only the tweeter cone operates at high frequencies. This gives improved high frequency directional characteristics and minimum distortion. Patented cone materials provide extremely smooth response over the range of 40-16,000 cps. Magnets are large and heavy with a flux density of 10,500 gauss and total flux of 56,000 maxwells. Terminals are screw-type for solderless connections. Sensitivity is 99.5 db/watt; free air resonance is 55-70cps; voice coil impedance is 8 ohms. Size is 8" diam., 4 1/4" deep and requires 6 3/4" diam. baffle opening. Shpg. wt., 5 1/2 lbs. Imported
SK-98 8" 2-WAY SPEAKER Net 9.95
2 FOR STEREO Net 18.95

NEW! 6 1/2" COAXIAL SK-97® HI-FI SPEAKER


- OVERALL RESPONSE 50-16,000 CPS.
- SPACE SAVING & ECONOMICAL FOR STEREO
- BUILT-IN L C NETWORK
- LARGE, HEAVY MAGNETS



6⁹⁵

An excellent speaker with all the best features of coaxial design, the SK-97 will provide the finest sound reproduction available from a speaker of this size. It is especially recommended where space and/or cost are factors. The 6 1/2" woofer is equipped with large, heavy magnet for maximum efficiency and low distortion. The 2" tweeter is a separate speaker coaxially mounted in a housing which completely seals off back radiation; a mesh dispersion screen provides smooth, wide-angle high frequency propagation. When properly enclosed, the response of this low cost hi-fi speaker is genuinely impressive. Its small size makes it perfect for use in a wide variety of small enclosures—ideal for use in pairs for stereo music systems of up to 8-10 watts. Frequency range, 50-16,000 cps. Woofer free-air resonance, 70 cps. Voice coil impedance, 8 ohms. Built-in electrical crossover network. Color-coded screw-type terminals. Requires 5 1/2" diam. cutout. Size is 6 1/2" diam., 3 3/4" deep. Shpg. wt., 3 1/2 lbs. Imported
SK-97 6 1/2" COAXIAL SPEAKER Net 6.95
2 FOR STEREO Net 12.95

COMPRESSION CHAMBER SPEAKER SYSTEM



1295

Priced for Low Budget Hi-Fi Stereo Systems

- Solid 3/4" Thick Hardwood • Beautiful Oiled Walnut Finish • 50-15,000 CPS

A truly magnificent speaker system which sounds many times its size. Utilizes air compression principle to reproduce all the lows and highs from 50-15,000 cps. Uses a heavy duty 6" high efficiency speaker. Solid 3/4" hardwoods are beautifully finished in oiled walnut. The power and sound quality of this speaker system makes it ideal for low cost quality stereo systems or extension speaker use anywhere in the house. Its wide range response is unbelievable! Full 15 watts power handling capacity. Impedance 8 ohms. Dimensions: 8 1/2Hx9 3/4Dx 15 1/4"L. Shpg. wt., 8 lbs.
SK-206W Net 12.95


LAFAYETTE'S ULTRA-COMPLIANCE 2-WAY SPEAKER SYSTEM

VERY SMALL IN SPACE — LESS THAN 1 CU. FT.

Absolutely Gigantic in Performance!

17⁵⁰

- Frequency Response 40-16,000 cps
- Especially Designed Vented, Tuned Duct Type Enclosures
- Unique Mechanical 2-Way Speaker With Extra Heavy Magnet
- Enclosure Finished on 4 sides • Excellent For Stereo



FULL SIZE PERFORMANCE — This outstanding Lafayette Ultra-Compliance 2-way speaker system achieves a purity of sound and musical quality that is astounding from a speaker system occupying less than one cu. ft. of space. A perfect speaker for use anywhere in your home or office makes ideal extension units or use in pairs for stereo.

The speaker features a unique dual cone with an extra heavy magnet structure, employed in a specially designed tuned ducted port enclosure. Both tweeter and woofer "float" on flexible, corrugated edges, with the outer edge of the tweeter cone attached to the mid-section of the woofer. This results in a mechanical crossover so that both cones operate in phase at low frequencies, but only the tweeter cone radiates high frequencies. The same type of wide-range frequency response is achieved that normally is found only in true coaxial or multiple speaker systems. Frequency response is 40-16,000 cps — Impedance: 8-16 ohms.

Available in rich mahogany or walnut. Finished on four sides — place it horizontally on its side or vertically on its base. Easily adapts to bookshelf placement or modular use. Dimensions are only 10 3/8Hx18 1/2Lx8 3/8"D. Shpg. wt., 15 lbs. Imported
MAHOGANY DR WALNUT (PLEASE SPECIFY)
Lafayette Ultra-Compliance 2-Way Speaker System
SK-124WX Net 17.50
SK-123WX Oiled Walnut Net 18.95
Set of Two SK-124 Speaker Systems Net 34.00
Set of Two SK-123 Speaker Systems Net 36.50

LAFAYETTE STYLUS PRESSURE GAUGE

4⁹⁵

With the advent of stereo records, correct stylus pressure becomes all important in obtaining the best reproduction and least stylus and record wear. Lafayette's stylus pressure gauge is an accurate device that allows you to read with the pickup in normal playing position. Range, 0-30 gm. No spring and minimum moving parts. Shpg. wt., 1 lb.
PK-223 Net .99

DUST COVERS
Molded to the contours of the players from sparkling, clear vinyl, these covers provide complete protection from dust and accidents to the precision bearings, levers and tone arm. Shpg. wt., 1 1/2 lbs.
PK-531 Fits Model A Net 4.95
PK-560 Fits Model AT6 Net 4.95
PK-561 Fits Autostim Net 4.95
PK-529 Fits Model 210 Net 4.95
PK-530 Fits 88/11 and RC88 Net 4.95



PHONO-TUNER ADAPTER

2 phono jack inputs; simple switch selects either. A convenient phono output jack for connecting to amplifier. Includes mounting screws. Av. shpg. wt. for above units is 1 lb. Imported
MS-795 Net .98

SPEAKER PHASING CONTROL

Allows you to reverse speaker connection to obtain correct phasing without disconnecting leads from speakers. A must for stereo. Complete with screw terminals and all mounting hardware. Shpg. wt., 1 lb. Imported
MS-756 Speaker Phasing Control Net .98

STEREO-MONAUURAL-REVERSE SWITCH

Lets you switch instantly from stereo to monaural or reverses stereo channels. 2 phono jacks input . . . 2 phono jacks output. Completely shielded, ready to mount with all hardware. Shpg. wt., 1 lb. Imported
MS-757 Stereo-Monaural-Reverse Switch Net 1.29

MULTI-INPUT SELECTOR CONTROL

Connects any one of 5 inputs to 1 output AM, FM, phono, tape, aux. Completely shielded to prevent hum. Complete with mounting hardware. 5 phono jacks input, 1 phono jack output. Shpg. wt., 1 lb. Imported
MS-758 Multi Input Selector Net 1.76

REMOTE MICROPHONE VOLUME CONTROL

No more running to the P. A. amplifier to adjust volume when you are using a mike. Now, control volume output right at the microphone. Attached between the microphone and the cable, this completely shielded control has practically no insertion loss and induces no hum. Can be used at any desired distance.
Fitted on one end with a female mike Connector and male mike Connector on the opposite end. Finished in gleaming chrome, its appearance will blend in with the most expensive microphones. Comes completely ready to use. Shpg. wt., 12 oz. Imported
MS-755 Remote Volume Control Net 1.76



Group your Components
Into A Distinctive,
Custom Home
Entertainment Center.

Decorator Inspired!!

NEW LAFAYETTE HI-FI COMPONENT SHELF/CONSOLE

52⁹⁵ OILED WALNUT FINISH
NO MONEY DOWN


28⁹⁵ UNFINISHED
NO MONEY DOWN

As functional as it is beautiful, this new Lafayette Shelf Console combines the beauty and compact all-in-one convenience of a console with the versatility of a shelf arrangement: The ideal answer to your Hi-Fi Stereo component placement problems — measures 66½" long, yet holds over 150 records with more than enough room for your amplifier, turntable or record changer, tape deck and stereo speakers. Available in both finished and unfinished versions. Both feature ¾" warp-proof construction. Top shelf measures 11Hx31½Wx16"D. Lower shelf is 15½Hx16Dx 3½"W and to protect your records contains a veneered rear panel, finished on both sides to allow placement of the unit as a room divider. Speaker compartments are 27Hx16Dx14¾"W—Large enough to accept virtually all of today's popular bookshelf size units and are spaced far enough apart to provide proper separation for stereo. Overall dimensions: 66½Wx16Dx33¾"H including 5" legs. Shipped knocked down—Assembles in minutes. Shpg. wt., 65 lbs.


CK-37WX Oiled Walnut Finish Net 52.95
CK-36WX Unfinished Chip Board Net 28.95

- ROOM FOR ALL YOUR COMPONENTS • STURDY ¾" WOOD NON-WARP CONSTRUCTION • HOLDS OVER 150 RECORDS
- AN ATTRACTIVE ADDITION TO ANY HOME - PLACE ALONG A WALL OR USE AS A ROOM DIVIDER

COMPLETE ALL-IN-ONE STEREO CABINETS BY Casard



Your Choice
of Contemporary, French
Provincial
or Italian
Provincial
Styling **88⁹⁵**
No Money
Down



- Ample Space For Your Components including Stereo Speakers • Luxurious Hand Rubbed Veneers
- Contains Two Sealed Bass-Reflex Ducted-Port Enclosures • Your choice of Contemporary, French Provincial or Italian Provincial Styling

Here's period styling and furniture craftsmanship in the old world tradition. And at Lafayette's low, low price these new all-in-one stereo cabinets represent a superb value. Hand crafted in luxurious ¾" woods and veneers. Cabinets have been acoustically designed to showcase your component stereo systems to its best advantage. Enclosure is structurally reinforced to eliminate cabinet resonance. Speaker sections are acoustically insulated with fiber glass and utilize a sealed, bass-reflex, ducted port construction designed to accept either an 8" or 12" full-range speaker or a two or 3 way speaker system. Speaker enclosure section measures 17x13½x15½". The center or component section is protected by two sliding front panels and features a removable shelf. Lower compartment contains a pull-out mounting base which will accept a turntable or record changer (mounting base requirements are 3" below and 6½" above mounting board). Upper compartment provides ample room for a tuner-amplifier combination (receiver) or a separate tuner and amplifier. Compartments measure: Upper—8½Hx17½Wx15½"D; Lower—9¾x 17½x15½". Available in three superb styles—Contemporary, in your choice of fine Oiled Walnut or Mahogany finishes plus Italian Provincial and French Provincial, both finished in Fruitwood. Special plastic case grill cloth is matched to each style and finish. Overall Size: 48x18x28"H. Shpg. wt., 90 lbs.

(A) CONTEMPORARY STYLE
CAB-143WX Oiled Walnut Net 88.95
CAB-144WX Mahogany Net 88.95

(B) FRENCH PROVINCIAL
CAB-146WX Fruitwood Net 88.95
ITALIAN PROVINCIAL STYLE (Not Illustrated)
CAB-145WX Fruitwood Net 88.95

NEW! LAFAYETTE CUSTOM CRAFTED EQUIPMENT CABINET



BEAUTIFUL CABINETRY
DESIGNED TO ENCLOSE
YOUR COMPONENTS
As Low as
42⁵⁰
NO MONEY
DOWN

• Available In A Variety Of Fine Finishes • Rigid ¾" Wood Warp-Proof Construction • "Component Engineered" To Provide Adequate Circulation For Your Equipment

A magnificent example of contemporary furniture design—it's slender, graceful styling is sure to win approval in virtually every fine music room/living room arrangement. Features rigid ¾" wood warp-proof construction with two adjustable center shelves to accommodate virtually any amplifier and tuner. The bottom section has space for a pull out drawer to provide easy access to your record changer. Proper circulation of air around components is maintained by use of a perforated rear panel. Precision fitted swing-out front doors are equipped with magnetic latches. Size: 33¾"H overall (including 5" legs) x 18Dx20"W.

CAB-151WX Oiled Walnut Net 52.50
CAB-152WX Walnut Net 52.50
CAB-153WX Mahogany Net 52.50
CAB-154WX Unfinished Birch Net 42.50

LAFAYETTE SPECIAL PHONOGRAPH SALE with

FREE DIAMOND STYLUS!

With FREE Diamond Stylus!

**LAFAYETTE
AUTOMATIC
STEREO PHONOGRAPH**

• Compatible—Plays Both Stereo and Monaural Records • 4-Speed British Changer

New, attractively styled automatic stereophonic phonograph featuring the latest Monarch 4-speed automatic intermix record changer. Complete with stereo crystal turnover cartridge with dual sapphire styli. Plays both stereo and monaural records. Among many features are automatic record intermix mechanism, automatic motor shut-off at the end of last record, automatic arm return, free-floating motor-board eliminating acoustic feedback. Careful design assures long life and freedom from trouble. Takes all record sizes, and plays all 4 speeds: 16½, 33½, 45 and 78 RPM. Controls include separate volume controls for each channel and dual channel tone control. Built-in Alnico 5 PM speaker provides clean, balanced sound. Second Alnico 5 PM speaker is housed in the removable phonograph cover. 8 ft. cable supplied, permits placement of second speaker for optimum stereo effect. Covered in charcoal linen leatherette with oyster white trim. Tubes 2-58C5, 1-2AX7 and 35W4 rectifier. Size: 19¼x 15½x8¼". Shpg. wt., 23 lbs.

PH-152WX Net 49.95

WITH FREE DIAMOND STYLUS

**LAFAYETTE
Deluxe AUTOMATIC
STEREO PHONOGRAPH**

• 3 Speaker System • 4-Speed V-M Changer • Plays Both Stereo and Monaural Records

New Lafayette deluxe automatic stereophonic phonograph features the famous 4 speed V-M changer. Plays all speeds: 16½, 33½, 45 and 78 RPM. Plays all sizes: 7", 10" and 12" records. Has such features as 4-pole motor, automatic shut-off after last record, etc. Supplied with turnover cartridge. Separate volume controls adjust optimum balance for perfect stereo realism. Separate bass and treble controls permit tonal adjustment of both channels. Has 3 Alnico V PM speakers—1 in main case and 1 in each wing. Wings may be left in position or can be detached from the sides and placed apart for individual stereo requirement. Tubes: 2-35C5, 1-12AX7, 1-50EH5, 1-35W4 rectifier. Attractive black gold branch leatherette case. Size: 20x15½x9". Shpg. wt., 29 lbs.

PH-153WX Net 62.95

With FREE Diamond Stylus!

You get BOTH Sapphire and Diamond Styli at no extra cost!

FREE DIAMOND NEEDLE OFFER EXPIRES AUG 30th, 1962

OUR finest PORTABLE PHONO!

NO MONEY DOWN!

9 Ft. Extension Cord

89⁵⁰

With FREE Diamond Stylus!

PLAYS BOTH STEREO AND MONAURAL!

- FULLY AUTOMATIC GARRARD CHANGER • TWO POWERFUL 10 WATT AMPLIFIERS
- SECOND SPEAKER EASILY DETACHED • 3 SPEAKERS

A complete portable and compact stereo phonograph in one convenient case. System uses the well-known Garrard High-Fi 4-speed stereo changer which features true intermix of 12" and 10" records in any order with instant selection of either automatic or full manual operation. Uses a stereo turnover cartridge to play all your records—whether monaural or stereo. Two powerful 10 watt amplifiers provide a frequency response of 50 to 12,000 cps. Controls included: Master Volume; Remote

Detachable front speaker cabinet houses a 6" x 9" speaker with 9 ft. extension cord. Main unit houses two speakers—one 6" x 9" woofer and one 4" tweeter. Phonograph has easy-grip handle on attractive smart-looking Pyroxylin covered case. Size: 23x16x9¼". Shpg. wt., 40 lbs. Available in choice of 2 attractive coverings: PH-150WX Charcoal Silver Net 89.50 PH-151WX Tan Net 89.50

"STANDARD" 4-SPEED MANUAL RECORD PLAYERS "LEADER"

13⁹⁵

PH-148W Net 13.95

Plays up to 12" monaural records at 16½, 33½, 45 or 78 RPM. A single lever selects any speed. The lightweight pickup arm is equipped with a single all-purpose needle for all records. Has volume control with on-off switch. Fine quality Alnico 5 PM speaker. Attractive leatherette covered case. For 110-120 volts, 60 cycles. Size 11¾x10¼x5". Shpg. wt., 9 lbs.

18⁴⁵

PH-149W Net 18.45

With this portable phonograph you can play any record up to 12" size at 33½, 45 or 78 rpm, or at the new "Talking Book" speed of 16½ rpm. A single lever selects any speed. The lightweight pickup arm is equipped with a turnover cartridge with dual sapphire styli. Has both tone control and volume control with on-off switch. Fine quality Alnico 5 PM speaker. Attractive 2-tone leatherette covered case. For 110-120 volts, 60 cps. AC. Dimensions 14x11¾x6¼". Shpg. wt., 10 lbs.



LAFAYETTE Amateur, SWL Equipment & Kits

BUILD YOUR OWN NEW! EXCITING "EXPLOR-AIR" 4 BAND RECEIVER KIT



• 4 Bands for total coverage: • 550-1600 Kc broadcast band • 1.7-5.0 Mc., 5.0-14 MC., 14-30 MC. shortwave bands • Complete band-switching from front panel • Built-in Big 4" PM Loudspeaker

A complete shortwave and standard broadcast set which covers the entire region from 550 kilocycles to 30 megacycles. Four whole bands of fascinating programming unavailable elsewhere. Only a regenerative circuit can offer such amazing performance and yet be so simple to build. Building this fine kit is an absolute pleasure—it's so well designed you can't go wrong. Kit includes all the parts you need, and the detailed step-by-step instruction book with its giant pictorial drawings shows you just how to put them together. One front panel knob does all the bandswitching at the flick of the wrist. All coils are prewound for greater accuracy. The chassis is completely isolated from the circuit, so there is no shock hazard.

This precision radio kit is just full of extra features. Complete 4 band coverage of broadcast stations, international broadcast bands, amateur, maritime, fire and police services, yes, even satellite signals. Big 4" speaker and sensitive circuit with 50C5 output stage, 35W4 rectifier and 12AT7 regenerative detector and amplifier stages give you all the volume you want. Phone jack for privacy automatically disconnects speaker. All controls are on the front panel: On-Off Volume, Main Tuning, Band Spread, Bandswitch, Antenna Tuning, and Regeneration. 110 volt 50-60 cycle AC-DC power supply lets you use this fine set anywhere. Size: 10x7x5".
KT-135 EXPLOR-AIR RECEIVER KIT (Less Cabinet) wt., 5 lbs. Net 21.95
ML-150 Leatherette covered Wooden Cabinet for above, 1 lb. Net 2.75

LAFAYETTE KT-196 2-STATION INTERCOM SYSTEM KIT



- Attractive, Modern Styling
- Complete—One Master and One Remote Station Plus 50 Ft. of Cable
- Perfect as Baby Sitter or Sickroom Watcher
- 2 Complete Stages of Amplification

14.75

The perfect 2-station intercom kit beautifully styled and engineered by Lafayette's Kit Divisions. It will grace any room in the home, office, shop, school, etc. Consisting of a Master Station and a Remote station, most useful to communicate with the basement, garage, playroom or nursery. The master unit features a highly sensitive 3-tube circuit with 2 complete stages of audio amplification for maximum talk-power, and sensitive reception. Makes a marvelous "baby-sitter." Remote unit may be left in permanent "Talk" position. Master Station has a 3-way lever switch which provides Momentary Talk, Listen, and a lock-in talk position to free hands for other duties or for extended conversation. Master station front panel also includes a combined on/off switch volume control. Only the master unit need be plugged into outlet—remote may be placed anywhere. The system may use up to 3 remotes. Famous Lafayette instruction manual simplifies assembly. Size of each unit: 4x8x4 3/4" D. Attractive metal enclosures. Tubes: 36AM3A, 60FX5, 18FV6. Complete with all parts necessary and 50 feet of 3-wire cable. For 105-125V 50-60 cycles AC or DC.
KT-196 2-Station Intercom Kit. Shpg. wt., 7 lbs. Net 14.75
LA-196 Factory Wired Net 19.50
Extra Remote Station Kit—For use with above. Less cable. Net 3.45
KT-197 Shpg. wt., 2 1/2 lbs. Net 3.95
LA-197 Factory Wired Remote Net 3.95
Hook-up wire for above. per ft. Net .03
WR-160

Tune in the World!

21.95

Made in U.S.A.

NO MONEY DOWN



SUMMER SALE SPECIAL!

LAFAYETTE KT-199

2 TRANSISTOR + DIODE BROADCAST RADIO KIT

POWERFUL REFLEX CIRCUIT

- No Soldering A Child Could Build It!
- Pre-wired Switch and Control
- 50 Mile Range
- Beautifully Styled Cabinet

was 11.63

6.95

Complete with Earphone & Battery

Absolutely no soldering or hole punching is necessary. All wiring and components are connected to faststock clips mounted on a pre-punched board. It is the ideal kit for beginners interested in transistor circuits. The on-off switch and level control are already prewired—just clip them in. A clear construction manual is included with simple How-To-Do-It instructions so that a child could build it. And that's not all. Lafayette engineers have designed this transistor radio to have a receiving radius of approximately 50 miles! Only one 9 volt battery powers its 2-transistor reflex circuit. Ferrite core loop antenna and a variable gang tuning condenser insure crisp reception on the entire AM broadcast band from 550-1600KC. Will accept any high impedance earphone for private listening. Size: 5 1/2 x 2 5/8 x 4 3/4" D. 2-2N165 PNP transistors, 1N48A diode. Complete with instruction manual. Shpg. wt., 1 1/2 lbs.
SP-262 Complete 2 transistor kit—Complete with earphone and battery. Only 6.95

Recommended Earphone Net 1.39
AR-50 Dynamic earphone 3,000 ohm Net .39
BA-2 9-volt battery Net .39


SUPER-SENSITIVE PHOTOCCELL ELECTRONIC RELAY KIT



Made in U.S.A.
• WITH CLAIREX CADMIUM SULPHIDE PHOTOCCELL • ADJUSTABLE SUPER SENSITIVITY —WORKS WITH JUST A FLASHLIGHT AT 250 FEET! • NEEDS NO SPECIAL HIGH-INTENSITY LIGHTS • INSTANTANEOUS OR SUSTAINED OPERATION ON THE FLIP OF A SWITCH!

Ideal for sustained operation required for burglar alarms, door buzzers and for instantaneous on-off operation required for countless industrial applications. Switch converts unit from instantaneous "on-off" to sustained "on" operation. "RESET" switch opens the external circuit and turns off the alarm. The unit operates on 110 volts AC and incorporates the efficient 5823 cold cathode tube. A simple change in wiring (in instructions), as well as convenient input terminals, enable you to supply the external circuit with any desired voltage. Relay contacts rated at 3 amps permitting up to 300 watts external load on 110 Volts AC. Complete with all parts, photocell, tube, chassis, silkscreened metal cabinet and easy-to-follow illustrated instructions. Size: 3x4x5".
KT-133A Kit, Complete. Shpg. wt., 3 lbs. Net 12.95

PHONO AMPLIFIER KITS



10.95


Made in U.S.A.

LAFAYETTE KT-92 5 WATT PUSH-PULL AMPLIFIER KIT

• PUSH-PULL AUDIO OUTPUT STAGE • INVERSE FEEDBACK CIRCUIT • SEPARATE VOLUME, BASS & TREBLE CONTROLS • AC OR DC OPERATION

Here in kit form is an AC-DC hi-fi amplifier that presents unusual features despite its amazingly low price. The separate bass and treble controls permit adjustment of both low and high frequency response and balance. Works equally well with both crystal or ceramic cartridges. Has a 4-tube line up—a 12AX7 amplifier and phase inverter, a 35W4 rectifier and a pair of 35C5's in push-pull, having a power-packed low distortion output. The circuit utilizes an inverse feedback loop to reduce the level of hum and distortion. Kit is complete containing all essential parts, tubes and detailed instruction manual showing pictorial and schematic diagrams. Shpg. wt., 4 lbs. Net 10.95

COMPLETE 5 WATT PHONO SYSTEM KIT



23.75

Everything required for a complete Hi-Fi system in this "easy-to-assemble" package—and Lafayette brings it to you at an unbeatable price. The system is centered about the excellent Lafayette KT-92 5 watt amplifier kit (as described above). The ML-24 4 speed turntable employs a rubber shock-mounted friction drive motor for quiet dependable operation. Tone arm is the Lafayette PK-157 containing turnover crystal cartridge with dual sapphire stylus. Completing the system in the Lafayette SK-109 miniature hi-fi speaker system beautifully finished in mahogany veneers and supplied with 25 feet of hookup cable. Speaker measures only 9 1/2 x 7 3/4 x 4 3/8" D. Shpg. wt., 15 lbs. Net 23.75
PK-333WX Unfinished mounting board for ML-24 turntable. Shpg. wt., 1 lb. Net .95
PK-149W

NEW! LAFAYETTE KT-195 WIRELESS BROADCAST AMPLIFIER KIT

Use it either as a Wireless Broadcaster or AM Audio Amplifier!
• POWERFUL SIGNAL
• PLAYS THROUGH ALL AM RADIOS
• WORKS WITH ALL CRYSTAL AND MAGNETIC MIKES AND PHONO CARTRIDGES

11.95

Treat yourself and your family to hours of fun with this new Lafayette Kit. Make your own radio programs, announcements, etc. through AM radios anywhere in the house without wires or extra gadgets. Designed for easy construction by youngsters or adults, the KT-195 combines in one compact unit a powerful 3-tube wireless broadcaster and an audio amplifier. Clearly written instruction manual makes it a cinch to build. Operates on any frequency between 900 and 1600 kilocycles on your radio dial. It will accept any crystal or magnetic microphone. In addition, the KT-195 may be used directly as a phono or microphone amplifier. No external preamp is required. Simple slide switch permits either form of operation. Just connect it to a PM speaker (4-16 ohms). No external FCC regulations and is designed to provide high quality voice record broadcasts. Within this range, however, the unit can provide high quality voice or record broadcasts. No license or permit is necessary. Complete with crystal clear Attractively styled metal cabinet suitable for any decor.
KT-195 Shpg. wt., 3 lbs. Net 11.95
Same as above, but factory wired and tested. Net 11.95
LA-23 Crystal microphone for above. Desk or hand held. 8 ft. cabl. Net 14.45
PA-73 Shpg. wt., 1 lb. Net 2.95

NEW! ELECTRONICS EDUCATIONAL KIT




Complete With 116 Page Instruction Manual — Virtually A Textbook & Laboratory Manual

24.50

• 194 ILLUSTRATIONS • INCLUDES QUESTIONS & ANSWERS FOR EACH SECTION • CLEARLY WORDED STEP-BY-STEP INSTRUCTIONS • COVERS BOTH AC & DC IN THEIR ENTIRETY • TEACHES, AS YOU BUILD • 12 COMPLETE EXPERIMENTS RESULT IN A FINISHED AC & DC TEST INSTRUMENT • ENABLES REPAIR OF HOUSEHOLD APPLIANCES

The fascinating world of electronics introduced in a simple, easy-to-follow manner through this new Lafayette KT-180 Electronic Educational Kit. Not a toy—this kit is a complete beginners electronics laboratory course featuring an extremely useful AC/DC Multitester. In the process of constructing this test meter, the fundamental principles of electricity and electronics are introduced in a "learn-by-doing" method. The focus of attention is on the basic sensitive meter for measuring the flow of electrical current. From this simple measurement, the meter is built up to indicate voltage and resistance. The detailed 116 page instruction manual contains 194 illustrations and is written in a simple, easy-to-read, step-by-step manner with questions and answers supplied for each section. Providing a virtual "guided tour" of electrical fundamentals, this kit furnishes a complete course in AC and DC including ohms law, series and parallel connections, making electro-magnets, producing electricity by induction and testing house appliances. The kit is supplied less batteries.
KT-180 Shpg. wt., 5 lbs. Net 24.50
BA-155 Burgess Z type battery, 2 required) Net ea. .095

NEW! AC/DC BROADCAST RADIO SEMI-KIT




9.95

• ALL MAJOR COMPONENTS PRE-MOUNTED
• CONTEMPORARY STYLING
• 5 TUBE SUPERHETERODYNE CIRCUIT
• FUSED POWER LINE

Imagine the joy of building your own full size table model radio. The perfect kit for beginners. Everything but tools is included in the kit to build this fine radio. All the major components are pre-mounted on the chassis by the factory. Two clearly marked cards identify the few resistors and capacitors necessary to complete the set. No special tools are required for alignment either. A simple procedure is outlined in the Lafayette illustrated instruction manual which will enable you to achieve excellent reception across the entire broadcast band (540-1600 KC). Sounds as good as it looks too. Styled in a beautiful contemporary plastic cabinet with a finished back. Vented back provides proper baffling and ventilation for components. 5 tubes (2 dual purpose) plus a high "Q" ferrite rod antenna for better AM reception. Cabinet measures 8 1/2 x 4 1/4 x 4" overall. Muted colors match any color scheme. Tubes: 35W4, 12AV6, 12BA6, 12BE6 and 50C5. For 117 V AC/DC. Shpg. wt., 3 lbs. Net 9.95
KT-204

LAFAYETTE P.A. AMPLIFIERS AND SYSTEMS

NEW! LAFAYETTE 40-WATT PUBLIC ADDRESS AMPLIFIER



- Power Output Sufficient to Drive Many Speakers Simultaneously
- Flat Response from 30 Cps to 15 Kc
- Two Microphone Inputs, One Phonograph Input
- Separate Volume Control for Each Input
- Excellent Hum and Noise Suppression
- Attractive New Styling


69⁹⁵

NO MONEY DOWN

Here is a powerful new public address amplifier suitable for use in large department stores, stadiums, amusement parks, industrial plants, summer camps, etc. Power output is a full 40 watts. Three inputs are provided: Two microphone inputs for crystal or dynamic mikes, and one phono input for a crystal or ceramic pickup, a tape recorder, tuner or other high level program source. Frequency response: ± 2 db from 30 cycles to 15 Kc. Input sensitivity: mike inputs, 5 mv for full output; phono 300 mv. Input impedance: mike, 1 megohm; phono, 500,000 ohms. Hum and noise are 64 db below rated output with mike inputs and 74 db below with phono input. Hum balance control provided in rear. Each input has its own volume control to permit proper blending and balance when two or three inputs are in use simultaneously. Separate bass and treble controls. Output impedances: 4, 8, 16 or 250 ohms, taken either from a terminal strip in the rear, or from two 6-prong sockets provided for rapid connection and disconnection. The 250 ohm output is a constant voltage tap for a 70 volt line. Groups of speakers may be connected directly to the amplifier in various series, parallel, and series-parallel configurations. Tube complement: 1-12AX7/ECC83 microphone preamplifier, 1-6AV6 tone control, 2-6AQ8's and 4-6B05/EL84 output tubes (two parallel pairs operating push-pull). For 110-120 volts, 50-60 cycles AC. In an unusually attractive metal cabinet with modern black and gray panel, 5 1/4" H x 13 1/4" W x 9 1/4" D. Shpg. wt., 30 lbs. PA-268WX

Net 69.95

NEW! 40 WATT DUAL SPEAKER PA SYSTEMS



125⁹⁵

- New Lafayette Powerful 40 Watt Public Address Amplifier
- 2 University or Electro-Voice Horns For Outdoor Systems
- 2 25-Watt Speakers & Wall Baffles For Indoor Systems
- Choice of Deluxe Dynamic Mikes
- 70 Ft. of Speaker Cable

Highly efficient permanent sound systems for large halls, department store music and paging systems, railroad stations, restaurant music, etc. The outstanding Lafayette PA-268 40 watt amplifier assures top performance under all operating conditions. For 117 volts, 60 cps AC.

- 40-WATT PERMANENT INDOOR SYSTEM**
Consists of the PA-268 40-watt amplifier, two 12" PM speakers, two attractive walnut wood baffles, two 35' speaker cables with plugs, an Atlas MS-10C floor mike stand and Argonne AR-3 dual impedance dynamic microphone with ball-joint desk stand, for hand-held, desk stand or floor stand use. Shpg. wt., 75 lbs. PA-284WX Net 125.95
- Same as above, except with Electro-Voice 664 mike in place of AR-3 PA-283WX Net 149.95
- 40-WATT OUTDOOR PA SYSTEM**
Consists of a PA-268 40-watt amplifier, two Lafayette PA-57 driver units and two University PH trumpets, two 35' speaker cables with plugs, and an Argonne AR-3 dynamic mike with desk stand. Shpg. wt., 75 lbs. PA-282WX Net 139.45
- Same as PA-282WX, except with Electro-Voice 664 dual impedance cardioid dynamic mike and MS-10C floor stand in place of AR-3 PA-281WX Net 168.45
- Same as PA-282WX except with 2 Electro-Voice 848 projectors in place of PA-57 and University PH. PA-280WX Net 157.95
- Same as PA-280WX with Electro-Voice 664 mike and floor stand in place of AR-3 PA-279WX Net 186.95

LAFAYETTE 30 WATT PA AMPLIFIER



PA-62 with PA-65 Phono Top Less phono-top


52⁵⁰

Ideal for use in churches, schools, small theaters, lecture halls and industrial plants. Separate bass and treble tone controls, permits adjustments to meet all acoustic requirements. Two mike inputs; optional 4-speed phono top. 70 volt constant voltage output tap. Provides coverage up to 100,000 square feet when used with trumpet type speakers. Chassis is equipped with 2-speaker plug-in output sockets. Housed in sturdy steel, well-ventilated cabinet, in baked hammerloid enamel. Removable escutcheon plate for rack and panel mounting.

SPECIFICATIONS: TUBES: 3-6EU7, 2-6L6GB, 5U4GB (Rectifier). **POWER OUTPUT:** 30 Watts. **INPUT GAIN:** Microphone 125 db, Phono 80 db. **FREQUENCY RESPONSE:** 30 to 15,000 cps, ± 1 db. **TONE CONTROLS:** Bass ± 15 db at 50 cps; Treble ± 15 db at 10,000 cps. **HUM LEVEL:** 70 db below rated output. **INPUTS:** 3; 2-Microphone and 1-Phono. **CONTROLS:** 6; Microphone-1, Microphone-2, Power off-on, Phono-Bass, Treble, Slide Switch for operating magnetic phono thru channel 2. **OUTPUT IMPEDANCES:** 4, 8, 16, and 250 ohms (70 volt line). High impedance output for coupling booster amplifier. **POWER CONSUMPTION:** 135 Watts, 110/120 V.A.C. 50-60 cycles. Fused. 14Wx8Dx6"H. Shpg. wt., 20 lbs. PA-62WX Complete with Tubes

- Net 52.50
- 4-SPEED PHONO TOP**
Fits in place of cover. 16 1/2, 33 1/3, 45 and 78 rpm. Turnover cartridge is complete with two precious metal needles. Has arm-rest and plug connection; for 110 Volt 60 cycle. Shpg. wt., 10 lbs. PA-65W 4-Speed Phono Top Net 17.95

DUAL-SPEAKER 30-WATT PORTABLE SYSTEMS




The most popular system for schools, RR waiting rooms, gyms, churches, noisy factories. Ideal for rentals.

AS LOW AS **110⁵⁰**

NO MONEY DOWN

- CHOICE OF DELUXE DYNAMIC MIKES
 - TWO 25-WATT SPEAKERS
 - MONEY-BACK GUARANTEE
- This 30-watt system is one of our most popular models. Large enough for the majority of sound system applications — used in thousands of school auditoriums, churches, theatres, dance halls, dance studios and lecture halls. The ideal system for rentals; these systems have been sold to many hundreds of dealers. AND REMEMBER OUR MONEY-BACK GUARANTEE AND OUR LOW, LOW PRICE! **DUAL SPEAKER 30-WATT PORTABLE SYSTEMS INCLUDE:** The outstanding feature-filled Lafayette Model PA-62 30-watt amplifier; 2—25-watt PM speakers; 2—35' speaker cables and plugs; your choice of the popular Argonne AR-3 All-Purpose Dynamic microphone for hand-held, desk stand or floor stand use, with removable ball-joint desk stand and floor stand adapter and 8' cable; or the deluxe dual-impedance Electro-Voice 664 Cardioid dynamic microphone for use where high-feedback problems exist, with 40-15,000 cps response, on-off switch and 18' cable; the famous Atlas MS-10C floor mike stand, and the handsomely designed split-type portable carrying case covered in high quality dark blue leatherette. Size of case 22 1/2"Hx16 1/2"Wx15"D — provides a secure place for the system components. For 110-130 volts, 60 cps AC operation. Shpg. wt., 75 lbs. less phono; with phono 85 lbs.
- PA-232WX 30-watt Portable System, Less Phono Top and less MS-10C floor stand, complete as described with Argonne AR-3 dynamic mike Net 110.50
- PA-233WX Same as above, with E-V 664 dynamic microphone and MS-10C floor mike stand Net 140.50
- PA-234WX Same as PA-232WX with 4-speed phono top Net 128.50
- PA-235WX Same as PA-233WX with 4-speed phono top Net 158.50


30-WATT MOBILE OUTDOOR PA SYSTEMS



AS LOW AS **145⁵⁰**

- FOR 6V-12V BATTERY, 117V AC
 - WITH OR WITHOUT 4-SPEED PHONO TOP
 - CHOICE OF EITHER OF 2 LAVALIER MIKES
- 2 sound systems for the price of 1, with plenty of power for any job, whether mobile or indoor. Provides coverage for areas up to 100,000 square feet. Operates from any 6 volt or 12 volt automobile, truck or bus storage battery or from 110-130 volts 60 cycles AC; 30 watts output. REMEMBER: THE AMPLIFIER IS UNCONDITIONALLY GUARANTEED AGAINST DEFECTS IN MATERIAL AND WORKMANSHIP FOR 1 FULL YEAR . . . AND COMPARE OUR PRICE!
- COMPLETE MOBILE SYSTEMS INCLUDE:** The Lafayette Model PA-64 30-watt mobile amplifier complete; a set of AC and battery cables; your choice of 2—Lafayette PA-57 driver units and University PH reflex trumpets or 2—Electro-Voice 848 CDP 30-watt compound diffraction projector wide-angle horns; your choice of the Lafayette PA-31 wide-range crystal microphone with on-off switch, lavalier cord and bracket and 7' cable and connector, and with swivel-type mike stand adapter, for chest, hand-held or stand use—or, the deluxe Electro-Voice 647 lavalier dynamic mike with neck cord, support clips and 18' cable, for chest, hand or desk use; PLUS 2—35' speaker cables and plugs. Shpg. wt., 75 lbs. less phono; with phono 85 lbs.
- PA-236WX Complete 30-watt mobile outdoor system with PA-64 30-watt mobile amplifier less phono top; with AC and battery cables, 2 Lafayette PA-57 driver units and 2—University PH trumpets, 2—35' speaker cables and plugs and Lafayette PA-31 microphone Net 145.50
- PA-237WX Same as PA-236 except with E-V 647 mike Net 177.00
- PA-238WX Same as PA-236 except with 2 E-V 848 CDP 30-watt projectors Net 164.00
- PA-239WX Same as PA-237 WX except with 2 E-V 848 CDP projectors Net 195.50
- PA-240WX Same as PA-236WX except with 4-speed phono top Net 165.50
- PA-241WX Same as PA-237WX except with 4-speed phono top Net 197.00
- PA-242WX Same as PA-238WX except with 4-speed phono top Net 184.00
- PA-243WX Same as PA-239WX except with 4-speed phono top Net 215.50
- PA-64WX 30-Watt Mobile Amplifier only, less phono top, 25 lbs. Net 84.75

NEW! LAFAYETTE MODEL LA-75 20-WATT MUSIC AMPLIFIER



INSTRUMENT CONTROL PANEL RECESSED FOR EASY ACCESSIBILITY

69⁵⁰


NO MONEY DOWN

- 20 Watt High-Fidelity Amplifier
- For Presenting Amplified Live Music and Voice to an Audience
- Adjustable Tremolo for "Quivering" Effect
- Built-in 12" Heavy-Duty Hi-Fi Speaker
- Separate Volume and Tone Controls for Instrument and Voice Inputs

Here is a music amplifier which will deliver 20 watts of clean power, to a built-in 12" heavy-duty 20 watt speaker or to an external 4, 8 or 16 ohm speaker. There are 3 inputs: two instrument inputs and one microphone input for voice. The two instrument inputs have volume and tone controls separate from the corresponding controls on the voice input. Built-in tremolo circuit super-imposes an oscillator signal on the audio signal to create a periodic fluctuation or "quiver" whose frequency and amplitude may be adjusted by the "speed" and "strength" controls, respectively. There is a jack provided for turning the tremolo on and off by means of a foot switch (available as an accessory). Frequency response: ± 3 db from 33 cycles to 20 Kc on voice input; ± 3 db from 33 cycles to 15 Kc on instrument inputs. Mike input sensitivity is 9 mv RMS; mike jack is shorting type to minimize hum pickup when mike is not plugged in. Tube complement: 2-12AX7's, 1-6AU6, 2-7189 output tubes, 1-6CA4 rectifier. Dimensions: 15 3/4"H (including rubber feet) x 19 1/2"W x 8 1/2"D. With carrying handle. Shpg. wt., 30 lbs. Net 69.50

LA-75 WX FOOT SWITCH to remotely control the tremolo in the LA-75. Equipped with cable terminated in standard phone plug to fit corresponding jack on LA-75. Shpg. wt., 1 1/2 lbs. Net 5.95

SW-103



FOOT PEDAL

LAFAYETTE 25-WATT MOBILE ALL TRANSISTOR PA AMPLIFIER



74⁵⁰

NO MONEY DOWN

• Plugs Directly Into Cigarette Lighter • Operates Off 12 Volt Battery


This all transistorized amplifier is ideal for sound trucks, parks, boats or any place where AC power is not available. Operates from any 12 volt DC source such as car battery and delivers 25 watts of power for outdoor meetings of any kind. Plugs right into cigarette lighter. Has 2 inputs: 1 for phono (2 volts) and 1 for low impedance microphone. Five control knobs are microphone volume, phono volume, bass, treble and power. Freq. response 80-12,000 cps ± 2 db. Output impedances 4, 8 and 16 ohms. Noise level: phono —80db, mike —60db. Low idling current drain. Fused. Size: 11Wx3 1/2"Hx8"D. Shpg. wt., 10 lbs. Net 74.50

PA-256WX less phono top Net 74.50


PA-257WX 4-speed phono top for above Net 92.40



Most Outstanding Values in Wireless History



LAFAYETTE WIRELESS INTERCOM




- Move it from Room to Room—No Wires Needed
- 3-Position Operation Bar-Lever
- Dependable 3" Speaker
- For Home and Office Use
- Add as many Extra Remotes as Desired

2 WIRELESS INTERCOMS
29⁹⁵
NO MONEY DOWN

Lafayette offers the most outstanding intercom value ever! The Lafayette Wireless Intercom offers quality performance at an amazing low price. Features a three-position operation bar-lever: Dictate (for use as "baby sitter", lengthy talking), Talk (has spring return to Listen position), and Listen. Can be plugged into any 117V outlet—move from room to room, no wires to connect. Front panel has volume control plus easy-to-see pilot light. Rear panel has adjustable squelch control. Dependable 3" speaker. For use in the home and office and use as many remotes as you need. Shpg. wt., 10 lbs.
PA-294 2-Station Intercom Net 29.95
Extra Remote for PA-294. Shpg. wt. 5 lbs. PA-293 Net 15.25

EASY-PHONE TELEPHONE AMPLIFIER



With Batteries
17⁵⁰

- Amplifies Telephone To Room Volume
- 4 Transistors + Varistor
- No Dangling Wires, Pick-ups To Connect
- No Warm-Up, Instant Operation

The Lafayette Easy-Phone Telephone Amplifier amplifies the telephone to room volume, making it ideal for use in the office or at home. Place the telephone receiver on the easy-phone and both hands are free for writing or typing. At home the entire family can listen in on telephone conversations—a great money-saver for long-distance telephone calls. The Easy-Phone is always ready for instant use. A 4-transistor, battery-powered amplifier and inductive pickup, completely installed in an attractive plastic case, compose the Easy-Phone. Completely self-contained without protruding plugs and twisted hook-up cords. Operation is this simple: by placing the tele-

phone receiver on the Easy-Phone you automatically turn on the amplifier, then adjust the volume to the desired level. The volume control is a separate control. Features 4-transistor circuit, with 1 varistor, powered by 4 penlight 1.5V batteries. 3" dynamic speaker is out of view, under the amplifier. Black, heavy Bakelite case with 2 sturdy chrome plated runners. Weighs only 25 ozs. With miniature plug and jack for recorder input. Overall: 3 1/4" L. 3 1/2" W. 2 1/4" H. Shpg. wt., 3 lbs.
F-759 with Batteries Net 17.50
Extra Batteries for Above. Net .095
BA-155 Penlight Battery

FAMOUS BRAND 2-STATION INTERCOM



13⁹⁵

• SMART STYLING • ALL-METAL CABINET
• 4" SPEAKERS • CABLE SUPPLIED
New! Low cost intercom system that combines smart new styling with quality performance. A Lafayette special, this 2-station intercom is a must for your home, store, or business office. Units come complete with 50 feet of interconnecting cable and will save you thousands of steps and needed energy. An additional remote station may be added if needed at very low cost. The Master unit has its own volume control with "on-off" switch. No switch is necessary on remote. Power consumption is only 29 watts. This set uses a 12AT7 Dual-triode amplifier plus a Selenium rectifier. 4" Alnico speakers are used in both Master and Remote. 110 Volts AC or DC. Measures only 6 5/8" x 4 1/2" x 4 3/8". Shpg. wt., 6 lbs.
PA-269 2-Station intercom complete Net 13.95
PA-270 Extra Remote Station Net 5.83

NEW! MINIATURE HORN PAGING SPEAKER



7⁹⁵

- Mounts Easily
- 90° Dispersion
- Weatherproof

An excellent general purpose paging speaker of amazingly compact size. Ideal for portable PA systems, patios etc. Long throw projection of 90° dispersion offers maximum speech intelligibility in high noise areas. Compact size enables it to be mounted anywhere in almost any position. Frequency response 400-12,000 CPS. Impedance 8 ohms. Power handling capacity 5 watts, 8 watts maximum. Complete with mounting bracket, 2-conductor cable. Horn diameter 5 1/8". Depth 4 1/4".
PA-295 Shpg. wt., 1.4 lbs. Net 7.95



FOURJAY

As Low As
1705

A THE PATIO PAIR

The Patio Pair consists of a separate loudspeaker baffle with weatherproof speaker, and an attractive patio lamp. Identical in styling in green and white fiberglass with pipe fitting for 1" pipe. Speaker provides even dispersion of sound. Lamp accommodates up to 100-watt bulb.
Model S-DF1 8 WG Speaker Baffle. Includes 20-watt, 8" weatherproof speaker with 40-11,000 cycle range, 8-ohm voice coil. Shipping weight 6 lbs. less lamp PE160 Net 17.05
Model LMP 60/100 WG Lamp. Includes weatherproof ceramic socket, less bulb. Shipping weight 4 lbs. PE161 Lamp for PE160 Net 10.05

B FOURJAY MELODY BELL FOR OUTDOORS — FOR INDOORS

Hang it from trees, overhangs, wires, posts, etc. All fiberglass construction and design assures even dispersion of sound as well as fine tonal quality. Includes efficient 10 watt 8" weatherproof speaker with 40-11,000 cycle range, 8-ohm voice coil. Attractively finished in white and green. Shpg. wt., 5 lbs.
PE-162 Net 14.26

NEW! LAFAYETTE HI-FI "THIN LINE" CEILING & WALL BAFFLE SPEAKER



Absolutely Incredible Sound Quality!
5⁹⁵

- Measures Only 2 1/4" Deep • Employs New Inverted Magnet
- Perfect for Hi-Fi Extension Speaker or P.A. Use
- Only 2 1/4" Deep • New Inverted Magnet

Frankly we were amazed at the phenomenal musical quality of this speaker. Never before have we heard a speaker of this size reproduce the true sounds of loud orchestral passages, drums, etc. with such definition and clarity. The perfect speaker to furnish music or paging throughout your home, office or factory. Advanced design employs an inverted magnet, placing the 12 oz. magnetic structure in front of the speaker rather than behind as in conventional speakers. Only 2 1/4" deep with its own metal baffle plate, the SK-175 easily mounts in any wall, ceiling, closet or ordinary wood enclosure. Two are perfect for stereo. Voice coil is 1" Diam. Frequency Response: 90-9,000 cps. Impedance: 8 ohms. Overall Dimensions including metal baffle is 9 1/2". Requires 6 3/4" wall cutout. Shpg. wt., 3 lbs.
SK-175 Net 5.95

6" PAGING SPEAKER

Ideally suited for multiple use where maximum coverage is needed. A small high efficiency trumpet horn speaker weatherproofed and sealed for outside use. Provides high penetration over 90° spread. Rubber rim protects horn and prevents resonance. Rugged 180° swivel bracket locks securely with thumb screw. Very solid mounting with heavy cast mounting base. Power handling capacity 5 watts. Frequency cutoff 360 cycles. Impedance 8 ohms. Horn size: 6" diam. 4 1/2" deep, total depth 5 3/4". Base size: 2 3/4" diam., 3 1/4" holes on 1 1/4" centers. Heavy duty 2 conductor color coded lead. Shpg. wt., 3 lbs.
PA-103 Net 10.95

- 90° Dispersion
 - Easily Mounted
 - Weather Proof
- 10⁹⁵**



LAFAYETTE 25-WATT DRIVER UNIT

- Fits All Trumpets And Projectors

9⁸⁵



Hermetically sealed weatherproof driver unit. Delivers 25 watts of power. Perfect for any location where high volume with low distortion is desired. The PA-57 will fit any trumpet or projector of your choice without modification. The wide-range frequency response of 20-7,100 cps assures excellent reproduction of music and speech. 16 Ohm impedance matches all amplifiers. Size 4" Diameter, 3-5/8" depth. Shpg. wt. 3 3/4 lbs.
PA-57 Net 9.85

NEW OUTDOOR 8" PATIO SPEAKER



ONLY **11²⁵**

- WEATHER PROOF — WATERPROOF
- CLEAR HI-FI Sound
- Mounts anywhere — Indoors or Out
- Use Two for Stereo

Now the perfect outdoor hi-fi speaker to let you enjoy favorite programs, records and music while relaxing outdoors on your patio; in your yard; at your bar-b-que. Handsome enough for recreation rooms and dens. It is completely wired, ready to install to the radio, phone or intercom system. Unaffected by dampness, humidity, rain or snow the metal baffle is finished in a golden-bronze enamel. With 3 1/2" voice coil and 3.16 oz. Alnico V magnet. 8 ohm voice coil impedance. 1 pad for perfect matching with max. output. Peak power 8-10 watts. Size: 10 1/2" x 11 5/8". Shpg. wt., 5 lbs.
PE-155 Net 11.25

TRANSISTOR POWER 'PHONE

• 125 MILE RANGE ON A SINGLE PAIR OF WIRES! • A COMPLETELY SELF-CONTAINED TRANSISTOR AMPLIFIER & BATTERY! • WORKS WITH STANDARD "PENLIGHT" CELLS • ANY NUMBER OF HANDSETS MAY BE USED IN A COMMON TALKING SYSTEM!

Lafayette brings you these unique transistorized telephone handsets at extremely low cost. Each handset is complete with its own transistor amplifier, buzzer, press-to-talk pushbutton switch, buzzer pushbutton switch and shielded coiled cord (extendable to 5') with male and female connectors ready to connect to 2-wire cable. Each handset is handsomely styled in heavy, high impact resistance, moulded plastic. All stations are connected to the same 2-wire cable, and good signals can be received up to 125 miles with #22 wire! Everything is self-contained in each handset, and any number of handsets can be utilized. Burgess #2 or RCA VS034 battery cell. SHIPPING WEIGHT (PER PAIR)—3 1/2 lbs. Complete with Batteries.
PA-8—2-Station Transistor Telephone System (2 units) Net 19.95
PA-6—Single Transistor Telephone Unit. Shpg. wt., 2 lbs. Net 10.95
BA-155—Burg. Z or equiv. (1 per handset) Shpg. wt. ea. 1 lb. Net ea. .095
Extra battery
WR-221 ALPHA 1172—2-wire cable for telephone systems. Shpg. wt., 1 lb. per 100' Net 2.41

TELEPHONES FOR INTERCOM AND PRIVATE PHONE SYSTEMS


WESTERN ELECTRIC HANDSET



4²⁵

Dependable, rugged Western Electric F-1 Handset. Has countless valuable applications for intercom, private phone, etc. Reconditioned for fool-proof service. Complete with retractable cord. Shpg. wt., 1 lb.
PA-375 Net 4.25

WESTERN ELECTRIC TYPE SG-1 SOUND POWERED HANDSETS.



5⁹⁸


Simple 2-way communications for miles. No batteries required. Just connect phone clips to two conductor wire. Excellent for Private Intercom System, Construction, TV Installer, Motels, Camps, Farms, Factories, Stores, Homes, Ski Resorts, etc. Any number of handsets can be installed on one line. Complete with retractable cord and alligator clips. Shpg. wt., 4 lbs.
PA-375 Net 5.98
PA-376 Set of two Handsets with 100 ft. of 2 Conductor Inside-Outside Wire Net 12.75

3 CONDUCTOR COILED CORD



.89

Exceptional value in a tough, 3-conductor coiled cord with strain relief. Excellent for phones in private phone systems, intercoms, etc. Extends to 6'. Shpg. wt., 1/2 lb.
PA-378 Net .89



PHOTOCELLS AND PARTS FOR KIT BUILDERS, for Experimenters & Engineers



NEW!

LAFAYETTE AUTOMATIC PHOTO-ELECTRIC 'LUMINATOR



• Automatic Light Switch
• Lights on at sunset—off at sunrise

4.95

New photo-electronic, light sensitive switch turns lights on and off at dusk and dawn. Better than a clock—no setting and re-setting of timer. Variance in "on-off" cycle adds extra protection when away from home. You need never come home to a darkened house. The controlled lamps go on as darkness falls—stay on until sufficient day light returns or until manually turned off. Just plug it in for protection from prowlers—to turn on night lights—illuminate outdoor areas—light up brooders—green houses—displays—show windows—any place you require automatic illumination. Mounts most anywhere on a rubber suction cup feet. Unobtrusive—measures only 3 3/4" x 2 1/2" x 1/4". Use on 117 volt AC only. Maximum 300 watts lamp load. Instructions included. Shpg. wt., 1 lb.

MS-790 Net 4.95

ULTRA-THIN MINIATURE SPEAKER

2 1/4" DIAM. x 5/8" THICK

• Ideal for Replacement and Miniature Builders — Hobbyists, Experimenters, etc.
• Only 3/8" Thick

1.29

A value-priced miniature speaker ideal as replacement in Japanese portable radios as well as initial speaker for experimenters and hobbyists for miniature building. Voice coil impedance: 8 ohms; minimum response: 350-450 cps; input power: 0.3 watt; frequency range: 50-6,000 cps. Overall 2 1/4" dia. x 5/8" thick.

SK-178 Shpg. wt., 4 oz. Net 1.29

NEW! ULTRA SUB-MINIATURE TRANSISTOR COIL KIT




• Smallest 2 Gang Variable Ever Made!
• Size: 1 1/8" Square, 3/8" Deep
• 3 I.F.'s and OSC: 1/4" Square, 3/8" High
• Ferrite Loop Antenna

All in one kit—a complete set of matched micro-miniature coils, ferrite loop antenna, ultra-compact 2 gang variable condenser, tuning dial and schematic diagram for building a subminiature 6 transistor radio. Kit includes: Shielded and impregnated high-Q 455 KC IF transformers and oscillator coil—all slug tuned. Proper impedances are provided for optimum circuit performance. Variable condenser has protective case and rear trimmer adjustment. Flat ferrite loop antenna measures 2 1/8" x 1 1/8" x 1/8" thick. Clearly-printed circuit diagram indicates all parts necessary for a powerful 6 transistor receiver. Tuning dial and knob (1 1/8" dia.) fits securely on V.C. shaft. Shpg. wt. of kit is 1 lb.

MS-B28 Net 3.45


POLARIS "MAJ-I" RESISTOR PHOTOCELL



A cadmium-sulphide light-dependent resistor used to actuate door openers, burglar alarms, smoke detectors, light controls, production counters, etc. Resistance varies from 200 ohms at approx. 93 foot-candles to over 10 megohms in total darkness. Maximum volts: 110VAC (peak) 110VDC; maximum dissipation: .2 watt @ 40°C, .1 watt @ 50°C, 0 @ 60°C. Capacity approx. 6 mmf. 1/2" diam. x 3/8" thick. Shpg. wt., 3 oz.

MS-922 Net .89

SELF GENERATING PHOTOELECTRIC CELLS



BELOW DISTRIBUTOR COST!

• Complete with leads
• No external power needed
• Output in sunlight up to 60 MA

• Up To 750 ua at 100 ft. Candles

.53

Selenium, self-generating photocells convert sunlight or artificial light energy into electrical energy without any auxiliary source of power. Sensitive to a wide spectrum including white, colored or ultra-violet light. All unmounted; complete with leads. Outputs in table below taken at 100 foot candle illumination with 100 ohm load. Higher outputs obtainable with greater light. Shpg. wt., 3 oz.

| Stock No. | Out μ a | Size | 1-4 | 5-9 | 10 |
|-----------|-------------|-----------------|------|------|------|
| MS-771 | 100 | 1 1/2" x 3/4" | .59 | .56 | .53 |
| MS-772 | 250 | 1 1/2" x 5/8" | .79 | .75 | .71 |
| MS-773 | 350 | 1 1/2" x 7/8" | .89 | .85 | .80 |
| MS-774 | 750 | 1 1/2" x 1 1/4" | 3.18 | 3.03 | 2.88 |

NEW! LAFAYETTE CADMIUM SULPHIDE PHOTOCELL




• Only 3/8" D x 1/2" W

.95

New head-type window cadmium sulphide photocell. Maximum Ratings: 200 volts DC or AC peak. Temperature is -40°C and +60°C; Resistance is over 10 megohms at zero ft. candles, 100,000 ohms to 10 megohms at 1 foot candle, 100,000 to 350,000 ohms at 10 foot candles; Range of sensitive wave length is 4000 to 8000 angstroms. Size: 3/8" diam. x 1/2" L. o/a. Standard screw mount: miniature base.

MS-855 Shpg. wt., 4 oz. Net .95

POWERMASTER TYPE CDS-10 CADMIUM SULPHIDE PHOTOCELL



2.50

A miniature crystal photocell that is ideal for actuating, counting, measuring photo-electric control. Acts as a resistor that varies with the intensity of light from over 1 megohm in total darkness to under 1500 ohms at 100 foot candles. Rapid response fast enough to operate relays in 1/10 second. Minimum current output 66 ma at 50 ft. candles at 90 Volts. Output varies with illumination intensity and applied voltage to as low as .08 ma at 1 ft. candle at 6 volts. Power dissipation 1/2 watt continuous, 2 watts for 5 seconds. Usable response to entire visible spectrum with peak sensitivity to blue-green light and good red response. Response to infra-red is low. Size 1/2" x 3/8" x 1/4".

MS-739 Net 2.50

CADMIUM SULPHIDE PHOTOCELL



• For Sensitive Relay Actuation
• For Photo Electric Control

A neatly constructed crystal photocell that has countless applications in counting, relay actuation, etc. Resistance varies with light from 1 megohm in total darkness to approx. 1500 ohms at 100 foot candles. Responds to entire visible spectrum and has 1/10 sec. response for relay operation. Minimum current output 60 ma at 50 ft. candles at 90 volts. Power dissipation 2 watts for 5 seconds, 1/2 watt continuous. Output as low as .08ma at 1 ft. candle at 6 volts, varying with illumination intensity and applied voltage. Neatly capsulated for easy mounting with leads for electrical connection. 1 1/4" x 1/2" x 1/8" overall.

MS-827 Net 1.59

SELENIUM PHOTOCELL



Excellent for
• Burglar Alarms
• Door Openers
• Counters

8.75

OPERATES RELAYS DIRECTLY

Barrier layer, self-generating type: light striking upon cell generates current sufficient to operate relays directly without the use of auxiliary power. Lifetime of cell is unlimited. 600 microamperes output at 100 foot candles. 2 inches in diameter. Mounted in a handsome plastic case.

MS-826 Photocell, Wt., 8 oz. Net 8.75
CM-70 Socket for MS-826 Net .13

LAFAYETTE SUPER-VALUE SUN BATTERY



• Excellent for Experimenter, Kit Builder, etc.

Sensational buy enables Lafayette to offer this amazing selenium photocell at a fraction of the price of similar photoelectric cells! Surpasses by far, specifications of cells of equivalent size! Specifications: 0.9 ma Current Output at 100 ft. candles with 100 ohm load; 0.27 ma Current Output at 100 ft. candles with 1000 ohm load. 1 1/2" diameter. With colored pigtail leads.

MS-891 Net 1.95

NEW! SELENIUM PHOTOCELL FOR HEAVY DUTY OPERATION



2.45

• 3/4" Light Area

An efficient selenium photocell utilizing an extremely sensitive film element with 3/4" light area. Ideal for relay operation, use door openers, counters, etc. Rated at 200V; 20ma; 0.2W power dissipation at 20°C. Sensitivity is 610 \pm 50. Resistance Value Characteristics — 0 Ft. Candles: 1M ohm/up; 0.929 Ft. Candles: 33K ohms; 9.29 Ft. Candles: 8K ohms. Size 3/4" Diam. x 3/8" depth.

MS-886 Net 2.45

NEW! LAFAYETTE SELENIUM PHOTOCELL



• 3/8" Light Area

A quality selenium photocell, perfect for transistor and printed circuit use. Employs sensitive film element with 3/8" light area. Rated at 200V; 10ma; 0.1W. power dissipation @ 20°C. Sensitivity is 610 \pm 50. Resistance Value Characteristics — 0 Ft. Candles: 2M ohms/up; 0.929 Ft. Candles: 100K ohms; 9.29 Ft. Candles: 25K ohms; Size 3/8" Diam x 3/8" Depth.

MS-885 Net 1.95

NEW! LAFAYETTE MINIATURE SILICON RECTIFIER



.49

• ONLY 3/4" D x 1/2" W

Premium quality and small size make this precision rectifier ideal for prototype and miniature applications. Measures 3/4" D x 1/2" W plus 1/4" mounting lip. Rated AC input voltage 100V, DC output current 20ma. Intermittent 40ma. Maximum Input Capacitance 80MF.

MS-887 Net .49

SUBMINIATURE TRANSISTOR AUDIO TRANSFORMERS

A new series of miniature transformers for transistor and experimental miniature circuits. Ideal for miniature radio receivers, amplifiers, hearing aids, etc., using standard transistors. Incorporate special heat-treated high permeability magnetic cores—treated to resist corrosion. Designed for improved frequency response with low distortion. 3" color-coded leads. Average shpg. wt., 4 oz.

| Stock No. | Circuit | Impedance | Pri. Ω | Sec. Ω | D.C. Resistance | Pri. Ω | Sec. Ω | Net |
|-----------|---------|-----------|---------------|---------------|-----------------|---------------|---------------|-----|
| TR-97 | INPUT | 100,000 | 1000 | 1000 | 1000 | 1000 | .79 | |
| TR-98 | DRIVER | 10,000 | 2000 C.T. | 240 | 60 C.T. | | .79 | |
| TR-99 | OUTPUT | 500 C.T. | 3.2 | 42 C.T. | | 0.7 | .79 | |
| TR-120 | INPUT | 200,000 | 1000 | 1400 | | 50.5 | .89 | |
| TR-116 | OUTPUT | 500 C.T. | 8 | 50 C.T. | | 1.7 | .79 | |



A FABULOUS BUY! GENUINE ALLEN-BRADLEY and IRC Resistor Kit

100 INSULATED RESISTORS WITH PLASTIC HINGED BOX!

Lafayette leads the field with a genuine Allen Bradley and IRC 1/2 watt, 10% tolerance, molded resistor kit with a Transparent Plastic Utility Box (built in partitions) size: 8 1/2" x 4 1/2" x 1 1/2". Meet JAN-R-11 specifications. Stock No. KI-23—Total 100 molded resistors with Transparent Plastic Case. Net 4.50

| 10% TOLERANCE 1/2 WATT RMA Color Coded | | 100 TOTAL | |
|--|--------|-----------|----------------|
| Quant. | Ohms | Quant. | Ohms |
| 3 | 100 | 10 | .1 meg |
| 3 | 470 | 4 | .15 meg |
| 4 | 1,000 | 4 | .27 meg |
| 3 | 2,200 | 10 | .47 meg |
| 4 | 4,700 | 10 | 1 meg |
| 5 | 10,000 | 4 | 2.2 meg |
| 4 | 22,000 | | Other |
| 4 | 27,000 | 20 | popular values |
| 4 | 33,000 | | |
| 4 | 47,000 | | |

NEW POWER TRANSISTOR AUDIO TRANSFORMERS

• DESIGNED FOR HIGH OUTPUT TRANSISTORS
• USED IN AUTO RADIOS—PA SYSTEMS—INTERCOMS—ETC.

1.75

Rated 6 watts. Frequency response 70 to 20,000 cycles \pm 2 db. Primary impedance, 48 ohms center tapped. Secondary, 3.2 ohms; Primary DC resistance 1.1 ohms, secondary 0.3 ohms. Unbalanced primary current \pm 50 ma DC. Size 1 1/4" x 1 1/4" x 1 1/4". Shpg. wt., 1 lb.

AR-503 Net 1.75

Rated 2 watts. Frequency response 70 to 20,000 cps \pm 2 db. Primary impedance 100 ohms. Secondary impedance 200 ohms CT. Primary DC resistance 1.8 ohms, secondary 2.7 ohms. Unbalanced primary current, 200 ma DC. Size 1 1/4" x 1 1/4" x 1 1/4". Wt., 1 lb.

AR-504 Net 1.50

NEW! UNIVERSAL POWER TRANSISTOR OUTPUT TRANSFORMER

• DESIGNED FOR THE EXPERIMENTER • RATED 10 WATTS
• PRI. TAPPED AT 8-12-16-24-32 AND 48 OHMS

Lafayette's latest transistor circuit component. Engineered for construction projects using the increasingly popular power transistors. Will also serve as a general replacement for many transistorized auto radios. Rated at 10 watts for push-pull operation. Primary tapped at 8, 12, 16, 24, 32 and 48 ohms. Secondary tapped at 4, 8 and 16 ohms. Sizes 3 1/4" x 2 1/4" x 2 1/4". Shpg. wt., 3 lbs.

TR-94 Net 3.75

NEW! MICRO-PERFORATED BOARDS

• Ideal For Transistor And Subminiature Circuitry
• Copper-Clad For Printed Circuits
• Unclad Type For Wired Circuits

These sturdy, perforated boards are the ideal base for builders, experimenters, and labs to mount miniaturized components. Two types available: either high grade bakelite for wired circuits, or one side copper-clad for "printed" circuitry. Holes are 1/16" diameter with 3/16" between hole centers. All boards are 1/8" thick. For contacts, the MS-263 flea clips listed on this page are ideal. Avg. shpg. wt., 6 oz.

| COPPER CLAD BOARDS | | | | UNCLAD BOARD | | | | | |
|--------------------|------------------|----------|---------|--------------|--------|------------------|---------|------|-----|
| Stock No. | Size | Net Each | Lots of | Stock No. | Size | Net Each | Lots of | | |
| MS-847 | 2 1/4" x 3 3/8" | .35 | .30 | .24 | MS-304 | 2 1/4" x 3 3/8" | .25 | .20 | .18 |
| MS-848 | 3 1/2" x 6 3/4" | .55 | .50 | .45 | MS-305 | 3 1/2" x 6 3/4" | .45 | .40 | .35 |
| MS-849 | 7 1/4" x 6 3/4" | 1.15 | .96 | .87 | MS-306 | 7 1/4" x 6 3/4" | .75 | .65 | .60 |
| MS-850 | 10 1/2" x 7 3/4" | 1.90 | 1.58 | 1.42 | MS-846 | 10 1/2" x 7 3/4" | 1.20 | 1.08 | .97 |

COPPER CLAD LAMINATE AT LAFAYETTE'S LOW PRICES!

| NO. | DESCRIPTION | NET |
|--------|------------------------------------|------|
| MS-510 | XXXX Copper Lam.—1 side—9"x12" | 1.50 |
| MS-511 | XXXX Copper Lam.—1 side—6"x4 1/2" | .45 |
| MS-512 | XXXX Copper Lam.—1 side—3"x4 1/2" | .30 |
| MS-513 | XXXX Copper Lam.—1 side—2"x4 1/2" | .25 |
| MS-514 | XXXX Copper Lam.—1 side—3"x2 1/4" | .24 |
| MS-515 | XXXX Copper Lam.—2 sides—9"x12" | 1.95 |
| MS-516 | XXXX Copper Lam.—2 sides—6"x4 1/2" | .60 |
| MS-517 | XXXX Copper Lam.—2 sides—3"x4 1/2" | .40 |
| MS-518 | XXXX Copper Lam.—2 sides—2"x4 1/2" | .30 |
| MS-519 | XXXX Copper Lam.—2 sides—3"x2 1/4" | .27 |

Finest quality XXXP bakelite base, copper clad boards for printed circuit work. Av. shpg. wt., 2 ozs.



FLEA CLIPS FOR TRANSISTOR AND SUBMINIATURE CONTACTS

"Flea" clips are specially designed for subminiature work. Fit perfectly in holes in perforated copper-clad and unclad boards listed above. Made of beryllium copper, silver plated finish. Simply insert wire thru hole for positive grip contact.

| Stock No. | Package of | Net |
|-----------|-------------------|--------|
| MS-263 | Package of 12 | .25 |
| MS-851 | Package of 1000 | 15.75 |
| MS-852 | Package of 5000 | 76.15 |
| MS-853 | Package of 10,000 | 149.30 |

LAFAYETTE SEMICONDUCTOR SPECIALS

FOR EXPERIMENTAL KIT BUILDER, HOBBYIST

QUALITY SEMICONDUCTORS AT ECONOMY 'PACKAGE' PRICES

10 GERMANIUM DIODES
 Pkg. of 10 germanium diodes (3" x 1 1/2" x 1/8") replaces 1N34, 1N34A, 1N46, 1N48, 1N51, 1N60, 1N64, 1N64A, 1N87, 1N105, 1N109, 1N127, 1N262, 1N268, 1N295, etc. Shpg. wt., 6 oz.
SP-234

10 SILICON DIODES
 Package of 10 silicon diodes. Replaces 1N34, 1N34A, 1N46, 1N48, 1N51, 1N60, 1N64, 1N87, 1N295, etc. Shpg. wt., 4 oz.
SP-235

4 PNP GERMANIUM TRANSISTORS
 SP-236
 Package of 4 PNP General Purpose Type Transistors similar in performance to 2N107, 2N218, 2N1265, CK722, CT222, TR722, 2N1191, etc. Shpg. wt., 6 oz.
.89 per pkg.
3.09 Any 4 Asst. Pkgs.

2 PNP TRANSISTORS
 SP-237
 Mixer/Oscillator Converter - Replaces 2N112, 2N114, 2N135, 2N136, 2N137, 2N140, 2N219, 2N411, 2N412, 2N414B, 2N415, CK760, CK766, 2S52 etc. Shpg. wt., 4 oz.

2 PNP GERMANIUM TRANSISTORS IF AMPLIFIER
 SP-238
 Pkg. of 2 PNP germanium IF amplifier transistors that replace 2N111, 2N111A, 2N112A, 2N139, 2N218, 2N409, 2N410, 2N413, 2N413A, 2N414, 2N414A, 2N416, GT760, 2S53, etc. Shpg. wt., 4 oz.

2 PNP GERMANIUM TRANSISTORS AF AMPLIFIERS (Up to 12 Volts)
 SP-239
 Pkg. of 2 PNP Germanium AF amplifier transistors that replace 2N133A, 2N138A, 2N138B, 2N151, 2N186A, 2N187A, 2N215, 2N217, 2N319, 2N320, 2N359, 2N360-363, 2N407, 2N408, 2N1008, A. B. GT81R, GT109, 2S56, 2S838, etc. Shpg. wt., 4 oz.

2 GOLD PLATED SILICON RECTIFIERS 500 MIL - 400 PIV
 SP-240
 Pkg. of 2 miniature size exceptional 24 karat gold plated silicon rectifiers rated at 500 milliamps, 400 PIV. Shpg. wt., 4 oz.

2 10 WATT POWER TRANSISTORS
 SP-243
 Package of 2 PNP 10 Watt germanium power transistors in popular TO-3 case. Similar to 2N155, 2N176, 2N235, 2N351, 2N242, 2N257, 2N268, 2N301A, 2N255, 2N554, 2N555, etc. Shpg. wt., 8 oz.

STUD MOUNT SILICON RECTIFIER 2 AMPERE 400 PIV
 SP-242
 Outstanding Buy! 2 amp. 400 Peak Inverse-Volts Silicon Rectifier, stud mounting. 3/4" long less lug. 1/4" hex nut. Shpg. wt., 6 oz.

2 TOP HAT SILICON RECTIFIERS 750 MIL - 400 PIV
 SP-241
 Pkg. of 2 top hat type silicon rectifiers rated at 750 milliamps, 400 PIV. Shpg. wt., 6 oz.

40 WATT HIGH POWER TRANSISTOR
 SP-244
 Amazing value is this 40-Watt high power PNP germanium transistor! Excellent for experimenter, hobbyist and kit builder for power supplies, auto replacement, audio outputs, etc. Similar to 2N175, CTP1504, SFT266, etc. Bolt mounted. Shpg. wt., 8 oz.

1 TOP HAT SILICON RECTIFIER 750 MIL 750 PIV
 SP-275
 Package of 1 top-hat axial lead silicon rectifier rated 750 milliamps, 750 Peak Inverse Volts. Shpg. wt., 4 oz.

4 TOP HAT SILICON RECTIFIERS 750 MIL 100 PIV
 SP-276
 Package of 4 top-hat axial lead silicon rectifiers rated 750 milliamps, 100 Peak Inverse Volts. Shpg. wt., 6 oz.

GENERAL PURPOSE DIODES
.19
 EXCELLENT DETECTOR FOR TRANSISTOR AND VACUUM TUBE RADIO RECEIVERS
 EQUIVALENT TO: 100 for 1N34, 1N34A, 1N38A, 1N48, 1N56, 1N69, 16.50
 SP-148 General Purpose Diode Net .19 each; 10 for 1.75

TRANSISTOR - DIODE PACKAGE SPECIAL
.79 Pkg.
 3 Pkgs. (can assort.) 2.09

5 GENERAL PURPOSE DIODES
 SP-218
 Package of 5 germanium glass diodes similar to 1N34A, 1N60, 1N64, 1N87A, etc.

4 PNP TRANSISTORS
 SP-220
 Package of 4 PNP Audio transistors similar to 2N107 Beta 15 minimum.

2 NPN TRANSISTORS
 SP-219
 Package of 2 NPN germanium transistors similar to 2N170 for Audio & RF Beta 70 minimum.

PNP AUDIO TRANSISTOR
 AS LOW AS **.31**
 LAFAYETTE SP-146 PNP TRANSISTOR TERMINAL LEAD IDENTIFICATION
 COLLECTOR, EMITTER, BASE, JETEC #30 WELDED CASE
 General audio type PNP transistor for experimenters and hobbyists, for code practice oscillators and similar small signal devices. In new JETC 30 welded case. SP-146 Net, singly, each .39
 10 for 3.69; 50 for 16.95; 100 for 31.90

LAFAYETTE SPECIAL SILICON POWER RECTIFIERS
 Top hat lead type silicon rectifiers excellent for TV Radio and power supplies as half-wave, full wave rectifiers and voltage doublers.
 Type A: 750 Ma, 400 PIV @ 25°C, 500 Ma, 400 PIV @ 90°C. SP-196 Shpg. wt., 4 oz. Net .57
 10 for 5.13; 100 for 47.00
 Type B: 750 Ma, 200 PIV @ 25°C, 500 Ma, 200 PIV @ 90°C. SP-197 Shpg. wt., 4 oz. Net .47
 10 for 4.25; 100 for 38.50

NEW! PHOTO-MULTIPLIER POWER TRANSISTOR

A COMPLETE PHOTOELECTRIC SYSTEM IN ONE UNIT
 • PHOTO ELECTRIC CELL
 • POWER TRANSISTOR AMPLIFIER **179** EA.
 • ELECTRONIC RELAY
 Complete with instructions, Data and Diagrams for photo control system, photo-electronic amplifiers, Relays, Alarms, etc.
 SP-256 Net ea. 1.79 3 for 4.77

750 MIL 400 PIV EPOXY SILICON RECTIFIER
 SP-266 Net. ea. .39; 10 for 3.45; 100 for 29.95

HIGH POWER STUD-MOUNT SILICON RECTIFIERS
 10 AMPERE 200 PIV SILICON RECTIFIER As low as **1.09**
 1 1/2" long overall, hex. Shpg. wt., 6 oz. SP-267 Net. ea. 1.09; 10 for 9.80
 10 AMPERE 400 PIV SILICON RECTIFIER Reliable Silicon Rectifiers For High Power Applications
 1 1/2" long overall, hex. Shpg. wt., 6 oz. SP-268 Net. ea. 1.98; 10 for 17.50

20 AMPERE 400 PIV SILICON RECTIFIER
 1 1/2" long overall, 1 1/4" hex. Shpg. wt. 8 oz. SP-269 Net. ea. 2.98; 10 for 26.00
50 AMPERE 50 PIV SILICON RECTIFIER
 1 1/4" hex. Shpg. wt., 10 oz. SP-270 Net. ea. 3.50; 10 for 30.00


30 MC HIGH GAIN TRANSISTOR
 High Quality PNP RF transistor—Excellent for 27MC Citizens Band Walkie Talkie Transceivers, etc. 30 to 35 MC, Average Beta 25. Shpg. wt., 6 oz. SP-271 Net. ea. .69; Lots of 10 ea. Net .62

POPULAR POWER TRANSISTORS
 TESTED AND GUARANTEED TO MEET SPECIFICATIONS
MEDIUM POWER TRANSISTORS
 Beta = 30, BV_{CE} = 36 Volts, Shpg. wt., 12 oz. Similar to: 2N155, 2N176, 2N235, 2N242, 2N255, 2N256, 2N301, 2N307, 2N554, AR-5, CTP-1104, TS-176, etc.
 SP-147 Medium Power Transistor Net ea. .65
 In Lots of 100, Each Net .55

HIGH POWER TRANSISTORS
 Beta = 50, BV_{CE} = 36 Volts Min. Shpg. wt., 12 oz. Similar to: 2N157A, 2N176B, 2N235A, B, 2N257, 2N285A, 2N301A, 2N352, 2N399, etc.
 SP-277 High Power Transistor Net ea. .69
 In lots of 100, Each Net .59

RECTIFIER MOUNTING KITS
 Consist of 2 Mica Washers, 1 plated nut, 1 Teflon Washer, 1 Plated Washer, 1 Connector Lug. Shpg. wt., 4 oz.
 FOR 3/4" HEX BASE Net. ea. .17; 10 for 1.59
 SP-272 FOR 1/2" HEX BASE Net. ea. .27; 10 for 2.49
 SP-273 FOR 1/4" HEX BASE Net. ea. .35; 10 for 3.15
 SP-274

NEW! "MITY-AMP" POWERFUL 2-WATT AUDIO AMPLIFIER MODULE



- For Monaural, Stereo, Intercom, P.A., Signal Tracer, etc.
- Full 2 Watt Power
- Ruggedly Constructed & Completely Encapsulated

8.95

With Applications Booklet and Schematics.

Specifically designed to offer compactness, ruggedness, versatility and quality. Adaptable to hundreds of audio applications. Full 2 watt power yet fits in the palm of your hand. Completely encapsulated in high quality epoxy—will not be affected by high humidity or salt content in air; water-proof and shock-proof.

Frequency Response: 20 cycles to 15KC ± 2 db at 1 watt. Input Impedance: 45 ohms to 50K ohms; Output Impedance: 3.2 ohms to 45 ohms; Power Requirements: 6 to 12 volts at 300 to 700ma. Overall 2x3 1/2 x 7/8". Shpg. wt., 10 oz. PK-638 Net 8.95

NEW! 4 TRANSISTOR SUBMINIATURE PUSH-PULL AUDIO AMPLIFIER

OUTPUT 100 MW
 • SIZE: 3" x 1 1/8" x 1 1/8"
4.95
 • TERRIFIC FOR THE EXPERIMENTER, HOBBYIST AND KIT BUILDER!
 • COMPLETELY WIRED, NOT A KIT!
 • PRINTED CIRCUIT BOARD
 • COMPLETE WITH TRANSISTORS

A tiny, transistorized push-pull audio amplifier with a multitude of applications. Only 3" x 1 1/8" x 1 1/8", it can be mounted inside other equipment to serve as a subminiature phono amplifier, tape recorder, amplifier, etc. Can be the complement of a homebuilt project which needs only an audio amplifier to make it complete and self-contained. Two stages of audio are followed by a push-pull output stage designed to deliver 100 mw to an 8-11 ohm impedance. Low impedance input, with a sensitivity of 0.9 mw. Input transformer for matching high impedances to the amplifier available as an accessory (see below). Includes leads for 9 volt miniature battery (one required). Shpg. wt., 5 oz. PK-543 Net 4.95

ACCESSORIES FOR ABOVE

- BA-2 9 volt battery. Shpg. wt., 2 oz. Net .39
- VC-31 50K ohm volume control w/switch. Shpg. wt., 2 oz. Net .69
- SK-193 8 ohm voice coil speaker. 3" Shpg. wt., 10 oz. Net 1.49
- SK-189 8 ohm voice coil speaker. 2" Shpg. wt., 8 oz. Net 1.49
- SK-191 8 ohm voice coil speaker. 2 1/2" Shpg. wt., 8 oz. Net 1.49
- Input transformer for matching high impedance (mike, etc.) to amplifier. TR-120 Net .89

5 TRANSISTOR PUSH-PULL AUDIO AMPLIFIER

360 MW OUTPUT
 • SIZE: 3 1/8" x 1 1/8" x 1 1/8"
6.95
 • 360 MW OUTPUT
 • COMPLETELY WIRED
 • DIRECT WIRING

A more powerful and more sensitive version of the PK-543, this amplifier employs 3 stages of audio driving a push-pull output stage. Power output is 360 mw, designed for speakers with a voice coil impedance of 8-11 ohms. Low impedance input has sensitivity of 300 microvolts. Input transformer for matching high impedance to the amplifier input available as an accessory (see below). Comes with leads for low impedance input, speaker, volume control/on-off switch. Battery clips and leads supplied for 9 volt miniature battery (one required). Shpg. wt., 5 oz. PK-544 Net 6.95

ACCESSORIES FOR ABOVE

- BA-2 9 volt battery. Shpg. wt., 2 oz. Net .39
- VC-28 10,000 ohm volume control w/switch. Shpg. wt., 2 oz. Net .69
- SK-193 8 ohm speaker. 3" Shpg. wt., 10 oz. Net 1.49
- SK-189 8 ohm speaker. 2" Shpg. wt., 8 oz. Net 1.49
- SK-191 8 ohm speaker. 2 1/2" Shpg. wt., 8 oz. Net 1.49
- Input transformer for matching high impedance (mike, etc.) to amplifier. TR-120 Net .89

3 TRANSISTOR SUBMINIATURE AUDIO AMPLIFIER

• SIZE: 2 1/8" x 1 1/4" x 3/4"
3.75
 • FOR THE EXPERIMENTER, HOBBYIST, AND KIT BUILDER!
 • PRINTED CIRCUIT
 • COMPLETE WITH TRANSISTORS

Here is an amazing little audio amplifier with a multitude of challenging applications: i.e., subminiature phono amplifier, tape recorder amplifier, hand-held public address amplifier, telephone pick-up amplifier, etc. Output sufficient for average listening. Has leads for any one of the following inputs: Tape recorder record/playback heads, radio-tuner, crystal or ceramic phono cartridge, and crystal or ceramic microphone. Has lead terminations for ON-OFF switch, Volume Control, 4 to 10 ohm speaker, and leads terminating in clips for a 9 volt miniature battery. Size 2 1/8" x 1 1/4" x 3/4". Can be readily mounted on chassis. Shpg. wt., 8 oz. PK-522 Net 3.75

- BA-2 9 Volt Battery Net .39
- 5K ohm Volume Control with SPST Switch and Knob. Shpg. wt., 2 oz. Net .59
- VC-62 Miniature Crystal Microphone 1 1/2" Diam. x 1/2" Deep. Shpg. wt., 6 oz. Net 1.49
- MS-108 Miniature Speaker 2 1/2" Diam. 10 ohms Voice Coil Impedance. Shpg. wt., 8 oz. Net 1.49
- SK-66 Net 1.49

LAFAYETTE Quality Test Equipment Kits

LAFAYETTE PEAK-TO-PEAK V.T.V.M. KIT

Outstanding Development In V.T.V.M. Design The Only V.T.V.M. Available With These Features

EXPERIMENTAL
HOBBYIST

MADE IN U.S.A.



- Special Low AC Ranges Provide Noise & Gain Measurements (as low as 1 mv) for Audio & Hi-Fidelity Applications
- Scope Monitor Terminals For Direct Connection To Oscilloscope
- Newly Designed Lafayette Push-Button AC/DC Omni-Probe
- Calibration Controls—Accessible Without Removing Cabinet
- Measures AC Peak-To-Peak, AC RMS, DC Voltage & Resistance
- Direct Reading DB Scale
- Regulated & Balanced Bridge Circuit Provides Unequaled Accuracy & Stability
- Circuit Employs 12AU7 Twin Triode Operating Only Within Its Linear Capabilities • 1% Precision Multiplier Resistors
- Accurate 200 μ a Meter Movement with Large 4 1/2" face

In Every Respect A Professional Test Instrument—Engineered to meet and exceed the rugged standards, accuracy plus required sensitivity demanded in laboratory, industrial and service applications. The KT-174 offers in remarkably easy-to-build kit form, a Vacuum Tube Volt Meter that achieves a level of performance and versatility rivaling factory wired equipment many times its price. Unquestionably The Finest VTVM in its class. Utilizing a printed circuit board, Lafayette's famous step-by-step instructions and huge pictorial diagrams assure ease of assembly. Attractive dark grey front panel is set in a contrasting textured light grey metal case. Complete with tubes, battery and special Lafayette Omni-Probe. Size: 8 1/2 x 6 x 5 1/2". For 105-125 volts, 60 cycles AC. Shpg. wt., 8 lbs.

KT-174 Kit Form Net 44.50
TE-31 Same as above, wired and tested Net 57.00
KT-205 RF Probe Kit For KT-174 and Any Other 11 meg Ohm Impedance VTVM Net 3.75

LABORATORY
TEST EQUIPMENT
IN EASY-TO-BUILD
KIT FORM

KT-174 | TE-31
44⁵⁰ | **57⁰⁰**
IN KIT FORM | COMPLETELY WIRED AND TESTED

NO MONEY
DOWN

COMPARE

THESE SPECIFICATIONS

DC VOLTMETER—Ranges: 0-1.5, 5, 15, 50, 150, 500, 1500V. Input Resistance: All ranges—11 Megohms. Sensitivity—1.5V Range: 7.3 Megohms/Volt. Accuracy: $\pm 2\%$ of full scale at 117VAC—deviation due to line voltage variation between 105-125 volts is negligible.
AC VOLTMETER—LOW AC—Ranges: RMS-0 to 50 mv, 0-150 mv, 0-500 mv. Peak-To-Peak—0-140 mv, 0-420 mv, 0-1400 mv. Accuracy: $\pm 5\%$ of full scale. Input Impedance: 1 megohm at 1 KC. Freq. Response: ± 1 db from 20 to 300,000 cps from 600-ohm source.
REGULAR AC—Ranges: RMS—0-1.5, 5, 15, 50, 150, 500, 1500 volts. Peak-To-Peak: 0-4.2, 14.0, 42, 140, 420, 1400, 4200V. Accuracy: 3% on all ranges except 5% on 0 to 5V. Freq. Response: ± 1 db 20 cps to 4 mc from 600-ohm source. Input Impedance at 1 KC: 0-1.5V, 5V, 15, 50-83 Meg. 0-150V, 1.3 meg—0-500V, 1500V—1.5 meg. Db.—10 to +5 OHMMETER—7 Ranges: 0-1000 RX1, RX10, RX100, RX1000, RX10K, RX100K, RX1M using precision 1% dividing resistors. Meter Movement: 200 μ a for full scale deflection. Tubes: 1—6BN8, AC full-wave peak rectifier and low AC amplifier; 1—12AU7 twin triode meter DC amplifier and balanced bridge. Incorporates Half Wave Selenium Rectifier and Well Filtered Fused Power Supply.

NEW! LAFAYETTE V.T.V.M. KIT



MADE IN U.S.A.

- Wide Band—AC Measurements on any Waveform from 30 Cycles to Over 5 MC, Without Additional Probes or Accessories
- 11 Megohm Input Resistance—Negligible Loading Effects on DC Circuits
- Direct Reading DB Scale
- Balanced Push-Pull Amplifier—Isolates and Protects Meter
- Etched Circuit Design Simplifies Construction
- Selected 1% Zero Temperature Coefficient Multiplier Resistors for Dependable, Accurate Readings
- Giant 6" Full-View Meter With Easy-To-Read Two-Color Scales

An indispensable test instrument for the service technician, experimenter or hobbyist. The KT-202 is a high quality V.T.V.M. In easy-to-build kit form, which offers features unusual at this low price. It is a highly accurate DC voltmeter, AC voltmeter and ohmmeter employing a giant 6", 400 μ a meter with clear black and red scales. High input impedance of 11 megohms, accurately measure DC voltages up to 1500 volts while presenting a negligible load to the circuit under test. As a wide band AC voltmeter, it will measure AC peak-to-peak voltages up to 2,000 volts on any waveform. All this from 30 cycles to above 5 Mc—without any accessory probes! AC RMS voltages may be read directly up to 1,500 volts if the waveform is sinusoidal. The wide frequency response makes this meter ideal in audio, radio and TV applications. Resistances can be read directly on the Ohms scale from 0.2 ohms to 1,000 megohms. A direct reading decibel scale is calibrated from -10 to +18 db (reference 1.73 volts, 6 mw into 500 ohm line). In addition, zero center measurements can be made. The KT-202 utilizes a 12AU7 balanced push-pull DC amplifier and two 9006 tubes as peak-to-peak voltage rectifiers. The meter is isolated making it virtually impossible to burn it out. Multiplier resistors are 1% zero temperature coefficient types, to assure maximum accuracy and minimum variation due to heat. Front panel controls: Function Selector—selects Pwr., Off, A.C.V./F.P.V., D.C.V., Neg., D.C.V., Pos., Ohms; Range Selector—for 7 voltage and resistance ranges; Ohms Adjustment; Balance (zero) Adjustment. There are 3 probes: Common, A.C.V.—Ohms, and a shielded D.C.V. probe with 1

megohm isolating resistor. Printed circuitry makes construction of this kit easy. Selenium rectifier transformer—operated power supply for 110-120 VAC, 60 cps. Dimensions: 7 1/2 x 6 1/2 x 5 1/2" overall. Kit comes with 1 1/2 volt battery for ohmmeter circuit and complete instructions. Shpg. wt., 7 lbs.

KT-202 Net 25.77
Accessory RF probe for KT-202 or other 11 megohm V.T.V.M. Net 3.75
KT-205 Carrying case for KT-202, complete with handle. Net 2.95
KT-203 Shpg. wt., 1 lb.

MODEL KT 202

25⁷⁷

NO MONEY DOWN

SPECIFICATIONS

DC VOLTMETER RANGES: 0-3, 15, 75, 150, 300, 750, 1500 volts. Input resistance: 11 megohms (1 megohm in probe) on all ranges.
AC VOLTMETER RMS RANGES: 0-3, 15, 75, 150, 300, 750, 1500 volts. PEAK-TO-PEAK RANGES: 0-8, 40, 200, 400, 800, 2000 volts.
DECIBEL RANGES: -10 to +18db, -10 to +38db, +30 to +58db. Response: 30 cycles to above 5 Mc.
OHMMETER RANGES: 0-1000, 10,000, 100,000 ohms: 0-1, 10, 100, 1000, megohms. CENTER SCALES: 10, 100, 1000, 10,000, 100,000 ohms, 1 megohm, 10 megohms.
TUBES: 1—12AU7 twin triode balanced meter bridge, 2—9006 peak to peak rectifiers, 1 power supply selenium rectifier.
POWER: 110-120 VAC, 60 cycles.

NEW! LAFAYETTE COMBINATION SIGNAL GENERATOR AND SIGNAL TRACER KIT

MODEL KT-208

Another Outstanding Achievement by Lafayette Test Equipment Engineers

SEMI-KIT CONSTRUCTION!!! This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory.

SIGNAL TRACER

- Hi-gain Cascode Pre-amplifier
- Front Panel Output For VTVM, Scope or Phones
- Low Distortion Triode Output Stage
- 4 1/2" Permanent Magnet Speaker
- Separate R.F. and Audio Signal Probes

SIGNAL GENERATOR

- Covers From 250 KC to 120 MC in 5 Bands
- High Stability Electron Coupled Oscillator
- Attenuator For Both RF and Audio Circuits
- Most Used Frequencies Marked on Panel in Color
- Utilizes New Ruggedized Industrial Type Tubes

19⁹⁵



MADE IN U.S.A.

Two test instruments in one! And available in easy-to-build kit form. The Signal Generator will serve as a full service instrument and the Signal Tracer will follow any signal whether generated by a broadcasting station or injected by the Signal Generator section of the Model KT-208. When used in combination, with no dependence on outside signals, the compatibility of Model KT-208 provides ideal service, for unlike any standard signal tracer, it first injects its own signal then traces that controllable signal to locate the source by standard signal tracing technique. Designed for use with AM, FM, TV and audio circuitry. Features 5 frequency ranges and an attenuator switch to control both the R.F. signal (either modulated or unmodulated) and the 400 cycle audio tone. Front panel output jacks which can be used for oscilloscope, VTVM or earphone connections. Famous Lafayette kit building manual with large pictorials will make it a pleasure to build. Housed in a beautiful cra-kie finish steel cabinet with a deep

etched aluminum panel. Dimensions: 7 1/2 x 9 1/2 x 5 3/4". Complete with 2 probes. Shpg. wt., 9 lbs.

This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory. All you have to do is wire it up!
KT-208 Kit Net 19.95

SPECIFICATIONS

RANGE: BAND A: 250KC to 950KC; B: 850KC—300MC; C: 3.0MC to 11MC; D: 11MC to 45MC; E: 35MC to 120MC; 400cps audio signal; modulation slide switch. RF AF attenuator and power switch; Signal output jack; AF input jack 2 Preamp. output jacks, 4 1/2" alnico 5 speaker. Tubes: 5965, 5687, 6350, 6AG5

NEW! LAFAYETTE TUBE TESTER KIT TESTS TUBES IN SECONDS

MODEL KT-209

- Test Over 1,000 Tube Types
- Checks For Shorts and Leakages Between All Elements
- Tests Filament Continuity
- Checks All Modern Tubes
- Five Year Free Tube Data
- 7 and 9 Pin Tube Straighteners
- Rugged, Accurate. Meter Movement With Sealed Air Damping Chamber

Features & Specifications:

The KT-209 is a complete portable tube tester designed to test the modern tubes found in radio, TV and hi-fi amplifier systems. Speedy operation is assured by use of a single rotary switch in place of one-at-a-time slide switches normally used. Just insert tube in one of the seven panel sockets, set filament selector switch and then rotate the Element switch. Shorts show up instantly on the "leakage indicator" lamp. Tube emission quality is indicated on the highly damped meter's calibrated "Good—?—Bad" scale. A two position slide switch for regular or special higher voltage tubes sets up the meter test. 7 and 9 pin straighteners are provided to insure long life for these sockets. Superbly detailed, step-by-step Lafayette instruction manuals with giant diagrams will assure you of factory-type assembly. This unit uses proven semi-kit construction with all

SEMI-KIT CONSTRUCTION
This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory.

17⁹⁵

major components pre-mounted and tested at the factory. All you have to do is wire it up! American made, and replacement parts are always available if needed. No finer value available anywhere. Housed in a portable leatherette carrying case with removable cover for easy accessibility. This unit uses proven semi-kit construction with all major components pre-mounted and tested at the factory. Dimensions: 10 1/2 x 8 3/4 x 3 1/2". Shpg. wt., 6 lbs.
KT-209 Kit Net 17.95

MADE IN U.S.A.

LAFAYETTE—RF SIGNAL GENERATOR

- Perfect for Engineers, Servicemen, Students and Experimenters
- Quality Assembled Equipment at a **KIT PRICE!**

COMPLETELY WIRED
NOT A KIT!



- FACTORY CALIBRATED AND TESTED
- SIX BANDS: 120 KC - 260 MC
- DUAL OUTPUT RF TERMINALS
- SEPARATE VARIABLE AUDIO OUTPUT
- DIAL CALIBRATION $\pm 2\%$
- ETCHED CIRCULAR DIAL - (Vernier Tuned)

A stable, wide-range signal generator engineered to fill the need for an accurate low cost service instrument. Saves you time and money compared to spent building a kit of lesser quality. Since the delicate oscillator coils and tuning assembly are factory mounted and adjusted for optimum performance, the TE-20 is ready to go to work for you the instant you unpack it. This top-flight signal generator can be used for IF-RF alignment, audio signal tracing of TV, FM and AM sets—TV linearity checks and 400 cycle audio testing. In addition, it can serve as a marker generator when used with a suitable sweep generator. Look at some of the TE-20's features which make it the service instrument buy of the year. Incorporates a large $4\frac{1}{4}$ " etched circular dial for easy, accurate frequency adjustments. Provides a fundamental frequency output of 120 KC to 130 MC in 6 bands plus a calibrated harmonic output of 130 mc to 260 MC. The built-in audio oscillator operates at 400 KC with adjustable output to 8 volts. Continuously variable RF attenuator for proper signal attenuation and two plug-in RF output terminals provide a choice of high and low outputs for maximum flexibility. High output and tuning dial calibration of $\pm 2\%$ give evidence of features not found elsewhere at twice its price.

Net 27.95

27⁹⁵
NO MONEY DOWN

SPECIFICATIONS

Full frequency range: 6 Fundamental bands—120-320 Kc 320-1000 Kc. 1-3.4 MC, 3.2-11 MC, 11-38 MC, 36-130 MC.
One harmonic band 130-260 MC.
Frequency Accuracy: $\pm 2\%$. Audio Output: to 8 volts.
Large $4\frac{1}{4}$ " Etched Circular Dial (Vernier tuned)
High-Low RF Output Terminals.
Tube Complement: 12BH7A, 6AR5, Selenium Rectifier.
Power Requirements: 105-125VAC 50/60 Cps., 12 Watts.
Attractive gray wrinkle steel case with leather carrying handle.
Complete with test leads.
Size: 7Hx10 $\frac{1}{2}$ Wx5 $\frac{3}{8}$ "D. Shpg. wt., 9 lbs.

LAFAYETTE—SINE SQUARE WAVE AUDIO GENERATOR

- FACTORY CALIBRATED AND TESTED
- LOW DISTORTION
- FREQUENCY RANGE - SINE: 20 cps—200 KC IN 4 BANDS; SQUARE WAVE RANGE: 20-25 KC (Vernier Tuned)
- ETCHED CIRCULAR DIAL
- FREQUENCY RESPONSE ± 1.5 DB, 60CPS - 150KC $4\frac{1}{2}$ " VERNIER DIAL

The Lafayette TE-22 is especially designed for radio-TV servicemen, Hi-Fi fans and students who require a dependable sine and square wave generator at low prices. A completely wired and tested instrument, it is equal in quality to higher priced separate generators and far more convenient to use. A terrific buy, this generator will outperform most higher priced kits with ease. Among its many applications are square wave testing of audio amplifiers, determining the frequency and transient response of loudspeakers, TV audio circuit testing and many other uses. Quality features consist of a frequency response of ± 1.5 db from 20 cps to 200,000 cycles in 4 bands. A large easy-to-read etched dial (vernier tuned) adds a professional quality touch. Variable attenuator prevents overloading circuits and permits proper tracking of test response. A full wave power supply is incorporated to provide low distortion and constant output. Factory wiring and calibration insure its accuracy to be within 3%. High output voltage is 7 volts (max.) across a 1 megohm load. A rugged steel cabinet and shock proof mountings protect components, complete with instructions and test leads. A handsome instrument—one which you will be proud to own.

Net 32.50

32⁵⁰
NO MONEY DOWN

SPECIFICATIONS

Frequency range: Sine wave—20-200,000 cps in 4 bands.
Square wave—60-30,000 cps
Output Voltage—Sine: 7V RMS; Square 7V P-P
Output Impedance—0-5000 Ohms. Frequency Accuracy: $\pm 3\%$.
Distortion: Less than 2%.
Tube Complement: 1-6BM8, 1-12AT7, 1-6X4
Power requirements: 117V 50/60 cps. 19W.
Gray wrinkle steel case with leather carrying handle.
Complete with a pair of test leads.
Size: 7Hx10 $\frac{1}{2}$ Wx5 $\frac{3}{8}$ "D. Shpg. wt., 10 lbs.

LAFAYETTE CAPACITANCE-RESISTANCE ANALYZER

- Factory Wired and Tested
- Capacitance Bridge Circuit
- Direct Reading Scales for Capacitance and Resistance
- "Magic-Eye" Null Indicator and Meter
- Checks Opens, Shorts, Leakage and Intermittents
- Determines Power Factor of Electrolytics
- 2 Turns Ratio Scales
- Measures Impedance


Here is a real service value which can do wonders in your shop or lab. The TE-25 is a completely self-contained AC operated, bridge-type capacitance-resistance analyzer which has a number of time saving applications. It is a high caliber, factory built instrument, not a kit. All readings are made directly without complex, time wasting calculations. "Lab" accuracy within $\pm 5\%$ for values to 200 mfd. and $\pm 5\%$ from 200 mfd up. It measures capacity and resistance in 4 separate ranges—from 1 mfd—5000 Mfd and from 0.5 ohms—500 megohms on a large permanently etched circular metal scale. You will find it invaluable for the following jobs: Measurement of Capacitance for paper, mica, ceramic and electrolytic capacitors. Resistance measurement, Power Factor measurement on electrolytics from 0-55%; shorts, opens and leaky capacitors. Also determines turn and impedance ratio of audio and power transformers. Read insulation resistance of paper, mica and ceramic capacitors directly on meter to 500 megohms. Eliminates guessing with neon lamps. DC voltage may be varied up to 600 volts to find leakage current of electrolytics. Two ranges (0-6) (0-60) ma is directly read on meter. No guesswork is necessary. Ratio scales are provided to measure impedance and turns ratio of power and audio transformers (to 500:1) in 2 ranges. "Magic-Eye" tube shows capacitance null indication—opens, shorts for electrolytics, a calibrated power factor control is provided to check capacitor efficiency. No service shop or laboratory should be without one. Shpg. wt., 12 lbs.

Net 37.50

37⁵⁰
NO MONEY DOWN

SPECIFICATIONS

Capacity, 4 Ranges — .00001 mfd — .005 mfd; .001 mfd — 5 mfd; .1 mfd — 50 mfd; 500 mfd — 5000 mfd. Resistance — 4 Ranges — 0.5 ohms — 500 ohms; 50 ohms — 50K ohms; 5K ohms — 5 megohms; 5 megohms — 500 megohms. Transformer Turns Ratio — 1:1 — 10:1; 10:1 — 500:1. Impedance Ratio: — 1:1 — 100:1; 100:1 — 250K:1. DC Leakage Test — Voltages: 0-600 Volts DC. Leakage Current — 6MA — 60 MA — 2 Ranges. DC Insulation Test — 600 Volts Constant — 10 megohms — 500 megohms. Tube Complement: — 1-6R4; 1-6E5. Power: — 117V; 50/60 cps AC. Size: 10 $\frac{1}{2}$ Wx7Hx5 $\frac{1}{4}$ "D. Complete with instructions and test leads. Handsome gray wrinkle steel case with leather carrying handle.



EICO MODEL 955 IN-CIRCUIT CAPACITOR TESTOR KIT

19⁹⁵

Checks for shorts (even in the presence of as little as 1 ohm shunt resistance). Checks for opens: capacitors as small as 15 mfm, in or out of circuit. Wien bridge circuit measures capacitance with $\pm 10\%$ accuracy between 0.1 mp and 50 mp. at any point on the "4" lucite dial-product, convertible into dissipation or power factor-indications visible on electron ray tube. Includes line adjust control. For 105-130 VAC. Size: 8 $\frac{1}{2}$ Hx5 $\frac{3}{4}$ Wx6"D. Shpg. wt., 4 lbs.

TE-737 955 Kit Net 19.95
TE-738 955 Wired Net 39.95

EICO MODEL 460 WIDE BAND SCOPE KIT

79⁹⁵

Excellent Lab precision scope featuring push-pull direct coupled vertical amplifier with high sensitivity: 25 mv/in. Response flat from DC to 4.5 mc, useful to 10 MC, ideal for reproduction of 3.58 mc color TV sync. burst. Complete with all components and instructions for easy assembly. 13x 8 $\frac{1}{2}$ x16". For 105-125 VAC, 50-60 cycles. Shpg. wt., 30 lbs.

TE-222WX Kit Net 79.95
MODEL 460 As above, but factory wired and tested. Net 129.50
TE-223WX

EICO MODEL 680 TRANSISTOR and CIRCUIT TESTER KIT

25⁹⁵

Provides accurate measurements of diodes and ICBO and ICEO. The VOM includes 5 DC current ranges, 2 DC volts ranges at 20,000 ohm volt, and 3 resistance ranges. 3 $\frac{1}{2}$ " D'Arsonval meter has 2% accuracy. Self-powered, uses 4 size AA and 1 "C" battery.

Includes 3 permanently connected clip-on test leads on a panel socket for transistor connections; 2 banana jacks. Housed in a sturdy bakelite case. Size: 6 $\frac{3}{4}$ Hx5 $\frac{1}{4}$ Wx3"D. Shpg. wt., 3 lbs.

TE-735 680K Kit Net 25.95
TE-736 680 Factory wired and tested Net 39.95

SIMPSON MODEL 260 SERIES III AC-DC V-O-M

47⁹⁷

Now offered in a new and improved form. Sensitivity — 20,000 ohms; V.D.C., 5,000 ohms—V.A.C. Ranges: DC-0-25V, 2.5V, 10V, 50V, 250V, 1000V, 5000V; AC: 0-25V, 10V, 50V, 250V, 1000V, 5000V; AF: 0-2.5V, 10V, 50V, 250V; DB: 20 to +10 db; —8 to +22 db; +6 to 36 db; +20 to +50 db. DC current ranges from 0-50 u amps, 0-1, -10, -100, -500 ma; 0-10 amps, DC resistance from 0-2000 ohms, 0-200,000 ohms, 0-20 megohms. Accuracies: DC volts $\pm 3\%$ F.S.; AC volts $\pm 5\%$ F.S., DC resistance $\pm 3\%$ of arc from absolute value of resistance measured. Meter housed in Bakelite case, measures 5 $\frac{1}{4}$ x7x3 $\frac{1}{8}$ ". Comes with battery and test leads. Shpg. wt., 6 lbs.

TE-310 Net 47.97

SUPERIOR MODEL 70 UTILITY TESTER

15⁵³

Test Appliances and Utilities

Appliance and utility tester. Will test toasters, irons, broilers, clocks, fans, fluorescent lamps, auto systems. Measures AC and DC voltages, AC and DC current, resistance, leakage (ohms scale from 0-5 Megohms). Voltage scales 0-150; 0-300. Amps Scales 0-15 amps. Comes with instructions and leads. Shpg. wt., 3 lbs.

TE-513 Net 15.53
TE-517 7.5V Battery Pack for Model 70 Net 1.00

EICO MODEL 666K DYNAMIC CONDUCTANCE TUBE AND TRANSISTOR TESTER KIT

666K

An ideal tube tester for color and monochrome TV servicing. Tests all receiving tubes, including 4, 5, 6, 7-pin, octal, loctal, miniature 7 and 9-pin, sub-miniature, 5, 6, 7-pin (in-line base) and 8-pin (circular base) receiving tubes, transmitting and special purpose tubes. TV picture tubes with accessory adaptor. Measures transistor collector current and shows current amplification factor. Measures Gp, Gm and also leakage in ohms. For 105-130 volts, AC 50/60 cps. 12x15x4 $\frac{1}{2}$ ".

TE-151WX Kit Shpg. wt., 18 lbs. Net 69.95
Model 666. As above, but factory wired and tested. Net 109.95
TE-152WX

SPECIAL 20,000 OHMS-PER-VOLT V.D.M. FEATURES GIANT 6 $\frac{1}{2}$ " METER 29.35

A V.O.M. with laboratory quality features such as a mirrored scale and use of selected resistors to assure accurate reading on all ranges. SPECS: 6 D.C. Voltage ranges 0-3000 volts @ 20,000 ohms per-volt; 6 A.C. voltage ranges, 0-3000 v @ 5,000 ohms-per-volt; 5 resistance ranges, 0-200,000 ohms. 0 to 2/20 megohms; 5 D.C. current ranges 0-7.5 amperes; 3 DB ranges: —6db to +52db. Complete. Fully wired and tested with operating instructions and test leads. Size: 4 $\frac{1}{2}$ x6 $\frac{1}{2}$ x7 $\frac{3}{4}$ ". Shpg. wt., 4 lbs.

TE-503 Net 29.35

TC-101 TUBE AND CIRCUIT TESTER

29⁹⁵

- Tube Checker Checks approximately 2000 Tubes
- Handy VOM For Circuit Testing

Satisfy your every need. Checks approximately 2000 tubes for emission, shorts and leakage. Front panel function switch converts it to a handy volt-ohm meter for circuit testing. Three voltage ranges for fast circuit testing, either AC or DC — 0 to 1200 volts. Measures resistance up to 5 megohms — completely self-contained. Easy to follow set-up booklet included, clips on back of unit. Measures 7 $\frac{1}{2}$ x9x3". Shpg. wt., 5 lbs.

TE-679 Net 29.95



The Sensational LAFAYETTE TE-15 TUBE TESTER

COMPLETELY WIRED — NOT A KIT

- Accurately Checks Over 1000 Different Tubes
- Tests for Cathode Emission, Leakage and Shorts plus Filament Continuity
- Completely Portable—Weighs Only 6 lbs.
- Highly Accurate Easy-to-Read Meter with Replace—Good Scale
- Fast-Setting Slide Switches
- Slide Out Tube Chart

LOW, LOW PRICE!
19⁹⁵

FULL SIZE
9³/₄" W
x 8¹/₈" D
x 2³/₈" H
NO MONEY DOWN

An accurate, versatile, precision instrument that actually tests over 1000 different tubes. The low cost and superior performance of the Lafayette TE-15 Tube Tester combine to make it the outstanding test instrument value today... the ideal tube tester for any radio-TV serviceman, experimenter, technician, etc.

Highly dependable, the Lafayette TE-15 is equipped to test most of the tube types employed in Radio, Hi-Fi, Monochrome, Color TV, etc. Sockets have been provided for 7-pin miniature, 9-pin miniature, octal base, loctal base, hoval and sub-miniature types. A special alligator clip lead is furnished for testing tubes with top caps. Slide switches are employed to connect the various tube elements to their respective test circuits. A 3-position tube slide switch adjust for checking shunted elements, cathode emission and filament continuity. In conjunction with the leakage-quality switch a leakage indicator light is employed which glows when on interelement short or leakage is present in a tube. A power switch turns the unit on and additionally serves to adjust for various AC line voltages. Large easy-to-read meter calibrated 0-100 has a red-green "Replace—Good" scale, plus a special scale for checking diodes.

A handy slide out metal tray contains tube charts which facilitate rapid selection of test settings. Metal case is attractively finished in cream and steel gray. Completely portable—weighs only 6 lbs. and measures 8³/₄" D x 9³/₄" W x 2³/₈" H. Supplied with carrying case. For 105-125 volts, 60 cycle AC. Shpg. wt., 7 lbs.
TE-15 Tube Tester Net 19.95

20,000 OHM PER VOLT SEMI-KIT MULTITESTER

A New Kind of Kit

ONLY 11.95

The semi-kit is a new concept in test equipment kits. All the important or difficult parts are already mounted. All that remains to be done is to mount and wire in a few small parts—a job so simple you'll finish before you realize it, and best of all, you'll have one of the finest high sensitivity multitesters on the market. When used in a circuit, the high input resistance on all DC and AC ranges does away with the highly inaccurate readings common to low resistance testers which load the circuit. Ranges: DC VOLTS, 0-10-50-250-500-1000; AC VOLTS, 0-10-50-250-500-1000; DC CURRENT, 0-500 ua, 0-10-250 ma; DHMS, 0-10K-100K-1 meg; DECIBELS, —20 to +36; PLUS 0-5000 henries and 250 mmf. to .02 mfd. Black case 5³/₄ x 3³/₄ x 1⁷/₈". Complete with test leads, all parts, and instructions and battery. Shpg. wt., 3 lbs.
TK-10 KIT Net 11.95

FILAMENT CONTINUITY TUBE CHECKER

1.69

Small and compact as a cigarette box. Quickly checks filament continuity in a matter of seconds. Ideal for the serviceman or the technician working in the field. Tests filaments of radio, TV picture tubes. Also can be used to test many other electrical devices and line cords, fuses, lamps and bulbs. Has sockets for TV picture tube and loctal, octal, 9-pin, as well as 7-pin sockets. Provided with two test leads. Grey hammertone finish. Size: 4x3x1¹/₂". Shpg. wt., 12 oz.
TE-11 Net 1.69

NEW! 10,000 OHMS PER VOLT MULTITESTER

9⁹⁵

OUTPERFORMS INSTRUMENTS MANY TIMES ITS SIZE

- EXTRA LARGE 3¹/₂" METER FACE
- ALL ACCESSORIES INCLUDED
- COMPLETELY WIRED (NOT A KIT)
- FULL SCALE RANGES

DC VOLTS: 0-6; 0-30; 0-120; 0-600; 0-1200; AC VOLTS: 0-6; 0-30; 0-120; 0-600; 0-1200; DC CURRENT: 0-120ua; 0-3M; 0-300M RESISTANCE: 0-30K; 0-3 MEG DECIBELS —20 to +63 in 5 scales; Capacity 50 uF to .01uF; and .001uF to .15u; DUTPUT RANGES 0-6; 0-30; 0-120; 0-600; 0-1200.

Unbelievable Bargain. Lafayette's new multitester is a complete factory wired and tested instrument (not a kit). It can be conveniently carried in the pocket, and features unusually sensitive 10,000 ohms-per-volt AC-DC meter, 1% precision resistors and the largest meter ever placed on an instrument of this size. Single easy-to-use range selector switch can be appreciated by the novice and the engineer alike. Case and panel are made of durable bakelite. First capacity range requires 120 volts AC, second range requires 6 volts AC. Probes and flexible leads are plastic coated and color coded. Size: 4¹/₂ x 3¹/₂ x 1¹/₄". Complete with leads and battery. Shpg. wt., 1¹/₂ lbs.
TE-10 Net 9.95
Pigskin carrying case for TE-10. Shpg. wt., 8 ozs.
TE-14 Net 1.95

NEW! 20,000 OHMS PER VOLT MULTITESTER

13.50

- 20,000 OHMS PER VOLT DC—10,000 OHMS PER VOLT AC
- 40 MICROAMPERE 3" D'ARSONVAL METER MOVEMENT
- HIGH INPUT RESISTANCE ON ALL DC AND AC RANGES

This new multitester has extra-luxury features, found in the most costly instruments. Easy visibility is provided by the large 3" meter with two color scales for resistance on all ranges: 20,000 ohms per volt on DC; 10,000 ohms per volt on AC. This plus 1% tolerance resistors all the measuring of voltages without unduly loading the circuit, thus preserving accuracy of readings. Besides the extreme sensitivity and superior versatility of this instrument, it features ranges not found on other, competitively priced VDM's. Measures 0-10-50-250-500-1000 DC volts, 0-10-50-250-500-1000 AC volts, 0-10K-100K-1 meg ohms, 0-500 microamperes, 0-10-250 milliamperes, —20 to +36 decibels, PLUS two special ranges 0-5000 henrys inductance and 250 mmf to .02 mfd capacity. EM-MODEL RW-60 Multimeter Net 13.50

TE-37 Felt-Lined carrying case for above instrument Net 2.95

NEW HIGH SENSITIVITY MULTITESTER

- 20,000 OHMS PER VOLT DC
- 10,000 OHMS PER VOLT AC
- RESISTANCE RANGE 0-60 MEGOHMS
- 40 uA MOVEMENT
- 1% RESISTORS
- 0-0.6 VOLT DC RANGE FOR AUDIO AND TRANSISTOR WORK
- COMPLETELY WIRED
- 28 RANGES

17.95

A new, high-quality, low-priced multitester. Its light weight makes it a perfect portable instrument for technicians, servicemen, etc. Rugged design withstands hard use. Features large easy-to-read meter and sensitive 40 microamp meter movement. 1% tolerance resistors provide extreme accuracy of measurements. Housed in rugged bakelite case. Single knob selector and clearly marked positions permit easy operation. Recessed zero-ohms knob adjustment provided. Features sensitivity of 20,000 ohms/volt DC, and 10,000 ohms/volt AC. Ranges—DC volts: 0-0.6, 0-6, 0-30, 0-120, 0-600, 0-1200, 0-3000, 0-6000 volts. AC volts: 0-6, 0-30, 0-120, 0-600, 0-1200 volts. Resistance: RX1, RX100, RX1K, RX10K. DC current: 0-0.06, 0-6, 0-60, 0-600 ma. Decibels: —20 to +17 (0 db — 0.774 V). Capacity: .0001-.01, .005-.20 mfd. Output ranges: 0-6, 0-30, 0-120, 0-600, 0-1200 volts. Complete with color-coded heavy duty test probes and battery. Size: 6x3⁷/₈x1³/₄". Shpg. Wt., 1¹/₄ lbs.
TE-12 Net 17.95
TE-37 Felt-Lined carrying case for above instrument Net 2.95

NEW! POCKET AC-DC VOM

ONLY **6⁹⁵**

- Extremely Compact, Measures Only 3⁷/₈ x 2¹/₈ x 1¹/₈"
- Weighs 5 Ozs. • 1,000 Ohms Per Volt Sensitivity
- Completely Wired (Not A Kit) • 1% Precision Resistors
- Reads 0-1000 Volts AC-DC 0-100KΩ, 0-150 MA

Lafayette's new, pocket multitester features small physical size, and a wide selection of useful ranges. It can be used for trouble-shooting any type of electronic circuits or electrical appliances such as irons, lamps, radios, television, hi-fi equipment, etc. It is also useful for testing complex electrical circuits. Extreme portability allows unlimited usage either at home or in the field.

1000 ohms per volt sensitivity, and 1% precision resistor components assure accurate, precise readings. Operation is extremely easy, simply plug the leads into the desired scale, and you are ready to go, no switching or fidgeting required. Ranges: Volts: 0-15-150-1000 AC and DC. Dhms: 0-100K MA; 0-150. The VOM comes completely wired and tested, and is enclosed in durable plastic case "ing battery are rubber insulated leads are supplied.
TE-13 AC PCKET VOM Shpg. wt., 1 lb. Net 6.95

NEW! CAPACITANCE SUBSTITUTION BOX

2⁹⁵

- 36" Color Coded Test Leads & Clips
- 9 Ranges From .0001 to .22 MFD

A must for the serviceman, experimenter or student. Fast accurate selection of any one of 9 capacitor values from .0001 to 22 MFD. Condensers are porcelain cased tubular type impervious to moisture and are rated at 600 volts working capacity. 9 capacitance ranges are .0001, .0022, .0047, .01, .022, .047, .1 plus 22 MFD. Complete with 36" red and black test leads and alligator clips. Size: 4³/₄ x 2³/₈ x 1¹/₈". Shpg. wt., 1¹/₂ lbs.
TE-16 Net 2.95

NEW! RESISTANCE SUBSTITUTION BOX

3⁹⁵

- 24 Resistance Ratings
- Two Ranges — Low 15-10K Ohms. High 15K-10 Megohms.
- 36" Red & Black Test Leads with Alligator Clips

Ideal for laboratory or service application. Substitute resistance values fast and accurately in trouble shooting circuits where values may have changed. Easy to find bias resistance in experimental vacuum tube or transistor circuits. Slide switch selects two ranges—Low: 15 ohm—10K ohm (1 watt resistors) High: 15 K ohm—10 Megohms (1/2 watt resistors). Two rotary switches (12 steps each) selects 24 separate resistances. Size: 4³/₄ x 2³/₈ x 1¹/₈". Shpg. wt., 1¹/₂ lbs.
TE-17 Net 3.95

SPECIAL SENIOR V.T.V.M. with 6¹/₂" METER

Not a Kit... This is a completely wired and calibrated instrument


29.35

- ± 3% Accuracy of Full Scale
- Giant 6¹/₂" Meter Face
- Direct Reading DB Scale


COMPARE THESE FEATURES
D.C. VOLTMETER. Ranges 0 to 3, 30, 150, 300, 1500 volts. Accuracy ± 3% of full scale. Input resistance: 11 megohms. ZERO CENTER VOLTMETER (for discriminator alignment) Ranges 0 to 1.5, 15, 75, 150, 750 volts. Accuracy ± 3% of full scale. Input resistance: 11 megohms. AC VOLTMETER. RMS RANGE: 0 to 3, 39, 150, 300, 1500 volts. Peak to Peak Ranges: 0 to 3, 30, 400, 800 volts. Accuracy ± 3% of full scale. OHMMETER: Ranges 0 to 1000 megohms (5 overlapping ranges). Center scale values: 10, 100, 1000, 100,000 ohms. 10 megohms. DECIBEL METER (for all audio measurements) Ranges: —10 to +5, +6 to +25, +26 to +45 decibels. All bases on zero Db. at 1.73 volts on 500 ohm line. Pilot light indicates when unit is "on." Complete with D.C. V.T.V.M. probe and cable plus pair of standard test leads. Housed in a rugged grey high-impact case, with color matched etched aluminum panel and portable handle. Size: 5x6¹/₂ x 7¹/₂".
TE-500 Shpg. wt., 6 lbs. Net 29.35

SAVE

LOWEST PRICES ON YOUR RECEIVING TUBE PURCHASES PLUS FREE VALUABLE GIFTS ON PURCHASE OF 15 OR MORE TUBES



30 WATT SOLDERING PENCIL



Reg. Price
1.79

FREE with Purchase of 15 Receiving Tubes

TECHNICIAN'S ELECTRIC TOOL KIT



Reg. Price
7.95

FREE with Purchase of 50 Receiving Tubes

20,000 Ohms-Per-Volt VOM



Reg. Price
13.50

FREE with Purchase of 100 Receiving Tubes

ALL BRAND NEW — FRESH STOCK — ORIGINAL BOXED TUBES • FULL 12 MONTH GUARANTEE • YOU MAY ASSORT FOR QUANTITY — PRICE SAVINGS!

| Tube Type | Mfr. Sugg. List* | Net Each | Asst. In Lots Of | 1-5 | 6-49 | 50-Up |
|--------------|------------------|----------|------------------|------|------|-------|
| 0Z4 | 2.40 | 1.27 | 1.18 | 1.06 | | |
| 1B3GT | 2.90 | 1.54 | 1.42 | 1.28 | | |
| 1G3GT/1B3GT | 2.90 | 1.54 | 1.42 | 1.28 | | |
| 1J3 | 2.90 | 1.54 | 1.42 | 1.28 | | |
| 1R5 | 2.70 | 1.43 | 1.32 | 1.19 | | |
| 1S5 | 2.65 | 1.40 | 1.30 | 1.17 | | |
| 1T4 | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 1U4 | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 1U5 | 2.20 | 1.17 | 1.08 | .97 | | |
| 1X2B | 3.20 | 1.70 | 1.57 | 1.41 | | |
| 2B4 | 2.55 | 1.35 | 1.25 | 1.12 | | |
| 2C5 | 2.80 | 1.48 | 1.37 | 1.23 | | |
| 3AL5 | 1.85 | .98 | .91 | .81 | | |
| 3AU6 | 2.15 | 1.14 | 1.05 | .94 | | |
| 3B6 | 3.00 | 1.59 | 1.47 | 1.32 | | |
| 3B26 | 2.25 | 1.19 | 1.10 | .99 | | |
| 3CB6 | 2.25 | 1.19 | 1.10 | .99 | | |
| 3CE5/3BC5 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 3DK6 | 2.40 | 1.27 | 1.18 | 1.06 | | |
| 3DT6A | 2.20 | 1.17 | 1.08 | .97 | | |
| 3Q5GT | 3.60 | 1.90 | 1.76 | 1.58 | | |
| 3S4 | 2.60 | 1.37 | 1.27 | 1.14 | | |
| 3V4 | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 4B7A | 4.00 | 2.12 | 1.96 | 1.76 | | |
| 5AM8 | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 5AN8 | 3.55 | 1.88 | 1.74 | 1.57 | | |
| 5AR5 | 2.20 | 1.17 | 1.08 | .97 | | |
| 5AS4A | 2.60 | 1.37 | 1.27 | 1.14 | | |
| 5AT8 | 3.25 | 1.71 | 1.59 | 1.43 | | |
| 5BR8 | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 5C6 | 3.20 | 1.70 | 1.57 | 1.41 | | |
| 5CL8A | 3.15 | 1.67 | 1.54 | 1.39 | | |
| 5T8 | 3.40 | 1.80 | 1.66 | 1.49 | | |
| 5U4GB | 2.10 | 1.11 | 1.03 | .93 | | |
| 5U9 | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 5V3A | 3.85 | 2.04 | 1.89 | 1.70 | | |
| 5V4GA | 3.50 | 1.85 | 1.71 | 1.55 | | |
| 5Y3GT | 1.75 | .93 | .86 | .77 | | |
| 6AB4 | 2.15 | 1.14 | 1.05 | .94 | | |
| 6AC7 | 4.85 | 2.57 | 2.38 | 2.14 | | |
| 6AF4A | 4.00 | 2.12 | 1.96 | 1.76 | | |
| 6AG5 | 2.75 | 1.45 | 1.35 | 1.21 | | |
| 6AG7 | 5.90 | 3.13 | 2.89 | 2.60 | | |
| 6AN6 | 4.65 | 2.46 | 2.27 | 2.05 | | |
| 6AK5 | 4.20 | 2.22 | 2.06 | 1.85 | | |
| 6AK6 | 2.90 | 1.54 | 1.42 | 1.28 | | |
| 6AL5 | 1.85 | .98 | .91 | .81 | | |
| 6AM8A | 3.25 | 1.71 | 1.59 | 1.43 | | |
| 6AN8A | 3.70 | 1.96 | 1.81 | 1.63 | | |
| 6AQ5A | 2.15 | 1.14 | 1.05 | .94 | | |
| 6AQ8 | 3.15 | 1.67 | 1.54 | 1.39 | | |
| 6AS5 | 2.45 | 1.29 | 1.20 | 1.08 | | |
| 6AS8 | 3.35 | 1.77 | 1.64 | 1.48 | | |
| 6AT6 | 1.90 | 1.01 | .93 | .84 | | |
| 6AT8A | 3.35 | 1.77 | 1.64 | 1.48 | | |
| 6AUSGT | 4.30 | 2.27 | 2.11 | 1.90 | | |
| 6AU6A | 2.10 | 1.11 | 1.03 | .93 | | |
| 6AU8A | 3.50 | 1.85 | 1.71 | 1.55 | | |
| 6AV5GA | 4.00 | 2.12 | 1.96 | 1.76 | | |
| 6AV6 | 1.65 | .87 | .80 | .72 | | |
| 6AW8A | 3.65 | 1.93 | 1.79 | 1.61 | | |
| 6AX4GTB | 2.65 | 1.40 | 1.30 | 1.17 | | |
| 6AX5GT | 2.95 | 1.56 | 1.44 | 1.30 | | |
| 6BA6 | 2.00 | 1.06 | .98 | .88 | | |
| 6BC8 | 4.00 | 2.12 | 1.96 | 1.76 | | |
| 6BE6 | 2.20 | 1.17 | 1.08 | .97 | | |
| 6BG6GA | 6.50 | 3.44 | 3.18 | 2.86 | | |
| 6BH6 | 2.70 | 1.43 | 1.32 | 1.19 | | |
| 6BJ6 | 2.60 | 1.37 | 1.27 | 1.14 | | |
| 6BK5 | 3.70 | 1.96 | 1.81 | 1.63 | | |
| 6BK7B | 3.35 | 1.77 | 1.64 | 1.48 | | |
| 6BL7GTA | 4.10 | 2.17 | 2.01 | 1.81 | | |
| 6BN4A | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 6BN6 | 3.15 | 1.67 | 1.54 | 1.39 | | |
| 6BQ5 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 6BQ6GA | 4.35 | 2.30 | 2.13 | 1.92 | | |
| 6BQ6GTB/6CU6 | 4.35 | 2.30 | 2.13 | 1.92 | | |
| 6BQ7A | 3.95 | 2.09 | 1.93 | 1.74 | | |
| 6BR8A | 3.50 | 1.85 | 1.71 | 1.55 | | |
| 6BS8 | 3.75 | 1.98 | 1.84 | 1.66 | | |
| 6BU8 | 2.80 | 1.48 | 1.37 | 1.23 | | |
| 6BY5GA | 4.20 | 2.22 | 2.06 | 1.85 | | |
| 6BY6 | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 6BZ6 | 2.25 | 1.19 | 1.10 | .99 | | |
| 6BZ7 | 4.00 | 2.12 | 1.96 | 1.76 | | |
| 6C4 | 1.85 | .98 | .91 | .81 | | |
| 6C6BA | 2.25 | 1.19 | 1.10 | .99 | | |
| 6C6GA | 5.80 | 3.07 | 2.84 | 2.56 | | |
| 6CE5/6BC5 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 6CF6 | 2.55 | 1.35 | 1.25 | 1.12 | | |
| 6CG7 | 2.45 | 1.29 | 1.20 | 1.08 | | |
| 6CG8A | 3.30 | 1.74 | 1.62 | 1.46 | | |

Serviceman & Dealer SPECIAL!



LAFAYETTE TUBE TESTER

FREE!

With Purchase of 150 Receiving Tubes
Reg. Price **19.95**

Full Size Tube Checker 8 1/2" x 9 3/4" x 2 3/8" H

| Tube Type | Mfr. Sugg. List* | Net Each | Asst. In Lots Of | 1-5 | 6-49 | 50-Up |
|-----------|------------------|----------|------------------|------|------|-------|
| 6CL6 | 3.75 | 1.98 | 1.84 | 1.66 | | |
| 6CM7 | 2.85 | 1.51 | 1.40 | 1.26 | | |
| 6CN7 | 2.75 | 1.45 | 1.35 | 1.21 | | |
| 6CQ8 | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 6CS6 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 6CU5 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 6CUB | 3.65 | 1.93 | 1.79 | 1.61 | | |
| 6CW4 | 4.45 | 2.35 | 2.18 | 1.96 | | |
| 6CX8 | 3.65 | 1.93 | 1.79 | 1.61 | | |
| 6CY5 | 2.75 | 1.45 | 1.35 | 1.21 | | |
| 6CY7 | 2.95 | 1.56 | 1.44 | 1.30 | | |
| 6CZ5 | 3.00 | 1.59 | 1.47 | 1.32 | | |
| 6DE6 | 4.50 | 2.29 | 2.10 | 1.88 | | |
| 6DJ8 | 4.30 | 2.27 | 2.11 | 1.90 | | |
| 6DK6 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 6DQ6B | 4.10 | 2.17 | 2.01 | 1.81 | | |
| 6DT6A | 2.15 | 1.14 | 1.05 | .94 | | |
| 6E5 | 3.00 | 1.59 | 1.47 | 1.32 | | |
| 6EA8 | 3.15 | 1.67 | 1.54 | 1.39 | | |
| 6EB8 | 3.70 | 1.96 | 1.81 | 1.63 | | |
| 6E6 | 3.50 | 1.85 | 1.71 | 1.55 | | |
| 6E5GT | 2.70 | 1.43 | 1.32 | 1.19 | | |
| 6E6A | 2.80 | 1.48 | 1.37 | 1.23 | | |
| 6E6GT | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 6E6 | 6.35 | 3.36 | 3.11 | 2.79 | | |
| 6L6CC | 4.20 | 2.22 | 2.06 | 1.85 | | |
| 6S4A | 4.20 | 2.22 | 2.06 | 1.85 | | |
| 6SA7 | 3.90 | 2.07 | 1.91 | 1.72 | | |
| 6SC7 | 3.80 | 2.01 | 1.86 | 1.67 | | |
| 6SG7 | 4.20 | 2.22 | 2.06 | 1.85 | | |
| 6SJ7 | 3.75 | 1.98 | 1.84 | 1.66 | | |
| 6SK7 | 3.55 | 1.88 | 1.74 | 1.57 | | |
| 6SK7GT | 3.55 | 1.88 | 1.74 | 1.57 | | |
| 6SL7GT | 3.50 | 1.85 | 1.71 | 1.55 | | |
| 6SN7GTB | 2.60 | 1.37 | 1.24 | 1.14 | | |
| 6ST7 | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 6SQ7GT | 3.00 | 1.59 | 1.47 | 1.32 | | |
| 6T8A | 3.35 | 1.77 | 1.64 | 1.48 | | |
| 6U8A | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 6V6 | 5.00 | 2.65 | 2.45 | 2.20 | | |

| Tube Type | Mfr. Sugg. List* | Net Each | Asst. In Lots Of | 1-5 | 6-49 | 50-Up |
|----------------|------------------|----------|------------------|------|------|-------|
| 6V6GTA | 2.15 | 1.14 | 1.05 | .94 | | |
| 6W4GT | 2.40 | 1.27 | 1.18 | 1.06 | | |
| 6W6GT | 2.80 | 1.48 | 1.37 | 1.23 | | |
| 6X4 | 1.65 | .87 | .80 | .72 | | |
| 6X5GT | 2.05 | 1.09 | 1.00 | .90 | | |
| 6X8 | 3.15 | 1.67 | 1.54 | 1.39 | | |
| 7AU7 | 2.60 | 1.37 | 1.27 | 1.14 | | |
| 7C5 | 3.50 | 1.85 | 1.71 | 1.55 | | |
| 7N7 | 3.55 | 1.88 | 1.74 | 1.57 | | |
| 10DE7 | 2.95 | 1.56 | 1.44 | 1.30 | | |
| 12AB5 | 2.45 | 1.29 | 1.20 | 1.08 | | |
| 12AD6 | 2.30 | 1.22 | 1.13 | 1.02 | | |
| 12AQ5 | 2.60 | 1.37 | 1.27 | 1.14 | | |
| 12AT6 | 1.65 | .87 | .80 | .72 | | |
| 12AT7 | 3.05 | 1.62 | 1.49 | 1.34 | | |
| 12AU6 | 2.15 | 1.14 | 1.05 | .94 | | |
| 12AU7A | 2.45 | 1.29 | 1.20 | 1.08 | | |
| 12AV6 | 1.65 | .87 | .80 | .72 | | |
| 12AV7 | 3.35 | 1.77 | 1.64 | 1.48 | | |
| 12AX4GTB | 2.70 | 1.43 | 1.32 | 1.19 | | |
| 12AX7A | 2.55 | 1.35 | 1.25 | 1.12 | | |
| 12AZ7A | 2.75 | 1.45 | 1.35 | 1.21 | | |
| 12BA4 | 2.85 | 1.51 | 1.40 | 1.26 | | |
| 12BA6 | 1.65 | .87 | .80 | .72 | | |
| 12BE6 | 1.75 | .93 | .86 | .77 | | |
| 12BH7A | 3.05 | 1.62 | 1.49 | 1.34 | | |
| 12BQ6GA | 4.45 | 2.35 | 2.18 | 1.96 | | |
| 12BQ6GTB/12CU6 | 4.45 | 2.35 | 2.18 | 1.96 | | |
| 12B7A | 3.20 | 1.70 | 1.57 | 1.41 | | |
| 12CA5 | 2.50 | 1.32 | 1.22 | 1.11 | | |
| 12CU5/12C5 | 2.35 | 1.24 | 1.15 | 1.03 | | |
| 12DQ6B | 4.20 | 2.22 | 2.06 | 1.85 | | |
| 12L6GT | 2.45 | 1.29 | 1.20 | 1.08 | | |
| 12SA7 | 3.90 | 2.07 | 1.91 | 1.72 | | |
| 12SA7GT | 3.25 | 1.71 | 1.59 | 1.43 | | |
| 12SK7 | 3.55 | 1.88 | 1.74 | 1.57 | | |
| 12SK7GT | 3.55 | 1.88 | 1.74 | 1.57 | | |
| 12SN7GTA | 2.70 | 1.36 | 1.26 | 1.13 | | |
| 12SQ7 | 3.30 | 1.74 | 1.62 | 1.46 | | |
| 12SQ7GT | 2.90 | 1.54 | 1.42 | 1.28 | | |
| 12V6GT | 2.15 | 1.14 | 1.05 | .94 | | |
| 17EW8/HGC85 | 2.60 | 1.37 | 1.27 | 1.14 | | |
| 25BQ6GA | 4.60 | 2.43 | 2.25 | 2.03 | | |
| 25BQ6GTB/25CU6 | 4.60 | 2.43 | 2.25 | 2.03 | | |
| 25C06GB | 5.85 | 3.10 | 2.86 | 2.58 | | |
| 25L6GT | 2.30 | 1.22 | 1.13 | 1.02 | | |
| 25W4GT | 2.70 | 1.43 | 1.32 | 1.19 | | |
| 25Z6GT | 2.90 | 1.54 | 1.42 | 1.28 | | |
| EL34/6CA7 | 5.20 | 2.75 | 2.55 | 2.29 | | |
| 35Y4 | 2.95 | 1.56 | 1.44 | 1.30 | | |
| 50A1 | 6.65 | 3.52 | 3.25 | 2.99 | | |
| 50A5 | 4.25 | 2.25 | 2.08 | 1.87 | | |
| 50B5 | 2.65 | 1.40 | 1.30 | 1.17 | | |
| 50C5 | 2.15 | 1.14 | 1.05 | .94 | | |
| 50EH5 | 2.30 | 1.22 | 1.13 | 1.02 | | |
| 50L6GT | | | | | | |

TRY TO BEAT THESE ANTENNA PRICES!

Lafayette Has The **BIGGEST** Selection At The **LOWEST** Prices.

27/rod
0

MAXIMUM PERFORMANCE FRINGE ANTENNA

- 21 Active Elements
- Snap Open Design
- Fiberglass Insulators
- Compound Yagi Array

Range to 100 Miles

1188

GOLD ANODIZED

Field proven design for fringe reception. Gold anodized to combat corrosion. Compound yagi array to "sock-in" signals where other designs fail. "Tension-loc" hardware. Heavy wall tubing throughout. Less mast. AN-67WX Gold Anodized. Shpg. wt., 8 1/2 lbs. Net 11.88

"U-INSTALL-IT" KIT with chimney mount. Includes AN-67WX antenna and installation kit AN-12W as shown below. Shpg. wt., 15 lbs. Net 14.88

FAMOUS BRAND SUPER COLOR 'TENNA

18 ELEMENTS—UP TO 125 MILES

- ELECTRONIC LENS DESIGN
- HIGHLY DIRECTIONAL—YAGI ENGINEERED
- COMPLETELY PREASSEMBLED
- MORE GAIN ON ALL VHF CHANNELS

1698

All the exclusive features that have made this antenna a national favorite for "problem area" reception. Electronic focussing—18 elements for more gain—quality construction—1" square crossarm—1" round driven elements—1" tubing boom brace—easy installation—automatic hardware—all aluminum construction. Dynamically balanced design—outstanding fringe area performance. AN-63WX Shpg. wt., 10 lbs. Net 16.98

Leader IN-LINE Antenna Kit

- Complete-Ready To Install
- Time-proven Design

GOLD ANODIZED

COMPLETE KIT 613

Ideal metropolitan and suburban antenna kit. Broad band, uni-directional response. Perfect impedance match on high and low bands results in reduced stray reflections and ghosts. Designed for maximum in phase currents on both high and low bands. Shpg. wt., 4 lbs. Net 3.49

"U-Install-It" Kit. Includes AN-154 and roof mount kit, AM-10, as below. Shpg. wt., 10 lbs. Net 5.99

"U-Install-It" Kit. Includes AN-154 and Chimney mount kit, AM-12, as below. Shpg. wt., 11 lbs. Net 6.13

ALL CHANNELS "RIVIERA"

WORLD'S MOST POWERFUL ULTRA-FRINGE VHF—UHF—FM ANTENNA

GUARANTEED 200 MILE VHF RECEPTION OR YOUR MONEY BACK

- Receives channel 2-83 from all directions without a rotor
- Broadband UHF-VHF and FM, motorless all direction reception
- All aluminum flip-out assembly

SPECIAL 1785

UNTIL SEPT. 15th

Field tests reception on VHF of up to 200 miles has made possible this unprecedented guarantee. Here is an antenna with one transmission line for all UHF, VHF and FM stations, in all directions without the use of a rotor. The nine position selector switch connected at the set electronically rotates antenna beam instantly without physically moving the antenna. Gain on channels 2-6 comparable to 4-bay conicals; on channels 7-13 comparable to stacked 10-element single channels yagis; on 14-83 comparable to bow-tie reflector. 16 1/2" doweled aluminum elements are 60 inches long. Complete with switch, coupler, 45" stacking bars and 2 7/8" angle type mast insulators for Polymicalene line listed below. AN-135WX Less Mast. Shpg. wt., 10 lbs. Net 17.85

The Riviera is ideal for FM Stereo/Multiplex reception. Elements are 3 full wave length at FM frequencies.

"U-Install-It" Kit: Includes Riviera antenna, chimney mount, two five ft. masts, 100 ft. of Polymicalene 4 conductor lead-in wire, 8 stand off insulators and complete instructions. AN-42WX Shpg. wt., 16 lbs. Net 27.32

THE RIVIERA MUST BE USED WITH THE LOW LOSS LEAD IN WIRE LISTED BELOW

Special 4 conductors, matched impedance transmission line. Low loss, mica-filled Polymicalene copperweld conductors.

WR-8W 50 ft. length Net 5.00
WR-9W 75 ft. length Net 7.50
WR-18W 100 ft. length Net 8.90

NEW! REMBRANDT RADAR COIL - X9

- Guaranteed 35 Mile VHF Reception or Your Money Back

695

A powerful indoor antenna utilizing 46" long arms to provide efficient reception to 35 miles, 12-position switch helps eliminate ghosts and snow. A real beauty to grace any decor—Brass plated coil and 4 section telescoping arms. Includes 6-foot transmission line. Available in Mahogany, Walnut and Ivory. Shpg. wt., 3 lbs. Net 6.95

FULL 20 ELEMENT STACKED

- SNAP OPEN CONICAL
- ALL ALUMINUM
- NO LOOSE PARTS
- FASTEST INSTALLATIONS

525 singly each
495 each, in lots of 3

Best antenna deal yet for servicemen-dealer-and installation specialists. All the most wanted features. Quickest-easiest installation possible. No loose hardware. All elements snap open and lock in without tools. Most efficient conical design for all reception areas. Two complete bays with Q bars, less mast.

AN-28WX—Singly, ea Shpg. wt., 8 lbs. 5.25
Lots of 3, ea. 4.95

"U-INSTALL-IT" KIT With All Angle Roof Mounts. Includes AN-28 antenna and installation Kit AM 11 with two 5 ft. masts. As shown below. AN-32WX—Sngl. wt. 18 lbs. Net 7.95
"U-INSTALL-IT" KIT With Chimney Mount. Same antenna and accessories but includes chimney mount instead of roof mount. AN-43WX—Shpg. wt. 18 lbs. Net 8.75

NEW LAFAYETTE UNI-TENNA

- RANGE TO 75 MILES
- ONE ARRAY FOR FM & TV
- A MUST FOR MULTIPLEX

585 **1055**

A high quality antenna designed for operation in semi-fringe areas. Excellent pattern and high gain provide top reception of color and black-white TV and is ideal for stereo FM multiplex. Uses combination TV and FM antenna on one boom with separate transmission lines. The 5 1/2" ft. boom has square cross sections for added strength and maintains parallel alignment of elements. 4 Element yagi is used for TV. 3 elements yagi for FM, 10 Elements operating on high band as patented calinear yagi. Shpg. wt., 6 lbs. Net 10.55

NEW LAFAYETTE UNI-TENNA

- ONE RIG FOR TV & FM
- METROPOLITAN AND SUBURBAN MODEL

Similar to AN 212 but with less elements and use of omnidirectional FM halo. Designed for local and suburban use. Provides full response operation for TV, FM and Multiplex. Shpg. wt., 3 1/2 lbs. Net 5.85

NEW LAFAYETTE ULTRA-LITE ALL DIRECTIONAL FM ANTENNA

210

- Perfect for Indoor Concealed Installations
- Solid Rod Elements.

Here is the FM antenna you have been waiting for. Designed for either outdoor mast or indoor closet/attic installation. Easy to install—no holes to drill. Provides excellent gain for areas up to 35 miles from station. Perfect for multiplex reception. Brings in all stations clearly. Gold corrodized finish for weather and corrosion protection. Strong, yet lightweight design. Shpg. wt., 1 lb. Net 2.10

FM Antenna Kit Same as above, but with kit containing 50 ft., 300 ohm line, 3-31 1/2" Stand-offs; 1-7 1/2" stand-off and 1 mast wrap around stand-off. Shpg. wt., 3 lbs. Net 3.23

"MULTIPLEX 10" EXTENDED RANGE FM ANTENNA

988

GOLD ANODIZED

Ideally suited to Multiplex FM reception. Stereo (Multiplex) FM signals, for the average tuner, have a range of approximately half that of ordinary (monaural) FM signals. This 10 element, double driven, yagi array has the necessary added gain, sensitivity and directivity to compensate for the lack of signal strength. Assures full-fidelity reception and highest signal/noise ratio. All aluminum, gold anodized construction. Fibreglas insulators. Torsion lock hardware, sure-lock mast clamp. Broad banded to cover the entire 88 to 108 mc band. Shpg. wt., 7 lbs. Net 9.88

NEW "HI-5 FM YAGI"

- DESIGNED EXPRESSLY FOR FM

595

GOLD ANODIZED

High gain antenna designed for the audiophile who seeks perfection in FM reception. Extra elements on this antenna serve to pull in stations where others fail. Trouble free operation even under severe weather conditions. The fully automatic snap-lock brackets insure easy, rapid and secure installation. AN-49WX Shpg. wt., 3 lbs. Net ea. 5.95

NEW! FM ANTENNA KIT ALL DIRECTIONAL

- GOLD ANODIZED
- FULL SIZED
- READY TO INSTALL
- FULLY ASSEMBLED

285

ANTENNA ONLY 3.98 COMPLETE KIT

Provides excellent gain for areas up to 35 miles from the station. Use on existing masts—new installation—or as an attic installation. Gold anodized aluminum for years of trouble free operation. Capable of receiving FM signals from practically all directions with equal efficiency. Complete with 50 ft. of 300 ohm twin lead, mast standoff, screw eye standoffs, mast mount. AK-53 Shpg. wt., 5 lbs. Net 3.98

FM ANTENNA ONLY. Shpg. wt., 3 lbs. Net 2.85

SPECIAL CONICAL & V-BEAMS

260 **229**

All aluminum 8 element conical. Full sized. Rugged insulator block. Designed for rapid assembly. Fan front of 6 full length elements. Real value. Shpg. wt., 4 lbs. Net 2.40

AN-11W Singly ea. Net 2.60
Lots of 3 ea. Net 2.40

"U Install It" Kit includes AN-11 and roof-mount kit AN-10 as shown below. Shpg. wt., 11 lbs. Net 4.95

AN-33W "U Install It" Kit. With chimney mount kit. AM-12 as below. Shpg. wt., 11 lbs. Net 5.50

AN-44W

Popular primary area antenna. Rugged aluminum construction. Light weight easy to install. Sharply directional. Shpg. wt., 4 lbs. Net 2.29

AN-21W Net 2.29
AN-20W 2 bays stacked Net 4.59
"U Install It" Kit. Includes AN-21W and roof mount kit AN-10. as below. Shpg. wt., 11 lbs. Net 4.70

AN-45W Net 4.70
"U Install It" Kit. With chimney mount kit, AM-12 as below. Shpg. wt., 11 lbs. Net 5.29

SPECIAL SHIELDED TWIN LEAD for FM MULTIPLEX

898

Improves the Signal-to-Noise Ratio so vital to satisfactory FM MPX reception.

300 ohm twin lead for FM MPX, shielded with tinned copper for outstanding noise-resistant performance. Each conductor insulated with heavy, 20 gauge abrasion-proof black vinyl. Delivers noise-free signal from antenna to set efficiently.

WR-161 100 ft. coil. Net 8.98
Shpg. wt., 7 lbs. per 100 ft. Net 43.01
WR-162WX 500-ft. spool Net 82.44
WR-163WX 1000-ft. spool

SPECIAL UHF ANTENNA

479

- Highest Gain on 70 UHF Channels
- Completely Preassembled
- Excellent Directivity
- Flat Response Across Each Channel

Four bay, UHF bow-tie antenna. Exceptionally high (12db) gain—relatively flat across the entire spectrum. Fully factory assembled. Quickest and easiest to install. High efficiency screen grid reflector boosts front to back ratio. Unique "cross-over" phasing bars—open V elements. Rugged—rigid—corrosion resistant construction. Shpg. wt., 5 lbs. Net 4.79

AN-200WX

UHF "TRANSLATOR" 4-BAY ANTENNA

Four bay bow-tie and screen reflector—tuned to the UHF translator frequencies. Average 16db gain on channels 70-83. Completely preassembled. Net 4.79

AN-201WX Shpg. wt., 5 lbs.

REMBRANDT TV DIRECTION FINDER

- Receives Signals From All Directions—Without a Rotor!
- Supercharges Any TV Antenna—Boosts The Pick-Up Power!
- Filters Out Interference
- Rejuvenates TV Antennas
- Amplifies The TV Signal
- No Installation Problem

595

The latest television invention! Seeks out—and beams in—TV signals from any channel, in any direction, without a mechanical rotor. Electrically rotates the polar-receiving pattern of your existing antenna and phases the ground wave picked up by the electrical wiring system with the sky wave picked up by the antenna. Improves any existing antenna: indoor, outdoor, master or built-in. Boosts pick-up power of any antenna—old or new. Just a flick of the selector control tunes out ghosts—filters out interference—tunes in those "hard-to-get" problem channels. Automatically amplifies TV signal strength for "snow" free, brighter, clearer pictures. Works on every channel—in any location—with any antenna—for any TV set. No installation problem—simply attach to antenna terminals in back of TV set—and plug into 110V AC/DC socket. Complete satisfaction guaranteed or your money back. AN-140 Shpg. wt., 2 lbs. Net, ea. 5.95

In lots of 6 ea 5.00


"U-INSTALL-IT" KITS

All the items for simple installation. You get an all angle roof mount—lightning arrester—75 feet of 300 ohm twin lead—screw eyes—mast standoffs and 5 ft., 1 1/4" O.D. steel mast.

AM-10W Shpg. wt., 7 lbs. ea. 2.95
AM-11W with 2.5 ft. masts. Shpg. wt., 10 lbs. ea. 3.55
AM-12W Same as AM-10W and chimney mount ea. 3.25
AM-13W Same as AM-11W with chimney mount ea. 3.75
AM-14W Same as AM-10W with aluminum wall bracket ea. 2.95
AM-15W Same as AM-11 with aluminum wall bracket ea. 3.55

Lafayette® Offers More Accessories—Better Service—Lower Prices

ALLIANCE ANTENNA ROTATORS



AS LOW AS
18⁰⁸

Rotator redesigned and restyled to provide faster, smoother, better efficiency. Rotation speed is 1 R.P.M. Magnetic brake affords instantaneous stop. There is full 360° rotation. Factory lubricated for life. Contacts are self-wiping. A reinforced zinc die cast housing affords all weather protection.

Model U-98 (1 & 2)—Fully automatic, just set control knob and antenna rotates to desired position and stops automatically. Indicator shows antenna position. Size: Rotator 7 $\frac{3}{4}$ x5 $\frac{1}{4}$ x8". Control Case 7x4 $\frac{1}{2}$ x4". 110V. 60 cps AC at 65 watts. Shpg. wt., 12 lbs. Net 25.77

T-12 (1 & 3)—Manually operated with direction indicator. Needle indicates position of antenna on control panel. Has clockwise and counter-clockwise revolution. Highly styled decorator case. Size: Rotator 7 $\frac{3}{4}$ x5 $\frac{1}{4}$ x8". Control Case 6 $\frac{1}{2}$ x2 $\frac{1}{2}$ x4 $\frac{1}{2}$ ". Operates on 110V 60 cps at 30 watts. Shpg. wt., 12 lbs. Net 22.12

Model K-22 (1 & 4)—Economy model—Provides positive instant finger tip control of rotation. Push on one end of bar and antenna turns clockwise. Push down on other end and antenna turns counterclockwise. Center disc automatic signal light indicates when limit of travel has been reached. Size: Rotator 7 $\frac{3}{4}$ x5 $\frac{1}{4}$ x8". Case 5x5x4". Shpg. wt., 12 lbs. Net 18.08

TBB THRUST BEARING BRACKET increases stress capacity of Tenna-Rotors up to 300 lbs. Withstands winds up to 90 M.P.H. Prevents buckling and bending. Shpg. wt., 3 lbs. Net 2.91

WR-24—4 conductor flat cable for above per ft. .03 per C ft. 2.39

LAFAYETTE TV/FM 4-SET POWER BOOSTER

The MOST Gain for the LEAST Money



9⁹⁵

- Boost Signal For Up To 4 TV Sets
- Ideal for Master "Home" Installation
- Equally Useful In Primary and Fringe Areas
- Electro-Matched to Lafayette TV-FM Antennas
- Updates and improves any TV/FM antenna installation

Provide a stronger TV or FM signal to up to 4 sets anywhere in the home. Low noise-high output amplifier boosts and distributes the signal over ordinary twin lead. Special isolation circuitry prevents interaction and interference between sets. Provides as much as 7 to 10 db gain on all channels 2 through 13 when used with one TV set. From 2.5 to 5 db when used with 2 sets. Will often supply more gain when used with an indoor antenna than elaborate, unboosted outdoor antenna supply. Requires no tuning. Installs with just a screwdriver. Uses ordinary twin lead to "antenna-matched" terminals. Mounts behind set—or in any convenient location. Measures 5 $\frac{3}{4}$ x3 $\frac{3}{4}$ x1 $\frac{1}{4}$ ". For 117 V.A.C. 60 cycles. Net 9.95

ALL CHANNEL UHF-TV CONVERTER


13⁴⁴



- For Clear Sparkling Pictures
- Class A Signal Areas
- Adds UHF Channels 14-83 to Your TV Set

Enjoy all the new programs on UHF channels 14-83 on your present TV set with this UHF converter. Simple one-knob tuning with single on-off knob. Easy to install to terminals of your TV set and is easily attached to rear or side of cabinet. Gold-plated, unbreakable metal housing. Power: 117V AC, 60 cycles. Size: 5x3 $\frac{1}{2}$ x2 $\frac{1}{2}$ ". Shpg. wt., 3 lbs. Net 13.44

NEW! MODEL AB-4 MAST MOUNTED TRANSISTORIZED TV/FM BOOSTER



- For up to 4 TV or FM Sets
- Transistorized Circuit
- Uses Inexpensive Flashlight Batteries

A complete, compact amplifier—distribution system for up to 4 TV or FM sets. Reliable transistor circuit provides low noise and high gain. Stripless 300-ohm terminals on booster, and remote power supply for fast, positive installation. Requires four 1.5 volts flashlight batteries for power. Noise Figure: 4 db avg. High TV gain from 2-17 db and FM 12 db avg. depending on number of sets connected. Shpg. wt. 1 $\frac{1}{2}$ lbs. Size: AB-4 2 $\frac{1}{4}$ x3x1 $\frac{3}{8}$ "H. RP-3 (power supply) 3Wx7 $\frac{1}{4}$ x1 $\frac{1}{8}$ "H. Net 18.62

BA-157 1.5 volt Battery (4 required) Shpg. wt., 15 oz. Net .13

Blonder Tongue "IT-3" TRANSISTORIZED 4-Set TV/FM Booster

- Antenna Matched Input
- Highest Gain—Lowest Noise
- Simple "Stripless" Installation



19⁴⁰

The highest gain of any home TV booster. Boosts antenna signal up to five times. More power for up to 4 TV or FM sets. The perfect basic unit for a home master TV-FM system. Designed as a rugged, long life unit. Requires almost no maintenance. Draws so little current it need never be turned off—no tubes to replace. Engineered to provide an excellent impedance match and maintain necessary isolation between sets. Can also be used to boost amplification from most mounted boosters or in master systems. Simple "stripless" installation—solid electrical contact with the turn of a screw. Size 6 $\frac{1}{4}$ x3 $\frac{3}{4}$ x1 $\frac{1}{2}$ ". For 117 volts, 60 cy. A.C., .01 amp. Shpg. wt., 1 lb. Net 19.40

TL-99 Net 19.40

UHF-VHF LIGHTNING ARRESTER

Saw-tooth washers grip transmission line without stripping. Designed for flat, tubular, oval or open types. With mounting screw and steel strap. U/L approved. Shpg. wt., 10 oz.

TS-11—Lots of 10 Each .29
Singly 35

TV TUBE RESTORER

3²³

- 120 Different Combinations
- Corrects Open Cathode—Heater to Cathode Short—Open Cathode Grid—Control Grid to Cathode Short—Low Emission
- For all picture tubes except 110° types

One simple unit provides the cure for most aging picture tubes. Latest model features slide switches—not pin plugs as older units do. Rugged, well made socket—compact, single unit design. Works on electrostatic or electromagnetic focusing tubes, in series or parallel circuits. Includes instructions. Shpg. wt., 1 lb., 4 oz. Net 3.23

STRAPLESS CHIMNEY MOUNT

Can be installed in seconds with hammer and wrench on brick, stone or cement block chimneys of any size, or on the corner of almost any building. Mount is capable of up to 1500 lbs. clamping pressure and cannot rust away. Shpg. wt., 2 lbs. Net 1.25

1²⁵

TS-351 Net 1.25

BLONDER-TONGUE UHF CONVERTER



The only converter with 3 section tuner for "Class A" signal areas with these exclusive features. Tuned input tracks with oscillator, rejects spurious signals, suppresses oscillator radiation. Precise impedance match gives maximum signal conversion—no line ghosts—no picture smear. Drift-free performance is achieved by use of a thermally compensated oscillator circuit. One knob tuning; no VHF channel switching; output on channel 4, 5, or 6. Complete with tubes and instructions. Shpg. wt., 4 lbs. Net 16.41

TL-100 Net 16.41

B-T ULTRAVERTER DELUXE UHF-TV CONVERTER



Adds all UHF channels (primary, satellite, and translator) to standard TV sets. Insures finest pix even in weak areas. Features dual-speed channel selection with direct and fine tuning controls; stable, shielded oscillator. Max. signal transfer to channels 5 or 6 of TV. Precise 300 ohm match and triode amplification; Improved tuner design meets new FCC standards; UL approved; Tunes channels 14-83 (470-890 mc); Tubes: 6AF4A and 6ER5; Power: 117 volts at 60 cps AC, 20 w. Size 6 $\frac{3}{4}$ x5 $\frac{1}{4}$ x4 $\frac{3}{4}$ ". Shpg. wt., 4 lbs. Net 27.44

TL-101 Net 27.44

TV TUBE 'BRITENER'



.59

Absolutely no tools or soldering needed for installing this handy inexpensive tube rejuvenator. You simply attach two plugs as directed on the instructions. For magnetic tubes and PARALLEL CIRCUITS only. Renews brightness contrast. Wt., 8 oz. Ea. singly .59

MS-12 Net .59

TV PICTURE TUBE SHORT ELIMINATOR



Eliminates expensive picture tube repairs. No elaborate equipment needed. Repairs grid and cathode shorts in two minutes—without pulling the chassis! Simple "plug in, switch-on" operation. Works with any TV picture tube. TS-282 Shpg. wt., 1 $\frac{1}{2}$ lb. Net .99

TS-282 Shpg. wt., 1 $\frac{1}{2}$ lb. Net .99

UNIVERSAL TV TUBE "BRITENER"



1²² In lots of 6 SINGLY 1.39

Restores brightness to dim TV picture tubes. Operates on all types—magnetic or electrostatic—and in all circuits—parallel or series. Shpg. wt., 10 oz. Ea. TS-170 In lots of 6 each 1.22
Singly each 1.39

TS-170 In lots of 6 each 1.22

TELESCOPING TV MASTS

Heavy-duty telescoping masts. Hot-dip zinc galvanizing inside and outside. Designed for easy installation and assembly. Husky thumb bolts lock sections automatically. Precision fitting. 18 gauge .003" wall. Supplied complete with all guy rings, clamps and necessary hardware. Total 5 10-ft. sections for height up to 50 ft.; O.D.: #1 (1 $\frac{1}{4}$ "), #2 (1 $\frac{1}{2}$ "), 50-FT. MAST—Consists of all 5 sections #3 (1 $\frac{3}{4}$ "), #4 (2"), #5 (2 $\frac{1}{4}$ "). Shipping express only. Listed above: Nos. 1, 2, 3, 4 and 5. Height 50 feet. Shpg. wt., 39 lbs. Net 13.73

TL-63WX Net 13.73

40-FT. MAST. Consists of 4 sections; Nos. 1, 2, 3 and 4. Height 40 feet. Shpg. wt., 28 lbs. Net 10.05

TL-62WX Net 10.05

30-FT. MAST. Consists of 3 sections. Nos. 1, 2 and 3. Height 30 feet. Shpg. wt., 21 lbs. Net 7.28

TL-61WX Net 7.28

20-FT. MAST. Consists of 2 sections. Nos. 1 and 2. Height 20 feet. Shpg. wt., 14 lbs. Net 4.58

TL-60WX Net 4.58

TV ANTENNA MASTS

STEEL MASTS. New corrosion-resistant 5 ft. steel mast made to fit all antennas. One end is tapered. "Jam Fit" construction with locking key. 1 $\frac{1}{4}$ " O.D. TL-12W 5 ft. Wt., 2 $\frac{1}{2}$ lbs. .69

TL-13WX 10 ft. Wt., 4 $\frac{1}{2}$ lbs. 1.29

TL-14WX 10 ft., 16 gauge. Wt., 8 lbs. 1.09

ALUMINUM MASTS. 19 gauge-heavy wall-high tensile strength. Rust and corrosion proof. Swaged for stacking. TL-66W 5 ft. Wt., 1 $\frac{1}{2}$ lbs. .89

TL-17WX 10 ft. Wt., 2 $\frac{1}{2}$ lbs. 1.69

10 Ft. Mast shipped via express only.

TV-FM HI-PASS FILTER



2³⁹

Hi-pass filter passes all frequencies above 40 mc. Rejects all frequencies below 40 mc. Automatically eliminates electrical disturbances in the antenna circuit. Clears disturbances caused by neon, X-Ray, ignition, appliances, diathermy, short wave, etc. Shpg. wt., 1 lb. Net 2.39

TS-331 Net 2.39

LO-PASS LINE FILTER



2⁴⁹

Exceptionally efficient line noise eliminator. Utilizing dual ferrite core coils, heavily wound. Eliminates line noises caused by motors, industrial RF, neons, appliances, etc. Particularly useful on TV and FM sets, radios, tuners, record players. Automatic attenuation of unwanted disturbances. Shpg. wt., 1 $\frac{1}{4}$ lbs. Net 2.49

TS-327 Line Filter Net 2.49

UNIVERSAL 110° CRT REJUVENATOR



2²⁰

A new Universal picture tube brightener designed for application on 110° picture tubes. A single heavy-duty unit which performs four ways. A simple adjustment adapts it for either series or parallel wired filaments and it can be used on electromagnetic or electrostatic focus tubes. Shpg. wt., 1 lb. Net 2.20

TS-283 For Sylvania Type 110° Tubes Net 2.20

TS-284 For RCA Type 110° Tubes Net 2.20

PEAK ROOF MOUNT



A heavy gauge steel peak roof mount. Heavily plated to resist corrosion. Will accommodate mast, up to 2" in diameter. Fully adjustable can be easily rotated. Complete with all necessary hardware. Shpg. wt., 5 lbs. Net 1.10

TS-41 Net 1.10

.99 ECONOMY MOUNT



Can be erected in minutes; without special tools or drilling. Adjustable, two-section design permits unlimited spacing between brackets for maximum support of masts 1 $\frac{1}{2}$ " to 1 $\frac{1}{2}$ " O.D. Complete with two 12-ft. lengths of 3/4" galvanized steel bands and hardware. Shpg. wt., 3 lbs. Net .99

TS-82 Net Each .99

NO RUST BARGAIN MOUNT



The ideal chimney mount for life-long satisfactory service under the most severe conditions. Hot dip galvanized steel "Y" mount. Two 10 ft. stainless steel straps and stainless steel seals. And at Lafayette's bargain prices. Shpg. wt., 4 lbs. Net Each 1.98
Lots of 3 Each 1.80

TS-80 Net Each 1.98

SPECIAL 300 ohm TWIN LEAD



★ 100 FT. **.98**

High quality—heavy gauge—all purpose twin lead. Perfect FM/TV transmission line. 80 mil polyethylene insulation. Shpg. wt., 2 $\frac{1}{2}$ lbs. SP-260 Net .98

TL-75 Shpg. wt., 2 lbs. Net 9.95

LIFELINE FM/TV TWIN LEAD

Guaranteed to Provide Perfect Transmission for the Life of Your Antenna—or Your Money Back **1⁹⁸**



Take advantage of this unprecedented guarantee—you can't lose! 100 ft. of heavy duty twin lead—made of the finest available materials. Chemically protected against deterioration. Supplied in a dust-proof—tangle-free—self-measuring dispenser. 100 ft. coil. Shpg. wt., 3 lbs. Net 1.98

WR-164 Net 1.98

TWO SET COUPLER



.39

Uses one antenna for two sets. Compact electronic set coupler assures performance of two TV sets on one installation. Easy to connect. Nothing to go wrong. Shpg. wt., 1 lb. Net .39

TS-326 Each .43

In lots of 3, Each .39

TRI-SET COUPLER



2²⁹

Highly efficient 3 set coupler. For coupling 2 or 3 TV or FM sets to one antenna of any type. No interaction—less than 6 db insertion loss. 40 to 50 db rejection ratio. Shpg. wt., 1 lb. Net 2.29

TS-332 Net 2.29

WIZARD 300 MASTER COUPLER

IDEAL FOR UNLIMITED SET COUPLING **1.15**

Provides for the coupling of any number of TV (color or black and white) and FM sets to one antenna line. The first set is connected directly to the line, and each additional set is connected through a separate WIZARD 300, without the need for an amplifier or booster. Shpg. wt., 3 oz. Net 1.15

TS-347 In lots of 3 Net ea. 1.03

UNIVERSAL TV-FM PLUG & SOCKET

Compact-low loss—300 ohm plug and socket combination. For all TV & FM lead-in applications. Surface mounting socket—low loss polystyrene plug. Constant impedance design. Solderless screw terminals. Includes hardware and instructions. Shpg. wt., 2 oz. Net .35

TS-328 Plug & Socket Net .35

DELUXE TV SERVICE LITE



Keep your hands free. Spring clamp with rubber covered ends attaches anywhere in T.V. cabinet. 4 $\frac{1}{4}$ " highly polished aluminum reflector uses standard 25 watt bulb. Complete with 6 ft. cord and plug, less bulb. Shpg. wt., 1 $\frac{1}{2}$ lbs. Net 1.59

MS-63 Net 1.59

Minivac 601 DIGITAL COMPUTER

95⁰⁰
NO MONEY DOWN

Not A Toy — Performs Functions of Full Size Computer — Solves Scientific and Business Problems



Model 6010

The Minivac 601 can be used by anyone with an inquiring mind. Designed to introduce teenagers and adults to the fascinating world of machines that "think". The 601 demonstrates how computers operate, what they can and cannot do by simulating computer applications in business, science and military. It can learn, remember, calculate, and make decisions. Indispensable to teachers, businessmen who need to keep up with modern technology, a first hand opportunity to explore space age techniques and experimentation. A set of six comprehensive manuals are provided with each Minivac 601. These provide step-by-step experiments demonstrating how computers do arithmetic, use logic, provide automatic control, and language translation. It even plays games as an opponent, partner or referee. The Minivac is ready to


- Teaches Basic Concepts of Computer Operation and Technology
- A Product of 2 Years of Research

use the moment you unpack it. Operates on a low 12 volt system—it is as safe to use as an electric train. Minivac consists of a 24" console with 12 indicator lights, 1 circuit breaker; 6 DPDT memory storage relays; 6 secondary memory storage switches; 6 data input push buttons; 16 position switch (motor driven); game matrix; 194 dual terminals and 100 program wires. The console measures 24x13x5 1/2" H. Shpg. wt., 17 lbs. Power input 110 V AC. HE-647W Net 95.00

NEW MINIVAC 6010. A deluxe version of the 601 which is capable of handling a larger variety of more advanced computer programs. Ideal for industrial use. A seventh capacitor/resistor manual will accompany the 6010. Now with the additional features of individual protective dust covers for relays, improved slide switches and pushbuttons for tighter specs and greater reliability. HE-644WX Net 155.00

MINIVAC CAPACITOR-RESISTOR KIT FOR THE 601 Enlarge your MINIVAC 601's capacity as a computer simulator with these new components. This kit makes it possible to construct and understand over 24 more advanced experiments. Kit includes 6 capacitors, 27 resistors and programming connectors and the Capacitor/Resistor manual. HE-648 Net 24.50

GENIAC PORTABLE MEMORY CARD FILE



HOW TO FILE A CARD IN 25 PLACES SIMULTANEOUSLY

17⁹⁶

For the busy scientist, engineer, teacher, business man or student who must keep basic information on file. NOW the Geniac Portable Memory Unit, (PMU), a low cost information retrieval system can conservatively sort 400 cards per minute—using no electrical parts or gadgets. Sorting is by rods. Information is coded into the cards by matching pre-punched holes around the edge of the card. No previous knowledge is necessary. Once coded the card is filed at random and will automatically appear during sorts for the various categories. Serves as a useful adjunct to company integrated information systems. The basic PMU contains a matching hand punch, sorting rods and 300 cards. F-832 Shpg. wt., 6 lbs. Net 17.96
F-833 Additional Cards, pkg. of 100 Net 3.92

NEW! LAFAYETTE VECTORLOG SLIDE RULE



The Slide Rule for Communications Engineers and Physicists 1688

- LAMINATED BAMBOO CONSTRUCTION • P, P', AND Q SCALES — FOR DIRECT VECTOR ADDITION • HYPERBOLIC SINE AND TANGENT SCALES • TWO SINE SCALES—ONE MARKED IN DEGREES, ONE MARKED IN RADIANES • 5 LOG LOG SCALES PLUS A VOLTAGE DB SCALE • COMPLETE WITH BELT CARRYING LOOP AND LEATHER CASE

The Lafayette VECTORLOG Slide Rule provides a new concept in scientific calculation, incorporating scales and arrangement designed for quick-easy-manipulation. Twenty-seven (27) scales incorporate the many problems encountered in Electrical Engineering and Physics. The unique P, P', and Q scales allow direct right angle vector addition. No longer are several settings required to obtain right angle. No longer are several settings required to obtain right angle. The C and D vector sums—these scales work in the same manner as the Hyperbolic D for multiplication. The two Hyperbolic Sine and one Hyperbolic Tangent Scale, the voltage db scale, and the five Log Log scales, provide maximum coverage of these dynamic fields. VECTORLOG is the result of extensive tests for ease of manipulation. Several of these features are: C and D scales on both the front and back of the rule; Sine scales in both degrees and radians, removing the necessity of bothersome conversion of units; A problem-tested location of scales; and adjustment screws to allow variable tension on the slide. Scales include: (FRONT) Tr-1, Tr-2, P, P', Q, ST, S-r, S-o, C, D, LLO1, LLO2, LLO3, LL1; (REAR) Sh-1, Sh-2, DF, A, B, Cl, CF, Th, C, D, LL3, LL2, db. With instruction book, leather carrying case, and belt carrying loop. F-686 Shpg. wt., 1 1/2 lbs. Net 16.88

LAFAYETTE'S ENGINE DIVIDED IMPORTED SLIDE RULES



10" LOG LOG DUPLI TRIG SLIDE RULE
• Laminated Bamboo Warp-Free Construction • Complete With Leather Carrying Case

Specially selected, laminated, non-hygroscopic bamboo. Scales machine engraved on white plastic in permanently accurate calibrations. Adjusting screws permit varying tension on slide. 21 scales including C, D and CI on both sides. LLO and LLOO scales refer to B scale. All other scales coordinate and refer to D scale. Scales are L, LL1, DF, CF, CIF, Cl, C, D, LL3, LL2, LLO, A, B, K, Cl, C, D, S, ST, and T. Scale characteristics permit multiplication, division, proportion, inverse proportion, reciprocals, cotangents, squares, square roots, cubes, cube roots, logarithms, tangents, sines, etc. F-341 Shpg. wt., 1 1/2 lbs. Net 10.45


NEW! DECI-LOG™ DELUXE 5" LOG LOG DUPLI DECIMAL TRIGONOMETRIC SLIDE RULE



ONLY 6⁸⁸

A pocket version of our 10" Log Log Dupli Decimal Trigonometric slide rule (F-428). Contains all the scales of the 10" rule except the "ST" scale. Two color scales—positioned for ease in use and rapid calculations. "C" and "D" scales on both sides of the rule. "P" scale for direct, cursor line reading of cosines of angles. Scales included, front face: LL1, LL2, LL3, DF, CF, CIF, Cl, C, D, LL3, LL2, LL1. Back face: LLO, L, K, A, B, S, T, C, D, DI, LLO. Engine divided rule of laminated, non-hygroscopic bamboo. Complete with instruction book and leather case with pocket clip. F-681 Shpg. wt., 8 oz. Net 6.88

DELUXE LOG LOG DUPLI DECIMAL TRIGONOMETRIC SLIDE RULE



- 25 Scales with 8 Log Log Scales
- Extended Range Avoids "Going Off Scale"
- Extra P Scale Simplifies Computations
- Two Color Scales

15⁹⁵

10" log log duplex trig slide rule contains 25 scales including 8 Log Log Scales. Troublesome end-for-end resetting is eliminated by 1.001 to 100,000 and .999 to .00001, enlarging the scale by one scale length each compared with ordinary log log slide rules. Extra value. Scales include LLO1, LLO2, LLO3, DF, CF, CIF, Cl, C, D, LL3, LL2, LL1, LLOO, L, K, A, B, S, T, T, C, D, D1, P, and LLO. With instruction book, saddle leather case. Overall length is 14". F-428 Shpg. wt., 1 1/2 lbs. Net 15.95



289

5" POCKET SLIDE RULE
5" Pocket Slide Rule: Convenient pocket sized slide rule of specially selected and treated bamboo. Will not warp, shrink or lengthen under varying atmospheric conditions. A, B, Cl, C, D and K scales engraved on white plastic surface. Reverse side of slide has standard S, L and T scales. The upper beveled edge of the rule is graduated in m/m to 13 cm. Other edge is divided into 5 inches by 32nds. Only 5 3/8" long over all. Carried easily in any pocket. Shpg. wt., 8 oz. F-340 Net 2.89



350
PROFESSIONAL GIANT BOW
• 6" Size with Center Wheel Adjustment
• Finely Balanced—Professional Type

Professional quality utility set in a fitted, velvet lined case. Made in Western Germany of nickel plated, hard-rolled brass. 6" giant bow has preferred center wheel adjustment. Makes circles from 1/8" to over 10" in diameter. Set includes 6" giant bow, interchangeable pen and pencil parts, extra needle for using bow as divider, handle for use with pen and pencil parts, lead, lead box and repair parts. Shpg. wt., 1 lb. F-44 Net 3.50




TECHNICAL DRAFTING SET

- Center Wheel Adjustment
- Professional Quality

659

A fine set of imported nickel plated brass instruments priced far below the usual price for this quality. Contains 6 1/2" self-centering compass, one leg knuckle joint with divider, pencil, pen parts and lengthening bar; 6 1/2" self-centering divider; spring bow divider 4 1/8", center wheel adjustment with interchangeable needle points; spring bow pencil and spring bow pen, both 4 1/8" with center wheel adjustment and interchangeable needle point; two 5 1/2" ruling pens; extra handle for pen and pencil parts; adjustment tool; lead case and leads; and spare parts kit, all in velvet lined snap closing case. Shpg. wt., 1 1/2 lbs. F-65 Net 6.59

8" PROFESSIONAL DIVIDER



• IMPORTED FROM GERMANY

496

Extremely accurate finely made proportional dividers. Basic equipment for draftsmen—architects—engineers—students. Replaceable steel points—in hard, leather covered, felt lined case. Used for proportional reductions and enlargements, copying drawings in enlarged or reduced scale, dividing lines or circles into equal parts, quick solving of difficult measuring problems, finding distances on maps without scales, etc. Flat form—replaceable steel points. Pressure setting. Graduated for lines from 1/4" to 10"—Circles from 6" to 20". Excellent, accurate utility model. Shpg. wt., 8 ozs. F-167 Net 4.96




1/10TH SECOND "ELECTRONIC" TIMER

- Made to Gov't. Specifications
- Mil-W-6510 (USAF) Type A-8
- Exceptional Accuracy

25⁹⁵

Especially useful as timing components of electronic and radar equipment. Made in accordance with government specification number MIL-W-6510 (USAF) type A-8. Dial face calibrated in 1/10 seconds. Sweep hand completes turn in 10 seconds. Register divided in 10 sec. increments, completes turn in 5 minutes. Luminous figures on black face. Start, stop and fly back to zero by successive depressions of the crown. Balance staff shock protected, unbreakable mainspring, nickel finished case. Swiss made. F-774L Shpg. wt., 8 ozs. Net 25.95

DECIMAL "TIME-OUT" TIMER




975 **690**

Ideal for industrial time-studies. Easy-to-read outer dial divided in 1/100 of a minute registering up to one minute. Inner dial graduated in minutes and registers up to 30 minutes. Push button, for timing out, brings both hands back to zero. Pressures on the crown will consecutively start, stop and again start the timer. Dependable 7-jewel movement. Swiss made. Shpg. wt., 8 oz. F-664L Net 9.75

1/10th Second "Time-Out" Timer
Suggested for close timing. Large hand registers 1/10 of a second, up to 30 seconds; small hand in minutes, up to 15. Start, stop, and continue from crown; instant return to zero by push button. Accurate 1-jewel movement. Chromium plated nickel case. Shpg. wt., 8 oz. F-665L Net 8.90

HARD MAPLE PANTOGRAPH



375

- ENLARGES
- REPRODUCES!

21" adjustable pantograph—21 different ratios from 1 1/4 to 8. Enlarges, reduces or reproduces drawings—sketches—diagrams—pictures—maps, etc. Most rapid accurate means of reducing or enlarging to scale. Lacquered highly finished bars are 21" long and 3/4" wide. Heavy metal standard, with bearing eliminates all friction. Chrome plated hardware—ratio thumb screws and nuts. Complete with lead, accessories and detailed instructions. Shpg. wt., 2 lbs. F-158 Net 3.75

SUPER DRAWING KIT



795

- COMPARE OUR PRICE!

Contains all the necessary equipment for drafting, mechanical drawing, designing. Sturdy accurate components. Includes 20x24 1/2" drawing board 24" T square, 10" 30°/60° triangle, 8" 45° triangle, french curve, 12" triangular rule, 6" 180° protractor, 4 pencils, pencil pointer, erasing shield, thumb tacks, and art gum eraser. If purchased separately these components would cost many times our low price. An unbeatable value. Shpg. wt., 10 lbs. F-180 Net 7.95

SPECIAL COMBINATION OFFER
Consists of F-65 Technical Drafting Set and F-180 Super drawing outfit. F-181 Shpg. wt., 12 lbs. Net 13.06

The NEW LAFAYETTE

CHOOSE THE PLAN THAT SUITS YOU BEST:

- REGULAR PLAN.** Monthly Payments as low as \$5. No Down Payment. (See Easy-Pay Payment Schedule.)
- E-X-T-E-N-D-E-D PLAN.** Up to 24 months to pay. No Down Payment. (See Easy-Pay Payment Schedule.)
- ALTERNATE 60-DAY PLAN** — No Credit Service Charge. Select the Regular or Extended Plan. Remit your payment within 30 days as scheduled. Pay the full balance, if any remains, within 60 days of shipment and you automatically convert to the Alternate 60-Day Plan and **SAVE THE ENTIRE CREDIT SERVICE CHARGE.**

Lafayette's Easy-Pay Plan
Makes It Easier For You To Buy Now ...
10 TIMES EASIER

"DOLLAR POWER PLUS"

You Get "DOLLAR POWER PLUS" with Lafayette's 3-IN-1 Easy-Pay Plan. One Low Monthly Payment Buys More For You.

| Monthly Payments FOR ONLY | Unpaid Balance (Total amount less down payment - if any) YOU CAN BUY UP TO |
|---------------------------|--|
| \$ 5 | \$100.00 |
| 6 | 120.00 |
| 7 | 140.00 |
| 8 | 160.00 |
| 9 | 180.00 |
| 10 | 200.00 |
| 11 | 225.00 |
| 12 | 250.00 |
| 14 | 275.00 |
| 15 | 300.00 |
| 17 | 350.00 |
| 19 | 400.00 |
| 22 | 450.00 |
| 24 | 500.00 |

For monthly payments on balances over \$500, please write us.

3-IN-1 easy-1 pay plan No Money Down

Here's How To Open Your Easy-Pay Account:-

Use the regular Lafayette order blank (more will be supplied upon request). Complete both sides of the form carefully, following the step-by-step instructions and illustration. Accuracy will speed handling of the form from the moment of receipt and permit immediate shipment upon approval of credit. Be sure to sign the agreement and indicate which Easy-Pay Plan you prefer — the liberal Regular or special Extended.

For both Plans, minimum order is \$20 and first instalment is not due until 30 days after shipment.

No Credit Service Charge for the alternate 60-Day Plan. For the Regular and Extended Plans, you are privileged to prepay the balance in full at any time to obtain a partial rebate of normal credit service charges.

Easy-Pay privileges are available to qualifying U.S. citizens or residents of all 50 States, Puerto Rico, Canada; and U.S. territories having comparable postal and express facilities. Any responsible individual over 21 years old with a steady source of income can apply.

FOR EASY PAY PURCHASE USE THIS SIDE AFTER FILLING IN MERCHANDISE ON REVERSE SIDE Before filling out amounts see EASY PAY PLAN SCHEDULE and example. Figure your sums first on separate paper to avoid errors. USE INK. DO NOT ERASE OR CROSS OUT.

RETAIL INSTALLMENT CONTRACT

Buyer's Copy Mailed - Date _____ By _____

(Please Print)
 Name _____
 Present (M) _____
 Home Address _____
 City _____ Zone _____ State _____ Telephone _____

To fill in spaces below correctly refer to EASY PAY PLAN Schedule on this sheet and note example:

EXAMPLE: (Standard Plan)
 If Item (5) Unpaid Balance = 106.50
 Item (6) Credit Service Charge = 11.00
 Item (7) EASY PAY Balance = 117.50
 Your Monthly Payment (See Schedule) is 10.00
 You will pay \$10.00 for 11 months or 110.00
 And your FINAL Monthly payment will be 7.50

Beginning one month after shipment BUYER AGREES TO PAY \$ _____ per month for _____ months, and a FINAL monthly payment of \$ _____ to the place and/or to any party designated in writing by the Seller.

1. Total Cash Price _____
 2. Sales Tax (N.Y.C. only) _____
 3. Total (Items 1 + 2) _____
 4. Down Pay (Altho Not Required Reduces Svce. Chrgs. & Paymts.) _____
 5. Unpaid Balance (Item 3 minus item 4) _____
 6. Credit Service Charge (See EASY PAY Schedule) _____
 7. EASY PAY BALANCE (Add items 5 + 6) _____

Total EASY PAY Price (Add items 3 + 6) _____
 Do not include shipping charges. Easy Pay orders are sent shipping charges collect, except for PARCEL POST CHARGES which are added to your account.

RETAIL INSTALLMENT CONTRACT

(L.S.) DATE _____

BUYER SIGN HERE _____ Signed _____

To combine additional purchase with a previous account, indicate UNPAID BALANCE \$ _____

NEW "EASY PAY PLAN" PAYMENT SCHEDULE

How to convert to Alternate 60-Day Plan. Pay 1st instalment within 30 days of shipment. Complete payment of balance, if any remains, within 60 days of shipment and Save Entire Credit Service Charge.

| IF Unpaid Balance Is | Standard Plan Credit Svce Monthly Payment | Extended Plan Credit Svce Monthly Payment | IF Unpaid Balance Is | Standard Plan Credit Svce Monthly Payment | Extended Plan Credit Svce Monthly Payment |
|----------------------|---|---|----------------------|---|---|
| UP to 20.00 | 2.00 | 3.00 | 225.01 - 250.00 | 25.00 | 38.00 |
| 20.01 - 30.00 | 3.00 | 4.00 | 250.01 - 275.00 | 27.50 | 41.00 |
| 30.01 - 40.00 | 4.00 | 5.00 | 275.01 - 300.00 | 30.00 | 44.00 |
| 40.01 - 50.00 | 5.00 | 6.00 | 300.01 - 325.00 | 32.50 | 47.00 |
| 50.01 - 60.00 | 6.00 | 7.00 | 325.01 - 350.00 | 35.00 | 50.00 |
| 60.01 - 70.00 | 7.00 | 8.00 | 350.01 - 375.00 | 37.50 | 53.00 |
| 70.01 - 80.00 | 8.00 | 9.00 | 375.01 - 400.00 | 40.00 | 56.00 |
| 80.01 - 90.00 | 9.00 | 10.00 | 400.01 - 425.00 | 42.50 | 59.00 |
| 90.01 - 100.00 | 10.00 | 11.00 | 425.01 - 450.00 | 45.00 | 62.00 |
| | | | 450.01 - 500.00 | 50.00 | 73.00 |

On orders over \$500.00 Credit service charge and payments will be in proportion to amounts shown on schedule

For purpose of receiving credit for above EASY PAY PLAN purchase, the buyer makes the following representation:

Permanent or previous address if (A) above is temporary or occupied less than two years.

Home Address _____ City _____ State _____

Age _____ Single Married Divorced Spouse Employed By _____

Draft Classification _____ Have you bought from Lafayette before? Yes No On Time Payment? Yes No If Yes, please give your Lafayette Real Estate Holdings - Address _____ Mortgage \$ _____

Recorded in Name of _____ Present Value \$ _____ City _____ State _____

Name _____ Position _____ Salary _____ (Months) _____
 Present Employer _____ Salary _____ (Months) _____
 Business Address _____ Source _____
 Name _____ Any Other Income _____
 Former Employer _____ How Long _____ (Years) _____ (Months) _____
 Bank Account With _____ Savings Checking (Address) _____

First Trade Reference _____ (Address) _____ Highest Credit \$ _____ Still Owing \$ _____ Monthly Payment \$ _____
 Second Trade Reference _____ (City and State) _____ Highest Credit \$ _____ Still Owing \$ _____ Monthly Payment \$ _____
 Third Trade Reference _____ (City and State) _____ Highest Credit \$ _____ Still Owing \$ _____ Monthly Payment \$ _____
 Nearest Relative _____ (City and State) _____ Highest Credit \$ _____ Still Owing \$ _____ Monthly Payment \$ _____

Name _____ Address _____ Relationship _____
 (DO NOT LIST THOSE WITH WHOM YOU RESIDE)

MINIMUM ORDER \$20.00 TOTAL CASH PRICE - NO DOWN PAYMENT
 No money down when you buy with Lafayette's new Easy-Pay Plan.

ADDITIONAL PURCHASES: Once you establish credit, you can "add-on" to your account with purchases of \$20.00 or more. No down payment required on "add-ons" or re-opened accounts. Just list the items you want on the order blank, write "add to my account", give your account number, also, "indicate" if you want instalment payments combined. Make certain you sign the Easy Payment Agreement.

NOTICE TO THE BUYER: 1. Do not sign this agreement before you read it or if it contains any blank space. 2. You are entitled to a completely filled in copy of this agreement. 3. Under the law, you have the right to pay off in advance the full amount due and under certain conditions to obtain a partial refund of the credit service charge.

LAFAYETTE RADIO ELECTRONICS CORPORATION (SELLER)
 111 JERICHO TURNPIKE, SYOSSET, L. I. N. Y.

sells and buyer purchases merchandise as described on reverse side hereof to be kept in good repair and unencumbered at buyer's stated address. Seller shall retain title and right to possession of merchandise until fully paid. The unpaid balance of this order together with applicable credit service charge, may be added to an existing unpaid account, for convenience of both buyer and seller. Should the buyer place subsequent orders, unpaid balances on such orders may be combined with any balance owing on this order together with applicable credit service charge, if buyer so authorizes and seller accepts in appropriate spaces elsewhere in this contract. Upon default of any payment or payments seller may declare entire unpaid balance due at once and may also repossess merchandise retaining previous payments as compensation for the use thereof. If proceeds of resale of merchandise are insufficient to cover buyer's obligation, buyer will pay the deficiency to seller; if proceeds result in overage, seller will pay such overage to buyer. Payments will be made to the place and/or to any party designated by the seller in writing.

LAFAYETTE RADIO ELECTRONICS CORPORATION (SELLER)

LAFAYETTE TELESCOPES ARE WORTH LOOKING INTO!



Arcturus

• 454x with Barlow Lens

3" EQUATORIAL REFRACTOR

• Ultra Precise Helicoid Focusing • 7 Coated Eyepieces Plus Barlow Lens • 76.2 mm Clear Aperture • Most Advanced Equatorial Mount • 25x, 42 mm Finder Scope

79-mm hard coated, air-spaced, Fraunhofer achromat of 910-mm focal length with 3" clear aperture, focal ratio of f/12 and resolving power of 1.6". Seven coated eyepieces provide magnifications of 22x, 152x, 101x, 73x, 35x, 18x and 25x through viewfinder. Helicoid focusing by means of a massive wheel and helicoid gear. Finder Scope, with rack and pinion focusing, features a 1.6 inch clear aperture objective of 500-mm focal length. Micro-motion controls with extended flexible shafts and compression locks in all axes. Accessories include three sunglasses, moon-glass, sun diagonal, two star diagonals, sun projection screen, erecting prism, heavy extensible field tripod, brace, accessory shelf, separate wooden cases for telescope and mount. Shpg. wt., 100 lbs. VIA EXPRESS ONLY. F-385WX Net 269.50

Galactic

• 454x with Barlow Lens

RESEARCH QUALITY 3" EQUATORIAL REFRACTOR

• Viewfinder Scope 25x, 42-mm • 910 mm Focal Length • 76.2 mm Clear Aperture • Micromotion Controls for Declination and Right Ascension • Resolving Power 1.6 • Barlow Lens Included

The objective lens is a 79-mm, hard coated, air spaced Fraunhofer achromat with a clear aperture of 76.2 mm (3"). Focal length 910 mm, focal ratio f/12, resolving power 1.6". Seven coated eyepieces provide magnifications of 22x, 152x, 101x, 73x, 45x, 35x plus 25x through the viewfinder. Barlow lens add ranges of 454x, 304x, 202x, 146x, 90x, 70x and 50x. Focusing by means of micro-precision rack and pinion drive. The viewfinder scope has a 42-mm (1.6 in. clear aperture) objective — 500-mm focal length-rack and pinion focusing — and will accommodate various eyepieces. Finely calibrated hour and declination circles for rapid finding and setting. Body tube of white enameled aluminum. Accessories include three sunglasses, moon-glass, two star diagonals, sun diagonal, erecting prism, sun projecting screen, extensible field tripod, chain brace, accessory shelf, wooden cabinet. VIA EXPRESS ONLY. F-384WX Shpg. wt., 60 lbs. Net 189.00

Polaris

• 320x with Barlow Lens

2.4" EQUATORIAL REFRACTOR

• Eyepieces for 160x, 88x, 40x, Barlow Lens gives 320x, 176x, 80x • 800 mm. focal length • 62-mm objective • Micromotion adjustments on both axes • Coated optics throughout • Equatorial mount

Objective: Fraunhofer-type achromat, hard coated, 62.5-mm., 800-mm. focal length. Collects about 75 times as much light as the naked eye. Resolving power 2 seconds, faintest discernible star 10.7 magnitude. Eyepieces are hard-coated Huygenians. 160x (5-mm), 88x (9-mm), 40x (20-mm). Barlow Lens included give ranges of 320x, 176x and 80x. Finder scope is 6x, 30-mm. Tripod head with latitude adjustment. Clamp lever for declination and inclination. Accessories include sunglasses, star diagonal, erecting prism, sun projection screen, field tripod, wooden case. Rack-and-pinion focusing. Heavy plating to prevent rusting.

F-342WX Shpg. wt., 30 lbs. Net 79.50
F-391 4-mm. orthoscopic eyepiece for 200x (400x with Barlow Lens) Net 8.95

(A) ZOOM SPOTTING SCOPE

• Any Power from 15X to 30X!
• Ideal for any "Spotting" Need!
• Pan-Head, elevator Tripod

True Zoom action—finger tip control—from 15 power to 30 power. Choose the right power for any "spotting" or viewing need. Brilliant image at any power. 50mm objective hard coated for maximum light gathering power. Prismatic system greatly reduces length—only 15" overall. Precisely machined, all metal body. Lightweight 'scope alone weighs only 2 lbs. May be hand held or used with tripod supplied. Precision fingertip focusing with oversized, milled ring. Aluminum and chrome-brass tripod adjustable from 12" to 18". Locking pan-head swivels and tilts to any angle. Optical train is fully hard coated. Shpg. wt., 5 lbs. F-685 Net 39.95

(B) 30x, 60mm SPOTTING SCOPE

• Coated Optics • Complete With Leather Case

Field of view is 85 feet at 1000 yds.! Both front and rear optics are coated. High relative brilliance due to 60mm objective lens. Exceptionally small and light—weighs only 2 lbs. including metal tripod! The perfect companion for shooting—hunting—viewing—naturalists—and hobbyists. Equipped with 11½" tripod and zippered leather carrying case. Shpg. wt., 3 lbs. F-145 Net 16.95

"MICRO'DAPTER"®



• Micro-photography! • Astro-photography!
• Inexpensive — accurate — easy to use
• Use any camera/microscope or camera/telescope set-up
• Photo-record your observations

1975

Permits the use of any camera—even movie cameras—with practically all microscopes and telescopes. No need to remove the camera lens. Cross hairs are super-imposed on the image for centering. The image is automatically in focus for the camera when viewed in focus through the MICRO'DAPTER. Accessory sleeves permit the MICRO'DAPTER to be used with other than Society size microscopes. The MICRO'DAPTER may be used with any telescope by attaching to eyepieces of 29mm (1½") maximum diameter. Shpg. wt., 1½ lbs. F-506 Net 19.75

NEW! "TRANSOTHERM" PRECISION ELECTRONIC CLINICAL THERMOMETER

A 20th Century Marvel—Temperature Readings in Seconds. Ideal for Children, Hospitals, Sickrooms, Veterinarians



• Direct Reading — Large Easy-To-Read Dial
• Portable—Use It Anywhere • Unbreakable—Safe, Sterile, Stainless Steel Probe • Lightweight—Only 4½ oz. • Accurate—± .2°F • Battery Powered—Lasts up to 5 yrs.! • Fully Guaranteed—for 6 Months
• Ideal Unit for the Veterinarian

39⁹⁵
NO MONEY DOWN

A new space age device which is superior to ordinary clinical thermometers. Modern as tomorrow, the "Transotherm" is so fast, children will hardly know their temperature has been taken. Perfect for hospitals, sickroom and veterinary use too—but you needn't be a physician or a trained nurse to use it. Simple to operate just press a button and read the large clear dial. No confusion—no waiting, only 15-20 seconds. Maintains readings even after the probe is removed. Completely safe and foolproof too. There is no danger of broken glass or mercury poisoning. The ¼ oz. sealed stainless steel probe can be easily detached for sterilizing in boiling water or cleaning in any standard sterilizing solution. Compact and lightweight, it can be carried anywhere—fits in the palm of your hand. No fear of breakage either. Hi-impact plastic case and rugged construction protect electronic components. The Transotherm may be used orally or rectally, there is no voltage of any kind on the probe. The fantastic accuracy of ± .2°F is achieved through its 98° — 108°F range by individually calibrating each probe during manufacture. Unlike other electronic thermometers, the accuracy of the Transotherm is not affected by battery fatigue or meter precision. This eliminates the need for periodic recalibration or battery replacement. The long life power cell will actually last up to five years! Fully guaranteed service at no charge is available for 6 months with nominal charge thereafter. Dimensions: 4¾x2¼x1¼". Includes compartmented case and instructions. Shpg. wt., ¾ lb. F-824L Clinical Thermometer Net 39.95

ATTENTION INDUSTRIAL USERS—A custom built "Transotherm" similar to the above, is available for a variety of uses. Allow 30 days for delivery.
F-836L 65°F to 115°F Net 39.95
F-837L 100°F to 200°F Net 39.95

LAFAYETTE BINOCULARS



AS LOW AS
1795

Precise design — quality material — and expert workmanship. All lenses are hard coated — prisms clamped in lightweight alloy frame and body — sealed against dust and moisture — properly collimated and aligned. All are center focus with adjustable right eyepiece. Hard leather case and neckstraps included.

7X35 Popular, versatile, all purpose binoculars. For the sportsmen—hunter—bird watcher—vacationer. High luminosity. Compact design. Shpg. wt., 3 lbs. F-183 Net 17.95
7X35 Wide Angle. Top performance—highest quality. Almost twice the field of view of ordinary 7x35 binoculars. Spots and holds a moving target faster and easier. Oversize oculars and prisms. Shpg. wt., 3½ lbs. F-184 Net 27.50
7X50 Navy style night glasses. Favored for marina use. The choice of professionals because of exceptionally high light gathering power. Superior image brightness. Shpg. wt., 3½ lbs. F-164 Net 21.95
20X50 King of the long range. Hunters, mountain climbers, plane spotters, forest rangers—any long distance viewing and observation requirement. Shpg. wt., 4½ lbs. F-185 Net 27.50

Add 10% Fed. Tax to the above prices.

TRU-ZOOM™



• Not a "Vari-Power"—One Control Zooms both barrels!

39⁹⁵

No Money Down!

• 7X to 12X— or any Power in Between

• Center Focus—right Eye Adjust—Plus Single Synchronous Zoom Control! • The Perfect Power For Any View!

Sensational Zoom action holds even fast-moving subjects in perfect view. Sight in any subject at 7 power—then Zoom up to 12 power (or any four in between) for closeup viewing. Full 40mm, objective lenses, hard coated achromats. Field of view is 250 feet at 1000 yds. at 12 power (5.5°). Prisms clamped in shock-resistant mounts. Lightweight alloy frame and body. Sealed against dust and moisture. Includes plush-lined, hard leather case and straps. Shpg. wt., 5 lbs. F-793 Net 39.95*
*Add 10% Fed. Tax

1500X "MICRO-STANDARD" ADVANCED ACADEMIC MICROSCOPE


SUMMER SPECIAL
69⁹⁵
SAVE 2000
Below Catalog Price

• 25X to 1500X IN 11 RANGES
• INTEGRAL MECHANICAL STAGE
• VARIABLE SUBSTAGE CONDENSER WITH IRIS DIAPHRAGM • FULL RANGE FINE ADJUSTMENT • STANDARD SOCIETY SIZE OPTICS - BOTH OBJECTIVES AND EYEPIECES



OPTICAL SPECIFICATIONS: Three Huygenian eyepieces: 5X, 10X, 15X. Four achromatic objectives: 5X, 10X, 40X, 100X (oil immersion). BODY: Monocular tube 140mm long. STAGE: Square stage 95mm x 95mm. Integral mechanical stage. Adjustable in any direction. FOCUSING: Coarse focus with adjustable tension. Fine focus vernier adjustment. Spring loaded safety device prevents objective from driving through slide. SUBSTAGE: Focusing Condenser with variable iris diaphragm. 41 mm plano/concave mirror. Overall 12½" high. 6½" deep. 5" wide. Includes fitted cabinet with lock and key, specimen slide, blank slide, bottle of cedar oil. Shpg. wt., 11½ lbs. F-602X Net 69.95

New! LAFAYETTE REFLEX TYPE F/1.8 ZOOM MOVIE CAMERA



WITH AUTOMATIC ELECTRIC EYE PHOTOMETER

ONLY
69⁹⁵

NO MONEY DOWN

- SINGLE LENS REFLEX SYSTEM LETS YOU SEE WHAT THE LENS SEES
- ULTRA FAST F/1.8 Lens—ZOOMS from wide angle to Telephoto
- Built-in Coupled Electric Eye Exposure Meter
- 4 Speeds—Including Slow Motion
- Single-Frame (animation) Exposure
- USES ANY FILM—ASA 10-40
- AUTOMATIC FOOTAGE COUNTER
- TRIGGER ACTION PISTOL GRIP

See exactly what the camera lens sees with this true single-lens reflex system. The bright viewfinder shows exactly what will appear on the film. No more parallel errors—no more focusing problems! Fast F/1.8 zoom lens is directly coupled to the electric eye photometer. Simply look through the viewfinder, line up the arrows and shoot! Needle sharp zoom pictures are yours from 10 mm. wide angle through 30 mm. telephoto. Trigger action, pistol grip handle provides a firm, comfortable grip for smoother, steadier movies. Fast, simple drop-in spool loading. Adjusts for films of ASA 10-40 speed rating. Film footage counter returns to the starting position automatically when roll is finished. Four motor speeds for 12-16-24 and 32 per second plus single frame for animation. Quiet ratchet-wind motor with a 6 ft. run. Die-cast aluminum body. Trigger action pistol grip handle and leather wrist strap included.

F-822L Shpg. wt., 5 lbs. Net 69.95
Zoom Case: Holds camera with pistol grip attached. Room for accessories. Measures 10x8 1/2 x 3 3/8". F-784 Shpg. wt., 2 lbs. Net 5.79

THE REMARKABLE LAFAYETTE f 1.8 TRIPLE TURRET 8 mm MOVIE CAMERA with Built-In Exposure Meter

- 3 TURRET INTERCHANGEABLE f 1.8 LENS — Wide Angle — Normal View-Telephoto
- Built-in Wide Scale Electric Eye Exposure Meter With Exposure Guide
- THREE Built-in Filters — For Color, Normal and Bright Scenes

Lafayette is proud to offer a modern 8 mm movie camera that is ready for "rapid fire" shooting. A three turret assembly for instant change over to one of three lenses, electric eye exposure setting, and pistol grip trigger release are time saving features the serious moviemaker should not overlook. A twist of the turret selects wide angle (f = 6.5 mm), normal (f = 13 mm), or telephoto (f = 25 mm), f 1.8 coated and color corrected lens. Turret action is smooth and positive. There is no need to fumble with focusing adjustments—all lenses are prefocused. The built-in exposure meter takes all the guess work out of exposure setting. Wide scale meter is matched with exposure guide to obtain proper lens opening, for perfecting filming. Also built-in are 3 filters: "conversion" for color film, "haze" for normal black and white and "neutral density" for extremely bright scenes. A choice of 4 speeds, 12, 16, 24 and 32 frames per second plus single exposure. Slide rule footage counter. Spring wound ratchet type motor runs 6 feet of film on a single winding. Exposure guide is calibrated for ASA 10 to ASA 40 film speeds. Direct optical viewfinder. Rugged die cast case in blue and gray. Trigger action, pistol grip handle and leather wrist strap included. Made to our specifications in Japan. Shpg. wt., 5 lbs.

- Pistol Grip With Trigger Release
- "Combo-View" Finder — For Normal, Wide Angle and Telephoto Areas
- Ratchet Spring Wind

was 39⁵⁰
29⁹⁵

NO MONEY DOWN



F-702L Net 29.95
F-648 Holster Case for F-702, Shpg. wt., 8 oz. Net 2.95

ZOOM MOVIE OUTFIT

SAVE 14.79 from catalog prices

Complete **136⁵⁰**

No Money Down

Complete ZOOM movie outfit contains all the equipment needed for success in taking and showing dramatic home movies. Included are the exclusive Lafayette 8 mm Zoom Camera (F-822), "Ultra" 500 watt projector (F-785), 30x40" folding tripod projection screen (F-536), bar light (F-531) with lamps and case, 2 reels and case (F-538), Zoom case (F-784) and 25 ft. of Kodak film with processing (F-576).
F-823WX Shpg. wt., 35 lbs. Net 136.50

MANSFIELD "ULTRA" 500 WATT 8 mm MOVIE PROJECTOR

- FAST, EASY LOADING
- FORWARD, STILL & REVERSE
- SELF-CONTAINED CARRYING CASE

No Money Down **52⁹⁵**

The new "Ultra" 8 mm projector features several unusual conveniences to uncomplacate movie showing. Has swing-out gate for fast threading. Forward, Still and Reverse positions. Bright 500 watt DFA lamp gives uniformly bright picture. Cinepar 750" f/1.6 lens. Self contained carrying case.
F-785 WX Shpg. wt., 10 lbs. Net 52.95
F-786 Replacement Lamp (DFA) Net 2.70

MATCHED MOVIE OUTFIT

79⁹⁵

No Money Down

Everything you need for movie-making and showing fun. No need to "shop" for unmatched equipment, no need to pay more. You get all this: Lafayette's F-702, f1.8, Triple Turret movie camera with exposure meter; holster type camera case; "Holiday," F-526, 500-watt projector; F-536 30x40" screen; F-537 Bar Light; 2 F-539 photo flood lamps; 2 F-538 400' reels and cans. Unbeatable for foolproof shooting and showing of indoor and outdoor movies.
F-789WX Shpg. wt., 30 lbs. Net 79.95

BIFLEX "LENS MASK" FOR POLAROID CAMERAS

- Cuts Film Costs in Half
- Makes Trick Shots Possible
- Doubles Your Enjoyment

4⁰¹

Here is an amazing device which will pay for itself the first two times you use it. Simply slips over your Polaroid camera lens and presto—you get 16 pictures from each 8 exposure roll of Polaroid film. Each double frame is 2-9/10" high by 1-4/5" wide. Does not introduce optical distortion, merely covers half the lens for each shot. Fun to use too, many types of trick photographs are possible. Shpg. wt., 6 oz. For series 95, 95a, 95b, 100, 150, 700, 800, 850, 900.
F-825 Biflex #1 Net 4.01
For Series 110, 110a, 110L, J66 F-826L Biflex II Net 4.82

AUTO-DIAL EXPOSURE METER

Holds its reading indefinitely. Meter is aimed and dial stopper depressed. The dial then swings to correct reading and remains fixed when stopper is released. Ideal for widely variant light conditions. Color and black and white calibration with ASA speeds to 25,000. Reflected and incident light read on same scale. EVS 1 to 19. Lens: f/1.0 to f/32. Direct reading cine speeds 8-64 fps. Meter has zero adjust. Leather carrying case and neck strap. Imported.
F-791L Shpg. wt., 1 lb. Net 6.75

6⁷⁵

"35" CLIP-ON EXPOSURE METER

3⁹⁵

- FITS CAMERA ACCESSORY SHOE
- ASA SCALE 10 TO 1000

Exceptionally convenient exposure meter. Clips right on camera—quick easy reading. Gives better, more accurately exposed pictures with a minimum of effort. Speeds 1/1000 to 1 Sec. Lens aperture f:1.4 to f:22. Mounts on camera or may be hand held. Complete with leather case and instructions. Shpg. wt., 1/2 lb. Imported.
F-351L Net 3.95

POLAROID ACCESSORIES

CLOSE UP KIT **7²⁵**

Focus as close as 6 inches from your subject. Take portraits — small still lifes — do photocopying. Includes 3 snap-on close up lenses, leather case and built in tape for accurate focusing. Shpg. wt., 8 ozs.
F-721L for all except 110B, 110A, 110, J33, J-66 Net 7.25

PICTURE ROLLS **10 SECONO DEVELOPING TIME**

32 and 42 are panchromatic types with an exposure index of 400 and 200 respectively. 37 and 47 have index ratings of 3000 and are used with the wink-light for indoor shots at normal room lighting levels. Shpg. wt., per roll, 5 ozs.

| Stock # | Type | Camera Model | Net Per Roll | Net ea. in Lots of 3 |
|---------|------|--------------------------------|--------------|----------------------|
| F-712L | 47 | All Except 80 Series, J33 | 1.89 | 1.80 |
| F-713L | 42 | All Except 80 Series, J33, J66 | 1.77 | 1.68 |
| F-714L | 37 | 80B, 80A, 80, J-33 | 1.48 | 1.40 |
| F-715L | 32 | 80B *2A, 80 | 1.38 | 1.30 |

LAFAYETTE ZOOM LENS **6⁹⁵**

• Fill the Screen From 12 to 15 feet—then ZOOM In!

The very latest in projection accessories for the movie fan. Coated, f1.5, 15 to 25mm focussible zoom lens fits most popular priced projectors. Converts our own "Holiday" (F-526) into a modern, zoom projector. Adds realism and depth to old "reels." Fills a 30x40" screen at from 12' to 15'—then zooms in for exciting closeups. Show your movies at the size you want—without moving projector or screen.
F-690L Shpg. wt., 6 ozs. Net 6.95

KODAK FILM WITH PROCESSING INCLUDED

- Slides Returned Mounted, Ready for Viewing or Showing!
- Rigid Processing Controls Assure Highest Quality
- Convenient, direct-mail "mailers" in every roll
- A full number of Prints guaranteed for Kodacolor and black and white.

You get factory-fresh film plus a convenient direct-mail mailer. After the complete roll has been filmed, put it into the mailer, drop into a mailbox and in a few days your finished films are delivered postpaid to your door. You get 3 1/2" square or 3 1/2 x 5" giant prints with Kodacolor and Black & White—and a full number of prints is guaranteed. Should you get less than the full number of prints of Kodacolor or Black & White printable negatives per roll, you will receive coupons for additional FREE prints. DO NOT MAIL FILM TO LAFAYETTE RADIO.

GENUINE LEATHER GADGET BAG **4⁹⁵**

Genuine pigskin—not plastic. 10x8x4". Holds your camera and all accessories. 20" zipper top. Pouch in lid holds filters, etc. Outside pouch with strap and buckle. All brass hardware. Loops and straps on bottom to hold tripod. Includes shoulder strap and pad. Shpg. wt., 1 lb.
F-320 Net 4.95

REPLACEMENT KIT FOR POLAROID WINK-LITE **1⁶⁷**

Kit contains both battery and bulb for replacement in Polaroid WINK-LITE. Manufacturer recommends both battery & bulb be replaced together to insure well lighted shots. Shpg. wt., 1 lb.
BA-320 Net 1.67

NEW 8 mm MOVIE EDITOR **17⁹⁵**

- Extremely Bright Hooded Screen
- Built-in Hand Framer

NO MONEY DOWN

This new 8 mm movie editor, compact designed—sturdily constructed, has an extremely bright hooded screen (24x13 1/4") for edge-to-edge sharpness and brilliance. 3:1 geared ratio revider for high speed rewinding. Built-in hand framer adjusts the frame properly on the screen; built-in individual frame marker makes editing easier. Folding winder and revider arms with 400-ft. capacities. Includes new dry splicer. Shpg. wt., 10 lbs.
F-652 Net 17.95

KODACHROME COLOR MOVIE FILM

| Stock No. | Description | Net ea. | Net ea. lots of 6 |
|-----------|----------------------------|---------|-------------------|
| F-575L | 8mm, 25 ft. roll, Daylight | 3.55 | 3.40 |
| F-576L | 8mm, 25 ft. roll, Indoor | 3.55 | 3.40 |
| F-577L | 8mm, 25 ft. Mag., Daylight | 4.60 | 4.42 |
| F-578L | 8mm, 25 ft. Mag., Indoor | 4.60 | 4.42 |

NEW! KODACHROME II COLOR MOVIE FILM

- 2 1/2 Times Faster; ASA Index Daylight 25, Indoor 40

| Stock No. | Description | Net ea. | Net ea. lots of 6 |
|-----------|---------------------------|---------|-------------------|
| F-794L | 8mm, 25 ft. roll Daylight | 3.78 | 3.60 |
| F-795L | 8mm, 25 ft. roll, Indoor | 3.78 | 3.60 |

KODACHROME 35mm COLOR SLIDE FILM

| Stock No. | Description | Net ea. | Net ea. lots of 6 |
|-----------|------------------------|---------|-------------------|
| F-580L | 35mm, 20 Exp. Daylight | 2.98 | 2.85 |
| F-581L | 35mm, 20 Exp. Indoor | 2.98 | 2.85 |
| F-582L | 35mm, 36 Exp. Daylight | 4.38 | 4.20 |
| F-583L | 35mm, 36 Exp. Indoor | 4.38 | 4.20 |

NEW! KODACHROME II 35mm COLOR SLIDE FILM

- ASA Index Daylight 25, Indoor 40.

| Stock No. | Description | Net ea. | Net ea. lots of 6 |
|-----------|-------------------------|---------|-------------------|
| F-796L | 35mm, Daylight, 20 Exp. | 2.99 | 2.85 |
| F-797L | 35mm, Daylight, 36 Exp. | 4.56 | 4.33 |

KODACOLOR COLOR SNAPSHOTS

| Stock No. | Description | Net ea. | Net ea. lots of 6 |
|-----------|--------------------|---------|-------------------|
| F-584L | 127 Indoor/Outdoor | 3.72 | 3.56 |
| F-585L | 120 Indoor/Outdoor | 3.72 | 3.56 |
| F-586L | 620 Indoor/Outdoor | 3.72 | 3.56 |

KODAK BLACK & WHITE ROLL FILM

| Stock No. | Description | Net ea. | Net ea. lots of 6 |
|-----------|-----------------------|---------|-------------------|
| F-587L | 127 Verichrome Pan | 1.28 | 1.17 |
| F-588L | 120 Verichrome Pan | 1.28 | 1.17 |
| F-589L | 620 Verichrome Pan | 1.28 | 1.17 |
| F-590L | 35mm, 20 Exp., Plus X | 2.32 | 2.24 |
| F-591L | 35mm, 36 Exp., Plus X | 3.45 | 3.35 |

ELEVATOR TRIPOD **8⁵⁹**

- Folds to 16" including Panhead!
- Extends to 47" PLUS 7" Elevator!
- Tri-Tilt head — Moves in 3 planes!

For any small camera—35 mm—reflex—or movie. Professional quality for professional results. Strong—steady—lightweight. Pencil slim, chrom plated, brass legs. Lock securely in place—fold down readily. Single action tilt-pan—and swing over for taking pictures in vertical or horizontal format. Geared elevator center-post with positive lock and folding crank. Weighs only 31 ozs. All the most wanted features in one tripod. Shpg. wt., 2 1/2 lbs.
F-339 Net 8.59

PROJECT-A-SCOPE **5⁹⁵**

- Projects Giant Pictures in Color Or Black and White — Without Films or Negatives
- For Lectures — Study — Classroom or Just Plain Fun!

Amazingly versatile! Delightfully simple! Adjusts to professional lenses. Just place it over anything that—magazines, books, photos, drawings, coins, stamps, documents, maps, natural objects—and see a brilliant giant enlargement projected on any white wall or screen in glowing true-to-life color or black and white. A boon to students, artists, collectors, lecturers, demonstrators. Children can project their favorite comics or story books to amuse themselves and their friends. Molded of heat resistant, hi-impact polypropylene. Rigid transparent base, flattens and protects photos, prints and stamps. Uses ordinary household bulbs. UL/UL Approved 110V. AC/DC. Shpg. wt., 2 lbs.
F-694 Net 5.95


NEW! CLAMP TRIPOD **5⁹⁸**

- World's Most Versatile Tripod

An indispensable photographic accessory. Combines, in one small unit, a clamp, tilt to, and table top tripod. Legs stored in shaft. Will clamp to trees, pipes, light stand, car, window, etc. Supplied complete zipper case. Shpg. wt., 1 lb.
F-654 Net 5.98

LAFAYETTE DIRECT IMPORTS Compare for VALUE!

TESTED AND SELECTED FOR CONSISTENT QUALITY




35mm CAMERA SPECIAL—THE RANGE FINDER III

- 4 Element F2.8 Coated Lens!
- Coupled Rangefinder • Luminous Bright Frame View-Range Finder!
- Single Stroke Rapid Film Transport!
- Nine Shutter Speeds to 1/300!
- MX Synchronization • Hi-Speed Rewind!
- Standard PC Flash Terminal!
- Double Exposure Prevention • Built-In Self Timer!

28⁸⁸ No Money Down

Fast F2.8 coated anastigmat lens and extra-wide lens aperture for brilliant, sharper full color or black and white. Sight and focus through combined range-view finder. Fully synchronized at all speeds for class M and electronic flash. Speeds from 1 sec. to 1/300th. Rapid advance sets shutter, counts exposure and transports film. Built-in delayed action timer—automatic exposure counter and film stop. 20 or 36 exposures on black and white or color 35mm film. PC flash terminal. Use series G accessories.

F-778L Less Case. Shpg. wt., 3 lbs. Net 28.88
 F-779L Leather Eveready Case. Shpg. wt., 1/2 lb. Net 3.95
 Auxiliary Wide Angle and Telephoto Lens Set for "Range Finder III" F-808L Shpg. wt., 1 1/2 lbs. Net 15.96
 Optical Viewfinder for Wide Angle and Telephoto Lenses. F-647L Shpg. wt., 6 oz. Net 3.39




SPRING PHOTO SPECIAL LAFAYETTE 35mm "ELECTRICK 2.8"

- Fast F2.8 Lens
- Lever-Type Film Advance
- Built-in Cross Coupled, Exposure Meter
- Match The Pointer—Focus and Shoot!
- Coupled Rangefinder

Save 10.00 Below Catalog Price **39⁹⁵** No Money Down

Perfect exposure every time is assured by the cross-coupled photoelectric exposure meter; merely set shutter speed and ASA film speed, aim camera, and line up light meter needle with colored mark on meter scale. Now a single twist gives perfect exposure at any speed. Superimposed coupled range finder with automatic parallax correction enables accurate focusing from 2.5 ft. to infinity on the fast F2.8 coated anastigmat lens. Shutter features speeds from a full second to 1/500. MX flash synchronization, and a self timer. Fast-action film advance cocks shutter, advances film, and counts exposure. Accepts 20 or 36 exposure

35mm film, color or black and white. F-655L Less Case. Shpg. wt., 3 lbs. Net 39.95
 F-656L Leather Eveready Case. Shpg. wt., 1/2 lb. Net 4.95
 Auxiliary Wide Angle and Telephoto Lens Set for "Electrick 2.8". F-809L Shpg. wt., 1 1/2 lbs. Net 15.96
 Optical Viewfinder for Wide Angle and Telephoto Lenses. F-647L Shpg. wt., 6 oz. Net 3.39
 Folding BC flash gun, with battery and leather case. F-209 Shpg. wt., 1 lb. Net 3.99



KALIMAT "35" CAMERA KIT

- 35mm Electric Eye Camera + Flash
- Automatic Exposure Control
- Double—exposure Prevention
- Automatic Film Exposure Counter
- Die Cast Aluminum body

A LAFAYETTE SPRING PHOTO SPECIAL **Only 37⁹⁹** No Money Down

Here is the camera you have been waiting for. No fumbling with exposure. No fumbling with different films—you can get a perfect exposure every time—automatically. A low price exclusive—the Kalimat "35" has a "viewfinder signal" which indicates when there is insufficient light to take a picture. In addition this camera automatically sets the exposure according to light conditions with a built-in meter. Other features include: fast single stroke film advance and shutter cocking lever, 40mm color corrected lens, bright frame viewfinder and built-in flash synchronization. The complete kit is supplied with camera, flash gun and leather carrying case. F-845L Shpg. wt., 6 lbs. Net 37.99



MAMIYA AUTOMATIC 16 SUBMINIATURE CAMERA

Featuring Exclusive Built-in Exposure Meter and Cross-Coupled Exposure Control.


- Fast, Clear F:2.8 lens • Focus—1 ft., to infinity • Shutter Speeds — B, 1/5-1/200
- Built-in Filter and Flash Synchronization • Life-Size Viewfinder • Automatic Exposure Counter • With Soft Leather Case and Braided Leather Wristband

Only 49⁹⁵ NO MONEY DOWN

The fabulous Mamiya 16 automatic combines professional quality and features with the simplicity of operation found in a box camera. Pocket size—it is always available to make that special shot often missed by slow, bulky cameras. With the automatic Mamiya 16, you achieve correct exposure all the time. The extremely wide shutter speed range—from B, 1/5 second up to 1/200 second; the fast F2.8 Mamiya-Sekor lens, and built-in exposure meter all combine to give accurate exposure control suitable for making enlargements of high-magnification. Focusing is adjustable from 1 ft. to infinity for maximum sharpness. Capable of high speed candid photography. Other features include: protective lens cover, built-in filter, flash synchronization, and automatic exposure counter. Dimensions 4 1/4 x 1 1/4 x 1 7/8". F-843L Shpg. wt., 1 1/4 lbs. Net 49.95

NEW! TRANSISTORIZED ELECTRONIC STROBE FLASH

Operates from Batteries and AC



- Lightweight & Compact — No Power Pack Needed • Fully Transistorized • Operates on 4 Economical "Z" Cell Batteries • Fits any Camera Shoe

24⁹⁵ NO MONEY DOWN

Now you can have a high-powered, transistorized electronic flash that operates from standard AC house current or 4 economical "Z" cell batteries. Compact and featherweight—no power pack is required. Flash duration of 1/2000 sec. for fast pictures. Recycling time: 6-10 seconds; color temperature: 6000° Kelvin. Guide number dial for F stop on back. Complete with AC cord. Less batteries. F-827 Shpg. wt., 2 lbs. Net 24.95
 Batteries for above (4 required). BA-155 Net each .095




NEW! COMMANDER CAMERA OUTFIT

EVERYTHING YOU NEED FOR PICTURE-TAKING

- Nothing else to buy • Built-in Flash • Perfect for the beginner
- Makes Super Slides • Shoots Color or Black & White

ONLY 9⁹⁸



INDOORS OR OUT—you can't go wrong with this new Commander camera. Makes an ideal gift too for birthdays and graduations. Look at what you get. A fine Commander camera which features double exposure prevention, built-in flash synchronization using tiny AG-1 bulbs for perfect indoor snaps; large optical viewfinder to see what you're taking and the American Optical Nycron lens is capable of shooting color or black and white film with perfect clarity. Also included are 2 rolls of Kodak 127 Verichrome pan, 2 penlight cells, 6 AG-1 miniature flash bulbs and a handy neck strap. The camera is guaranteed for one year, takes 12 jumbo pictures on roll of 127 size film. F-844 Shpg. weight of Commander Set, 2 lbs. Net 9.98

BOOSTER EXPOSURE METER

- Includes booster—Leather cases—neck cord
- Stills or Movies • ASA Scale—LVS Scale

6⁴⁵



Extremely versatile—extremely simple. Highly legible direct reading dial. Speeds from 4 sec. to 1/1000 sec. Lens aperture settings from f:1 to f:32. ASA scale 6 to 800. LVS scale 1 to 18. Cine scale 8, 16, 24 and 32 frames per second. Booster cell makes possible readings at extremely low light levels. Small-rugged-lightweight. Includes booster cell, leather cases, neck cord and instructions. Shpg. wt., 1 lb. F-349L Net 6.45

MANSFIELD 300 WATT 35MM PROJECTOR

Self Contained Case



- Brilliant 300 Watt—Turbo Blower Cooled
- 4 Inch, 13.5 Coated, Corrected Lens
- Designed for Easy Operation

28⁹⁵ NO DOWN PAYMENT

- For All 35 mm, 2 x 2 and Super Slides

Compact, convenient, semi-automatic, plus big-picture, 300 watt brilliance. Takes all 2x2 inch slides—35mm 828 (bantam) and 127 (super-slides). Semi-automatic "Presto-Matic" changer, one push-pull movement picks, shows and replaces 36 slides in sequence. Self-contained storage for over 100 slides. Die cast aluminum. Self-contained case. All optics hard coated. Designed for optimum projection brilliance. For 110-120V, AC/DC. Shpg. wt., 12 lbs. Net 28.95
 F-667

FOTOCHROME COPY TRAVELER

Photocopies Anything — Even Color

- Never Any Chemicals To Handle
- Portable—Lightweight

No Money Down **Only 134⁵⁵**

Now you can duplicate in the field with the revolutionary copy Traveler. Light in weight, you can take it with you anywhere—but that isn't all... the copy traveler photocopies automatically anything—even color in seconds. Yes anything printed, typewritten, handwritten, drawn or photographed. It picks up the slightest markings, even those made of subtle pastels and reproduces in proper shades of gray and black on permanent, never fade crystal white paper. No messy chemicals to handle either. Solution stays fresh in a special plastic disposable cartridge. Copies are ready to use at once, legally acceptable. For 110-120V AC, 60-cycle only. Complete with carrying case. Size: 18x12 1/2 x 5 1/2". F-840WX Shpg. wt., 15 lbs. Net 134.55
 F-841 Copy chemical cartridge Net 1.35
 F-842 Copy paper (50 sheets) Net 4.46



LAFAYETTE AG FLASH GUN

- Compact in Size
- Made for the New AG Bulbs
- Dependable B-C Operation

2⁹⁹



The new Lafayette AG flash gun is a compact, palm size yet offers dependable B-C operation. Made for the new AG flashbulbs which are small in size and big in performance. The Lafayette flash gun has a fan-type reflector which measures 2" in diameter when opened. Standard shoe fits all standard accessory clips. Features a Computer Dial for determining correct F stop. Testlight for checking battery and bulb, and Bulb Ejector. Complete with cord. Operates on 15V battery (not incl.). Shpg. wt., 8 oz. Net 2.99
 F-699
 BA-116 15-Volt Battery for above Net .81

THE RIGHT TOOLS AT THE RIGHT PRICE

THOR SPEEDWAY 3/8" DRILL

- FEATURING THE MOTOR THAT WON'T BURN OUT
- COMPLETE DRILL UL INDUSTRIALLY RATED & CSA APPROVED
- PRECISION GEARED CHUCK WITH KEY
- HI-TORQUE MOTOR RATED AT FULL 2.5 AMPS



1195

Here is a professional 3/8" electric drill at an amazingly low price. Hi-torque 2.5 amp, 115 VAC motor with 3-conductor lead cord, precision geared 3-jaw chuck with key, all-steel precision hobbled gears and newly developed special alloy bearings throughout. Capacity in steel, 1/2" in hardwood, 1". No load speed, 1750 rpm, full load speed, 1150 rpm. Momentary contact switch with locking pin. Sturdy diecast aluminum alloy housings with attractive hi-polish finish. Overall length, 8 1/4". Shpg. wt., 5 lbs. Net 11.95 HD-939

Power House DELUXE ELECTRIC HEDGE TRIMMER with Double Edge Blade

- Trims Shrubs and Hedges Quickly, Easily
- Adjustable Multi-Position Handle




1888

• **Self Sharpening—Through Hardened Teeth**
An easy to use tool that takes the time and effort out of shaping and trimming hedges. Double edge blade with unique tooth design grips and cuts branches off cleanly. 13" hardened spring steel cutting bar with multi-position adjustable handle. Slip clutch protects heavy-duty motor and gears. Fingertip switch gives complete control over trimmer at all times. 9-ft. cord. 1950 strokes per minute. 115V, 50-60 cycle, AC-DC, 2.5 amps. Shpg. wt., 6 lbs. Net 18.88 EL-109 50-ft., 3-Wire Extension Cord. Shpg. wt., 2 1/4 lbs. Net 3.51

NEW! FULL POWER 1/4 DRILL

OUR TOP DRILL VALUE

788



- UL APPROVED • GEARED CHUCK AND KEY
- UNIVERSAL 3/8 H.P. MOTOR

Lafayette's top drill value. 1/4" geared chuck drill rated at a full 3/8th horsepower. Universal motor. U.L. approved. 1/4" capacity in steel, 1/2" capacity in hardwood. 1200 to 1500 rpm speed under load, 2000 to 2400 rpm no load speed. Precision anti-friction bearings. Automatic trigger switch. Specially designed gear train for maximum torque transfer. Overall length, 8". For 115 VAC, 25-60 cycles. Shpg. wt., 4 lbs. Net 7.88 HD-708

THOR-SPEEDWAY 3/8" ELECTRIC DRILL




64-PIECE PROFESSIONAL POWER WORKSHOP

- A Complete Workshop For Do-It-Yourself Jobs
- Drills, Sands, Grinds, Buffs, Saws • Home, Garage, Shop

Here is the complete electric power workshop at Lafayette's typical low price. You can do almost every at-home job with this versatile 64-piece set. Look what you get: Thor Speedway 3/8" electric drill; 11-pc. power boring set with bits from 1/4" to 1 1/4"; 14-pc. twist drill set with metal index; 12-pc. sanding and polishing set; 7-pc. grind and buff set; 9-pc. 7-size hole saw; 7-pc. countersink and drill saw set; 3-pc. power screwdriver attachment. The Thor-Speedway 3/8" drill has 2.5 amp., 110 V AC motor. No-load speed, 1750 rpm; full load speed, 1150 rpm. Special alloy bearings throughout. U.L. approved. Shpg. wt., 10 lbs. Net 19.95 HD-976

NEW! WEN ZIPP SAW, MODEL 920



3305

NO MONEY DOWN

- Cuts Anything—Anywhere—Fast
- 1/2 HP, 4.25 Amp Motor
- "Free Hand" Cutting

The new Wen Zipp Saw handles like a keyhole saw, but the motor does the work. Uniquely designed base plate permits cutting flexibility without adjustments. Cuts metal up to 1/2" steel and wood up to 6x6"; flush cuts; fine scroll-work. Powerful 1/2 HP motor delivers 3200 1" strokes per minute. Heavy-duty roller and oilite bearings; heavy-duty hardened gears. Conventional saw grip with finger control trigger switch. Use it anywhere—from a construction job to a hobby shop. 115V, AC. Shpg. wt., 8 1/4 lbs. Net each 33.05 In lots of 3 Net each 29.37

THOR SPEEDWAY 1/2" ELECTRIC DRILL

Featuring the Motor that Won't Burn Out

- Complete Drill UL Industrially Rated & CSA Approved
- Powerful 4.0 Amp Rating
- Precision Hobbled Steel Gears

2133

No Money Down




An outstanding value featuring a universal series wound motor that won't burn out. Top handle and 2-position rear handle are removable. Top quality construction with precision hobbled steel gears. 1/2" capacity in steel, 2" in wood. No-load speed 600 rpm; full load 400 rpm. AC-DC momentary contact switch with locking pin; special alloy self-oiling bronze bearings. Lustrous hi-polish finish with rich black crackle trim. Overall length 14 1/2". Shpg. wt., 12 lbs. Net 21.33 HD-999

Thor-SpeedWay SUPER SANDER

1189

- 2.75 AMP MOTOR
- MOTOR DRIVEN 3450 RPM
- SANDS—SMOOTHS—BUFFS—POLISHES—RUBS!
- USE SHEET OR FREE (WET) ABRASIVES



Work-saving power for the master craftsman! The top sander with universal electric motor. Rough or finish sanding and buffing are done twice as fast! Hi-speed orbital action produces perfect finish every time. No load speed, 3450 r.p.m. Paper size, 4 1/2 x 6 1/2"; sanding area, 4 1/2" x 5 1/4"; overall length, 8". Sealed ball and oilite bearings. Neoprene ball guide and pad. Two pole induction motor, AC only; standard voltage 115V. 6 ft. 3 conductor UL approved line cord. UL approved push button switch. Shpg. wt., 6 lbs. Net 11.89 HD-707

HD-865 Lambswool Polishing Pad Net .79
HD-866 18 Sheets, Ass'd Sandpaper Net .98

WEN 'SOUPED UP' SABRE SAW MODEL 909



NO MONEY DOWN

3305

- HEAVY DUTY—FULL 6 AMP.
- 1/2 H.P. MOTOR—1" STROKE
- LARGEST CUTTING CAPACITY
- 6" 90° CUT • 4" 45° CUT

Trigger—more powerful—more versatile—faster cutting. Super-long blade easily cuts through 6x6" lumber. Cuts 4x4" at a 45° angle! Power enough to cut steel plate up to 1/2" thick—iron pipe up to 2" in diameter. Comfortable—conventional saw grip with auxiliary knob for 2 hand control. Saw tilts 45°—sole plate always remains flat. Finger control trigger-switch. Constant air stream flows dust from line of cut. 3400 1" strokes per min. Includes seven blades for cutting wood—steel—hardboard—sheet metal—pipe—leather—rubber—formica—etc. Equipped with rip guide and circle cutter guide. 8 ft. 3 cond cord and adapter. 110 watts. 6 amp., AC-DC. 8Lx7Wx7 1/2" H. Shpg. wt., 8 1/4 lbs. Net 33.05 HD-466 In lots of 3 Net 29.37

SPRAYIT 600 PROFESSIONAL-STYLE SPRAY UNIT

- Integral Compressor-Motor
- All-Aluminum Spray Gun
- Sprays Oil, Paints; Stains

2621

NO MONEY DOWN




All-purpose spray unit that gives professional results from the start. Adjusts pattern from small-as-a-dime to a fan 10" wide—4 times faster than a brush, and cleans easier, too. Easy-to-use 2-finger trigger gun. Never needs lubrication. Air delivery: 1.5-2.0 CFM @ 15-20 lbs. Complete with 6-ft. cord with plug, 8-ft. hose with connections. Net 26.21 HD-933 Shpg. wt., 11 lbs.

Thor-SpeedWay SUPER JIG SAW

1388

- CUTS 2" WOOD—1/8" STEEL
- 3 AMP MOTOR
- 3000 STROKES PER MINUTE



Enjoy a new thrill in sawing! The powerful No. 5 jig saw cuts curves, scrolls, straight cuts and rips. Cuts 45° angle on either side. Cutting capacity: 2" soft wood, 1/4" in steel; length of stroke 3/4". Motor rating, 3 amps; no load speed, 3000 strokes per minute; oilite bearings. Base tilts 45°. Overall length 6 3/4", height 5". Universal series wound motor, AC or DC; positive on-off position, push-through slide switch UL-approved; 6 ft. 3 conductor lead cord UL-approved. One wood cutting jig saw blade and wrench. 115V, AC/DC. Shpg. wt., 5 lbs. Net 13.88 HD-706

HD-439 Pkg. of 5 wood and metal cutting blades Net .59

MODEL 4100 VERSAMATIC

1125

- WITH YANKEE STYLE BIT HOLDER
- TURNS 1/4" DRILL INTO HIGH POWER TOOL
- REVERSES—INCREASES POWER—REDUCES SPEED



Seven to one speed reduction develops tremendous torque! Hand clutch control for easy, instant stop-start action! Look at these fabulous features! Power screw driver—handles largest screws—reverses to extract them! Power drill tapping head! Plenty of power for oversized drilling! Perfect for concrete or any kind of masonry drilling! Low speed and high power for hole saw attachments! A professional tool that anyone can use! Comes complete with screwdriver bit—Phillips bit—1/4" socket set adapter—wrench pin and instruction book. Shpg. wt., 5 lbs. Net 11.25 HD-195

1/2" CHUCK FOR VERSAMATIC

Geared chuck—3/4" to 1/2" capacity—#33 taper to fit Supreme Versamatic. Shpg. wt., 1/2 lb. Net 7.38 HD-268

JACOBS TYPE DRILL CHUCK

298

Comparable to Jacobs 1B. Key type geared tooth chuck. Capacity 0-1/4" thread 3/8x24". Ruggedly constructed. Polished finish. Used as standard equipment on most electric drills. Made to rigid specifications. Compare our really low price. You'll find this same chuck selling for twice as much! Net 2.98 HD-186 Shpg. wt., 1 lb.

STANLEY HEAVY DUTY SABRE SAW



No Money Down

2797

- CUTS FLUSH TO A WALL
- FULL 3/8" STROKE—3300 STROKES PER MINUTE
- ANTI VIBRATION MECHANISM

New Stanley Heavy Duty Sabre Saw—rugged enough to cut 1/2" steel bars. Will do the work of rip, crosscut, band, jig, keyhole and hack saws. Particularly suited for use where it's difficult to use a circular or band saw. Cuts curves, scrolls, pockets, intricate patterns in wood, plastics, veneers. Cuts full 2" lumber—conduit—cable—flush cutting blade allows cuts right up to a wall. Improved chip blower—single screw blade lock—positive slide switch—cool, comfortable handle. 2.5 amp. 115V AC/DC motor. Includes one each wood—metal—and flush cutting blade. Shpg. wt., 6 1/2 lbs. Net 27.97 HD-701

RAM BUFF-N-SAND

2373

NO MONEY DOWN



- Two Tools in One—A Combination Polisher Buffer & Sander

A rugged all-purpose polishing and sanding tool half the weight of similar units. Perfect for sanding or polishing furniture, cars, floors and walls. Engineered to operate at 500 rpm to avoid hi-speed heat and friction on working surfaces. Universal AC-DC motor employs thrust ball bearings for smooth rotary action. Supplied with heavy duty 3-conductor cord, 7 1/2" O.D. lambswool bonnet and 24 sanding discs. Overall length 13 1/2". Shpg. wt., 5 1/2 lbs. Net 23.73 HD-931

ARCO SCREW & NUT DRIVER ELECTRIC DRILL ATTACHMENT

584

- Complete 15 Piece Screw and Nut Driver

For rapid fastening of both screws (slotted and Phillips) and nuts (hex and square head). Has non-slip industrial type clutch for fast easy driving. Bit holder prevents screw head slippage. Includes flat bits and bit holders for #4-8 and #8-14 screws, #1-2 Phillips head bit, 6 hex socket wrenches (1/4", 3/8", 1/2", 5/8", 3/4", 7/8"), 2 sq. socket wrenches (1/4", 3/8") and socket wrench holder with ball lock. Net 5.84 HD-944 Shpg. wt., 1 1/2 lbs.

SPECIAL TOOL VALUES

Stanley 1/4" Power Drill



1397

- APPROVED AND POWERED FOR FULL TIME USE
- 3 AMP—2500 RPM—AC MOTOR
- PRECISION GEARED CHUCK

The perfect drill for use with drill attachments. Designed for continuous duty—ease of maintenance. Advanced styling for comfort and balance. Dependable bronze bearings—extra long brush life. 2500 RPM no-load speed. 1600 RPM under full load. Capacity 1/4" in steel, 1/2" in hardwood. Trigger switch with locking pin for intermittent or continuous run. Accurately machined precision gears. High speed airflow ventilation. 8 3/4" overall length. Weighs only 3 1/4 lbs. 3 Amps. 115v. AC only. Shpg. wt., 4 1/2 lbs. Net 13.97

BRAND SKIL RECIPRO SAW With 3 BLADES

NEW!



"Roughing-in" cuts in walls, floors, ceiling.

Cross-cuts wood, angle iron, pipe.

36⁹⁵

No Money Down

- Cuts anything from Thinnest Plastic Sheeting to 6" Logs
- Exclusive 3-Position Foot—Flush, Stationary, Rocking
- Exclusive 4-Position Blade


It's the brand new Skil Model 577 Recipro Saw—the amazing tool with a virtually unlimited cutting capacity... from 6" logs to the thinnest plastic sheeting. Cuts any material from soft wood to steel or plaster. Makes tough rip cuts, intricate scroll work, miter and bevel cuts, flush cuts without attachments, pocket cuts with its own starting hole, cross-cuts. Features Universal 3-amp motor with self-lubricating bearings; no load speed of 2000 strokes per minute. Stroke 3/4"; overall length 11 3/4". 3-wire cord with 3-prong and 2-prong adapter. Double reduction gears; 3-position side handle, automatic blower, canted blade, etc. Complete with 3 blades (MD-784, MD-785, MD-786). UL approved, 115V, 60 cycle AC. Shpg. wt., 6 1/2 lbs. HD-781 Net 36.95

ACCESSORY BLADES

| STOCK NO. | TEETH PER IN. | LENGTH (IN.) | USE | NET EA. |
|-----------|---------------|--------------|---|---------|
| MD-782 | 10 | 4 | Metal cutting—ferrous 1/4" or thicker; non-ferrous 1/2" or thicker | .40 |
| MD-783 | 10 | 8 | Fast scroll cutting in wood. | .60 |
| MD-784 | 6 | 4 | Fast scroll cutting in wood. | .60 |
| MD-785 | 8 | 4 | Hollow ground for smooth wood cutting. | .67 |
| MD-786 | 10 | 4 | Multi-purpose—rough-in cuts in wood with nails, soft metals, under 1/2" thick | .20 |
| MD-787 | 10 | 12 | Plastic cutting or wood, building tile | .47 |
| MD-788 | 6 | 6 | Plastic cutting or wood, building tile | .27 |

Stanley Heavy Duty Builders Saw

- PERFECTLY BALANCED
- 9.5 AMPS—5000 RPM
- SELF-LUBRICATING BALL AND BRONZE BEARINGS



Power-packed 9.5 amp motor provides high cutting force. Wrought aluminum base connected to motor housing by spring steel beam. Rear position control panel. Rear-position wing-nuts for depth and bevel adjust. "Free Start" ball bearing guard—moves at slightest pressure. Big "window" for wide open view of cut. "Motor Saver" drive protects motor against damage when blade cuts nails or knots. Weighs only 9 3/4 lbs. Cuts 1/2" to 2" at 45°, 3/8" to 2 1/2" at 90°. Blade size 7x3/8". 5000 RPM no load speed. Ball and bronze bearings. 9.5 amps. 115/230 volts AC/DC. Shpg. wt., 13 1/2 lbs. Net 34.97

NEW! ONE-PIECE MOLDED TOOL HOLSTER

.99

- No Rivets or Seams to Give-way
- Impervious to Rot, Mildew, Moisture
- 5 Pockets

Here's a one-piece molded tool holster that will give you years of service. No more seams to tear, rivets to pop; no more rotting due to mildew or moisture. 5 pockets—center pocket 2 front pockets, 2 deep side loops. Double belt loop. Overall 9 1/2" x 6 3/4". Shpg. wt., 8 oz. Net .99

BABCO GRASS TRIMMER

- FAST SHEARING ACTIONS
- SAFE OPERATION WITH BLADE GUARD
- SMOOTH, CLEAN CUTTING

262

Now you can take advantage of that electric drill in your work shop to trim grass with this unit. Attaches to any 1/4" electric drill. Ideal for cutting grass grown over sidewalk, stepping stones or close to wall. Neat and fast cutting. Ten times faster than hand shears. The rotary blade is well guarded, top and sides, to insure safe operation. 5 1/2" blade can be easily re-sharpened with any kitchen knife sharpener. Shpg. wt., 1 lb. Net 2.62

POWERHOUSE ELECTRIC SHRUB AND GRASS TRIMMER WITH HANDLE-ROLLER ATTACHMENT

- Ideal for Trimming Ornamental Shrubbery
- Trims Easily Around Fences, Walks, Trees, House
- Can Be Hand-Held—Simply Remove Handle-Roller Attachment

1995

Eliminate back-breaking gardening and keep your shrubs, hedges and grass trim and neat. Scissor-action type blades are safe—won't throw stones or dirt. Built-in clutch protects the heavy-duty motor and gears. Self-sharpening, cuts 5" wide swath. Die cast aluminum housing—shears weigh just over 3 lbs. 4-position, adjustable auxiliary handle; handy on-off switch. Handle-roller attachment, on plastic wheels, lets you trim as fast as you walk. Special clamp holds cord next to handle, out of the way. 10 teeth (5 on each blade); 1800 strokes per minute. 9" cord. 115V, 50-60 cycles, AC-DC. 2.5 amps. Shpg. wt., 9 lbs. Net 19.95

RAM 1/4 HORSE POWER

ELECTRIC HEDGE TRIMMER

2403

No Money Down

- 1800 Cutting Strokes Per Minute
- 14" Tempered Steel Blade

A full 1/4 horsepower hedge trimmer ideal for straight or angle shrub trimming. A 14-inch tempered steel blade with "vari-action" design delivers 1800 cutting strokes per minute. Handle is adjustable for right or left hand use. Mirror finish housing contains a powerful, air-cooled 115V AC-DC stable-proof motor. Complete with heavy-duty 50-foot 3-conductor cord. Shpg. wt., 10 lbs. Net 24.03

Yo-Lift LIFT-A-TON WINCH

Multiplies Your Strength More Than 20 Times

- Over 2000 Lbs. Capacity
- For Home, Farm, Shop, Autos, Camping, Civil Defense
- Lightweight Sturdy Construction

The Mighty Muscle provides you with tremendous lifting or pulling power with an over 2000 pound capacity. Actually multiplies a man's strength more than 20 times. Note these features: a safety factored panel gives instant release. Cannot be accidentally disengaged. Steel aircraft cable of 3/8" diameter has over 4,000 lbs. test strain. Easy to operate. 8 holes for handle give maximum number of adjustment positions. Lightweight, the complete assembly weighs only 6 lbs. Unconditionally guaranteed against defects by the manufacturer. Complete assembly includes cable, hook and 12" steel handle. Shpg. wt., 7 lbs. Net 22.50

2250

ELECTRA-SPRAY

- FOOLPROOF SPRAY PAINTING
- INCLUDES NEW VISCOMETER

746

Sprays every kind of sprayable paint or liquid—adjustable, jeweled nozzle provides fine, medium or coarse spray. Completely rustproof construction. Brass and stainless steel parts. High impact plastic housing. 22 ounce interchangeable mason-type jar. Electro-magnetic motor never needs oiling or adjustment. Comfortable pistol grip handle with self-releasing trigger switch. The new VISCOMETER insures perfect paint consistency—regardless of brand—every time. Complete with 8 ft. heavy duty cord, 22 ounce jar, viscometer, wrench and instructions. For 115 V. A.C. only. Shpg. wt., 5 lbs. Net 7.46

NEW! "THIMBLE" SCREWDRIVER

- Excellent for Hard-To-Reach Places
- No Shaft Handle Needed
- Handy for Shop, Home, Office, Anywhere

.45

It's the newest design in screwdrivers. Your own finger pressure holds the "Thimble" screwdriver securely on the screw for quick, efficient insertion or removal. Gets around corners and into tight spots an ordinary, shaft-handled screwdriver can't reach. Sturdy, high-compact styrene construction. Shpg. wt., 3 oz. each.

| | |
|-----------------------------|----------|
| HD-730 Screwdriver | Net .45 |
| HD-731 Phillips Screwdriver | Net .45 |
| HD-732 1/4" Socket Driver | Net .45 |
| HD-733 Set of 3 | Net 1.20 |

ELECTRIC CULTIVATOR ATTACHMENT

- Attaches to any 1/4", 3/8" or 1/2" Electric Drill
- Weeds and Tills Soil Easily
- Digs Furrows and Plots Quickly

10⁸⁸

Gardening can be fun with this electric cultivator attachment. Just attach it to any 1/4", 3/8" or 1/2" electric drill and you can weed, till or dig. Six tiller blades are of long-lasting spring steel. Interchangeable handle for right or left-handers. Powerful gear reduction. Absolutely safe. Lightweight, it saves you time and energy. Shpg. wt., 7 lbs. Net 10.88

"SHOP KING" HEDGE TRIMMER

699 • 14" BLADE

Converts any 1/4" drill into an easily handled hedge trimmer. Cuts, trims and shapes hedges and shrubbery. Extra long 14" blade of hardened tool steel. Keen edges for fast shearing action. Steel drive gear—permanently lubricated. Long, comfortable handle. Locks in any of 10 different positions. Light weight-compact. Shpg. wt., 3 lbs. Net 6.99

25-PC. DELUXE TOOL KIT

279



Hardened, tempered alloy steel tools for handy use in the house or workshop. Kit consists of 1 plastic screwdriver handle with aluminum chuck; 4 screwdriver blades (1/4"x4 1/4", 3/8"x4 3/8", 1/2"x5" flat drivers and one No. 1 Phillips blade); 8 open and box end wrenches (1/8", 3/16", 1/4", 5/16", 3/8", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3", 3 1/2", 4", 4 1/2", 5", 5 1/2", 6", 6 1/2", 7", 7 1/2", 8", 9", 10", 11", 12", 14", 16", 18", 20", 22", 24", 26", 28", 30", 32", 34", 36", 38", 40", 42", 44", 46", 48", 50", 52", 54", 56", 58", 60", 62", 64", 66", 68", 70", 72", 74", 76", 78", 80", 82", 84", 86", 88", 90", 92", 94", 96", 98", 100"); 2-way flat ratchet handle; 2-way flexible shaft extension; 2-way 1/4" extension bar; 8 steel sockets (3/16", 1/8", 1/4", 3/8", 1/2", 5/8", 3/4", 7/8", 1", 1 1/4", 1 1/2", 1 3/4", 2", 2 1/4", 2 1/2", 3", 3 1/2", 4", 4 1/2", 5", 5 1/2", 6", 6 1/2", 7", 7 1/2", 8", 9", 10", 11", 12", 14", 16", 18", 20", 22", 24", 26", 28", 30", 32", 34", 36", 38", 40", 42", 44", 46", 48", 50", 52", 54", 56", 58", 60", 62", 64", 66", 68", 70", 72", 74", 76", 78", 80", 82", 84", 86", 88", 90", 92", 94", 96", 98", 100"); All in a convenient roll pouch with handy pocket for each tool. HD-688 Shpg. wt., 1 1/2 lbs. Net 2.79

DUPONT NYLON NUT KIT

- Fits Over 250 Combinations of Thread Sizes
- Self Tapping! Self Locking

.73

A selection of 21 tough DuPont Nylon nuts for hundreds of uses in the home or shop. Fits sizes from 1/8" to 3/8" diameter. The nylon nut is strong, durable and lightweight with outstanding resistance to vibration, impact, corrosion, hot and cold temperatures, and chemical erosion. Fits over 250 combinations of thread sizes—U.S., foreign, left hand, right hand, wood screws. Self tapping, self locking. Shpg. wt., 3 oz. Net .73

NEW! NYLON MINICLAMPS

- Reaches Areas Where No Other Clamp Will Work
- For Home, Hobbyists, Electronics, Workshops
- Featherlite—Vise-Like Grip

.95

A completely new, lightweight clamp for those small and impossible clamping jobs. Constructed of tough, durable nylon and as useful as a third hand. Miniclamps are ideal for most soldering jobs requiring normal temperatures, are unaffected by most glues and cements used in model making, etc. The larger Miniclamps are husky enough for heavier jobs. You get 5 clamps (3/8", 1/2", 3/4", 1", 1 1/2" jaw sizes), 4 platens, and rubber binders. Shpg. wt., 6 oz. Net .95


.89 UTILITY-SWIVEL MIRROR

- 14" Reach • 2 1/4" Diameter Mirror
- Comfortable-Grip Handle • Swivel-Head

A handy little aid for mechanics at home or in the shop. Large 2 1/4" diameter mirror on a swivel arm enables you to look into hard-to-see places—no need to "work in the dark". Brightly chrome-plated with easy-to-grip plastic handle. Overall 14" long. Shpg. wt., 8 ozs. Net .89

PAIR PORTABLE SAWHORSES

- For Home and Shop
- Portable—Lightweight—Safe
- Folds for Compact Storage



798

Now... a truly portable sawhorse with folding legs for easy carrying and storage. Absolutely safe—sanded finish and rounded corners; patented construction makes it impossible to collapse while in use. Sturdy and lightweight, made of kiln dried Douglas fir with a walnut stain. Cadmium plated hardware will not rust; brass handles. Weight capacity of 1000 lbs. Ideal for handy man or carpenter, strong enough for utility table or workbench. Shpg. wt., 16 lbs. Net Pair 7.98

DELUXE HOPPY-SPLIT IMAGE TRANSIT

- Low Cost, Precision Level and Incline Measure
- Prism-Like Optical System
- Plate Glass Mirrors
- External Sights

Amazingly accurate instrument that will indicate level and measure a minimum of 1/4" rise or fall at 25'. Makes present day bubble and string type levels obsolete. It not only indicates level but shows exactly how much correction is needed. One man can perform any leveling or incline measuring job quickly, easily, and accurately. Makes any complicated measuring/leveling job simple. Use it for patio layout, bricklaying, flooring, surveying, terracing, fencing, plumbing, shelving, guttering, drainage, irrigation. Indispensable as a leveling and grading tool for model railway pike. Shpg. wt., 6 lbs. Net 6.72

HD-441 case—Shpg. wt., 1 1/2 lbs. Net 3.20

ARC JOINT PLIERS

189

- Fully Chrome Plated

Heavy duty, slip-groove jointed water pump pliers. Fully chromed and polished. 5 adjustments. 1 1/4" parallel opening. Forged steel. Deep milled jaws. 9 1/2" long overall. Shpg. wt., 1 lb. Net 1.89

REVOLVING LEATHER PUNCH

.99

Has 6 standard punching tubes. Made of long-lasting tempered steel. Shpg. wt., 12 ozs. Net .99

BUYS-BUYS and MORE BUYS!


Another First From Lafayette!!

KAR-KOOL



ONLY **39⁹⁵**
No Money Down

PUTTNIK-INDOOR PUTTING PRACTICE



- Indoor Fun for the Entire Family
- Takes off Strokes from Dad's Golf Game
- Returns Balls Within 5" Radius of Cup

ONLY **8⁸⁸**

Improves putting technique of any golfer as well as providing many hours of play for the entire family. This all-steel unit is as close to being a cup on the green as is possible. Your golf ball is retrieved automatically—when the ball lands on the green surrounding the cup, it is collected and returned electromagnetically. Takes strokes as long as 10 to 20 feet away. UL approved. 115V, AC. Shpg. wt., 5 lbs. Net 8.88
Sudden Death Regulation Putter. Shpg. wt., 1 1/2 lbs. Net 3.88



... Drive In Air Cool Comfort All Summer Long, Inexpensively!

A fantastic new development in car comfort—cools air in seconds, instantly ends windshield fogging and steaming quickly clears tobacco smoke and odors. Here's how Kar-Kool works: using the principle of air expansion (expanding air is cooling air), the old air is drawn into the unit, compressed and released in an expanding state. The Kar-Kool motor runs at 4000 RPM which is produced by the car in motion, or directly from your 12 volt auto battery (uses only 2 1/2 amps). The air movement is 2200 feet per minute, through each of the two air vents. The entire air in the car is changed twice each minute, while at the same time drawing out dirt,

dust, tobacco smoke and odors. Operates with or without the car motor running. Equipped with mounting brackets, the Kar-Kool is quickly and easily installed under the car-dash by fastening two screws—operates off the cigarette lighter, or attaches to any live terminal in back of the dashboard. Attractive, sturdy extruded aluminum construction in contrasting black and silver. Features a large screen-guarded air intake vent and two flanking manually adjustable outlet vents for directing cooled air flow. For all cars with 12 volt systems. Size: 17 1/4x18x7 3/8"H. Shpg. wt., 6 lbs. AA-134 Net 39.95

BRAND NEW! TRANSISTORIZED "BULL HORN"



ONLY **9⁹⁵**

HUNTERS CAMPERS BOATING SPORTS

- Weighs only 2 1/2 lbs.
- Range up to 2,000 ft.
- Completely Transistorized
- Can be Used as Long-Range Listening Device

Considered the most modern development in bull horns because it is completely transistorized—instantly operates on 6 standard 1 1/2V. "C" flashlight batteries (not incl.). With its range up to 2,000 ft., it is ideal for all outdoorsmen, for work or sports. Trigger switch is simple to operate—just press to talk. May be used as a sound detector and amplifier as well as a voice amplifier. Shpg. wt., 3 lbs. PA-271 Net 9.95
BA-274 1.5 Volt Batteries (6 req.) Net ea., .16

6 PUSH-BUTTON TELEPHONE



16⁹⁵

- Made by Western Electric
 - Complete with Dial and Ringer
 - 6 Illuminated Type Buttons
- Popular cradle-type phone with 6 push-buttons that can be illuminated. Reconditioned like new and guaranteed to work. Ideal for intercom and private phone systems. Size and appearance may vary slightly. Factory packed. PA-377 Shpg. wt., 10 lbs. Net 16.95

GLARE GUARD VISOR

- Molded from Acrylic Plexiglass®
- Built in "Diffusion Band" 269
- Fits All Cars and Trucks



First major improvement in sun visors in 30 years! Scientifically designed to filter out 87% of the sun's rays. Optically clear, "Dawn Blue" filter lets you see road signs, signal lights and traffic hazards in their natural color and clarity. Simultaneously protects your eyes from glare, squint, fatigue and eye strain. Provides eye ease and comfort—safe, clear vision. Fits all cars and trucks. Non-slip, heavy duty spring clips, snap on regular visor. A "flick" of the finger positions it. Adaptable to sports cars with no original visor. A year 'round necessity. Overall size 16x4 3/4". AA-46 Shpg. wt., 1 lb. Net 2.69

FAN-O-TROL THERMOSTAT

3 39
• For window fans—ventilators roll-a-rounds
You can convert any window ventilating or other electric fan to automatic—thermostatic operation—controlled by room temperature. Gives any fan the features of the latest, deluxe models. Simple, plug in installation—done in minutes. Just set it—and forget it. Automatic cool comfort—day and night! Switches your fan on and off as the temperature demands. Completely assembled unit—ready to plug in. With instructions. UL Approved. AP-56 Shpg. wt., 1 lb. Net 3.39


NEW! DYNAMIC HIGH POWER INVERTER

- Operate TV, Hi-Fi or CB Equipment On Board Your Boat!


- Completely Transistorized
- Exceptionally Stable
- Ruggedly Constructed

The Dynamic Television Inverter is just the right power converter capable of operating any TV, CB, Ham or Hi-Fi rig from any 12 volt battery source. Completely transistorized, it features the same output power characteristics as AC house power. No loss of B+ in TV brilliance. Has excellent stability under loads to 220 watts. The Dynamic inverter is equipped with a heavy gauge line cord for connection to a 12 volt battery. Not recommended for motors or fluorescent lights. Complete with instructions and 90 days warranty. Shpg. wt., 5 lbs. CV-57 Net 49.95

ONLY **49⁹⁵**
No Money Down



NEW! "CARRI-ALL" KIT



Now a car-carrier you can adapt to fit your individual needs. Cross members can be of wood, metal, plywood, aluminum... one piece to cover the entire car roof, or bars fitted at different angles for the best support. You supply the crossmembers best able to fit your job. For passenger cars, station wagons, trucks. 6 position dial setting for exact adjustment to fit all cars, including compacts. 4 snap on supports fit without drilling or suction cups. Shpg. wt., 5 lbs. ML-314 Net 4.49

Cordomatic DOG TENDA

Automatically Controls Your Dog's Freedom
6 47
Do away with outmoded chains and ropes, give your dog a larger area of freedom with no tangling or binding. This new Dog Tenda extends or retracts automatically with your pet's movement. Rotates 360° both horizontally and vertically. 15 ft. nylon covered flexible steel cable allows 30 ft. of running room and a roving area of over 700 sq. ft. Feather light tension with freely rotating snap bolt fits any dog collar. Complete with all mounting hardware for both wall and inground mounting. Shpg. wt., 3 1/2 lbs. HD-660 Net 6.47

NEW! ASTRO-LITE EMERGENCY LIGHT TURNS ITSELF ON WHEN ELECTRICITY FAILS

13³³

A Must For Every Home, Office & Factory—This new development in emergency lighting offers protection in case of electrical failure, windstorm, floods, hurricanes etc. The Astro-Lite turns itself on automatically when power fails. Keep it ready as an emergency light or use it continuously as a night light. Ruggedly constructed, the Astro-Lite utilizes a heavy duty replaceable bulb and lantern type battery that will burn constantly for 25 hours and has a shelf life of 3 years. Decorator designed to provide an attractive wall fixture, the Astro-Lite may be employed as a free standing unit or easily wall mounted. Measures only 6 1/2x8". Shpg. wt., 5 lbs. ML-304 Net 13.33




EXPANSION LASH-TITE

1⁹⁹

- Powerful Lashing Device For All Loads
- Eliminates need for Ropes & Lashing Straps
- Stretches Up to Twice Its Length
- Eight Tentacles For Maximum Security

This "Octopus" type device lashes down any load, safely and securely in only a few minutes. The eight strands of powerful high tensile rubber expansion cords, covered with weatherproof fabric, eliminate any need for lashing straps or other tie down ropes. Each cord will stretch up to twice its 30" length and has a rugged steel spring fastened to its end, plastic coated to provide a positive, cushioned grip. AA-62 Net 1.99



7⁵⁹

BASKET CARRIER

BASKET CARRIER—Take advantage of the low, low price. Five sturdy steel slats; all metal parts finished in baked-on auto enamel. Top quality web straps and gutter hooks. Four heavy-duty suction cups. Easy-to-assemble. 37 1/2x42x6". Shpg. wt., 20 lbs. ML-214 Net 7.59

NEW! PRUNING SAW

1 97
Remarkable new blade development for all fast pruning-trimming-wood sawing. Fine Sheffield steel blade combined with heavy duty hacksaw frame. The ideal tool for pruning-cutting green or dried logs-rough or heavy lumber. Perfect for campers-foresters-public utilities, etc. Cuts three times faster than ordinary saws. Shpg. wt., 2 lbs. HD-454 Net 1.97
HD-453 Blade only, fits all 12" Hack saws Net .83
HD-211 Heavy Duty Hack saw Net 1.35

"SHEAR MAGIC" POCKET PRUNER

1 12
• Double Compound Action
• High Quality Tool Steel
Tremendous power—cuts like magic. Double compound leverage action gives maximum cutting power with minimum effort. Hardened and tempered tool steel blades. Bevel ground and polished for keenest cutting edge. Blades satin finished—handles chrome finished. Positive action "return-spring". Slipping lock. Shpg. wt. 1 lb. HD-719 Net 1.12

FIRST AID KIT

220

Includes First Aid Booklet
For Cars—Trucks—Boats—Homes
The perfect first aid kit for the car—boat—camp—and home. Contains all the essential first aid needs. 1 Adhesive Tape—3 way, 3/8, 5/8, 1"x1 yd. each; 10 Plastic Strips; 1 Tincture of Merthiolate, 1/4 oz. (Lily); 1 Unguentine Antiseptic; 1 Roll Gauze Bandage, USP 1"x6 yards; 1 Scissors; 1 Roll Gauze Bandage, USP 2"x6 yards; 2 Paper Cups; 2 Gauze Sponges, USP 4x4"—16 ply; 1 Ampoule Ammonia Inhalant; 2 Gauze Compresses, USP 3x3"—12 ply; 1 Absorbent Cotton, 1/4 oz.—USP; 1 First Aid Booklet. Shpg. wt., 1 lb. AA-60 Net 2.20



BAR CARRIER

3 70
BAR CARRIER—A quality product at a big saving! Rigid 1-piece construction with attractive, baked-on enamel finish. Suction cups assure positive grip. Completely assembled. 42" long. Shpg. wt., 5 lbs. ML-213 Net 3.70



Amazing New CHEMTRON CAR SHAMPOO

Contains Carnauba Wax
Non-Strak—No Wiping Needed— you'll be amazed with the results of this new wash and wax car shampoo. Removes grease, road film, insect stains, etc. Special formula contains Carnauba-Wax. Provides your car with an amazing show-room finish. Contains 16 ozs. Shpg. wt., 1 1/2 lbs. AA-133 Net .88



NEW! SPRINKLE MINDER

4 20
• Take the guess work out of watering!
• Save Plants—Save Time—Save Water—Save Money
The Sprinkle Minder tells you when to water—when not to water. Tells when roots are dry—Prevents over watering—Tells when water is wasted—Prevents washing away of nutrients—Tells depth of water penetration. Can be used all year round. Outdoors or indoors to instantly indicate the amount of moisture in lawn, flower bed, shrubbery, trees, hotbeds, cold frames, window boxes, flower pots. Works on a long proven electro-chemical principle. Requires no batteries or maintenance. Works instantly and automatically. Simple instructions included. Shpg. wt., 1/2 lb. HO-718 Net 4.20



SUMMER CLEARANCE HOBBY SALE - SAVE up to 38%

Draft-a-Plan Kit

- Learn Use of Professional Drafting Tools
- Complete, Easy-to-Follow Instructions
- Includes Electric Drafting Desk



Make exciting drafting plans and blueprints without chemicals. Learn how to make your own scale drawings plus basic lettering, sketches, perspective drawings and layouts. "Drafting is Fun" book and design project sheets educate in each drafting instrument. Kit includes tracing and blueprint paper, drafting pencils, pencil sharpener, T square, triangles, French curve, scale, protractor, slide rule with instructions, electric drafting desk with lamp.
F-817 Shpg. wt., 6 lbs. Net 4.59

LIMITED QUANTITY **4 59**

GILBERT GILBERT CHEMISTRY EXPERIMENT LAB

• Perform Hundreds of Exciting Experiments

- Complete Assortment of Chemicals
- Includes New Molecular Model Building Kit
- Sturdy Steel Storage Cabinet



4 88
CLOSEOUT PRICE

Fully safety-tested and approved (this worthwhile Chemistry Experiment Lab has been designed by leading Science Teachers. Furnishes the budding young scientist with the equipment and know how for such exciting experiments as: making Liquid Gold, changing White Cloth to Red, making Liquid Rock, the White Smoke Mystery and many more. Also included are interesting Crime Detection experiments and a new Molecular Model Building Kit, containing colored spheres representing atoms which joined together make and illustrate various chemical compounds. Supplied with a large assortment of chemicals in a fold-out steel cabinet. Size: 9 1/2" x 13 1/4" x 4 1/2" D. Shpg. wt., 9 lbs. Net 4.88
KT-183

GILBERT PHYSICS SET

• Professional Laboratory Equipment



- Professional Laboratory Equipment
- Provides Real Stimulus for Serious Study
- Answers Questions about Everyday Physics
- Hours of Endless Fun

7 88
CLEARANCE SALE

A popular physics lab set, chock-full of laboratory equipment offering fascinating experiments in solar heat, light bending, optics, fluid dynamics, and scores of others. The equipment includes professional radiometer, parabolic reflector, polarizing filters, optical bench beaker, illuminator, thermometer, ring stand and many related pieces. Colorful instruction manual teaches basic principles of physics and gives step-by-step procedure. Shpg. wt., 5 lbs. Net 7.88
KT-190

Custom-Styling



Design your own boats, auto, planes and space vehicles. Stimulates interest in designing, encourages imaginative development of line, form, perception and color. Kit includes directions, portfolio, interchangeable component and design sheets, drawing paper, color pencils with sharpener, eraser, electric drawing desk with lamp.
F-818 Shpg. wt., 5 lbs. Net 3.69

3 69

Draw-a-Cartoon




Provides hours of exciting fun drawing colorful comic strip or story characters. Cartooning sheets with dozens of funny heads, eyes, ears, noses and costumes, are reversible and interchangeable—draw and color any cartoon, any way. Kit contains directions, character and story idea sheets, portfolio, drawing paper, color pencils and sharpener, eraser, electric cartooning desk with lamp. For 5-year olds and up.
F-819 Shpg. wt., 5 lbs. Net 3.69

3 69

TRANSISTORIZED PORTABLE BIKE RADIO

4 Transistor Radio Plus Horn Plus Light in One Streamlined Unit



- Built-In Speaker
- Telescoping Antenna
- Sturdy Clip-on Mount


12 95
CLOSEOUT PRICE

A sensitive 4 transistor radio, powerful horn plus a light, all in one streamlined unit. The perfect accessory for that new bike or for that matter your Golf-Cart, Baby Carriage or Boat. A sturdy handle bar clip-fitting allows you to attach this unit virtually anywhere. Radio covers full AM band from 530 to 1605 KC and is equipped with volume control, station selector and built-in speaker and earphone jack. In addition a detachable telescopic antenna is provided. Horn is activated by a simple to use push-button, while an On-Off slide switch controls light. Supplied with earphone for private listening plus 9V transistor battery for radio and standard D cell for horn and light. Shpg. wt., 3 lbs. Net 12.95
FS-122L

ELECTRONIC POWERMEG

TRANSISTORIZED PORTABLE MEGAPHONE

- RANGE 100-300 FEET
- LIGHTWEIGHT COMPACT
- COACHES • CHEERLEADERS • SCOUTING • HIKING • BOATING



5 99
CLOSEOUT PRICE

Carries the voice 100-300 feet, loud and clear. Can be used at outdoor gatherings, picnics, song fests, square dances, hikes, camping trips—anywhere there is a need for a small portable P.A. system. A valuable aid for the safe conducting of waterfront activities at camps and resorts, or for close range boat-to-boat communications. Just press button and talk into microphone (included). Volume control regulates loudness. Requires 4 standard 1.5 volt flashlight cells. With shoulder strap. Shpg. wt., 4 lbs. Net 5.99
PA-275
BA-274 1.5V Battery (4 required) Net ea. .16

"CHAMPION" 6-CAR FREIGHT TRAIN SET



Value of components if purchased separately **48.32**

- Authentic Scale Models • Complete with Tracks
- Operating Hopper Car—Lighted Locomotive

Top notch quality working valve gear and electric head light. Set consists of 4-6-2 lighted pacific type steam locomotive and tender, 1 box car, 1 operating hopper car which unloads by remote control, 1 stock car, 1 refrigerator car, 1 flat car w/load skids and girder, 1 9 wheel caboose, 11 sections 18" radius curved track, 1 curved terminal track, 1 section 9" straight track, 1 straight re-railer track for a 45"x36" oval. Complete with 1 NMRA portable, automatic uncoupling ramp.
AP-77 Shpg. wt., 7 lbs. Net 15.75

15 75
CLEARANCE SALE

"SUNSHINE LIMITED"



Value of components if purchased separately **38.72**

STREAMLINE DIESEL PASSENGER TRAIN

- Double GM "A" & "B" Diesel Units
- Coaches-Cars Dual Lighted • Complete with Tracks

"A" type diesel locomotive with front headlight, followed by a non-powered "B" type diesel. Other cars are: 1 streamline combine, 2 streamline coaches, and 1 streamline observation. All are dual lighted. Also included are 11 18" radius curved track, 1 curved terminal track, 1 9" straight track, 1 straight re-railer track. Makes oval of 45x36". 1 NMRA portable, automatic uncoupling ramp.
AP-78 Shpg. wt., 7 lbs. Net 14.40

LIMITED QUANTITY **14 40**



"Pace Setter" 7-CAR DIESEL FREIGHT TRAIN

Complete with Tracks • Lighted Twin Diesel Locomotives • Operating Hopper Car
Powered by a lighted F9 "A" type Diesel locomotive followed by a matching non-powered "A" Diesel. Balance of set includes: 1 gondola w/calvert pipe load, 1 chemical tank car, 1 box car, 1 operating hopper car, 1 8 wheel caboose, plus 11 curved track, 1 curved terminal, 1 9" straight track and 1 straight re-railer. 1 NMRA portable automatic uncoupling ramp.
AP-67 Shpg. wt., 6 lbs. Net 11.23

SAVE 1/3 **11 23**

Value of components if purchased separately **32.33**



"BOOSTER SPECIAL"

- 4 Freight Cars • Complete With Track

Authentic 0-4-0 NYC steam locomotive. The freight train consists of 1 flat car w/snap on load skids and girder, 1 refrigerator car, 1 gondola car, 1-4 wheel caboose, plus 11 sections of straight track, and 1 18" radius curved terminal track. Makes a 36 inch circle. Shpg. wt., 4 lbs. Net 6.75
AP-68

6 75
CLOSEOUT PRICE

Value of components purchased separately **22.53**

HO MODEL RAILROAD POWER SUPPLY

- Heavy-Duty Transformer with Full-Wave Selenium Rectifier
- Operates up to 2 HO Train Sets



QUANTITY LIMITED **4 50**

Operates either two complete train sets or one set with lighted cars and smoke or sound features. Heavy-duty transformer and full protection circuit breaker. 16 volts A.C., 12 volts D.C. output at 1.5 amps. Operates on 115V 60 cycle A.C. Shpg. wt., 3 1/2 lbs. Net 4.50
AP-79



AMERICAN FLYER CORVETTE RACE

- Sets Up on Table Or Floor • Total of 67 Pieces

Each car is controlled by a separate pedal-type Accelerator and has its own DC electric motor. Scale model Red Corvette and Ivory Corvette include car customizing kit of decals, insignia, head and tail light reflectors, chrome bumper strips, race numbers, motor cowling covers, 24 pieces (20 curved, 4 straight E-Z Faster Roadway sections, 20 plastic fence set, 2 speed controls.) 1/4 amp D.C. output. Motor pack power unit. Shpg. wt., 9 lbs. Net 14.40
AP-71

CLEARANCE SALE **14 40**

ERECTOR ROCKET LAUNCHER SET

- Includes Powerful Electric Motor
- Supplied With Rugged Steel Chest
- All-Steel Parts

Build Toys That Actually Work



Complete set consists of a true-to-life rocket launcher, that actually raises, while radar scans the sky. With the press of a button, a rocket streaks off the launching track and into space. And, this fascinating model is only one of the hundreds possible to build with this excellent construction set. Set includes a powerful electric motor with forward and reverse gear shift and power take-offs. Size 16 1/4" x 10 1/4" x 3 1/4" H. Net 8.99
KT-182 Shpg. wt., 10 lbs.

LIMITED QUANTITY **8 99**



AMERICAN FLYER 1940 FORD COUPE

Completely assembled, ready to operate. Includes decal kit. D.C. motor. 5 1/4" long. Net 3.36
AP-85 Shpg. wt., 1/2 lb.

(B) REVERSING SWITCH. Makes your model cars go forward or back. Shpg. wt., 1/2 lb. Net 1.96
AP-86



ELECTRICAL ENGINEERING SET

- Safe, Fascinating Experiments in Electrical Phenomena
- Perfect Introduction to Electricity
- Fun with Lights, Buzzers, Magnetism, Telegraph System, and Much More

This complete set offers dozens of fascinating electrical hook-ups. The exciting experiments include: a telegraph code practice set; conductance tests of various metals; miner's lamp; lanterns; electric spider; electromotive powered car; DC motor; batteries; and much more. Shpg. wt., 7 lbs. Net 5.89
KT-193

5 89
CLOSEOUT PRICE

SUMMERTIME..AND THE LIVING COULD BE EASY

KING-SIZE STEEL "STOR-SHED"



- Sturdy All-Steel Construction
- Weatherproof, Fireproof, Rustproof
- Room Enough for Your Garden and Lawn Equipment and Tools Too!

All-steel utility storage shed holds everything including the kitchen sink. Completely weatherproof; undercoated to prevent rust. Sloped roof with rain gutter for quick, easy run-off of rain water. All-steel floor. Locks securely and safely, keys included. Safely handle inside prevents "lock-ins". Pegboard on back and side walls for easy hanging of tools. Easy-to-open hinged doors open practically an entire end for walk-in ease. Prime coat of green paint, may be repainted for your own taste; white doors. Ventilated for air circulation. Complete with nuts, bolts and instructions for assembly. Shipped F.O.B. Altoona, Pa. warehouse. No C.O.D.

As low as
79⁵⁰
No Money Down

ML-308WX 6'x6'x4'D: shpg. wt., 220 lbs. Net 79.50
ML-309WX 6'x6'x6'D: shpg. wt., 275 lbs. Net 99.95

"STOR-ALL" LAWN LOCKER




22⁸⁸
No Money Down

Sturdy steel construction including steel floor. Roof folds back on piano-type hinge for easy access. . . . doors snap shut with spring latch. Provides 24 cu. ft. of clean-lined storage space for hundreds of uses—storing, protecting and concealing. Green prime coat may be repainted if you wish. Overall 4'W, 2'D, 3'H. Complete instructions for easy assembly. Shpg. wt., 60 lbs. Net 22.88
ML-310WX

- For Toys, Lawn and Pool Equipment, Trash Cans, etc.
- Heavy-Duty Steel Construction

ELECTRIC POWER PLANT



145⁵⁰ NO MONEY DOWN
1000 WATT

- 3-H.P. Engine • 90-Day Parts Warranty • Regulating Governor • Easy-To-Use Rope Starter • 1000 Watts Continuous • 1250 Watts Intermittent

A compact, rugged direct coupled power plant. Supplies 115 V.A.C., 60 cycles at 1000 watts continuous, 1250 watts intermittent duty. The engine is a 3 h.p., 4 cycle, air cooled Briggs & Stratton. Operates on regular gasoline. Uses standard weight motor oils. Recoil manual start. Drip-proof, continuous duty, self excited, 2 pole, 3600 RPM generator. Features a pre-lubricated, sealed, ball-bearing commutator, mica insulated, 3 cycle maximum frequency variation, $\pm 5\%$ voltage regulation. Gas consumption at 1000 watts; 0.2 gal per hr.; at 1250 watts, 0.39 gal. per hr. Includes instructions, parts lists and 90 day parts warranty. Made in U.S.A. Shpg. wt., 70 lbs. VIA EXPRESS ONLY. ML-266WX Net 145.50

1750/2000 WATT POWER PLANT: Similar to above with 4 h.p., 4 cycle engine. Shpg. wt., 110 lbs. Net 194.50
ML-267WX

2500/3000 WATT POWER PLANT: Similar to above with 5 1/2 h.p., 4 cycle engine. Shpg. wt., 156 lbs. Net 279.95
ML-268WX

HOME FIRE ALARM



- Loud Clear Buzzer Alarm
- Input for Adding Multiple Detector Switches
- Provides Protection Everywhere in the Home

4⁹⁵

Set up a fire alarm system in your home now. This home fire alarm alerts you and your family before the flames can spread. The Basic Unit trips at 145° with a clear, loud buzzer alarm. Measures 4 1/2 x 5 1/4 x 2 1/4". Has input for adding as many detector switches as needed to protect your entire house. Hang-up hole in rear for easy mounting. Oblong slot on bottom for testing of unit. With AC line cord and plug. For 110-120V. AC. SP-280 Basic Unit. Shpg. wt., 2 lbs. Net 4.95

135° DETECTOR SWITCH. Shpg. wt., 3 oz. Net 1.95
EL-103

200° DETECTOR SWITCH. Shpg. wt., 3 oz. Net 1.95
EL-104

TEST BUTTON. Shpg. wt., 3 oz. Net .16
EL-30

18 Gauge, Twisted Pair Control Wire. Shpg. wt., 3 lbs. per 100-ft. Net 1.65
WR-122 100-ft.

WR-123 500-ft. Net 7.50

STEEL STORAGE UNITS


5.95 For 4 Shelves
30"x12"x60"

- Triple Bent Shelves
- Heavy Angle Posts
- Shelves Adjustable on 1 1/2" Centers
- Braced on Back & Sides

For stores, offices, garages, basements, pantries, closets—just what you need to solve your storage problems, you'll find dozens of uses for these rugged racks. And now, Lafayette offers them at a bargain price. Available in two sizes to fit virtually anywhere. 30Wx12Dx60"H with 4 shelves, or 36Wx12Dx72"H with 5 shelves. Corner post and all edges are rounded and snag proof with back and side braces providing added strength and rigidity. Gray enamel finish. Shipped unassembled with all necessary hardware for fast easy assembly. Size 12x30x60". Shpg. wt., 25 lbs.

ML-306WX Net 5.95
Size 12x36x72" Shpg. wt. 33 lbs.

ML-305WX Net 6.89



RUGGED 24-IN. ROTARY RIDER MOWER



As low as **99⁹⁵** No Money Down

- Full 24" Cut
 - 4-Wheel Safety and Stability
 - 3 H.P. Engine with Recoil Starter
- The modern way to do a man-size mowing job. Features 4 wheels with semi-pneumatic tires for greater safety and stability; fully enclosed transmission; 3 H.P., 4 cycle Briggs & Stratton engine with easy-spin recoil starter. 2 speeds, forward and reverse, with close tolerance guarded chain drive. Full 24" rotary cut; cutting height adjustable from 1 1/2" to 2 1/2". Sturdy channel frame; comfortable bucket seat. Shipped F.O.B. Newark, Ohio. No C.O.D. Shpg. wt., 142 lbs. Net 99.95
AP-91WX

DELUXE 24-IN. ROTARY. Deluxe version of above. 3 1/2 H.P., 4 cycle Tecumseh engine. Features blade clutch—makes it possible to ride mower without blade turning. . . . can be "locked in". Shipped F.O.B. Newark, Ohio. No C.O.D. Shpg. wt., 169 lbs. Net 125.95
AP-92WX

"GYRO-VAC" DELUXE ROTARY POWER MOWER

- 20" Steel Rotary Trimmer
- 3 H.P. 4-Cycle Aluminum Engine with Lo-Tone Muffler
- Removable All-Metal Grass Catcher

AS LOW AS **89⁹⁵**
NO MONEY DOWN

With Cyclonic-Vacuum Cleaning Action

No more raking or sweeping, cuts wet or dry lawns. New "silent winding" impulse starter. 14-gauge, reinforced, stamped steel chassis. One knob control for start, run and stop. Chrome-plated tubular steel handle. One-piece austenized alloy steel blade revolves above bottom edge of chassis. Cutting height adjusts from 1 1/2" to 3". Includes hinged grass catcher; deflector plate attachment. Shipped F.O.B. Chicago, Ill. No C.O.D. Shpg. wt., 77 lbs. Net 89.95
AP-93WX

"GYRO-VAC" SELF-PROPELLED ROTARY POWER MOTOR. Better version of above. Combination self-propelled and push-type. Transmission protected against overload. Cutting height adjusts from 1 1/2" to 2 3/4". Shipped F.O.B. Chicago, Ill. No C.O.D. Shpg. wt., 80 lbs. Net 99.88
AP-94WX

PLASTIC GAS CANS. Net 1.59
AA-121 1-Gal. Size Net 2.69
AA-122 3-Gal. Size

HEAVY-DUTY SUMP PUMP

- Rust-Proof Cast Aluminum Base
- Rust-Proof Seamless Aluminum Column
- 3,920 Gallons-per-Hour to a 10-ft. Head

NO MONEY DOWN **37⁵⁰**

A rugged automatic electric pump with a dependable 1/2 HP motor with safety-designed overload protector. Features a plastic float, non-corrosive in any water; extra large separate screen to prevent clogging; vertical 1 1/4" discharge that eliminates base elbow. Lifetime guarantee on all moving parts (1-yr. guarantee on electrical components). Oilite base bearing for long life. Individual pressure plate to assure consistent water flow. Designed to operate at top performance:

| Gallons Per Hour | Discharge Height |
|------------------|------------------|
| 3,920 | 10-ft. |
| 3,215 | 15-ft. |
| 1,600 | 20-ft. |
| 540 | 25-ft. |

ML-297WX Shpg. wt. 25 lbs. Net 37.50

FASCO 200 CFM BLOWER

- 3,000 RPM — 200 Cubic Feet Per Minute
- 3 1/4" Screened Intake Diam. — 2 1/2" x 2 1/2" Output
- Flange with Mounting Holes

Efficient, quiet, dependable and economical. Usable in many applications—air distribution in confined areas, exhausting fumes and gas, etc. Suitable for ventilation equipment in home, marine and commercial use. Welded pressed steel housing. Shaded-type motor for efficient, quiet operation. Moves 200 cubic feet of air per minute. Mounting flange, 5 1/4 x 4". 2-ft. AC line cord and plug. 110V, 60 cycles; 1.4 amp. SP-279 Shpg. wt., 7 lbs. Net 9.95



9⁹⁵

TRAVELER UMBRELLA TENT



39⁵⁸
No Money Down

FEATURES ALUMINUM EXTERIOR FRAME—EASY TO CARRY, SETS UP FAST, LENGTHENS TENT LIFE. LEAVES INTERIOR UNOBSERVED.

- Nylon Screened Window and Zipper Door
- Water-Resistant, Mildew-Resistant Fabric
- Sewed-in Floor

Easy to erect, the exterior spring steel framework enables tent to be set up in less than 10 minutes. Leaves the interior obstruction-free. Top of 6.74 oz. and sides of 6 oz. forest green water and mildew resistant drill. Sewed-in floor, nylon screened window, nylon screened zipper door, hardwood stakes, 9x9-ft. base, 6 1/2-ft. center height, eaves 5 1/2" high and 28" square. Sleeps 2-3 people and capacity can almost be doubled by using double-decker cots. (Awning poles not included). SE-18WX Shpg. wt., 45 lbs. Net 39.58

TWO-MAN MOUNTAIN TENT

- Nylon Screened Plus Canvas Front

Hardwood "A" frame at front and exterior rear pole eliminate interior poles and provides full doorway access. Nylon screened insect-proof door with full-length front zipper and bottom zippers. Sewed-in floor; extension end. Rugged 6 oz. forest green, water and mildew resistant drill. 7'3" long, 5' wide, 3 1/2" high. With jointed metal poles, hardwood stakes, guy ropes. SE-20W Shpg. wt., 14 lbs. Net 15.88

15⁸⁸

AIR-VENT CAMPER

Features nylon screened ventilator on top for fresh air even during a rain. Insect-proof zipper door with two 10x15" nylon screened windows with storm flaps. Sewed-in floor. Exterior steel framework leaves interior obstruction-free. Hardwood stakes included but tent need not be staked down under normal conditions. 6 oz. forest green, water and mildew resistant drill. 7x7-ft. base, 5 1/2-ft. center height. Ideal for 2-man camping. Shpg. wt., 26 lbs. Net 29.95
SE-19WX

5 LB. DN-200 FILLED SLEEPING BAG



As Low As **9⁷⁷**

- Double Pull Zipper—2 Bags Zip Together to Form One Double Bag

Filled with 5 lbs. of DN-200 (70% rayon, 12% polyester, 7% acetate 6% cotton, 5% nylon)—the all-new filling which provides excellent insulation, is lightweight, resilient, non-irritating, mat resistant and comfortable. Water repellent forest green outer cover and hood of rugged duck soft flannel lining. Double air mattress pocket. 100" double pull zipper, weatherstripped. Cut size 36x80"; approx. finished size 33x75". Shpg. wt., 9 1/2 lbs. SE-16W Net 14.55

DACRON-FILLED SLEEPING BAG. Similar to SE-16 above but filled with 3 lbs. of Dacron Fiberfill—keeps shape, won't absorb moisture. Snap-on hood built-in tabs for attaching removable flannel lining. Double pull zipper. Cut size 36x80"; approx. finished size 33x75". Shpg. wt., 8 lbs. SE-15W Net 19.44


ECONOMY SLEEPING BAG. 3-lbs. DN-200 filling. Water repellent olive green top cover, with vinyl coated fabric bottom and hood; colorful lining. Heavy-duty 32" zipper, weatherstripped for warmth. Cut size 36x80"; approx. finished size 33x75". Shpg. wt., 7 lbs. SE-17W Net 9.77

GRILLMASTER MOTORIZED "RANCH WAGON"

- Motor, Spit, Meat Forks
- Half Hood; Full-View Glass Window

29⁹⁵ No Money Down

Motorized spit simplifies your barbecuing. Large 25 x 15" grill adjusts for best cooking height. Full view, heat resistant glass window; heat indicator; draft regulator. Two handy pull-out front shelves; convenient side shelf; roomy storage area on bottom. Spit has 2 adjustable meat forks. Removable firebox. 6" rubber tired wheels. Overall 45 x 18 x 46" high. U.L. approved motor. 110-120V. AC. Shpg. wt., 52 lbs. Net 29.95
AP-90WX



DELRON SUBMERSIBLE PUMP

- Will Not Corrode or Rust
- Hermetically Sealed Motor
- For Circulating and Dispensing Water

12⁷⁵

It's the all-new Delron aluminum pump for underwater use. Guaranteed not to corrode or rust; hermetically sealed motor. Circulates and dispenses water and mild acid solutions for use in fountains, beverage dispensers, aquariums, photo developing, air conditioning, etc. Gallons per hour delivery: 240 @ 1 ft.; 180 @ 3 ft.; 125 @ 5 ft.; shut off @ 12 ft. Outlet 3/8"; inlet 1/2" pipe O.D.; height 4 1/2"; depth 4 1/4". 6 ft. safety cord. 115 V, 60 cy. AC, 49 watts load; .87 amps load. Shpg. wt., 3 1/4 lbs. Net 12.75
ML-312



WATERFALL KIT

Enchanting waterfall of cascading water constantly recirculated by electric pump. Gallons per hour delivery: 180 @ 1 ft.; 140 @ 3 ft.; 100 @ 5 ft.; shut off @ 10 ft. Outlet 3/4"; inlet 1/2" pipe O. D. Load: amps .65; watts 43. No concrete needed; complete with instructions. Kit consists of pump, 8-ft. plastic hose, 7-ft. sealing poly. pump filter. Shpg. wt., 4 lbs. Net 15.88
ML-311

DRY CHEMICAL FIRE EXTINGUISHER

The Most Efficient Fire Extinguisher Ever Made!

- 6 B:C—Highest U.L. Rating for ITS SIZE
- Exceeds I.C.C. & U.S. Coast Guard Requirements
- Safety Zone Pressure Gauge
- 12 Times as Effective as 1 1/2 Quart Carbon Tetrachloride Units
- Twice as Effective as a CO₂ Extinguishers of Comparable Size

The most powerful, efficient fire extinguisher of its size. This new Perfection dry chemical extinguisher utilizing a specially developed non-toxic, non-corrosive dry chemical powder is rated 6 B:C by Underwriters' Laboratories. . . . A rating usually found only in 4 lb. and 5 lb. units. Other features include: Extremely fast rate of damp in spraying chemical, non-clogging valve insures perfect closure without leaking, Safety Zone Pressure Gauge shows instantly whether extinguisher is ready for use . . . reveals tampering or unreported use, plus a forged brass valve body equipped with vehicle mounting bracket locking clamp. HD-987 Shpg. wt., 7 lbs. Net 11.33




11³³

DD-IT-YOURSELF RECHARGE KIT. Contains 2 1/4 lbs. of Dry-Kern-S dry chemical powder. Shpg. wt., 5 lbs. Net 1.47
HD-988

LAFAYETTE HAS MORE VALUES FOR EVERYONE


NEW LAFAYETTE PHOTO-ELECTRONIC RELAY SYSTEM

Includes Photo Cell Receiver Plus Electronically Operated Relay Plus Exciter Lamp
Efficient 2-Unit, 3-Element Design



- Complete — Ready to Operate — NOT A KIT!
- Operates Bells, Buzzers and Counters
- The Perfect "Guard for Homes, Stores and Industry"
- Removable Infra-Red Filter For "Invisible-Light" Operation

1895
Per Set




The Lafayette Photo-Electronic Relay is your key to an inexpensive indoor warning or counting system. Consisting of a rugged exciter and relay unit and operating on 110-120V AC, it can be connected to signal persons entering a room, counting people or merchandise or function as an effective alarm system to warn of intruders. Effective up to 23 feet (without filter, 15 to 18 feet with filter), relay unit has a convenient variable sensitivity control and switch for intermittent alarm operation. Exciter has removable infrared filter. Mounts easily across area to be supervised. Metal case. Size: 4 1/4"x3Wx4 1/2"D. PC-40 Shpg. wt., 6 lbs. Net 18.95

ACCESSORIES FOR ABOVE

| | |
|---|----------|
| EL-85 Electric Bell, 110V AC. Shpg. wt., 2 oz. | Net 1.49 |
| EL-86 Electric Buzzer, 110V AC. Shpg. wt., 10 oz. | Net 1.29 |
| F-553 6-Digit Electric Counter. Shpg. wt., 1 1/2 lbs. | Net 9.95 |

NEW HIGH SPEED 3500 RPM MOTOR

- Dual Shaft • Oilite Bearings



169

Ultra-quiet, durable high speed AC motor for driving fans, pumps, etc.—hundreds of applications. Features twin motor cooling fans for continuous operation; dual shaft, 3/8" diameter, 3/4" long each side; oilite bearings give long life lubrication; 12" color coded trimmed leads. For 115 volts 60 cycle AC. Size: 2 3/4"x2 1/4"x2 1/4"H. Shpg. wt., 2 lbs. Net 1.69

LAFAYETTE R/C TRANSMITTER KIT

MADE IN U.S.A.



WITH .005% TOLERANCE CRYSTAL TWICE AS GOOD AS FCC REQUIRES! OVER 1 MILE LINE-OF-SIGHT TRANSMISSION! EXCEPTIONAL STABILITY FOR FOOL-PROOF CONTROL OF MODEL PLANES, BOATS AND CARS.

You'll marvel at the neatness, simplicity and dependability of Lafayette's RC Citizens Band Transmitter. Crystal controlled with a .005% tolerance crystal for extra frequency stability; exceeds FCC tolerance requirements. Fits comfortably in the palm of your hand, yet is unaffected by hand capacitance or motion. Has new attractive wide scale meter for visually tuning transmitter. Wide, non-critical tuning for optimum foolproof performance. Tuning for proper output and antenna loading easily accessible. Complete with telescoping antenna, meter, tube, crystal, alignment tool, all parts and easy step-by-step instructions. FCC license application forms enclosed. Size 10x4x2 1/2". Shpg. wt., 5 lbs. Net 17.25


KT-127A less batteries Net 17.25
BA-157 Burgess No. 2 battery Net .13
BA-1 BATTERY (2 needed) 1.59 ea.

FALLOUT DETECTION METER Made by VICTOREEN

Largest Maker of Civil Defense Instruments

- Large Easy-to-Read Meter
- Simple One-Switch Operation
- Rugged Metal All-Weather Construction
- Includes Full Survival & Operating Instructions

4995



NO
MONEY
DOWN

Designed especially for use by private citizens, this is a civilian model of the official instrument used by federal agencies. Enclosed in a rugged steel case, this instrument has been designed and constructed to withstand extreme shock and immersion. Transistorized circuit requires virtually no maintenance and operates from two easily obtainable flashlight batteries. Extremely simple to use and understand—a child can be taught to operate it. This instrument is an absolute necessity for schools, fallout shelters, offices and plants. Includes manual with full survival and operating instructions. TE-667 Shpg. wt., 5 lbs. Net 49.95
Replacement Batteries (2 required) 1.5 volts Net ea. .13

BENDIX RADIATION MEASUREMENT SET

Certified by Bendix to Meet or Exceed Office of Civil Defense Mobilization Specifications

- Simple To Use • Direct Reading • Pocket Size
- Rugged—Reliable—Portable

1895 Each
1795 Each Lots of 3




Set Includes:

Bendix CD V-736 Ratemeter (0-120 r/hr)—Indicates precisely how much radiation is present at a given moment
Bendix CD V-746 Dosimeter (0-600 r/hr)—Records total radiation exposure
Bendix VD V-756 Charger—Charges and retests the Ratemeter and Dosimeter to zero for reading 10 minutes after exposure should the first reading be below 10 r/hr. The Ratemeter may also be used in industry for determining protection in any isotope program. The Dosimeter records total radiation exposure and is calibrated from 0-600 roentgens.
TE-668 Complete Set. Shpg. wt., 5 lbs. Net 19.95
TE-668 Pocket Dosimeter. Shpg. wt., 1 lb. Net 11.25
TE-669 Pocket Ratemeter. Shpg. wt., 1 lb. Net 11.25

Fishing Gear CLOSE OUT SALE — Compare!

LIMITED QUANTITIES



(A) SPECIAL TUBULAR FIBREGLASS SPINNING ROD

- GENUINE TUBULAR SUPER GLASS ROD • STANDS ROUGHEST ACTION-NEEDS MINIMUM CARE • SOLID-COMFORTABLE-NATURAL CORK GRIP
- SINGLE WIRE-NON FOULING GUIDES

A first quality tubular (hollow) fiberglass spinning rod—plenty of power, action and eye appeal. All the features of rods selling far above Lafayette's price. Solid-comfortable-natural cork handle with anodized aluminum reel retaining rings. Holds reel solidly and securely. Extra large guides with neat, even nylon wrapping. Sealed against moisture. Long, strong extra deep joining ferrule—precisely fitted. Guides are hard-rust resistant—and properly spaced. Braced tip-top guide. Entire rod finished in hard, durable, black lacquer. Popular 2 piece, 5 foot length. Shpg. wt., 1 1/2 lbs. Net 2.59

(B) TUBULAR FIBREGLASS SPIN CAST ROD

• 5 1/2 FT. MEDIUM-LIGHT ACTION • POSITIVE LOCK REEL SEAT
Finest 2 piece, hollow fiberglass, medium-light action spin cast rod. Five inch web, shaped cork grip on a die cast aluminum offset handle. Positive, threaded ring, locking reel seat. Designed for closed face spin cast reels! Chrome plated, stainless steel guides and braced, offset tip-top. Chromed, stainless buttplate. Extra deep, precisely fitted ferrules. Colorful, sealed, nylon wrappings. Fine action with plenty of backbone. Casts flies, streamers, bugs and poppers. Shpg. wt., 1 1/2 lbs. Net 2.99

(C) TUBULAR FIBREGLASS "7 SEAS" SPINNING ROD

• FOR FRESH AND SALT WATER SPINNING!
• ACTUAL WEIGHT ONLY 5 OZS!
• COMPARE TO RODS SELLING FOR TWICE AS MUCH
All the extra power you need to land the "big ones"—in fresh or salt water. Hollow glass construction for that "live" action—plus "backbone" when you need it. 4" cork fore grips 6 1/2" cork butt with vinyl butt plate. Extra-large, non-fouling, diamond-hard guide. "Snake" design allows guides to flex with rod. Braced tip top of super-hardened, stainless steel. Fixed reel seat polished brass with chrome retaining collar and lock nut. Glossy black lacquered finish. Colorful, sealed nylon windings. 2 piece blade with extra deep ferrules. Overall length 6 1/2 ft. Superbly tapered—designed for maximum lure action-trouble free construction. Shpg. wt., 1 lb. Net 4.39



(D) SPECIAL SPINNING REEL

• GOLD ANODIZED SPOOL • NYLON BEVEL GEAR • ANTI-REVERSE LOCK
A fine, light spinning reel with all the features found in far more expensive reels. Strong-sturdy handsome appearance. Selective anti-reverse lock. Chrome plated pickup arm. Body of non-corroding, ebonized aluminum alloy. Housing and spool of gold anodized aluminum for maximum corrosion resistance. Noiseless, smooth running, nylon bevel gear. Handle is removable for storage. Holds 200 yds. of 4 lb. test line. Gear ratio of 3 to 1. Shpg. wt., 1 lb. Net 1.79

(G) NEW! "7 SEAS" SPIN REEL

• ALL THE FEATURES OF THE MOST EXPENSIVE REELS
The "greatest" for surf-casting, trolling, spinning or any salt water fishing. High pressure moulded of an aluminum-magnesium alloy, surface treated and anti-corrosion coated. Eliminates need for the usual care and cleaning associated with salt water gear. Unique planetary gear system crosswinds line for greater line capacity and the smoothest, longest casts you ever made! "Back-lash" is a thing of the past. Fully adjustable, positive drag action. Built right into the spool for smooth, constant tension. Full bail pickup of chromed bronze. Line guide of super hard chromium carbide. Torpedo handle, spring loaded, folds back for storage. Positive, finger tip anti-reverse control. All the features normally found in the most expensive reels. Actual weight 19 ozs. Shpg. wt., 2 lbs. Net 8.99

(H) "SPIN-STAR" SPINNING REEL

• Fresh Water or Light Salt Water • Aluminum Alloy Construction • Weighs only 11 oz.
All the features of nationally famous spinning reels costing dollars more. Full-bail pickup, specially hardened lineguide, die cast aluminum drive gear, brass pinion gear. Special spool design prevents line snag—crosswinds the line evenly. Aluminum alloy construction—light but strong. Anti-reverse lever. Designed for fresh water or light salt water fishing. All parts protected against rust and corrosion. Gear ratio: 3.5 to 1. Spool capacity: 200 yards 8-lb. monofilament line. Shpg. wt., 1 lb. Net 3.79

(I) THRIFT-BUY FLY REEL

• SINGLE-ACTION • ALUMINUM FRAME
Strong lightweight aluminum frame—perforated for fast line drying. The actual weight is only 3 1/2 oz.—our lightest reel. Counter-balanced handle, adjustable click. Quiet Action. Capacity: 50 yds. D line. Shpg. wt., 6 oz. Net 1.29

COLLAPSIBLE METAL FISH BAG

- Rustproof Live Bag
- Chainlink 1/2" Mesh

299

This king-size fish bag keeps fish alive and fresh. Armored to protect the big fish. Has convenient top and bottom spring doors. Collapsed flat for easy carrying and storing. 24" tall; 8" mouth, 14" max. diam. Shpg. wt., 1 1/2 lbs. Net 2.99



COMBINATION BAIT-CAST AND FLY-CAST KIT

- Fine Quality Split Bamboo Rod
- Converts from 8 ft. Fly Rod to 5'4" Casting Rod

379

The perfect all-around "Fisherman-Friend." Features a split bamboo rod with interchangeable tips and reversible handle. Chrome plated, screw locking reel seat. Shaped cork handle. Chromed stainless steel guides and extra deep chromed brass ferrules. High gloss lacquered surface—colorful, sealed nylon windings. Kit contains



4 pc. Split bamboo rod, brass swivel, split-shot, line winder, float, nylon line, 12 assorted flies, 2 streamers, 6 hollow point hooks with leaders, leader cutting scissors and fitted wooden case to hold complete kit. Shpg. wt., 3 lbs. Net 3.79

"WIGGLY-EEL" NATURAL LURE

3 for .59

A natural soft black plastic eel tied with 15-lb. test nylon to a 2-gang hook harness. Wire shaft directly attached to eye of front hook with revolving propeller blade located between 2 solid metal beads. Size 2 gold plated hooks. Shpg. wt., 4 oz. Net 3 for .59

FT-525 "WIGGLY-EEL" NATURAL LURE 3 for .59

LAFAYETTE BOAT-LITE KIT

- For All Class 'A' and Class 'I' Boats
- Meets U.S.C.G. Requirements



Ideal for the small boat owner. The combination red and green running light has correctly shielded lens for clear visibility for over one mile. The flag-staff stern light has a unique plug-in feature for quick and easy removal—no nails, clamps or screws—just plugs in. Light is visible for 2 miles. All parts are corrosion-resistant. Kit includes mounting brackets. Mounting instructions. F-559 Kit (less battery). Shpg. wt., 3 lbs. Net 3.69
BA-163 6V Battery for above (wt., 3 3/4 lbs.) Net 1.83

24 DIVIDED WING FLIES

.98



Finest quality, hand tied dry flies. Skillfully made with just the right amount of natural-tip hackle. Upright divided wings cocked well forward. Decorated silk bodies. Favorite patterns: Black Gnat, Silver Doctor, Royal Coachman, Yellow Sally, Parma Belle, Etc. Compare to flies selling as high as .30 each! #10 hook. Shpg. wt., 8 oz. Net .98

FT-531 24 DIVIDED WING FLIES Net .98

24 ATLANTIC SALMON STREAMERS

159

Famous "New England" streamer flies. Resemble small live minnows in the water. Beautifully dressed and fitted with jungle feathers tied in at the head. All dressing tight and smooth. Two dozen all time favorites tied on long shank No. 2 hook. Includes Black Ghost, Light Tiger, Aunt Ider, Gray Ghost, Parmachene Belle, Jack Scott, etc. No two alike. Regularly sell as high as .49 ea. all 24 identified on labeled card. Shpg. wt., 12 oz. Net 1.59

FT-532 ATLANTIC SALMON STREAMERS Net 1.59

24 ASSORTED WET AND DRY FLIES

.59



24 hand tied expertly detailed-most popular flies. The perfect kit for the beginner or old pro. All tied on #10 hooks. Includes such famous types as Royal Coachman, Black Gnat (female), Red Ibis, Silver Doctor, Quill Gordon, etc. Each fly is individually identified. Made with universally accepted fly materials. Wt., 8 oz. Net .59

FT-534 ASSORTED WET AND DRY FLIES Net .59

NOW! NO MONEY DOWN WITH LAFAYETTE'S NEW 3-IN-1 EASY-PAY-PLAN

Lafayette Catalog No. 626 Page 63

The Magnificent Fidelity of Stereo Tape

... YOURS WITH THIS NEW

LAFAYETTE 2 SPEED STEREO PLAYBACK TAPE DECK WITH 6 TRANSISTOR DUAL STEREO PREAMPS

There is nothing to equal the superlative reproduction and fidelity of prerecorded stereo tape. And now, at the price you'd expect to pay for a record changer you can equip your music system with this new Lafayette Stereo Playback Tape Deck. Precision engineered to satisfy the most discriminating music listener, the RK-141 will playback with uncompromising fidelity 1/4 track and 1/2 track stereo tapes plus 1/2 track and full track monaural tapes. Unlike other units requiring separate playback preamplifiers, the RK-141 is equipped with its own built-in 6 transistor dual stereo playback preamplifiers equalized for the NARTB tape curve... allows use with virtually any stereo amplifier by merely connecting to the auxiliary, tuner, or hi-level tape inputs. The transistorized playback preamplifiers, powered by a highly rectified DC power supply, together with a specially designed tape head shield on which the pressure pad is mounted, reduce hum and noise levels to professional standards. Its tape handling qualities and mechanism reflect the careful design and construction employed—the precision laminated tape playback head is of the same type found in the costliest units; tape is automatically disengaged from the tape head in rewind, fast, forward and stop positions. In addition, the unit automatically shuts off at the end of the tape (without any need for attaching metal leaders at the tape ends). The 4-pole, heavy-duty, constant speed induction motor is fused and employs a dynamically balanced flywheel. A front panel speed selector switch allows instant selection of 7 1/2 or 3 3/4 ips speeds. In addition, two rugged lever-action controls provide for Rewind, Off, Play and Fast Forward functions. Accepts all size tape reels up to and including 7". Measures 10 3/4 x 14 3/4 x 5 1/4". Complete with shielded hook up cables. Shpg. wt., 17 lbs. RK-141WX Net 59.50 Furniture Grade Walnut Base for RK-141. Shpg. wt., 4 lbs. RK-148W Net 6.95 Portable Carrying Case for RK-141 Shpg. wt., 5 lbs. RK-147W .95

Fully Equipped!
Contains its own
built-in Stereo
Playback Preamps



OPTIONAL PORTABLE CARRYING CASE

59⁵⁰
NO MONEY DOWN

- Dual NARTB Equalized Transistorized Stereo Playback Preamps Allows Use With Virtually Any Stereo Amplifier
- Frequency Response: 50-15,000 cps @ 7 1/2 ips
- 2-Speeds—7 1/2 & 3 3/4 ips
- Accepts Full-Size 7 Inch Reels
- Automatic Shut-Off At End Of Tape
- Playback 1/4 Track, 1/2 Track Stereo Plus 1/2 Track and Full Track Monaural

Priced At
No More Than You'd
Expect to Pay For
A Record
Changer!

**NOTHING
EXTRA TO BUY**

COMPARE THESE PERFORMANCE SPECIFICATIONS
• Frequency Response: @ 7 1/2 IPS, 50-15,000 CPS ± 1.5db; @ 3 3/4 IPS, 50-9,000 CPS ± 2db
• Wow & Flutter .15% @ 7 1/2 IPS, 0.2% @ 3 3/4 IPS
• Cross Talk & Stereo Channel Separation: 50db
• Signal To Noise Ratio: 50db
• Playback Output with Built-In Stereo Playback Preamplifiers 0.5V • 110-120V 60 cycles AC operation

NOW! NO MONEY DOWN WITH LAFAYETTE'S NEW EASY-PAY PLAN!

BRAND NEW! HE-29B 10-TRANSISTOR CITIZENS BAND

With Extra RF Stage -
50% More Powerful!

"WALKIE TALKIE" T.M. No License, Test or Age Limit

39⁹⁵
2 for 78.88
NO MONEY
DOWN

- Transmits & Receives Up to 2 Miles
- Crystal Control on Both Transmit & Receive
- Leather Case with Shoulder Strap
- Requires 8 Inexpensive Penlight Batteries
- Up to 50 Hours Battery Life
- 46" Telescoping Antenna
- Push-To-Talk Operation
- Earphone For Personal Listening

OTHER CHANNELS ARE AVAILABLE

If desired with any channel other than channel 10, order HE-31BL and specify channel.

No License or Permit Required—Complete portable two-way communications for everyone, everywhere. Perfect for hunting, fishing, boating, virtually all sports; use at work in construction, warehouse, office, on the farm or for in plant communications. Receives and transmits up to 2 miles under average conditions (no intervening obstructions.)

As simple and easy to use as your telephone and twice as handy—weighs only 18 ounces and slips easily into your pocket. Just two controls provide fast, efficient operation, on/off volume and push-to-talk. When push-to-talk button is depressed for transmitting the built-in-speaker acts as a sensitive microphone. Private monitoring of conversation is made possible by means of a special jack and earphone. Telescoping antenna extends to 46 inches.

Constructed with the care and precision of a fine watch, this new Lafayette Citizens Band "Walkie Talkie" achieves optimum reliability and performance by use of sophisticated transistor techniques and advanced design. Full transistor circuitry employs 10 transistors plus 1 diode. Transmitter section is crystal controlled and delivers a power input of 100 milliwatts, meeting FCC specifications for unlicensed units in the 27mc Citizens Band spectrum. Crisp—clear reception is furnished by the efficient superheterodyne receiver. Power is supplied by 8 miniature standard penlight batteries with a life expectancy of up to 50 hours.

Housed in a handsome black and gold aluminum case with leather carrying case and shoulder strap. Supplied with earphone, antenna, batteries and crystals for channel 10. Size 6 3/4 x 3 1/4 x 1 3/8".

HE-29BL Shpg. wt., 3 lbs. Net 39.95
Set of 2 Net 78.88

Replacement batteries for HE-29 "Walkie-Talkie," 8 required.

BA-155 Z Cells Net Each .095

CRYSTALS FOR HE-29B

HE-830L TRANSMITTING CRYSTAL (Specify Channel) Net 2.25

HE-758L RECEIVE CRYSTAL (Specify Channel) Net 2.25

Amazing "MIGHTY 9"

The Most Powerful 9 Transistor
Personal Portable



- Lightweight Shirt-Pocket Size
- Plays for Hours on 2 Most Inexpensive Batteries
- Personal, Built-in Earphone Jack
- Full-Tone Speaker

19⁹⁵

SENSATIONAL
SUMMER
SPECIAL!

Was 25.88

9 TRANSISTORS PLUS 2
DIODES PLUS THERMISTOR

Complete with
carrying case,
batteries
and earphone

Compare this portable with others selling for much more—compare feature for feature and you'll see why the Lafayette "Mighty-9" is your best buy inside the sturdy, attractive plastic case you'll find an engineer's dream—separate mixer and oscillator, diode detector and diode bias stabilizer, 2 IF stages, AVC amplifier, 4 audio stages including push-pull audio output. Lightweight (only 9 ozs.), pocket size (4 1/2 x 3 3/4 x 1 1/4"); self-contained stand. Operates on two of the most inexpensive batteries. Complete with leather carrying case, batteries and earphone for private listening. FS-91L Shpg. wt., 2 lbs. Net 19.95
BA-155 (Burgess Z type battery—2 required) Net ea. .095

UP TO 24 MONTHS TO PAY — FOR DETAILS SEE PAGE 54

LAFAYETTE RADIO ELECTRONICS "ASSOCIATE STORE" DEALER LOCATIONS

- | | | | |
|--|--|--|---------------------------------------|
| BUENA PARK, CALIF. 6306 Beach Blvd. | SPRINGFIELD, MASS. 527 Belmont Ave. | ALBANY, N. Y. 335 Central Ave. | ALLEN TOWN, PA. 20 North 7th St. |
| SAN FRANCISCO, CALIF. 1480 Market St. | BALTIMORE, MD. 2014 No. Charles St. | BINGHAMTON, N. Y. 129 State St. | HARRISBURG, PA. 1419 No. 3rd St. |
| DENVER, COLO. 9515 E. Colfax Ave. | BEL AIR, MD. 139 Thomas St. | BUFFALO, N. Y. 747 Main St. | PITTSBURGH, PA. 640 Grant St. |
| BRIDGEPORT, CONN. 2710 Fairfield Ave. | HAGERSTOWN, MD. 13 W. Antietam St. | ROCHESTER, N. Y. 792 W. Main St. | WILKES-BARRE, PA. 115 No. Main St. |
| GROTON, CONN. 171 Thames St. | BAY CITY, MICH. 408 E. Midland St. | AKRON, OHIO 34 North Main | BRYAN, TEXAS 3219 Texas Ave. |
| STAMFORD, CONN. 85 Prospect St. | DETROIT, MICH. 1326 Broadway | CANTON, OHIO 300 Walnut St. | HOUSTON, TEXAS 8601 Long Point Rd. |
| WATERBURY, CONN. 386 West Main St. | ASBURY PARK, N. J. 1027 Highway No. 35 | CINCINNATI, OHIO 505 Elm | 3903 Richmond Ave. |
| ORLANDO, FLA. 1203 No. Mills St. | CAMDEN, N. J. 305 Broadway | CLEVELAND, OHIO 2001 Euclid Ave. | SAN ANTONIO, TEXAS 5090 Blanco Rd. |
| TAMPA, FLA. 3328 Henderson Blvd. | NORTHFIELD (Atlantic City), N. J. Tilton Shopping Center | COLUMBUS, OHIO 122 E. Long St. | LYNCHBURG, VA. 1624 Park Ave. |
| SALINA, KANSAS 314 West Cloud | TRENTON, N. J. 229 South Warren St. | STEUBENVILLE, OHIO 411 Washington St. | GREEN BAY, WISC. 412 Dousman St. |
| ASHLAND, KY. 212 - 15th St. | | AKRON, PA. 127 No. 7 St. | CHEYENNE, WYO. 1400 Hugur |

Lafayette Radio Electronics "Associate Store" Dealers own and operate their own stores as independent franchised dealers. They establish their own terms and prices, which may vary slightly and do not handle mail orders.

LAFAYETTE RADIO

111 JERICO TURNPIKE
SYOSSET, LONG ISLAND, NEW YORK

BULK RATE
U. S. POSTAGE
PAID
New York, N. Y.
Permit No. 8486

G H J K L M N
1 2 3 4 5 6 7