

# FOR EVERYTHING IN ELECTRONICS

# Wireless World

AUGUST 1983


80p

**Daisywheel typewriter interface**

**Spectrum analysis on the cheap**

**Did Morse get it right?**

**Ultrasonics for robots**



**How to stop a travelling wave**

Australia A\$ 2.70  
Canada C\$ 3.25  
Denmark DKR. 33.25  
Germany DM 7.00  
Greece DRA. 190.00  
Holland DFL. 8.50  
Italy L 3700  
New Zealand NZ\$ 3.00  
Norway NKR. 26.00  
Singapore M\$ 5.50  
Spain PTS 275.00  
Switzerland FR. 7.00  
U S A. \$ 3.75

# The PSG520H



a small, lightweight  
synthesized signal generator  
for field or bench use

100kHz to 520MHz

Runs from clip-on NiCd battery pack, external 12Vd.c.  
(vehicle battery via cigar lighter socket) or,  
from any standard a.c. mains supply

Reverse power protection to 50W (standard)


Excellent specification and features

from



**Farnell**

FARNELL INSTRUMENTS LIMITED · WETHERBY · WEST YORKSHIRE LS22 4DH · TELEPHONE (0937) 61961 · TELEX 55478 FARINT G  
REGIONAL OFFICE (SOUTH) · DAVENPORT HOUSE · BOWERS WAY · HARPENDEN · HERTS. AL5 4HX · TEL. (05827) 69071 · TELEX 826307  
WW-001 FOR FURTHER DETAILS



Red and green arcs of light represent crests and troughs of an electromagnetic wave brought to rest in the laboratory, as described by Professor Jennison on pages 36-38.

### NEXT MONTH

During his work on crises control R. E. Young saw a connexion between shock caused by a mass of data too enormous and possibly suspect to comprehend and the 'shell' condition of hyperautism in the mentally handicapped. R. E. Y. describes how electronics is now being applied to help people escape from the shell by communication.

Ian Wade's RTTY program runs on a basic Nascom 1 or 2 microcomputer and displays received text on a tv screen in lower-case letters, transmitted text in upper case.

Exceeding its designers expectations, the 6809-based Forth computer can be used with disc drives requiring high data-transfer rates - including Sony's microdrive and 8in floppy-disc drives.

Current issue price 80p, back issues (if available) £1, at Retail and Trade Counter, Units 1 & 2, Bankside Industrial Centre, Hopton Street, London SE1. Available on microfilm; please contact editor.

By post, current issue £1.23, back issues (if available) £1.80, order and payments to EEP General Sales Dept., Quadrant House, The Quadrant, Sutton, Surrey SM2 5AS Tel: 01-661 8668.

Editorial & Advertising offices: Quadrant House, The Quadrant, Sutton, Surrey SM2 5AS.

Telephones: Editorial 01-661 3614. Advertising 01-661 3130. See leader page.

Telex: 892084 BISPRS G.

Subscription rates: 1 year £14 UK and £17 outside UK.

Student rates: 1 year £9.35 UK and £11.70 outside UK.

Distribution: Quadrant House, The Quadrant, Sutton, Surrey SM2 5AS. Telephone 01-661 3248.

Subscriptions: Oakfield House, Perry-mount Road, Haywards Heath, Sussex RH16 3DH. Telephone: 0444 459188. Please notify a change of address.

USA: \$44 surface mail, \$93.80 airmail. Business Press International, Subscriptions Office, 205 E. 42nd Street, NY 10017.

USA mailing agents: Expeditors of the Printed Word Ltd, 527 Madison Avenue, Suite 1217, New York, NY 10022. 2nd class postage paid at New York.

© Business Press International Ltd 1983  
ISSN 0043 6062.

# FOR EVERYTHING IN ELECTRONICS Wirelessworld


AUGUST 1983

VOL 89 NO 1571

- 21 **ENGINEERING, NOT POLITICS**
- 22 **COMMUNICATIONS COMMENTARY**  
IARU accountability CB collapse? HF jamming
- 24 **TYPEWRITER TO DAISYWHEEL PRINTER**  
by N. Duffy
- 29 **AERIAL INEFFICIENCY AT SEA**  
by J. J. Wiseman
- 32 **LOUDSPEAKER MEASUREMENTS SIMPLIFIED**  
by P. F. Dobbins
- 36 **ELECTRIC CHARGE FROM A RADIO WAVE**  
by R. C. Jennison
- 38 **LITERATURE RECEIVED**  
Application notes and equipment data
- 39 **CIRCUIT IDEAS**  
Monitor conversion Cable reflectometer Rom selector
- 42 **SHORTCUTS IN CIRCUIT ANALYSIS**  
by W. A. Vincent
- 44 **FORTH COMPUTER**  
by B. Woodroffe
- 46 **300BAUD FULL-DUPLEX MODEM**  
by D. Richards
- 49 **LETTERS TO THE EDITOR**  
Electromagnetic Doppler Heretics feedback Waves in space
- 53 **BOOKS RECEIVED**
- 54 **ULTRASONIC RANGING FOR ROBOTS**  
by H. W. Gleaves
- 58 **HOBBYIST'S SPECTRUM ANALYSER**  
by R. Hartkopf
- 62 **DID MORSE GET IT RIGHT?**  
by A. S. Chester
- 64 **ELECTRONIC MAIL ORDER FOR ELECTRONICS**  
Estelle Rewtel and Cashtel
- 65 **NEWS OF THE MONTH**  
Microchip mic Erasable optical disc Colour with mono crt
- 68 **ASSEMBLY LANGUAGE PROGRAMMING**  
by R. F. Coates
- 70 **TWO-METRE TRANSCEIVER**  
by T. Forrester
- 74 **NEW PRODUCTS**  
Logic game Eurocube computer Autodial modem

# CHERRY PROTO-PADS

## Membrane keyboards – cut out for custom-design.



# CHERRY MEMBRANES

CHERRY ELECTRICAL PRODUCTS LIMITED, Coldharbour Lane, Harpenden, Herts AL5 4UN  
 Telephone: 05827 63100 Telex: 826012 CHERRY G  
 WW - 037 FOR FURTHER DETAILS

Now Cherry offers you a cost-effective answer to prototype development, in application areas hitherto not possible with conventional keyboards.

The Protopad range of self-adhesive membrane panels offers you a wide choice, with keypad configurations of 4 x 4, 2 x 4 and 1 x 4 in single or double pad size, with or without LED windows.

Their modular design makes for easier layout and unwanted pads can be progressively cut away, without disturbing circuit continuity.

For improved operator keying, all pad areas are embossed and have a special finish to accept custom legends using dry transfers or water-based ink pen.

But most important of all, Protopads carry the Cherry name that assures you of no short-cuts in reliability and performance.


'Protopad design evaluation modules are available, ex-stock, from our distributors.'

Semicomps, telephone: (0635) 67921  
 Tennco, telephone: (0793) 485255

**HBED**

# 6FT. PARABOLIC DISHES

## FROM ONLY £85 PLUS V.A.T.



6ft. dia. dishes, feed horns and electronics for use in 4GHz satellite reception. GaAs Fet transistors, SMA connectors, P.T.F.E., etc. available. Please send s.a.e. for full details and data sheets.

## Harrison Bros.

Electronic Distributors

22 Milton Road, Westcliff-on-Sea, Essex SS0 7JX  
 Tel. Southend (0702) 332338

WW - 010 FOR FURTHER DETAILS

# THE SOURCE OF ALL GOOD USED TEST EQUIPMENT

## ANALYSERS

- Drantz**
- 606-3 Line Disturbance Monitor £2500.00
- Hewlett Packard**
- 5004A Signature Analyser ..... £550.00
- 5420A Digital Signal Analyser £21,000.00
- 8407A/B412A Network Analyser ..... £1800.00
- Marconi**
- TF2303 Mod Meter ..... £460.00
- TF2337 Automatic Distortion Analyser ..... £250.00
- Tektronix**
- AA501 opt. 01, Distortion 10Hz - 100KHz to Less than 0.0025% ..... £1450.00
- DAS 9103 opt. 01, 02, Logic Analyser ..... £11,000.00
- DF1 Display Formatter For 7001 £850.00
- 308 Portable 8 Channel 20MHz Data Analyser ..... £2100.00
- 491 Spectrum Analyser 10MHz-40GHz ..... £7500.00
- 492 (opt. 01, 08) Spectrum Analyser 50KHz-220GHz ..... £13000.00
- 492P (opt. 01, 2, 3) Programmable Version of 492 ..... £20000.00
- 1401A Spectrum Analyser 1-500MHz ..... £950.00
- 7L5 Spectrum Analyser with opt. 25 (Tracking Gen) and L3 (50Ω Input) 20Hz - 5MHz ..... £7300.00
- 7L12 Spectrum Analyser 100KHz-1.8GHz ..... £6000.00
- 7L13 Spectrum Analyser 1KHz-1.8GHz ..... £7500.00
- 7L14 Spectrum Analyser 10KHz-1.8GHz ..... £9450.00
- 7L18 Spectrum Analyser 1.5GHz-60GHz ..... £9950.00
- TR502 Tracking Generator [for 7L12, 13 & 14] ..... £3200.00
- TR503 Tracking Generator [for 492/496 series] ..... £3250.00
- 5L4N Spectrum Analyser 20Hz-100KHz ..... £2350.00
- 7D01 16 Channel 100MHz Sample Rate ..... £2450.00

## TEKTRONIX TM500 SERIES

- AF501 Bandpass Filter/Amplifier ..... £400.00
- AM501 Op. Amp Gain 10,000 ..... £300.00
- AM502 Diff. Amp Gain 1 - 100K ..... £500.00
- DM502A True RMS 3 1/2 digit DMM ..... £325.00
- DC503A 125MHz Counter ..... £475.00
- DC505A 225MHz Counter ..... £600.00
- DC509 Counter/Timer 135MHz ..... £950.00
- FG501 Function Generator 0.001Hz-1MHz ..... £375.00
- FG501A Function Generator 0.002Hz-2MHz ..... £450.00
- FG502 Function Generator 0.1Hz-11MHz ..... £425.00
- FG503 Function Generator 1Hz-3MHz ..... £275.00
- PG501 50MHz Pulse Gen ..... £320.00
- PG502 250MHz Pulse Gen ..... £1,450.00
- PG505 Pulse Generator 1Hz-100KHz ..... £450.00
- PG507 Pulse Gen 50MHz ..... £900.00
- PG508 50MHz Pulse Gen ..... £1,250.00
- SC502 15MHz Dual Trace Scope ..... £1000.00
- SC504 80MHz Dual Trace Scope ..... £1250.00
- SG503 Sinewave Generator 250KHz-500KHz ..... £1,950.00
- SG504 Sig Gen 1050MHz ..... £350.00
- TM515 Mainframe (5 wide) ..... £350.00

We stock a complete range of Plug Ins for use with 7000 and 5000 series Mainframes.

## TEKTRONIX PLUG INS

- ### MISCELLANEOUS
- Bruel & Kjaer**
  - 2209 Sound Level Meter ..... £850.00
  - Datatabs**
  - DL901 Transient Recorder ..... £750.00
  - DL905 Transient Recorder ..... £995.00
  - Ferragraph**
  - RTS1 Test Set ..... £295.00
  - Fluke**
  - 515A Portable Calibrator DC/AC and Resistance with DC Resolution 0.2µV ..... £1750.00
  - 760A Meter Calibrator ..... £2950.00
  - 883 AC/DC Differential ..... £615.00
  - 845 AB Null Detector ..... £610.00
  - 9316 Diff. V Meter ..... £500.00
  - 2020A-4-6 Printer ..... £500.00
  - 2020A-3-6 Printer ..... £500.00
  - 9010A Logicaster, Self Contained, Portable, Full Spec. on Request. £8500.00
  - Hewlett Packard**
  - 355A Trans Test Set ..... £1,500.00
  - 5300B/5306A DMM/Counter ..... £1,200.00
  - 5340A Counter 10Hz-18GHz 8 Digit ..... £3750.00
  - 8013B Pulse Generator ..... £750.00
  - 8350A/83525A Sweeper System ..... £9,500.00
  - 8403A Modulator Fitted With 8732B PIN MDDULADR ..... £1500.00
  - 8745A S Parameter Test Set, Fitted with 11604A Universal Arms 0.1-2GHz ..... £2750.00
  - 59308A HP-IB Timing Generator ..... £300.00
  - Marconi**
  - TF131A LCR Bridge ..... £775.00
  - TF2603 RF Millivoltmeter ..... £750.00
  - Racal**
  - 9301A RF Millivoltmeter ..... £495.00
  - Tektronix**
  - 106 Square Wave Generator 1ns risetime 10Hz-1MHz without accessories ..... £175.00
  - 577/D1 Curve Tracer ..... £3000.00
  - 651HR PAL Monitor ..... £2,100.00
  - 832 Data Comms. Tester ..... £925.00
  - 833 Data Comms. Tester ..... £1350.00
  - 2701 Step Attenuator 50Ω 0.79dB in 1dB steps DC to 2GHz ..... £295.00
  - 2901 Time-Mark Generator ..... £195.00

Please note: Prices shown do not include VAT or carriage.

## OSCILLOSCOPES

- Hewlett Packard**
- 1332A High Quality CRT Display ..... £1250.00
- 9.6 x 11.3cm ..... £1250.00
- 1809A 100MHz 4 Channel Plug In ..... £2000.00
- 1821A Timebase Plug In ..... £1000.00
- Philips**
- PM3232 Dual Beam 10MHz ..... £495.00
- Tektronix**
- 305 Portable battery scope/DMM, D T 5MHz ..... £975.00
- 335 Dual Trace 35MHz Small portable with delay T Base ..... £1300.00
- 465 100MHz Portable ..... £1,550.00
- 468 Dual Trace 100MHz with Digital Storage (10MHz) Delay T Base ..... £4950.00
- 485 350MHz Portable ..... £4,950.00
- T922-01 15MHz DT Scope Diff. input ..... £515.00
- 200C Trolley for 400 Series ..... £120.00
- 7313 100MHz Storage Mainframe ..... £2225.00
- 7603 100MHz Mainframe ..... £1850.00
- 5440 50MHz Mainframe ..... £1000.00
- 5441 50MHz Variable Persistence Storage Mainframe ..... £1600.00
- 7704A Scope DC-200MHz Mainframe ..... £2500.00
- 7613 Storage Scope Mainframe DC-100MHz ..... £2600.00
- 7633 Multimode Storage Scope Mainframe DC - 100MHz ..... £2450.00
- 7834 Storage Scope Mainframe ..... £7200.00
- 7844 Dual Beam 400MHz Mainframe ..... £7750.00
- 7854 Waveform Processing Scope DC-400MHz ..... £9000.00
- 7904 opt. 02, 03 500MHz ..... £5350.00

Please note: Prices shown do not include VAT or carriage.

Electronic Brokers Ltd., 61/65 Kings Cross Road, London WC1X 9LN. Tel: 01-278 3461. Telex 298694



WW - 202 FOR FURTHER DETAILS

# Miscellaneous Hardware for sale

- Cabinets (6ft) ..... £95
- Delta Data VDUs ..... £50
- Centronics 101 Printers ..... £40
- 8K Micronova Memory ..... £45
- D.G. Cassette Tape Drive ..... £65
- Series 30 Diablo Drives ..... £245
- Tally 2200 Printer ..... £245
- Teletype ASR 33 ..... £15
- Olivetti TE 300 ..... £20
- Nova 800 Memory ..... P.O.A.

Call ALASTAIR DODS 01-467 1985/8489

WW - 031 FOR FURTHER DETAILS

# 1.5 GHz UP-CONVERTER 260

## works with any 240-350 MHz generator



Designed for economic testing and calibration of 1.5 GHz communications equipment, the Model 260 is a linear heterodyne up-converter employing advanced techniques to generate a very clean signal in the 1440-1550 MHz band from signal generator inputs 1200 MHz lower. It has zero insertion loss and allows the input signal generator controls to be used directly to set the output signal level and modulation conditions. Full accuracy and stability is ensured by phase-locking the internal 1200 MHz local oscillator to the signal generator frequency standard.


Full details from:  
 Techtest Ltd, Street Court, Kingsland  
 Leominster, Herefordshire HR6 9QA, England  
 Telephone: KINGSLAND (056881) 744. Telex: 837264

WW - 054 FOR FURTHER DETAILS

# STATIC DRAIN AND LIGHTNING PROTECTION COMPONENTS

## Line Transformer Type DDL/14A/1

To provide a DC path for static drain between coaxial centre contacts and earth.




### Brief Specifications

- Freq. Range 30-1000 MHz
- Impedance 50 Ohms
- Power Rating 50 or 100 W
- Terminations BNC or 'N' to customers' requirements

## Highpass Filter Type 2DL01

To protect VHF and UHF equipment from static discharges and lightning induced EMF which predominate below 20MHz.



### Brief specifications

- Pass band 20-1000 MHz
- Impedance 50 Ohms
- Power Rating 20 watts
- Terminations BNC, N or to customers' requirements

## Gas Discharge Lightning Arrestor Type LA1

To provide both protection from lightning strikes and prevention of significant static build-up on antennas and transmission lines.



### Brief Specifications

- Freq. Range 0.54 MHz
- Impedance 50/75 Ohms
- Power Ratings 1Kw
- Terminations SO239 only
- Surge Capability: 10 or more surges of 15,000 amperes in 5 microseconds

SMC also supply a wide range of RF Baluns Rx to 30KW 1.5-30 MHz, ground or antenna mounted, with most combinations of connector or open wire termination earth rods, earthing wire, etc.

# SOUTH MIDLANDS COMMUNICATIONS LTD.

RUMBRIDGE ST., TOTTON  
 SOUTHAMPTON SO4 4DP  
 Telex: 477351 SMCMM G  
 Tel: Totton (0703) 867333

WW - 051 FOR FURTHER DETAILS

Sole Distributors for the United Kingdom  
**SPECIAL PRODUCTS (DISTRIBUTORS) LTD**  
 81 Piccadilly, London W1V 0HL. Phone: 01-629 9556  
 As supplied to the M.O.D., U.K.A.E.A., C.E.G.S. British Rail and other Public Authorities;  
 also major industrial and electronic users throughout the United Kingdom.  
 WW - 024 FOR FURTHER DETAILS

# EuroCUBE 6502/6809

## One small Eurocard - more computer than ever


EuroCUBE is just one, small 100x160mm Eurocard but it is an Industrial Computer of exceptional power and versatility.

The user has a choice of 6502 or 6809 microprocessors. Programs can be developed on a full CUBE development Eurorack or on any other microprocessor development system in a high level language such as Industrial BASIC or machine code.

EUROCUBE has four memory sockets whose function and position in memory is fully user selectable. For example, the first socket might contain a 4KB operating system EPROM, the second a BBC BASIC interpreter in ROM, the third the user's BASIC program in whatever size EPROM is convenient, and the fourth might contain 8KB of battery backed non-volatile CMOS RAM.

An on-board calendar clock is also supported by the battery, and provides the time of day to 1/10th second and the date correct for the whole century.

EUROCUBE communicates with the outside world through 20 digital i/o channels, RS423/RS232 serial port and the full CUBE/Acorn data bus through which the entire CUBE/Acorn range of video, disk, analog, solid state switches and other peripherals can be controlled.



£139

Exc. VAT. No charge for Operating System Software

Control Universal's new 150 page catalogue and technical overview is now available free of charge. Use the reply service for your copy, or ring one of our engineering team to discuss your application.



Unit 2, Andersons Court,  
Newnham Road, Cambridge CB3 9EZ  
Telephone (0223) 358757

WW - 017 FOR FURTHER DETAILS

## NEW! ICOM ICH2 SYNTHESIZED FM HANDPORTABLE



The ICH2 is the first of a new breed of synthesized hand-held radio transceivers. Being synthesized, it requires no crystals to be set on to frequency. All that is required is to lift a recessed panel on the top of the set and cut the correct diodes to program the set to one or two channels. Duplex or simplex is obtained in the same way. This really is a boon to the busy dealer and convenient for the customer who wants those extra few sets "yesterday".

The ICH2 is very versatile, coming complete with a rechargeable ni-cad pack, small mains charger, rubber helical antenna, earphone and strong spring belt clip. Optional extras include: A speaker/microphone, cigarette lighter plug 12V charging lead, 12V converter to operate direct from the car supply, leather and leatherette cases, various different types of slide on/off battery packs both rechargeable and dry and a desk charger that fast charges some of the battery packs in 1 to 1 1/2 hours. The battery packs slide on and off very easily, enabling a spare to be carried in your pocket and an exchange made in the field. Sizes are 6.5"H x 2.6"W x 1.4"D, weighing 1.1lb. Power output is 1-3 watts and covers a frequency range of 164.975-174.975Mhz, duplex or simplex.

Retail price is 269 pounds each plus VAT. We are also looking for dealers for general distribution. More details from

**Thanet Electronics** **ICOM**

143 Reclver Road, Herne Bay, Kent  
Tel: 02273 63859. Telex 965179

WW - 013 FOR FURTHER DETAILS

**TO BE CRYSTAL CLEAR**  
Tel. 029-34-5353 Telex 87116 Aero G  
MOD approved CAA approved

WW - 032 FOR FURTHER DETAILS

## ELECTRON GUNS TV TUBE COMPONENTS

If you are Rebuilding or Manufacturing TV Tubes - We are the leading suppliers of Electron Guns and TV Tube Components to the TV Tube Industry. We specialise in all aspects of Electron Mount Technology. Our product range includes more than 250 gun types for Colour, In Line, Mono and Display Tubes along with Mount Parts, Bases, Getters, Sealoffs, and all other associated items for TV Tube Production. A Full Technical Back-up and Advisory Service is available to all customers Worldwide.

Please request our current catalogues and Data Information.

**GRIFTRONIC EMISSION LTD**  
2 SWAN STREET  
ALCESTER  
WARWICKSHIRE  
B49 5DP  
ENGLAND


Telephone: (0789) 764852/764100. Telex: 312354 Grifem G

WW - 033 FOR FURTHER DETAILS


WIRELESS WORLD AUGUST 1983

# Hilomast Ltd

HILOMAST SYSTEMS



PNEUMATIC TELESCOPIC MASTS



HILOMAST LIMITED

THE STREET HEYBRIDGE - MALDON  
ESSEX CM9 7NB ENGLAND  
Tel. MALDON (0621) 56480  
TELEX NO. 995855

WW - 019 FOR FURTHER DETAILS

WIRELESS WORLD AUGUST 1983

# DEC SALE

a selection from our huge stocks. All items reconditioned unless otherwise stated.

NEW AUTUMN '83 CATALOGUE now out send for your free copy

### SPECIAL PURCHASE

**OF PDP11/34A PROCESSORS**  
11/34A CPU  
MS11JP 64KB MOS Memory  
DL11W Console Interface  
KY11LB Programmers Panel,  
M9312 Bootstrap  
BA11L 5 1/4" Chassis  
**ONLY £2,500**

### DEC PDP11/60 SYSTEMS special offer

11/60 Processor with 256KB  
2 x RK06 Disk Drives + control  
LA36 Console Rack Cabinet  
**OUR BARGAIN PRICE**  
**£5250.00** All items  
ex DEC-maintained site

### PDP8A/RL01 SYSTEMS

special purchase - immaculate as new condition BA400-BR Processor complete with  
KK8A CPU  
MM8AB 16KW Core  
KC8AA Programmers Panel  
KM8AA Option module  
DKC8A Option module  
2 x RL01AK Disk Drive  
RL8A Controller  
H967 4ft. cabinet  
**£4750.00**

### DEC LSI PROCESSORS

11/03LX KD11HA CPU,  
KEV11 EIS/FIS, BDV11AA Terminator/Bootstrap.  
BA11N 5 1/4" Chassis with Backplane and Power Supply.  
No memory included.  
**NEW £1200**

11/03N KD11G CPU,  
KEV11 EIS/FIS, BDV11AA Terminator/Bootstrap. BA11R 5 1/4" Chassis with Backplane and Power Supply, MSV11DD 32KW MOS

**NEW £1495**

### DEC DISK DRIVES

RK07ED 28MB	£2,500
RK07PD 28MB	£2,500
RL01A 5MB	£995
RM02AD 67MB NEW	£6,250
RM03AD 67MB NEW	£6,250
RM05AD 256MB NEW	£14,750
RM80 124MB	£9,500
RPO6AB 176MB	£7,500
RX11BD Dual Floppy	£995
RX211BD Dual Floppy	£1,725

### DEC PRINTERS AND TERMINALS

LA34 DECwriter IV EIA 300 baud	£425
LA36 DECwriter II 20mA	£295
LA36 DECwriter II RS232	£325
LA180-PD DECprinter (NEW)	£495
LS120 DECwriter III EIA 1200 baud	£750
VT50 DECscope 20mA	£199
VT50 DECscope RS232	£225
VT105 Graphics Terminal	£950
VT131AB	£995
VT132	£875

## TEKTRONIX DESKTOP COMPUTERS

Special Purchase of Ex-Demonstrator Stock

### 4051

High resolution Graphics and Alphanumerics. 32KB Memory. Integral Cartridge Tape Drive  
**£2,250 INCLUDING OPTION 22 32KB MEMORY**

### 4052

High performance stand-alone processor with 64KB Memory. Integral Cartridge Tape Drive  
**£4,950 INCLUDING OPTION 24 64KB MEMORY**

### JOYSTICK 4952

(for 4050 series) sensitive cursor-control with .1% accuracy and XY zero feature. **£275**

Other Tektronix graphics equipment currently available includes 4006-1, 4010-1, 4027, 4014-1, 4015-1, 4016-1, 606/606A/606B and 611

ADD 15% VAT TO ALL PRICES Carriage and Packing extra

**Electronic Brokers Ltd., 61/65 Kings Cross Road, London WC1X 9LN. Tel: 01-278 3461. Telex 298694**

Electronic Brokers

WW - 203 FOR FURTHER DETAILS

5

# HART

## LINSLEY-HOOD 300 SERIES AMPLIFIERS



30 Watt Complete Kit.....£85  
35 Watt Complete Kit, MosFet O/P.....£79.50  
45 Watt Complete Kit, MosFet O/P.....£83.50  
Reprints of 30 Watt Article from 'Hi-Fi News'.....50p  
Reprints of MosFet Postscript to above.....30p

## 'P.W. WINTON' TUNER AND AMPLIFIER



Sleazy matching slimline tuner and amplifier in beautiful wooden cabinets. These Ted Rule designs are for the enthusiast. Tuner covers LW, MW, SW, FM and TV sound! Digital frequency readout with clock and timer features. FM has 6 section front end and switchable bandwidth for exceptional fringe area performance. Amplifier has Toroidal transformer, Mosfet output stages, 50 watts per channel and got a cracking review in Practical Wireless.  
Tuner, Complete Kit.....£163  
Amplifier, Complete Kit.....£98  
Amplifier Reprint.....£1.25

## FEED YOUR MICRO BYTES WITH OUR SOLENOID CONTROLLED CASSETTE DECK



Front loading deck with full solenoid control of all functions including optional read in fast wind modes, 12 volt operation. Fitted 3-digit memory counter and Hall IC Motion Sensor. Standard erase and stereo R/P Heads. Cheapest price ever for all these features. Only £39.90 plus VAT. Full technical specification included.

## LINSLEY-HOOD 100 WATT POWER AMPLIFIER

Our complete kit for this brilliant new design is the same size as our Linsley-Hood Cassette Recorder 2. Kit includes all parts for two power amplifiers with large heatsink area, huge power supply and speaker protection circuit. Total cost of all parts is £114.48 but our special introductory price for all parts bought together is only £109.50.

## THIS MONTH'S SPECIAL OFFERS

### DOLBY 'B' NOISE REDUCTION IC LM1011

Marvellous opportunity for home experimenters, build your own noise reduction system. Supplied complete with circuit showing typical application. Absolute knockout price only £3.50 for two. inc. VAT and post.

### COMPLETE STEREO CASSETTE DECK

Brand new high quality top-loading Cassette Deck complete with Record/Play electronics. Supplied with connection data and circuit diagram. Automatic chrome/ferric switching. Only needs 9v DC supply. Total price only £18.34 inc. VAT and post.

### COMPLETE STEREO TUNER MODULE

Three band LW/MW/FM Stereo Tuner fully assembled on PCB 165 x 85mm. Supplied with Ferrite rod aerial and band switch fully wired. Facility provided to drive tuning meter and stereo LED. Only needs 12v DC supply. FM sensitivity 2.5uV. Price only £7.99 inc. VAT and post.

### SUPER SLIM FLOPPY DRIVE



Very latest low consumption 5 1/4 in Disk Drives. Fit two in the space previously taken by one! Compatible with major standards. Connects directly to BBC and other microcomputers fitted with disk interface. The 80 track drive can be made switchable to read 40 or 80 track disks, very useful when upgrading to higher density storage.  
40 Track Drive £154. 80 Track Drive £214

## HIGH QUALITY REPLACEMENT CASSETTE HEADS



Do your tapes lack treble? A worn head could be the problem. Fitting one of our replacement heads could restore performance to better than new! Standard mountings make fitting easy and our TC1 Test Cassette helps you set the azimuth spot-on. We are the actual importers which means you get the benefit of lower prices for prime parts. Compare us with other suppliers and see! The following is a list of our most popular heads, all are suitable for use on Dolby machines and are ex-stock.  
HC20 Permalloy Stereo Head. This is the standard head fitted as original equipment on most decks.....£4.25  
HW90 High Beta Permalloy Head. A hard-wearing, higher performance head with metal capability.....£6.20  
HS16 Sendust Alloy Super Head. The best head we can find. Longer life than Permalloy, higher output than Ferrite, fantastic frequency response.....£8.20  
HQ551 4-Track Head for auto-reverse or quadrophonic use. Full specification record and playback head.....£7.40  
Please consult our list for technical data on these and other Special Purpose Heads.

## STUART TAPE CIRCUITS

(For reel-to-reel decks)  
These circuits are just the thing for converting that old valve tape deck into a useful transistorised recorder. Total system is a full three head recorder with separate record and replay sections for simultaneous off tape monitoring. We also stock the heads. This kit is well engineered but does not have the detailed instructions that we give with our more recent designs. We would not therefore recommend it to beginners. Reprints of the original three articles 45p. Post free. No VAT.

## HART TRIPLE-PURPOSE TEST CASSETTE TC1

One inexpensive test cassette enables you to set up VU level, head azimuth and tape speed. Invaluable when fitting new heads. Only £3.80 plus VAT and 50p postage.

Tape Head De-magnetiser. Handy size mains operated unit prevents build up of residual head magnetisation causing noise on playback.....£3.88

## CASSETTE MOTORS

Brand New Governed 12v DC Tape Drive Motor Type MMI-6A2LK.  
As used in SF925 and many other decks. 40mm Dia x 35mm Long. Shaft 10.5mm long x 2mm Dia. 6 x 2.5mm Mounting Holes on 26mm PCO on shaft and face. Anti-clockwise rotation at rated speed of 2200 RPM. Free run current 25mA. £4.85 each.


Full details of the entire range of HART products is contained in our illustrated lists.  
Ask for your FREE copy NOW.  
Enquiries for lists are also welcome from overseas but please let us have three IRCs to cover the cost of surface post or 5 IRCs for airmail.  
In a hurry? A telephone order with credit card number placed before 3 p.m. will be despatched THAT DAY!  
Please add part cost of post, packing and insurance as follows:

INLAND Orders up to £10 - 50p  
Orders £10 to £49 - £1  
Orders over £50 - £1.50  
OVERSEAS Orders at cost plus £2  
Postage at cost plus £2  
documentation and handling

PLEASE ADD VAT  
TO ALL PRICES.



## METER PROBLEMS?



137 Standard Ranges in a variety of sizes and stylings available for 10-14 days delivery. Other Ranges and special scales can be made to order.

Full information from:  
**HARRIS ELECTRONICS (London)**  
138 GRAY'S INN ROAD, W.C.1 Phone: 01-837 7937  
Telex: 892301 HARTRO G

WW - 021 FOR FURTHER DETAILS

## Sowter Transformers

With 40 years' experience in the design and manufacture of several hundred thousand transformers we can supply:

### AUDIO FREQUENCY TRANSFORMERS OF EVERY TYPE

YOU NAME IT! WE MAKE IT!

### OUR RANGE INCLUDES

Microphone transformers (all types), Microphone Splitter/Combiner transformers, Input and Output transformers, Direct Injection transformers for Guitars, Multi-Secondary output transformers, Bridging transformers, Line transformers, Line transformers to G.P.O. Isolating Test Specification, Tapped impedance matching transformers, Gramophone Pickup transformers, Audio Mixing Desk transformers (all types), Miniature transformers, Microminiature transformers for PCB mounting, Experimental transformers, Ultra low frequency transformers, Ultra linear and other transformers for Transistor and Valve Amplifiers up to 500 watts, Inductive Loop Transformers, Smoothing Chokes, Filter, Inductors, Amplifier to 100 volt line transformers (from a few watts up to 100 watts), 100 volt line transformers to speakers, Speaker matching transformers (all powers), Column Loudspeaker transformers up to 300 watts or more.

We can design for RECORDING QUALITY, STUDIO QUALITY, HI-FI QUALITY OR P.A. QUALITY. OUR PRICES ARE HIGHLY COMPETITIVE AND WE SUPPLY LARGE OR SMALL QUANTITIES AND EVEN SINGLE TRANSFORMERS. Many standard types are in stock and normal dispatch times are short and sensible. OUR CLIENTS COVER A LARGE NUMBER OF BROADCASTING AUTHORITIES MIXING DESK MANUFACTURERS, RECORDING STUDIOS, HI-FI ENTHUSIASTS BAND GROUPS, AND PUBLIC ADDRESS FIRMS. Export is a speciality and we have overseas clients in the COMMONWEALTH, E.C. USA, MIDDLE EAST, etc. Send for our questionnaire which, when completed, enables us to post quotations by return.

## E. A. Sowter Ltd.

Manufacturers and Designers  
E. A. SOWTER LTD. (Established 1941) : Reg. No. England 303990  
The Boat Yard, Cullingham Road, Ipswich IP1 2EG, Suffolk  
P.O. Box 38, Ipswich, IP1 2EL, England  
Phone: 0473 52794 and 0473 21390  
Telex 987703G Sowter

WW - 044 FOR FURTHER DETAILS

# Midwich

COMPUTER COMPANY LIMITED

choice for microcomputer components

<b>BBC MICROCOMPUTERS</b>				
Model B	346.95			
Model B 4-Disc Int.	441.95			
<b>BBC MICRO DISC DRIVES</b>				
BBC31 Single 100K	229.00			
BBC32 Dual 100K	340.00			
BBC34 Dual 400K	649.00			
All disc drives include all Cables, Manual & Utilities Disc.				
<b>BBC MICRO UPGRADE KITS</b>				
BBCA2B Complete A TO B	44.75			
BBC1 16K Memory	18.00			
BBC2 Printer	7.50			
BBC3 Disc	95.00			
BBC4 Analogue	6.70			
BBC5 Serial & RGB	7.30			
BBC6 Bus	6.45			
Filling service available.				
<b>BBC MICRO CONNECTORS</b>				
BBC21 Printer Cable	13.00			
(not assembled)				
BBC22 User Port Connector	2.46			
BBC23 Cassette Lead	3.50			
BBC24 7 Pin Din Plug	0.60			
BBC25 6 Pin Din Plug	0.60			
BBC26 5 Pin Din Plug	0.60			
<b>BBC MICRO ACCESSORIES</b>				
BBC45 Joysticks	11.30			
BBC67 Eeprom Programmer	57.95			
<b>BBC MICRO SOFTWARE</b>				
Word Processor	52.00			
1.0 M.O.S.	36.00			
<b>ACORN/SMART</b>				
Full range available. Please telephone for stock position.				
<b>MEMORIES</b>				
2114L 200NS	D1 0.80			
2708 450NS	D2 2.95			
2716 450NS	D1 2.45			
2716 350NS	D1 4.95			
2716 3 Rail	D1 7.90			
2532 450NS	D2 3.45			
2732 450NS	D1 3.45			
2732 350NS	D1 5.45			
2764 300NS	D1 7.95			
4116 150NS	D1 0.85			
4116 200NS	D2 0.80			
4118 150NS	D1 3.25			
5516 200NS	D2 9.45			
6116 150NS	D1 3.30			
6116 Low Power 150NS	D2 4.95			
4184 200NS TI	D3 3.95			
4184 200NS NEC	D3 3.60			
4516/4816 100NS	D2 2.25			
4532 200NS	D2 2.95			
<b>6800 FAMILY</b>				
6801	D7 2.25			
6802	D5 2.50			
6809	D6 6.30			
6810	D1 1.15			
6821	D3 1.00			
6840	D4 3.75			
6845	D5 6.50			
6850	D2 1.10			
68488	D2 7.30			
68800	D7 5.25			
68809	D6 12.00			
68810	D1 2.26			
68821	D3 2.20			
68840	D4 6.00			
68850	D2 2.20			
<b>7800 FAMILY</b>				
780 ACPU	D2 2.99			
780 BCPU	D2 9.00			
780 ACTC	D1 2.60			
780 BCTC	D1 9.00			
780 ADART	D1 5.90			
780 ADMA	D2 6.95			
780 AP10	D1 2.75			
780 BP10	D1 9.00			
780 AS10	D4 9.00			
<b>8080 FAMILY</b>				
8085A	D4 3.50			
8212	D1 1.10			
8216	D1 1.00			
8224	D1 2.10			
8228	D1 3.27			
8251A	D5 2.50			
8253A	D4 4.00			
8255A	D6 2.25			
<b>6500 FAMILY</b>				
6502	D3 3.25			
6502A	D3 5.00			
6520	D1 2.50			
6520A	D1 3.16			
6522	D5 3.00			
6522A	D5 5.50			
6532	D2 5.50			
<b>FLOPPY DISC CONTROLLERS</b>				
8271	D6 36.00			
FD1771	D6 15.00			
FD1791	D6 12.00			
FD1793	D6 23.00			
FD1795	D6 28.00			
FD1797	D6 28.00			
WD1691	D2 12.00			
WD2143-01	D2 6.99			
<b>INTERFACE DEVICES</b>				
TL507	D1 1.33			
725	D1 1.60			
741	D1 0.14			
747	D1 0.48			
748	D1 0.27			
<b>REGULATORS</b>				
78L05	D1 0.30			
78L12	D1 0.30			
78L15	D1 0.30			
7805	D1 0.40			
7812	D1 0.40			
7815	D1 0.40			
7805	D1 0.45			
7812	D1 0.45			
LM309K	D1 1.20			
LM317K	D1 2.40			
LM332K	D1 4.50			
LM338K	D1 6.25			
<b>DATA CONVERTERS</b>				
UPD7002	D1 4.26			
ZN425	D1 3.45			
ZN426	D1 3.00			
ZN427	D1 5.99			
ZN428	D1 4.75			
ZN429	D1 2.10			
ZN432	D1 13.00			
ZN449	D1 2.55			
<b>CRYSTALS</b>				
1MHZ	D1 2.75			
1.8432 MHZ	D1 1.92			
4MHZ	D1 0.64			
8MHZ	D1 0.86			
<b>DIL SOCKETS</b>				
Plns				
8	7	16	25	
14	10	26	35	
16	10	29	40	
18	13	33	50	
20	15	37	60	
22	17	38	65	
24	21	46	70	
28	24	55	80	
40	30	76	99	
<b>ZIF SOCKETS</b>				
24 Pin			5.75	
28 Pin			8.20	
40 Pin			9.75	

Data sheets are available on items marked D. Prices are as follows:  
D1 0.75 D5 2.00  
D2 1.00 D6 4.00  
D3 1.25 D7 4.00  
D4 2.00 D8 5.00

A full range of the following products is carried in stock and is listed in our FREE catalogue.

- 74LS Series TTL
- 4000 Series CMOS
- T.I. Bipolar Memories
- 9900 Series Micros
- Crystals
- IDC, Card Edge & D-Type Connectors
- Dip Jumpers
- Monochrome & Colour Monitors (NEC & KAGA)
- Eeprom Programmers & Erasers
- Custom Cable Assemblies

SPECIAL OFFER! SPECTRUM 32K UPGRADE KIT £24.95

Carriage Orders up to £199 are sent by 1st class post, and £200+ by Securicor.  
0-£100 0.50 £100-£199 1.25 £200+ 5.00 by Securicor.  
Prices quoted (+ carriage charges) are exclusive of VAT and are subject to change without notice.  
Quantity Discounts are available on many products, please ring for details.  
Official Orders are welcome from Education Establishments, Government Bodies and Public Companies.  
Credit Accounts are available to others subject to status.  
Payment is due strictly net by the 15th of the month.  
Credit Cards are accepted (Access and Visa) for telephone and postal order and NO SURCHARGE is made.  
Out of stock items will follow automatically, at our discretion, or a refund will be given if requested.

THE ABOVE LIST SHOWS JUST A FEW OF THE ITEMS IN STOCK PLEASE TELEPHONE YOUR REQUIREMENTS - OR BETTER STILL SEND FOR OUR FREE CATALOGUE

Please complete this coupon for a copy of our FREE catalogue.

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

TEL NO \_\_\_\_\_

MIDWICH COMPUTER COMPANY LIMITED  
RICKINGHALL HOUSE, RICKINGHALL, SUFFOLK IP22 1HH  
TELEPHONE (0379) DISS 898751

WW - 023 FOR FURTHER DETAILS

## 80 Column Conversion for PET/CBM

Suitable for small screen PET with basic 4. Plug in PCB, no track cutting Gives all the features of an 8032. £149 + V.A.T., C.W.O.

for further details contact:  
**Delph Electronics Ltd.**  
4 Deeping Road, Baston, Peterborough. PE6 9NP.  
Tel: 077 86 535

WW - 040 FOR FURTHER DETAILS

IN VIEW OF THE EXTREMELY RAPID CHANGE TAKING PLACE IN THE ELECTRONICS INDUSTRY, LARGE QUANTITIES OF COMPONENTS BECOME REDUNDANT. WE ARE CASH PURCHASERS OF SUCH MATERIALS AND WOULD APPRECIATE A TELEPHONE CALL OR A LIST IF AVAILABLE. WE PAY TOP PRICES AND COLLECT.

# GET THE COMPLETE PICTURE

AT YOUR NEWSAGENT DURING JULY — OR DIRECT

— ORDER YOUR COPY NOW —

★ STILL THE ONLY CATALOGUE FOR THE COMPLETE RANGE OF COMPONENTS. BATTERIES, CRYSTAL FILTERS, RF POWER, MOSFET, TOKO COILS, CHOKES, ALPS PLOTTERS, SOLENOID CASSETTE MECHS ETC.

COMPONENTS FOR ELECTRONICS, COMMUNICATIONS & COMPUTING

**ambit**<sup>®</sup>  
INTERNATIONAL

WORLD OF RADIO & ELECTRONICS  
— CATALOGUE —



80p  
144 PAGES  
3 x £1 DISCOUNT VOUCHERS

★ FIRST WITH ON-LINE COMPUTER SHOPPING

★ FIRST FOR INNOVATION

★ FIRST FOR VALUE

★ FIRST FOR CHOICE

★ FIRST FOR SERVICE

**ambit**<sup>®</sup> INTERNATIONAL

200 North Service Road, Brentwood, Essex CM14 4SG  
Tel: (Consumer Sales/Enquiries) 0277-230909.  
Tel: (Industrial Sales/Enquiries) 0277-231616.  
Tlx: 995194 AMBIT G. Data 24hrs (RS232/300 baud) 0277-232628.

WW - 039 FOR FURTHER DETAILS

## CX80 COLOUR MATRIX PRINTER

New low price  
£795 + V.A.T.

At last a low-cost Colour Matrix Printer for Text, Graphics, Histograms, Colour VDU Dumps, etc.

Colour printout is quickly assimilated, makes graphics more understandable and is an ideal medium for the presentation of complex data or concepts.



Compatible with most microprocessors, prints in 7 colours — sophisticated internal programme makes the CX80 easy to use.

Dot Addressable + 15 user programmable characters, 96 ASCII and 64 graphics characters in rom. Centronics interface with RS232 and IEEE488 options. Apple II interface gives dot for dot colour dump. New viewdata interface prints out two pages side by side in full colour. See Prestel 200650.

The CX80 is a product of our own design and development laboratories. It represents a British breakthrough in colour printer technology. Colour brochure on request. OEM pricing available.

**INTEGREX LIMITED**

Portwood Industrial Estate, Church Gresley  
Burton-on-Trent, Staffs DE11 9PT  
Burton-on-Trent (0283) 215432. Telex: 377106

## Essex Tiny Basic System

The Essex Tiny Basic Computer is an ideal choice for data acquisition and process control systems. Its crystal controlled timer and interrupts provide accurate timing and fast response to critical events while the watchdog timer ensures reliable operation. Programs can be entered and tested from an EPROM terminal and then be copied into EPROM. Alternatively, Instant ROM modules may be used both during development and for program storage.

£185



## Essex Buffer Timer

A convenient means of buffering the I/O lines of the Essex Tiny BASIC Computer provides 24 inputs, 16 outputs and four hardware timers.

£78



## Essex Opto-Isolator

Connects to the Essex Tiny BASIC System bus to provide an additional 12 opto-isolated inputs and 12 opto-isolated outputs per card for safe connection to external equipment. Isolation voltage — 1500 volts.

£150



now available...

## Essex Backplane

A four slot backplane with printer and terminal connector to accept these cards.

£35

## Alex

A powerful software utilities package that provides the user with an enhanced editor and all the tools needed to program efficiently in assembly language.

£65

- all prices exclude V.A.T.
- \* substantial quantity discounts available
- \* carriage within U.K. £2

- \* Text Editor
  - \* Assembler
  - \* Disassembler
  - \* Debug Monitor
- Supplied as a 4K EPROM with comprehensive manual.

**Essex Electronics Centre**  
Wivenhoe Park, Colchester, Essex CO4 3SQ  
Telephone: Colchester (0206) 865089

WW - 057 FOR FURTHER DETAILS

# AUDIO ELECTRONICS

TEST EQUIPMENT CENTRES ALL MODELS ON DISPLAY OPEN SIX DAYS A WEEK

RETAIL • MAIL ORDER • EXPORT • INDUSTRIAL • EDUCATIONAL

DIGITAL MULTIMETERS (UK C/P Free)

<b>HAND HELD</b>	With free carry case	<b>Beckman T110 As T100 plus cont. test.</b>	£67.85
KD25C=13 range 0.2A DC 2 meg ohm	£24.95		
KD30C=16 range 10A DC 2 meg ohm	£29.95		
KD55C=26 range 1A AC/DC 20 meg ohm	£34.95		
6010= 28 range 10A AC/DC 20 meg ohm	£34.40		
7030= As 6010 but 0.1% basic.	£41.30		
KD615=16 range 10A DC 2 meg plus Hfe tester	£39.95		
185M 30 range 10A AC/DC 20 meg plus Hfe tester	£69.95		
HD30 16 range 0.2A AC/DC 2 meg ohm	£41.95		
HD30/B As above plus cont. buzzer	£44.50		
HD31 22 range 10 AC/DC 2 meg ohms plus cont. buzzer	£58.95		
DM2350 = 21 range 10A AC/DC 20 meg ohm miniature hand held auto range	£49.95		
Beckman T100 34 range 10A AC/DC 20 meg ohm	£56.35		
		Optional carry case £6.84	
		2001 28 range LCD 10A AC/DC plus 5 range Cap. Meter with case	£108.00
		TM451 4 1/2 digit LCD every facility (0.02%)	£171.00
		1503a 4 1/2 digit LCD every facility (0.05%)	£171.00
		1503H 0.05% basic version of above	£201.25
		1504 true RMS version	£201.25
		Sifram 2500 24 range LCD 2A AC/DC	£99.95
		Metrix (ITT) professional 3 1/2 + 4 1/2 digit DMM's standard & true RMS 4 models stocked	£77.00 - £201.25

FREQUENCY COUNTERS

PFM200A MHz hand held pocket 8 digit LED	£77.60
B110A 8 digit LED bench 2 ranges 100 MHz	£77.00
0610B 9 digit LED bench 2 ranges 600 MHz	£113.85
8000B 9 digit LED 3 ranges 1 GHz	£178.00
TF040 = 8 digit LCD 40 MHz	£126.50
TF200 = 8 digit LCD 200 MHz	£166.75
Frequency counters - Extended range of most counters	
TP600 600 MHz	£43.00
TP1000 1 GHz	£74.00

ELECTRONIC INSULATION TESTER

YF 501 500 V/0-100m with carry case	£63.00
-------------------------------------	--------

MULTIMETERS (UK C/P 65p)

HM102Z 20K/V 10A DC 22 range & cont. buzzer	£13.50
HM102Z 20 K/V 22 range & cont. buzzer	£14.95
ETC5000/5001 21 ranges, 50K/V. Range doubler, 10A DC.	£18.95
TMK500 23 ranges 30K/V, 12A DC plus cont. buzzer.	£24.75
NH56R 20K/V, 22 range pocket	£10.95
ETU102 14 range 2K/V pocket	£6.50
830A 26 range 30K/V, 10A AC/DC overload protection, etc.	£23.95
360TR 23 range 100K/V, Large scale 10A AC/DC plus Hfe	£39.95
AT1020 18 range 20K/V, Deluxe plus Hfe tester	£18.95
YN 360TR 19 range 20K/V plus Hfe tester	£15.95
Matrix Professional multimeters in stock 3 models from	£74.75

VARIABLE POWER SUPPLIES (UK C/P £1.00)

PP241 0/12/24V, 0/1A	£35.00
PP243 3 amp version	£59.95
PS 1307S 8/15V 7 amp twin meter	£24.95

DIGITAL THERMOMETER

TH301 LCD -50°C to +750°C with thermocouple	£68.43
---	--------

AC CLAMP METER

ST300 0/300A, 0/600 VAC, 0/1 Kohm 9 ranges	£28.50
--	--------

LOGIC PROBES

LP10 10 MHz	£28.50
DLPS0 50 MHz with carry case and accessories	£52.33

TRANSISTOR TESTER

Direct reading PNP-NPN, etc. TC1 (UK C/P 65p)	£21.95
---	--------

**AUDIO ELECTRONICS** Cubegate Limited  
301 EDGWARE ROAD, LONDON W2 1BN, TEL: 01-724 3564  
ALSO AT HENRY'S RADIO, 404/406 EDGWARE ROAD, LONDON, W2, TEL: 01-724 0323  
HENRY'S COMPONENT SHOP, TEL: 01-723 1008

WW - 016 FOR FURTHER DETAILS

**NEW PRODUCT**



The new microprocessor controlled EP8000 Emulator Programmer will program and emulate all EPROMs up to 8k x 8 sizes, and can be extended to program other devices such as 16k x 8 EPROMs, Bipolar PROMs, single chip microprocessors with external modules. Personality cards and hardware changes are not required as the machine configures itself for the different devices. The EP4000 with 4k x 8 static RAM is still available with EPROM programming and emulation capacity up to 4k x 8 sizes.

- EP8000 8k x 8 Emulator Programmer – £695 + £12 delivery
- BSC8 Buffered emulation cable – £49
- SA27128 Programming adaptor – £69
- SA25128 Programming adaptor – £69
- EP4000 4k x 8 Emulator Programmer – £545 + £12 de-

**FEATURES**

- Software personality programming/emulation of all EPROMs up to 8k x 8 bytes including 2704, 2708, 2716(3), 2508, 2758A, 2758B, 2516, 2716, 2532, 2732, 2732A, 68732-0, 68732-1, 68766, 68764, 2564, 2764. Programs 25128, 27128 with adaptors.
- No personality cards/characterisers required.
- Use as stand alone programmer, slave programmer, or EPROM development system.
- Checks for misplaced and reversed insertion, and shorts on data lines.
- Memory mapped video output allows full use of powerful editing facilities.
- Built-in LED display for field use.
- Powerful editing facilities include: Block/Byte move, insert, delete, match, highlight, etc.
- Comprehensive input/output – RS232C serial port, parallel port, cassette, printer O/P, DMA.
- Extra 1k x 8 scratchpad RAM for block moving.

- livery
- BSC4 Buffered emulation cable – £39
- BP4 (TEXAS) Bipolar PROM Module – £190
- Prinz video monitor – £99
- UV141 EPROM Eraser with timer – £78
- GP100A 80 column printer – £225
- GR1 Centronics interface – £65

VAT should be added to all prices

**DISTRIBUTORS REQUIRED ● EXPORT ENQUIRIES WELCOME**

**GP Industrial Electronics Ltd.** Tel: Plymouth (0752) 332961  
Telex: 42513  
Unit E, Huxley Close, Newnham Industrial Estate, Plymouth PL7 4JN



**NEW PRODUCT**

- Checks, Programs, Compares up to 8 devices simultaneously
- Handles all NMOS EPROMS up to projected 128K designs with no personality modules or characterisers – See list
- Easy to use, menu driven operation for blankcheck, program, verify, illegal bit check, checksum, self-test
- Constant display of device type, mode and fault codings
- Individual socket LED indicators for EPROM status
- Comprehensive EPROM integrity checks – Illegal bit check, data and address shorts, constant power line monitoring
- Full safeguard protection on all sockets
- Automatic machine self-test routine
- RS232C interface supplied as standard
- Powered down sockets
- Cost effective price – £695 + VAT
- Available from stock

Write or phone for more details

**DISTRIBUTORS REQUIRED ● EXPORT ENQUIRIES WELCOME**

**GP Industrial Electronics Ltd.** Tel: Plymouth (0752) 332961  
Telex: 42513  
Unit E, Huxley Close, Newnham Industrial Estate, Plymouth PL7 4JN

- 2704
- 2708
- 2716(3)
- 2508
- 2758A
- 2758B
- 2516
- 2716
- 48016
- 2532
- 2732
- 2732A
- 68732-0
- 68732-1
- 68766
- 68764
- 2764
- 2564
- MK2764
- 25128
- 27128

# TOROIDALS


The toroidal transformer is now accepted as the standard in industry, overtaking the obsolete laminated type. Industry has been quick to recognise the advantages toroidals offer in size, weight, lower radiated field and, thanks to I.L.P., PRICE.

Our large standard range is complemented by our SPECIAL DESIGN section which can offer a prototype service within 7 DAYS together with a short lead time on quantity orders which can be programmed to your requirements with no price penalty.

\*G ld service available.  
21 days manufacture for urgent deliveries.

\*Orders despatched within 7 days of receipt for single or small quantity orders.

\*5 year no quibble guarantee.



TYPE	SERIES	SECONDARY	RMS	PRICE	TYPE	SERIES	SECONDARY	RMS	PRICE	TYPE	SERIES	SECONDARY	RMS	PRICE
	No	Volts	Current			No	Volts	Current			No	Volts	Current	
<p><b>NEW! NEW! NEW!</b></p>														
<p><b>15 VA</b> 0x010 6+6 1.25 62 x 34mm 0x011 9+9 0.83 0.35Kg 0x012 12+12 0.83 Regulation 0x013 15+15 0.50 19% 0x014 18+18 0.42 0x015 22+22 0.34 0x016 25+25 0.30 0x017 30+30 0.25</p> <p><b>£5.12</b> + p &amp; p £0.78 + VAT £0.89 TOTAL £6.79 (encased in ABS plastic)</p>					<p><b>120 VA</b> 4x010 6+6 10.00 90 x 40mm 4x011 9+9 6.66 1.2Kg 4x012 12+12 5.00 Regulation 4x013 15+15 4.00 11% 4x014 18+18 3.33 4x015 22+22 2.72 4x016 25+25 2.40 4x017 30+30 2.00 4x018 35+35 1.71 4x028 110 1.09 4x029 220 0.54 4x030 240 0.50</p> <p><b>£7.42</b> + p &amp; p £1.72 + VAT £1.51 TOTAL £10.51</p>					<p><b>300 VA</b> 7x013 15+15 10.00 110 x 50mm 7x014 18+18 8.33 2.6Kg 7x015 22+22 6.82 Regulation 7x016 25+25 6.00 6% 7x017 30+30 5.00 7x018 35+35 4.28 7x026 40+40 3.75 7x025 45+45 3.33 7x033 50+50 3.00 7x028 110 2.72 7x029 220 1.36 7x030 240 1.25</p> <p><b>£10.88</b> + p &amp; p £2.05 + VAT £1.94 TOTAL £14.87</p>				
<p><b>30 VA</b> 1x010 6+6 2.50 70 x 30mm 1x011 9+9 1.66 0.45Kg 1x012 12+12 1.25 Regulation 1x013 15+15 1.00 18% 1x014 18+18 0.83 1x015 22+22 0.68 1x016 25+25 0.60 1x017 30+30 0.50</p> <p><b>£5.49</b> + p &amp; p £1.10 + VAT £0.99 TOTAL £7.58</p>					<p><b>160 VA</b> 5x011 9+9 8.89 110 x 40mm 5x012 12+12 6.66 1.9Kg 5x013 15+15 5.33 Regulation 5x014 18+18 4.44 8% 5x015 22+22 3.63 5x016 25+25 3.20 5x017 30+30 2.66 5x018 35+35 2.28 5x026 40+40 2.00 5x028 110 1.45 5x029 220 0.72 5x030 240 0.66</p> <p><b>£8.43</b> + p &amp; p £1.72 + VAT £1.52 TOTAL £11.67</p>					<p><b>500 VA</b> 8x016 25+25 10.00 140 x 60mm 8x017 30+30 8.33 4Kg 8x018 35+35 7.14 Regulation 8x026 40+40 6.25 4% 8x025 45+45 5.55 8x033 50+50 5.00 8x028 110 4.54 8x029 220 2.27 8x030 240 2.08</p> <p><b>£14.38</b> + p &amp; p £2.40 + VAT £2.50 TOTAL £19.30</p>				
<p><b>50 VA</b> 2x010 6+6 4.16 80 x 35mm 2x011 9+9 2.77 0.9Kg 2x012 12+12 2.08 Regulation 2x013 15+15 1.66 13% 2x014 18+18 1.38 2x015 22+22 1.13 2x016 25+25 1.00 2x017 30+30 0.83 2x028 110 0.45 2x029 220 0.22 2x030 240 0.20</p> <p><b>£6.13</b> + p &amp; p £1.35 + VAT £1.12 TOTAL £8.60</p>					<p><b>625 VA</b> 9x017 30+30 10.41 140 x 75mm 9x018 35+35 8.92 5Kg 9x026 40+40 7.81 Regulation 9x025 45+45 6.94 4% 9x033 50+50 6.25 9x042 55+55 5.68 9x028 110 5.68 9x029 220 2.84 9x030 240 2.60</p> <p><b>£17.12</b> + p &amp; p £2.55 + VAT £2.95 TOTAL £22.62</p>					<p><b>225 VA</b> 6x012 12+12 9.38 110 x 45mm 6x013 15+15 7.50 2.2Kg 6x014 18+18 6.25 Regulation 6x015 22+22 5.11 7% 6x016 25+25 4.50 6x017 30+30 3.75 6x018 35+35 3.21 6x026 40+40 2.81 6x025 45+45 2.50 6x033 50+50 2.25 6x028 110 2.04 6x029 220 1.02 6x030 240 0.93</p> <p><b>£9.81</b> + p &amp; p £2.05 + VAT £1.78 TOTAL £13.64</p>				

ALSO AVAILABLE  
Sizes up to and including 5KVA are  
manufactured to order.

For mail order please make your crossed cheques or postal orders payable to ILP Electronics Ltd. Barclaycard/Access welcome. Trade orders standard terms.

Post to: ILP Electronics Ltd, Graham Bell House, Roper Close, Canterbury CT2 7EP, Kent, England. Telephone (0227) 54778 Telex 965780.



WW - 006 FOR FURTHER DETAILS

# LANGREX SUPPLIES LTD

RST Climax House, Fallsbrook Rd., Streatham, London SW16 6ED RST  
Tel: 01-677 2424 Telex: 946708 RST

SEMICONDUCTORS				VALVES				INTEGRATED CIRCUITS													
TYPE	SERIES	SECONDARY	RMS	TYPE	SERIES	SECONDARY	RMS	TYPE	SERIES	SECONDARY	RMS	TYPE	SERIES	SECONDARY	RMS						
	No	Volts	Current		No	Volts	Current		No	Volts	Current		No	Volts	Current						
AA119	0.10	AS215	1.20	BC173	0.11	BD132	0.48	BF257	0.27	GEX541	5.00	0AZ207	1.50	OC205	2.75	ZTX504	0.21	2N1671	5.00	2N3819	0.30
AA199	0.10	AS216	1.10	BC177	0.28	BD136	0.40	BF259	0.27	GJ3M	1.50	OC210	2.50	OC206	2.75	ZTX531	0.24	2N1893	0.32	2N3820	0.39
AA330	0.17	AS217	1.00	BC178	0.28	BD137	0.40	BF336	0.34	KJ100A	0.45	OC221	2.50	OC207	2.75	ZTX550	0.25	2N1477	4.00	2N3823	1.60
AA330	0.17	AS220	2.30	BC179	0.28	BD137	0.40	BF338	0.36	MJ3E70	0.73	OC222	2.50	OC208	2.75	ZTX550	0.25	2N1478	4.00	2N3826	1.60
AA330	0.17	AS221	2.50	BC182	0.11	BD139	0.48	BF351	0.40	MJ3E71	0.71	OC223	2.50	OC209	2.75	ZTX550	0.25	2N1479	4.00	2N3830	0.17
AA330	0.17	AS222	2.50	BC183	0.11	BD140	0.50	BF352	0.40	MJ3E72	0.71	OC224	2.50	OC210	2.75	ZTX550	0.25	2N1480	4.00	2N3830	0.17
AA330	0.17	AS223	2.50	BC184	0.11	BD141	0.50	BF353	0.40	MJ3E73	0.71	OC225	2.50	OC211	2.75	ZTX550	0.25	2N1481	4.00	2N3830	0.17
AA330	0.17	AS224	2.50	BC185	0.11	BD142	0.50	BF354	0.40	MJ3E74	0.71	OC226	2.50	OC212	2.75	ZTX550	0.25	2N1482	4.00	2N3830	0.17
AA330	0.17	AS225	2.50	BC186	0.11	BD143	0.50	BF355	0.40	MJ3E75	0.71	OC227	2.50	OC213	2.75	ZTX550	0.25	2N1483	4.00	2N3830	0.17
AA330	0.17	AS226	2.50	BC187	0.11	BD144	0.50	BF356	0.40	MJ3E76	0.71	OC228	2.50	OC214	2.75	ZTX550	0.25	2N1484	4.00	2N3830	0.17
AA330	0.17	AS227	2.50	BC188	0.11	BD145	0.50	BF357	0.40	MJ3E77	0.71	OC229	2.50	OC215	2.75	ZTX550	0.25	2N1485	4.00	2N3830	0.17
AA330	0.17	AS228	2.50	BC189	0.11	BD146	0.50	BF358	0.40	MJ3E78	0.71	OC230	2.50	OC216	2.75	ZTX550	0.25	2N1486	4.00	2N3830	0.17
AA330	0.17	AS229	2.50	BC190	0.11	BD147	0.50	BF359	0.40	MJ3E79	0.71	OC231	2.50	OC217	2.75	ZTX550	0.25	2N1487	4.00	2N3830	0.17
AA330	0.17	AS230	2.50	BC191	0.11	BD148	0.50	BF360	0.40	MJ3E80	0.71	OC232	2.50	OC218	2.75	ZTX550	0.25	2N1488	4.00	2N3830	0.17
AA330	0.17	AS231	2.50	BC192	0.11	BD149	0.50	BF361	0.40	MJ3E81	0.71	OC233	2.50	OC219	2.75	ZTX550	0.25	2N1489	4.00	2N3830	0.17
AA330	0.17	AS232	2.50	BC193	0.11	BD150	0.50	BF362	0.40	MJ3E82	0.71	OC234	2.50	OC220	2.75	ZTX550	0.25	2N1490	4.00	2N3830	0.17
AA330	0.17	AS233	2.50	BC194	0.11	BD151	0.50	BF363	0.40	MJ3E83	0.71	OC235	2.50	OC221	2.75	ZTX550	0.25	2N1491	4.00	2N3830	0.17
AA330	0.17	AS234	2.50	BC195	0.11	BD152	0.50	BF364	0.40	MJ3E84	0.71	OC236	2.50	OC222	2.75	ZTX550	0.25	2N1492	4.00	2N3830	0.17
AA330	0.17	AS235	2.50	BC196	0.11	BD153	0.50	BF365	0.40	MJ3E85	0.71	OC237	2.50	OC223	2.75	ZTX550	0.25	2N1493	4.00	2N3830	0.17
AA330	0.17	AS236	2.50	BC197	0.11	BD154	0.50	BF366	0.40	MJ3E86	0.71	OC238	2.50	OC224	2.75	ZTX550	0.25	2N1494	4.00	2N3830	0.17
AA330	0.17	AS237	2.50	BC198	0.11	BD155	0.50	BF367	0.40	MJ3E87	0.71	OC239	2.50	OC225	2.75	ZTX550	0.25	2N1495	4.00	2N3830	0.17
AA330	0.17	AS238	2.50	BC199	0.11	BD156	0.50	BF368	0.40	MJ3E88	0.71	OC240	2.50	OC226	2.75	ZTX550	0.25	2N1496	4.00	2N3830	0.17
AA330	0.17	AS239	2.50	BC200	0.11	BD157	0.50	BF369	0.40	MJ3E89	0.71	OC241	2.50	OC227	2.75	ZTX550	0.25	2N1497	4.00	2N3830	0.17
AA330	0.17	AS240	2.50	BC201	0.11	BD158	0.50	BF370	0.40	MJ3E90	0.71	OC242	2.50	OC228	2.75	ZTX550	0.25	2N1498	4.00	2N3830	0.17
AA330	0.17	AS241	2.50	BC202	0.11	BD159	0.50	BF371	0.40	MJ3E91	0.71	OC243	2.50	OC229	2.75	ZTX550	0.25	2N1499	4.00	2N3830	0.17
AA330	0.17	AS242	2.50	BC203	0.11	BD160	0.50	BF372	0.40	MJ3E92	0.71	OC244	2.50	OC230	2.75	ZTX550	0.25	2N1500	4.00	2N3830	0.17
AA330	0.17	AS243	2.50	BC204	0.11	BD161	0.50	BF373	0.40	MJ3E93	0.71	OC245	2.50	OC231	2.75	ZTX550	0.25	2N1501	4.00	2N3830	0.17
AA330	0.17	AS244	2.50	BC205	0.11	BD162	0.50	BF374	0.40	MJ3E94	0.71	OC246	2.50	OC232	2.75	ZTX550	0.25	2N1502	4.00	2N3830	0.17
AA330	0.17	AS245	2.50	BC206	0.11	BD163	0.50	BF375	0.40	MJ3E95	0.71	OC247	2.50	OC233	2.75	ZTX550	0.25	2N1503	4.00	2N3830	0.17
AA330	0.17	AS246	2.50	BC207	0.11	BD164	0.50	BF376	0.40	MJ3E96	0.71	OC248	2.50	OC234	2.75	ZTX550	0.25	2N1504	4.00	2N3830	0.17
AA330	0.17	AS247	2.50	BC208	0.11	BD165	0.50	BF377	0.40	MJ3E97	0.71	OC249	2.50	OC235	2.75	ZTX550	0.25	2N1505	4.00	2N3830	0.17
AA330	0.17	AS248	2.50	BC209	0.11	BD166	0.50	BF378	0.40	MJ3E98	0.71	OC250	2.50	OC236	2.75	ZTX550	0.25	2N1506	4.00	2N3830	0.17
AA330	0.17	AS249	2.50	BC210	0.11	BD167	0.50	BF379	0.40	MJ3E99	0.71	OC251	2.50	OC237	2.75	ZTX550	0.25	2N1507	4.00	2N3830	0.17
AA330	0.17	AS250	2.50	BC211	0.11	BD168	0.50	BF380	0.40	MJ3E00	0.71	OC252	2.50	OC238	2.75	ZTX550	0.25	2N1508	4.00	2N3830	0.17
AA330	0.17	AS251	2.50	BC212	0.11	BD169	0.50	BF381	0.40	MJ3E01	0.71	OC253	2.50	OC239	2.75	ZTX550	0.25	2N1509	4.00	2N3830	0.17
AA330	0.17	AS252	2.50	BC213	0.11	BD170	0.50	BF382	0.40	MJ3E02	0.71	OC254	2.50	OC240	2.75	ZTX550	0.25	2N1510	4.00	2N3830	0.17
AA330	0.17	AS253	2.50	BC214	0.11	BD171	0.50	BF383													

# Accurate Digital Multimeters at Exceptional Prices

28 RANGES, EACH WITH FULL OVERLOAD PROTECTION

## SPECIFICATION MODELS 6010 & 7030

- 10 amp AC/DC
- Battery: Single 9V drycell. Life: 200 hrs
- Dimensions: 170 x 89 x 38mm.
- Weight: 400g inc. battery.
- Mode Select: Push Button.
- AC DC Current: 200µA to 10A
- AC Voltage: 200mV to 750V
- DC Voltage: 200mV to 1000V
- Resistance: 200Ω to 20MΩ
- Input Impedance: 10MΩ
- Display: 3 1/2 Digit 13mm LCD
- O/Load Protection: All ranges

**OTHER FEATURES:** Auto polarity, auto zero, battery low indicator, ABS plastic case with tilt stand, battery and test leads included, optional carrying case.

Quantity discount for trade on application.

NEW ANALOGUE METER WITH CONTINUITY BUZZER AND BATTERY SCALE

NEW HM102 BZ £13.00

## NEW HM 102 BZ SPECIFICATION

- DC Voltage: 0-25, 1, 2.5, 10, 25, 100, 250, 1000 volts 20,000 ohms/volt.
- AC Voltage: 0-10, 25, 100, 250, 1000 volts 10,000 ohms/volt.
- Decibels: -20 to +22dB
- DC Current: 0-50, 500µA, 0-5, 50, 500mA
- Ohmmeter: 0-6 Megohms in 4 ranges. 30 ohms Centre Scale
- Power Supply: One 1.5V size 'A' battery (incl)
- Size & Weight: 135 x 91 x 39mm, 280gr.


## HM 101 POCKET SIZE MULTIMETER SPECIFICATION

- DC & AC Voltage: 0-10, 50, 250, 1000 volts, 2000 ohms/volts
- Decibels: -10 to +22dB
- DC Current: 0-100mA
- Ohmmeter: 0-1 Megohm in 2 ranges, 60 ohms Centre Scale
- Power Supply: One 1.5V size 'A' battery (incl)
- Size & Weight: 90 x 60 x 29mm, 92gr. incl. battery
- Price: £5.50



Add 15% to your order for VAT. P&P is free of charge.

Payment by cheque with order



**ARON ELECTRONICS LTD.**

Cottrell House, 53-63 Wembley Hill Road, Wembley, Middlesex HA9 8BH, England

Telephone: 01-902 4321 (3 lines)

TELEX No 923985

WW - 007 FOR FURTHER DETAILS

# Toroidal Transformers

THE COTSWOLD "BUDGET RANGE" OFFERS BUILT-IN QUALITY COUPLED TO A RELIABLE DELIVERY SERVICE MOST TYPES FROM STOCK

IEC 65  
VDE 0550  
BS 415  
TO ORDER

PHONE  
TELEX, WRITE  
FOR DATA SHEET  
AND PRICE LIST

**Cotswold Electronics LTD.**

Unit T1, Kingsville Road, Kingsditch Trading Estate, Cheltenham GL51 9NX

Tel: 0242-41313

Telex: 897106

Sales Office in U.S.A.  
AVELINBERG INC.  
Peacock Alley 116, 1 Padanaram Road, Danbury, CT 06810 U.S.A.  
203-797-8698. Telex: 710-456-9984

WW - 012 FOR FURTHER DETAILS

## STEREO DISC AMPLIFIER 4

THE MOST THOROUGHLY RESEARCHED DISC AMPLIFIER THERE IS for Broadcasting, Disc Monitoring and Transfer



Supersedes Stereo Disc Amplifier 2. Unique Response Variable Filter which provides, through a single control knob, a 3dB turnover frequency variable between 13 and 4kHz but always with an appropriate phase and amplitude characteristic for psychoacoustic considerations. Ring or write for full specifications:

SURREY ELECTRONICS LTD., The Forge, Lucks Green, Cranleigh Surrey, GU6 7BG - Telephone: 0483 275997

## METAL FILM RESISTORS

100R	1k	10k	100k
110R	1k1	11k	110k
120R	1k2	12k	120k
130R	1k3	13k	130k
150R	1k5	15k	150k
160R	1k6	16k	160k
180R	1k8	18k	180k
200R	2k	20k	200k
220R	2k2	22k	220k
240R	2k4	24k	240k
270R	2k7	27k	270k
300R	3k	30k	—
330R	3k3	33k	330k
360R	3k6	36k	—
390R	3k9	39k	—
430R	4k3	43k	—
470R	4k7	47k	470k
510R	5k1	51k	—
560R	5k6	56k	—
620R	6k2	62k	—
680R	6k8	68k	—
750R	7k5	75k	—
820R	8k2	82k	820k
910R	9k1	91k	1M

1/4 Watt, 1% tolerance, 3p each. 89 Values, E24, see left. Minimum order £20. Minimum 10 pcs per value. VAT, P&P incl.

**SPECIAL OFFER**  
10 pcs of each value, 890 pcs  
**£25.30**

**SPECIAL 'POP' PACK**  
100 pcs: 100R, 1k, 4k7, 10k, 47k, 100k, 1M. 50 pcs: 330R, 470R, 1k5, 2k2, 3k3, 22k. Total 1000 pcs. £28.50.


One of each pack £50 only

ORION SCIENTIFIC LTD - 16 Orange Street - London WC2H 7ED

WW - 047 FOR FURTHER DETAILS

# Versatower:

A range of telescopic towers in static and mobile models from 7.5 to 36 metres with tilt-over facility enabling all maintenance to be at ground level.



Designed in accordance with CP3 Chapter V: part 2: 1972 for a minimum wind speed of 85 mph in conditions of maximum exposure and specified by professionals world-wide where hostile environments demand the ultimate in design, quality and reliability.

Suitable for mounting equipment in the fields of:

- Communications
- Security surveillance - CCTV
- Meteorology
- Environmental monitoring
- Geographical survey
- Defence range-finding
- Marine & aero navigation
- Floodlighting
- Airport approach lighting

Further details available on request.



Strumec Engineering Limited,  
Portland House, Coppice Side,  
Brownhills, Walsall, West Midlands,  
WS8 7EX, England.  
Telephone: Brownhills (05433) 4321.  
Telex: 335243 SEL G.

WW - 020 FOR FURTHER DETAILS

hi! performance hi! competitive hi!

# MORE people are buying TRIO

\*\*\* FOR \*\*\*

## MORE DISPLAY

nearly 50% more with the NEW LARGE 6 inch rectangular CRT with illuminated inner face graticule, 6KV accelerator voltage for a brighter, higher resolution display with guaranteed accuracy.

\*\*\*


## MORE SENSITIVITY

1 milli Volt per cm in the vertical axis, valuable for observing complex low level waveforms especially with 20 nano sec per cm Sweep Speed.

\*\*\*

## MORE FACILITIES

like push-button MODES inc. Add, Sub, Alt and Chop - V mode trigger SOURCE - NEW super video sync - Front panel control of Astig, Trace rotation, Scale illum and X-Y - Chan I O/P, Int. Mod etc, etc.



**NEW** 20 MHz 1mV/cm  
CS 1022 Dual Trace  
CS 1020 Single Trace

**NEW** 10 MHz 1mV/cm  
CS 1012 Dual Trace  
CS 1010 Single Trace

AT REAL VALUE FOR MONEY PRICES

\*\*\*

Fully Guaranteed for 2 years inc.  
Free 'pick up' and 'return'



In a hurry? Then ring (0799) 24922

House of Instruments,  
Clifton Chambers, 62 High Street,  
Saffron Walden, Essex CB10 1EE  
Telephone: (0799) 24922 Telex: 818750

Ask for FREE DATA

# TRIO

# hi!

hi! competitive hi! House of Instruments Ltd.


WW - 028 FOR FURTHER DETAILS

# GET BIG POWER



## ILP Modular Amplifiers the third generation

Due to continuous improvements in components and design ILP now launch the largest and most advanced generation of modules ever.



## WE'RE INSTRUMENTAL IN MAKING A LOT OF POWER

In keeping with ILP's tradition of entirely self-contained modules featuring, integral heatsinks, no external components and only 5 connections required, the range has been optimized for efficiency, flexibility, reliability, easy usage, outstanding performance, value for money.

With over 10 years experience in audio amplifier technology ILP are recognised as world leaders.



Module Number	Output Power Watts rms	Load Impedance $\Omega$	DISTORTION T.H.D. Typ at 60Hz/1KHz	I.M.D. 7KHz 4:1	Supply Voltage Typ	Size mm	WT gms	Price inc. VAT
HY80	15	4-8	<0.005%	<0.006%	$\pm 18$	76 x 68 x 40	240	£8.40
HY81	30	4-8	<0.005%	<0.006%	$\pm 25$	76 x 68 x 40	240	£9.55
HY6060	30 + 30	4-8	<0.005%	<0.006%	$\pm 25$	120 x 78 x 40	420	£18.69
HY124	60	4	<0.005%	<0.006%	$\pm 26$	120 x 78 x 40	410	£20.75
HY128	60	8	<0.005%	<0.006%	$\pm 35$	120 x 78 x 40	410	£20.75
HY244	120	4	<0.005%	<0.006%	$\pm 35$	120 x 78 x 50	520	£25.47
HY248	120	8	<0.005%	<0.006%	$\pm 50$	120 x 78 x 50	520	£25.47
HY364	180	4	<0.005%	<0.006%	$\pm 45$	120 x 78 x 100	1030	£38.41
HY368	180	8	<0.005%	<0.006%	$\pm 60$	120 x 78 x 100	1030	£38.41

Protection: Full load line. Slew Rate: 15v/ $\mu$ s. Rise time: 5 $\mu$ s. S/N ratio: 100db. Frequency response (-3dB) 15Hz - 50KHz. Input sensitivity: 500mV rms. Input impedance: 100K $\Omega$ . Damping factor: 100Hz > 400.

Module Number	Module	Functions	Current Required	Price inc. VAT
HY6	Mono pre amp	Mic/Mag. Cartridge/Tuner/Tape/Aux + Vol/Bass/Treble	10mA	£7.60
HY66	Stereo pre amp	Mic/Mag. Cartridge/Tuner/Tape/Aux + Vol/Bass/Treble/Balance	20mA	£14.32
HY73	Guitar pre amp	Two Guitar (Bass Lead) and Mic + separate Volume Bass Treble + Mix	20mA	£15.36
HY78	Stereo pre amp	As HY66 less tone controls	20mA	£14.20

Most pre-amp modules can be driven by the PSU driving the main power amp. A separate PSU 30 is available purely for pre amp modules if required for £5.47 (inc. VAT). Pre-amp and mixing modules in 18 different variations. Please send for details.

Mounting Boards For ease of construction we recommend the B6 for modules HY6-HY13 £1.05 (inc. VAT) and the B66 for modules HY66-HY78 £1.29 (inc. VAT).

POWER SUPPLY UNITS (Incorporating our own toroidal transformers)

Model Number	For Use With	Price inc. VAT	Model Number	For Use With	Price inc. VAT	Model Number	For Use With	Price inc. VAT
PSU 21X	1 or 2 HY30	£11.93	PSU 52X	2 x HY124	£17.07	PSU 72X	2 x HY248	£22.54
PSU 41X	1 or 2 HY60, 1 x HY6060, 1 x HY124	£13.83	PSU 53X	2 x MOS128	£17.86	PSU 73X	1 x HY364	£22.54
PSU 42X	1 x HY128	£15.90	PSU 54X	1 x HY248	£17.86	PSU 74X	1 x HY368	£24.20
PSU 43X	1 x MOS128	£16.70	PSU 55X	1 x MOS248	£19.52	PSU 75X	2 x MOS248, 1 x MOS368	£24.20
PSU 51X	2 x HY128, 1 x HY244	£17.07	PSU 71X	2 x HY244	£21.75			

Please note: X in part no. indicates primary voltage. Please insert '0' in place of X for 110V, '1' in place of X for 220V (Europe), and '2' in place of X for 240V (U.K.) All units except UC1 incorporate our own toroidal transformers.

Module Number	Output Power Watts rms	Load Impedance $\Omega$	DISTORTION T.H.D. Typ at 1KHz	I.M.D. 7KHz 4:1	Supply Voltage Typ	Size mm	WT gms	Price inc. VAT
MOS 128	60	4-8	<0.005%	<0.006%	$\pm 45$	120 x 78 x 40	420	£30.41
MOS 248	120	4-8	<0.005%	<0.006%	$\pm 55$	120 x 78 x 80	850	£39.86
MOS 364	180	4	<0.005%	<0.006%	$\pm 55$	120 x 78 x 100	1025	£45.51

Protection: Able to cope with complex loads without the need for very special protection circuitry (fuses will suffice). Slew rate: 20v/ $\mu$ s. Rise time: 3 $\mu$ s. S/N ratio: 100db. Frequency response (-3dB) 15Hz - 100KHz. Input sensitivity: 500mV rms. Input impedance: 100K $\Omega$ . Damping factor: 100Hz > 400.

### 'NEW to ILP' In Car Entertainments

C15 Mono Power Booster Amplifier to increase the output of your existing car radio or cassette player to a nominal 15 watts rms. Very easy to use.

Robust construction. £9.14 (inc. VAT)

Mounts anywhere in car.

Automatic switch on.

Output power maximum 22w peak into 4 $\Omega$ .

Frequency response (-3dB) 15Hz to 30KHz. T.H.D. 0.1% at 10w 1KHz

S/N ratio (DIN AUDIO I) 80dB. Load Impedance 3 $\Omega$ .

Input Sensitivity and Impedance (selectable) 700mV rms into 15K $\Omega$  3V rms into 8 $\Omega$ .

Size 95 x 48 x 50mm. Weight 256 gms.

C1515 Stereo version of C15. £17.19 (inc. VAT)

Size 95 x 40 x 80. Weight 410 gms.

# WITH A LOT OF HELP FROM ILP ELECTRONICS LTD

## PROFESSIONAL HI-FI THAT EVERY ENTHUSIAST CAN HANDLE...

### Unicase

Over the years ILP has been aware of the need for a complete packaging system for its products, it has now developed a unique system which meets all the requirements for ease of assembly, adaptability, ruggedness, modern styling and above all price.

Each Unicase kit contains all the hardware required down to the last nut and bolt to build a complete unit without the need for any special tools.

Because of ILP's modular approach, "open plan" construction is used and final assembly of the unit parts forms a compact aesthetic unit. By this method construction can be achieved in under two hours with little experience of electronic wiring and mechanical assembly.

### Hi Fi Separates

UC1 PRE AMP UNIT: Incorporates the HY78 to provide a "no frills", low distortion, (<0.01%), stereo control unit, providing inputs for magnetic cartridge, tuner, and tape/monitor facilities. This unit provides the heart of the hi fi system and can be used in conjunction with any of the UP Unicase series of power amps. For ultimate hum rejection the UC1 draws its power from the power amp unit.

POWER AMPS: The UP series feature a clean line front panel incorporating on/off switch and concealed indicator. They are designed to complement the style of the UC1 pre-amp. Performance for each unit which includes the appropriate power supply, is as specified on the facing page.

### Power Slaves



Our power slaves, which have numerous uses i.e. instrument, discotheque, sound reinforcement, feature in addition to the hi fi series, front panel input jack, level control, and a carrying handle. Providing the smallest, lowest cost, slave on the market in this format.

#### UNICASES

HIFI Separates	Price inc. VAT
UC1 Preamp	£29.95
UP1X 30 + 30W/4-8 $\Omega$ Bipolar Stereo HiFi	£54.95
UP2X 60W/4 $\Omega$ Bipolar Mono HiFi	£54.95
UP3X 60W/8 $\Omega$ Bipolar Mono HiFi	£54.95
UP4X 120W/4 $\Omega$ Bipolar Mono HiFi	£74.95
UP5X 120W/8 $\Omega$ Bipolar Mono HiFi	£74.95
UP6X 60W/4-8 $\Omega$ MOS Mono HiFi	£64.95
UP7X 120W/4-8 $\Omega$ MOS Mono HiFi	£84.95

Power Slaves	Price inc. VAT
US1X 60W/4 $\Omega$ Bipolar Power Slave	£59.95
US2X 120W/4 $\Omega$ Bipolar Power Slave	£79.95
US3X 60W/4-8 $\Omega$ MOS Power Slave	£69.96
US4X 120W/4-8 $\Omega$ MOS Power Slave	£89.95

Please note X in part number denotes mains voltage. Please insert '0' in place of X for 110V, '1' in place of X for 220V (Europe), and '2' in place of X for 240V (U.K.) All units except UC1 incorporate our own toroidal transformers.



TO ORDER USING OUR FREEPOST FACILITY Fill in the coupon as shown, or write details on a separate sheet of paper, quoting the name and date of this journal. By sending your order to our address as shown at the bottom of the page opposite, with FREEPOST clearly shown on the envelope, you need not stamp it. We pay postage for you. Cheques and money orders must be crossed and made payable to I.L.P. Electronics Ltd. if sending cash, it must be by registered post. To pay C.O.D. please add £1 to TOTAL value of order.

PAYMENT MAY BE MADE BY ACCESS OR BARCLAYCARD IF REQUIRED

Post to: ILP Electronics Ltd., Freepost, 5 Graham Bell House, Roper Close, Canterbury, CT2 7EP, Kent, England. Telephone: (0227) 54778. Technical: (0227) 64723. Telex: 965780.

Please send me the following \_\_\_\_\_  
 Total purchase price \_\_\_\_\_  
 I enclose Cheque  Postal Orders  Int. Money Order   
 Please debit my Access/Barclaycard No. \_\_\_\_\_  
 Name \_\_\_\_\_  
 Address \_\_\_\_\_  
 Signature \_\_\_\_\_

WW - 005 FOR FURTHER DETAILS



# No Contest!

The SC61 waveform analyser from Sencore stands head and shoulders above any other oscilloscopes for speed, accuracy and versatility even from semi-skilled operators — **and we're prepared to come round and prove it.**

For an on-site test and more information:  
**Mike Dawson 01-897 6446.**



**Fieldtech  
Heathrow**

**Fieldtech Heathrow Limited**  
Huntavia House 420 Bath Road  
Longford Middlesex UB7 0LL  
Telex: 23734 FLDTEC G

WW - 022 FOR FURTHER DETAILS



## FOR EVERYTHING IN ELECTRONICS Wirelessworld

**Editor:**  
PHILIP DARRINGTON  
01-661 3128

**Deputy Editor:**  
GEOFFREY SHORTER, B.Sc.  
01-661 8639

**Technical Editor:**  
MARTIN ECCLES  
01-661 8638

**News Editor:**  
DAVID SCOBIE  
01-661 8632

**Drawing Office Manager:**  
ROGER GOODMAN  
01-661 8690

**Technical Illustrator:**  
BETTY PALMER

**Advertisement Manager:**  
BOB NIBBS, A.C.I.I.  
01-661 3130

BARBARA MILLER  
01-661 8640

**Northern Sales:**  
HARRY AIKEN  
061-872 8861

**Midland Sales:**  
BASIL MCGOWAN  
021-356 4838

**Classified Manager:**  
BRIAN DURRANT  
01-661 3106

IAN FAUX  
01-661 3033

**Production:**  
BRIAN BANNISTER  
(Make-up and copy)  
01-661 8648

**Publishing Director**  
DAVID MONTGOMERY  
01-661 3241

## Engineering, not politics

Even in the pre-war days when Japanese industry was best known for its imitative tendencies, its imitations were often better products than the originals. Modern Japanese engineering demonstrates little need to take other nations' ideas and has made Japan an industrial giant.

In design and reliability, products from Japan have gained a formidable reputation for quality — to the extent that they now dominate world markets in several important groups of product. With the exception of those Western companies who refuse to be intimidated and who also possess reputations for high quality, European and American firms tend to see the reply to imports from the Far East in political, rather than in commercial and engineering terms. They require the Japanese to restrict their exports voluntarily and frequently ask politicians to apply pressure to that end.

An approach as negative as that to the imbalance of trade can surely not succeed over a long period. In reply to huge imports from Japan, the proper action is to redress the balance by exporting, not politicking. Admittedly, it is not easy to sell to the Japanese but, according to the Department of Trade, "formal barriers are disappearing and the desire of the Japanese to be self-supporting — the 'Buy Japanese' policy — is on the way out. Import tariffs on over 2000 products have now been reduced to a lower level than those of European countries or the US".

In common with any other manufacturers, the Japanese want the best products at the lowest price. If a UK exporter can supply well-designed products, either to fill a gap in Japanese production or to beat local efforts on quality or price, he will win orders.

An important point to watch is that the

customer must be given what he wants, not what the vendor thinks he ought to want. Time and time again, Western makers of, for example, audio equipment have introduced new models in enclosures which they thought were sensible and attractive, in spite of the fact established by the successful marketing of Japanese products that customers prefer satin chrome, coloured lights and masses of knobs and switches. Presentation is a matter of taste and who is to say that the customers are wrong?

This office recently received a note from a maker of illuminated switches, in which he claimed that his company has taken massive orders from Japan and is now going into Hong Kong. The customers say that the switches are visually attractive to them, they are reliable and are cheaper to buy than locally made types: there is therefore a ready sale for them in Japan.

British industry began the industrial revolution and was able to dominate world markets when it was possible to tell customers what they could have and why they should want it. In the words of Adam Smith: we "founded a great empire for the sole purpose of raising up a people of customers". Perhaps more of our industrial base would still be firm if our manufacturers had recognised a good deal earlier that the world has developed while they were not looking, and will not now buy equipment that is not designed and made with customers in mind.

George Moore said that "a man travels the world over in search of what he needs and returns home to find it". Perhaps we could reduce the number of homing customers by making sure they find what they need here, not what we feel they should need.

## Out of this world for value!

**ET** Not our extra-terrestrial friend, but a versatile bench power supply —

— the ET30/2

For a modest price it will provide you with:

2 outputs at 0 to 30 volts d.c. at 1 amp or  
2 outputs at 0 to 15 volts d.c. at 2 amps or  
0 to 30 volts d.c. at 2 amps or 0 to 60 volts  
d.c. at 1 amp or 0 to 15 volts d.c. at 4 amps.

from



**Farnell**



Send for details now from: FARNELL INSTRUMENTS LIMITED · WETHERBY · WEST YORKSHIRE LS22 4DH  
TELEPHONE (0937) 61961 · TELEX 557294 FARIST G | REGIONAL OFFICE TELEPHONE (05827) 66123/4 · TELEX 826307

WW - 034 FOR FURTHER DETAILS

## C.B. market collapse?

The Home Office tells me that fewer new CB licences were issued during the first quarter of 1983 than the number of licences that lapsed. At the end of April valid licences totalled 289,108 compared with 313,318 at the end of November 1982. The percentage of renewed licences seems to vary widely from month to month: 42% in October 1982; 72% in November; and only 27% in December. Fidelity Radio has claimed that its CB division lost £700,000 in the year to March 1983 and the firm has since disposed of the division "for a nominal sum", blaming "the collapse of the CB radio market".

The Japanese radio communications industry seems to be setting its sights on the para-military field with increasing emphasis on such products as v.h.f./u.h.f. manpack equipment providing digital encryption. European communications firms have long been worried at the prospect of a full-scale entry of Japan into defence electronics.

## Antennas galore!

I have to confess that I did not attend ICAP 83 (Third International Conference on Antennas and Propagation, London, April 1983) but I have been making up for this omission by ploughing (or at least skimming) through the two thick volumes of papers (IEE Conference Publication 219). This is no lightweight matter: 193 papers filling 961 pages from authors whose names literally span A to Z (O. Aboul-Atta to Zi Shen Lui in volume 1 and I. Y. Ahmed to Z. W. Zhang in volume 2). One really does wonder how many of the delegates managed, in four days, to absorb almost 200 papers – or indeed whether thereby they learned much that was of vital importance to them. These large international conferences, free from the constraints of "commercial" exhibitions do tend to take off into the stratosphere or, more appropriately in this case, the ionosphere. Radio propagation and aerials (to get back on the editorial wavelength of *Wireless World*) are both subjects that envelope themselves in an unusual degree of mythology and mysticism. I hasten to add that there are interesting and some thoroughly practical papers among the 193 but it could be argued that, since these come over clearly from the printed page, attendance was possibly not the optimum learning process. It is always said, of course, that the most interesting discussions at conferences are those that take place out in the bar rather than in the conference hall. Experience tends to support that view – although the more memorable conversations seldom seem to relate to conference topics!

The difficulty for the non-specialist reader (or delegate) is to decide what really

is new and what is not. ICAP 83 included some useful invited survey papers, though apparently prepared independently of the other contributions.

A. W. Rudge of ERA Technology Ltd in "Current trends in antenna technology and prospects for the next decade" highlights three major themes, the influence of environmental factors, the impact of v.l.s.i. electronics and the continuous search for improved characteristics. He aptly quotes Professor Mayes of the University of Illinois: "The popular conception in 1950 was that electromagnetics was a mature field and that it was improbable that any new discoveries remained to be made in the field of antennas. The development of frequency-independent antennas was certainly evidence to the contrary. Today similar sentiment seems to be prevalent. History shows it prudent to be sceptical." 193 papers suggests there must still be rich ore to be mined in these subjects.

## Moral persuasion?

The BBC took the opportunity, as hosts of the 17th European DX Council Conference, to launch another strong attack on the 10% increase in "jamming" of h.f. broadcasts by the USSR since the Polish crisis of December 1981. Douglas Muggidge, managing director of BBC External Broadcasting, protested "The h.f. bands are very congested. There is more broadcasting than they can contain satisfactorily. A conference is soon to be held, the first session in 1984, with the task of trying to plan and regularize this position. Its job is made extremely difficult, if not impossible, by the large amount of 'deliberate, harmful interference' – better known as 'jamming' – which is present within the shortwave bands.

Many people have not been aware of the extent to which this is a worldwide problem. Every country that broadcasts on h.f. and all who listen on h.f. are affected. Perhaps there may be a solution. If there is not, then it is difficult to see how any order can be brought out of the chaos that exists at certain times of the day".

The BBC apparently hopes that "moral persuasion", plus the fact that the USSR is anxious that its own transmissions should be well received throughout the world may prove a powerful argument to reduce jamming. Keith Edwards presented data showing co-channel and adjacent-channel jamming as monitored in Vienna and at Caversham that underline the extent of the current problem. This is particularly true on the 15, 17 and 21MHz broadcast bands, with between 70-80% of channels (pre-WARC 1979) affected from about 1200 to 1800 hours on 17MHz, over 60% on all three bands around 1600 hours, etc. Other statistical data show the massive use made of the 6MHz broadcast band. Although

WARC 1979 gave Western broadcasters much less additional spectrum than they sought, over 30 countries are already using the new frequencies despite the WARC agreement not to do so until after the 1984-86 planning conferences. There are also a number of countries using parts of the spectrum not allocated to broadcasting. China, for example, has quit out-of-band operation at 7.0 to 7.1MHz but is now using many channels around 8.3MHz!

A happier prospect arises from the use of satellite feeds. The BBC are using digital audio at 128kilobits (two adjacent 64kb/s speech channels) to distribute programmes via satellite to overseas relays; these links have uniform frequency response to 6kHz, distortion around 1% or less and s:n ratio of about 50dB. One result is that the BBC may soon reduce long-distance h.f. coverage from the UK of areas better served from the relay bases of the BBC or the Foreign & Commonwealth Office: Atlantic Relay on Ascension Island; Caribbean Relay (Antigua); East Mediterranean Relay (Cyprus); Far Eastern Relay (Singapore); Eastern Relay (Masira) and (later) a possible relay at Hong Kong, and an East African Relay in the Indian Ocean.

## Stereo all ways

A new twist to the American a.m.-stereo fight between the four competing systems has been given by demonstrations at NAB of the prototype of a new Sansui multisystem a.m. stereo tuner, type TU-S77AMX, that uses a Japanese-manufactured single-chip decoder handling signals in any of the four systems. A.m.-stereo in the USA has been delayed by the FCC "leave it to the market place" decision. By April 1983 there were 50 stations using the Harris system, around 30-plus with Kahn, six using Motorola and three using Magnavox out of some 4600 commercial a.m. stations. However, retail price of the Sansui tuner is around \$400 and their car radio tuner around \$50. Even with multisystem decoding it will still be necessary for American broadcasters individually to make the difficult choice between the four systems.

## Mercurial thoughts

I do not know what the new Mercury communications network will do for British business – but it must already be helping our printers and typographers and illustrators. That is if the three very large and very glossy advertising brochures that have come my way are anything to go by. They proudly proclaim: "Mercury is the new force in communications . . . it exists to facilitate the dynamic interchange of ideas that are vital to your business . . . Mercury means communications. At the speed of thought". The global village, I am told, is

no longer a concept but a reality. Pages are filled with large colour pictures of eggs, a charming little chameleon, a chisel, a honeycomb and a small globe in the palm of a giant hand. All this represents "a new approach to communications for the '80s and beyond".

Just the thing presumably for the businessman who has caught a chameleon, intends to put it inside an egg-shell after slicing the top off with his chisel, and is not afraid of being stung by bees. Or is my dynamic interchange of ideas failing me?

## In brief

Costs of the NASA Space Telescope project may exceed \$1000-million instead of the original estimate of \$435m and is unlikely to be launched until 1986 or later . . . Launch of the second Tracking and Data Relay Satellite (TDRS) is being delayed in the hope that NASA can find out what went wrong with the first launch last March . . . A spate of fraud and cheating – "doctoring" and "massaging" data – in scientific research papers has led to Nicholas Wade of the *New York Times* claiming: "It is not just a matter of rotten apples in the barrel but something to do with the barrel itself" . . . the opportunities to cheat are becoming more frequent because of the readiness of laboratory chiefs to put their names to papers prepared by junior colleagues with little or no supervision".

# AMATEUR RADIO

## Planning the bands

The problems of spectrum regulation are increasingly reflected inside the amateur bands. There have been some gains – 7000 to about 7030kHz or so is now refreshingly clear of Radio Beijing (Radio Peking) in the evenings and has become a far more usable piece of spectrum. The upper part of the world "exclusive" 7000-7100kHz however, still includes broadcast "intruders" such as Radio Tirana on 7065kHz.

But there is increasing unease within the amateur movement over the future of "voluntary band-planning".

For very many years mandatory sub-band allocations have been part of North American amateur licensing in the USA and Canada, to provide exclusive A1A (c.w.) segments and also in connection with American "incentive licensing" whereby higher "grades" are given access to additional segments of the bands.

Until the immediate post-war period no attempt was made to segment the fre-

quency bands available to British amateurs. In 1948 the RSGB set-up a working party (I was a member) which, *inter-alia*, recommended a voluntary h.f. band-plan (our first effort was so unpopular that we promptly revised it). Basically this followed North American practice in locating exclusive A1A segments at the low-frequency ends of the bands, and later formed the basis of the IARU Region 1 recommendations. These also took into account the then still rare use of r.t.t.y., although neither IARU or RSGB are official regulatory bodies.

As the years have gone by the band-plan has been extended to v.h.f. and u.h.f. bands and covers more and more modes and special activities, offering protection to minority interests, such as "raynet" emergency services, beacons, space satellites, "local" and "long-distance" working, repeaters and dividing bands into simplex channels, etc.

The IARU decided that, in view of the limited (50kHz) bandwidth, there should be no s.s.b. on the new 10.1MHz band (for different reasons the Home Office has temporarily similarly restricted UK operation on 18 and 24MHz). Where countries, such as South Africa, have declined to follow these recommendations, both IARU Region 1 Bureau and the RSGB officials have separately urged the South Africans to reconsider their decision. Being primarily a c.w. operator, I personally benefit from the new IARU recommendations, but nevertheless it does raise important matters of principle: are such organizations as the IARU justified in assuming a "regulatory" role that goes well beyond the original concepts of "voluntary bandplanning" without first providing greater "accountability" to those whose activities are being restricted? Individual amateurs have no direct control over IARU decisions, member societies have one vote per member, regardless of the size of the individual societies.

The 1983 IARU statistics show that there are now roughly 1.8-million amateur radio operators world-wide, using 1.4-million stations. Licensed members belonging to IARU member-societies are, however, under 450,000, despite the fact that 22% of the countries make membership of their national society an obligatory condition of the licence. The RSGB is listed as having, as members, precisely 50% of the UK's 40,000 licensed amateurs, of whom the majority are v.h.f.-only operators. In such circumstances can "voluntary bandplanning" continue to work?

## No r.m.s. power!

W. J. Omer, G3DOJ, who lectures in electrical and electronic engineering in higher education, is concerned to find that some 90% of his students believe that power in an a.c. circuit can correctly be

defined as an r.m.s. quality. The term r.m.s. watts has been creeping into the literature for the past 20 years – stemming largely from the audio field where it first came to be used to distinguish between "continuous average output" ratings and "music power" ratings (now tending to be replaced by "dynamic headroom") and the even less demanding peak envelope power rating.

Bill Omer has for some time been waging virtually a one-man crusade against 'r.m.s. power' which, since the definitions of r.m.s. voltage and current in an a.c. circuit are themselves derived from power, is a technical nonsense. He notes that 'r.m.s. power' has spread from the audio field to r.f. amplifiers and transmitter ratings in the editorial and advertising columns of many technical journals. When challenged some writers and firms have dismissed his objections as semantics while others insist that power is an r.m.s. quantity. To Bill Omer, r.m.s. watts is as ludicrous as 'average feet'.

A problem for the transmitter engineer is that "continuous wave" or c.w. has come to mean the A1A mode which is far from continuous. Nevertheless there do seem very good reasons for *not* using either r.m.s. watts or even watts (r.m.s.)!

## Notes and news

Since June 1 the Home Office has imposed a 50 per cent increase in the annual amateur radio licence fee: from £8 to £12. This means that with RAE, Morse Test fees, training fees, travelling expenses, etc, it now costs around £50 or more to obtain a Class A transmitting licence issued for purposes of "self-training, inter-communication and technical investigations". It seems regrettable that at a time when emphasis is being placed on the need to encourage expansion of "sun-rise industries" such high barriers are being erected, affecting particularly the younger enthusiasts, or those who may later be seeking employment in the still-expanding communications field.

There must be a diminishing number of people who can recall actually hearing Pip Eckersley announcing that they were listening to "Two Emma Toc (2 MT) Writtle testing". The historic callsign, converted to G2MT, was due to come on the air on July 2 and should be heard frequently later this year. The Home Office has re-allocated the callsign at the request of the recently formed "Marconi Radio Society", formed by enthusiasts at the Stanmore headquarters of Marconi Space and Defence Systems.

The RSGB has decided to hold future annual National Amateur Radio Exhibitions and Conventions at the National Exhibition Centre in Birmingham. The 1984 dates are April 28-29.

PAT HAWKER, G3VA

# Typewriter to daisywheel printer

With an Olivetti Praxis typewriter, this interface makes one of the cheapest word-processing printers around. It can be used with any microcomputer fitted with an RS232 or RS423 port.

by Neil Duffy

A typewriter-printer offers a number of advantages over a conventional daisy-wheel printer with no keyboard. For example, headings can be added to its output and margins set from the keyboard without the requirement to send special control codes from the computer, although this can be done if required. When not in use as a printer the typewriter can still be used in the normal manner.

The typewriter chosen for conversion here is the Olivetti Praxis series compact typewriter which was one of the first electronic typewriters and is well proven. It is also used as the basis of a number of commercially available printers and has turned out to be an excellent choice for this application. It is available in two versions, the Praxis 30 and the Praxis 35. Both feature interchangeable daisywheels, automatic correction of the last ten characters typed, and cartridge ribbon loading with a choice of correctable, carbon or fabric ribbons. The two models are almost identical but the 35 has a type-head position indicator and keyboard selection of 10, 12 or 15 characters per inch. Type pitch on the Praxis 30 is preset in the factory by means of links on the circuit board.

Daisy-wheel printers are in general much slower than their dot-matrix or thermal counterparts and are intended for use where letter quality output is required. They are not ideal for day to day listing of programs because of their relatively low speed. The basic typewriter mechanism is capable of a maximum print speed of around 8 to 10 characters per second and so a standard baud rate of 75 was chosen for the computer-interface to give a print speed of 7.5 characters per second.

A special feature of the interface is the provision of an electronic paper sensor on the typewriter to halt the computer output when the paper has run out. This feature is seldom provided even on high cost printers but has been found to be invaluable when errors are made in estimating the length of text that can be printed on a page.

The typewriter keyboard circuit (Fig. 1) operates on a matrix scanning principle. Each of the matrix columns is pulsed low

in turn. When a key is pressed the appropriate pulse is fed on to a particular keyboard matrix row. The typewriter electronics uses the row and pulse timing information to determine which key has been pressed.

The interface (Fig. 2 and Fig. 3) consists of a circuit board powered from the typewriter 5V power supply. Connection to the typewriter is made via a 40-way ribbon cable. In the interface, data from the computer is received by a uart and decoded by eeprom IC<sub>4</sub>. The three least significant bits output from the eeprom are fed to multiplexer IC<sub>6</sub> which has its inputs connected to the keyboard columns and which selects the appropriate strobe pulse. The next three bits from the eeprom route

the selected pulse via demultiplexer IC<sub>7</sub> to the selected keyboard row. The seventh bit controls the typewriter shift function and the eighth triggers a circuit which signals back to the computer to halt data transmission until the typewriter has completed a carriage-return, line-feed operation.

## Circuit operation

Incoming serial data is buffered by the RS232 receiver IC<sub>1</sub> and fed to the uart IC<sub>2</sub> which decodes the serial data and presents it in parallel form to the eeprom IC<sub>4</sub>. The clock to the uart is derived from a 2.4576MHz crystal via the divider IC<sub>3</sub>, configured for 75 baud operation and providing clock pulses to the uart at 16 times this rate. The uart must be set up to match the format of the incoming serial data from the computer. This is done by selecting links on the circuit board according to Table 1.





Fig. 1. Typewriter keyboard matrix: columns are each pulsed low in turn and pressing a key connects a column to a row. For clarity, diagram shows lower-case characters only.



When a data word is received by the uart it generates a high-going data-ready signal which turns off Tr<sub>1</sub> releasing the short circuit across C<sub>1</sub> on the 555 timer IC<sub>5</sub>. Capacitor C<sub>1</sub> charges up towards 5V and at the end of a time period of approximately 70ms reaches the timer threshold voltage level. The output from the 555 goes low and resets the data-ready signal from the uart. Transistor Tr<sub>1</sub> turns on, discharging C<sub>1</sub> until the voltage on C<sub>1</sub> falls below the timer trigger voltage. The 555 output then reverts to the high state. The data-ready signal from the uart is used to strobe data to the keyboard via IC<sub>9</sub>.

The eeprom is used to convert the incoming ASCII code from the computer into an output code suitable for energising the keyboard rows at the correct time. The contents of the eeprom are shown in Table 2. The eeprom is programmed to cause the typewriter to print spaces in place of ASCII codes for which the daisy-wheel has no corresponding symbol. ASCII codes from 0 to 32 are programmed to cause the typewriter to set and clear tabs, margins and so on.

During typewriter carriage-return/line-feed operations the data output from the computer must be halted by setting negative the clear-to-send (CTS) line on its RS232 port. This is done to prevent data loss caused by the typewriter buffer overflowing. When a carriage return signal is received from the computer, IC<sub>10b</sub>

Fig. 2. Incoming serial data from the computer is converted by the interface into parallel data in a form suitable for connection to the keyboard matrix of the typewriter. IC<sub>1</sub> is a section of an MC1489 line-receiver device.

latches with its  $\bar{Q}$  output low. The  $\bar{Q}$  output is reset to the high state when S<sub>1</sub> on the interface has completed a line-feed operation. This latter is detected by monitoring an existing limit switch on the line-feed mechanism.

For the handshake circuit to operate correctly, the typewriter must perform a carriage-return and then wait until the print head has returned to the left margin before performing a line-feed and thus operating the limit switch. If this is to happen the computer has to output a carriage-return and a line-feed symbol in the correct sequence. Because there is no convention for the sequence the interface has to allow for both possibilities. This is done by connecting a link on the interface board to select data either from locations 0 to 127 or from locations 128 to 255 on the eeprom. The data in the first set of locations is identical to that in the second except that in the second set, incoming carriage-return commands cause the printer to carry out a line-feed operation and line-feeds cause it to carry out a carriage-return.


The paper sensor is a reflective opto-

switch device with built-in infra-red led. Resistors R<sub>1</sub>, R<sub>3</sub> and the sensitivity adjusting potentiometer R<sub>2</sub> are mounted on a small circuit board which is attached to the sensor mounting bracket. The paper-low signal from the sensor is fed back along the ribbon cable to the interface card.

Paper-low signals are inhibited by IC<sub>8</sub> until the CR output from the eeprom indicates that a carriage return has been received from the computer. If the paper is low, then at the end of the current print line IC<sub>10a</sub> latches with its Q output low. Led<sub>1</sub> lights and Tr<sub>2</sub> is turned off sending the CTS line to the computer negative to prevent any further data transfer. IC<sub>10a</sub> is restored to the high state by pressing S<sub>1</sub> after feeding a fresh sheet of paper into the typewriter. If S<sub>1</sub> is pressed when the paper low signal is still active then a further line of text will be printed. A -5V supply for the collector resistor of Tr<sub>2</sub> is provided by the negative-voltage generator IC<sub>11</sub>. Note that the CTS signal taken from Tr<sub>2</sub> collector is not a full-specification RS232 signal in terms of voltage swing but is perfectly adequate for the short cable likely to be required.

## Construction

There is a shortage of space inside the typewriter casing so the interface was housed outside in a small metal box. It connects to the typewriter via a 40-way



**Fig. 3.** Output from the computer is halted by this sensor circuit when the paper runs out. This feature is often not provided even on high-cost printers. IC<sub>8</sub> is a 74LS132 and IC<sub>9</sub> a 74LS03. A suitable opto-switch is type 307-913 from RS Components.

capacitor for every two i.c.s. Remember when connecting wires both to the typewriter and to the interface that some of the i.c.s are static-sensitive m.o.s. devices.

The photoelectric sensor is fitted onto a bracket mounted underneath the typewriter platen roller and views the paper through a hole cut in the paper guide (Fig. 6).


#### Commissioning the interface

With the interface disconnected from the typewriter, feed a sheet of paper into the typewriter and monitor the voltage at pin 1 of the connector at the end of the ribbon


cable. Adjust R<sub>2</sub> until the voltage just falls to 0V. Give the potentiometer a further turn in the same direction. The voltage should now rise to 5V when the paper is removed.

**Table 1:** Links 1 and 4 in this table set up the uart for the expected serial data format. Link 5 selects appropriate data from the eeprom for the expected carriage-return, line-feed sequence from the computer (see text).

Link	Function	Low (0V)	High (+5V)
1	character length	7 bits	8 bits
2	parity inhibit	enable	inhibit
3	even parity enable	odd	even
4	stop bit select	1 bit	2 bits
5	CR-LF sequence	LF-CR	CR-LF




**Fig. 4.** 40-way ribbon cable connects the interface to the underside of the typewriter main circuit board. Alternate wires in the ribbon are connected to +5V or 0V either at the interface end or the typewriter end. This helps to prevent crosstalk between the signal wires.



**Fig. 5.** Platen roller must be swung upwards to allow access for fitting the paper-out detector. Remove screw B on the right-hand roller support bracket. Swing plate C clear on the right-hand bracket and swing the platen roller assembly upwards, pivoting it about nut D.


**Fig. 6.** Opto-sensor mounted underneath the platen roller views the paper through a hole cut in the paper guide roller carrier (Fig. 6).



**Fig. 8.**

#### Attaching the paper sensor

The paper sensor is mounted on a bracket on the underside of the platen roller. A hole must be cut in the paper guide under the platen roller for the sensor to view the paper through. To cut the hole the guide must be removed from the typewriter. Remove from the rear of the platen roller the four springs which tension the paper guide and the paper bail bar. Next refer to Fig. 5 and pivot the whole platen roller assembly upwards. Remove the small spring which can now be seen on the underside of the assembly at the right hand end. Remove circlip E from the right hand bracket and pull the bar that was retained by the circlip out of the bracket. The bar can now be sprung to enable the paper guide to be removed. To avoid damaging the guide a hot soldering iron can be used to melt a hole in the plastic in the position shown in Fig. 6. The hole should be carefully trimmed with a file to ensure that there are no sharp edges that can snag the paper. The mounting bracket for the sensor is shown in Fig. 7 and is attached as shown in Fig. 8 to the left hand spring bar on the underside of the platen roller by a single screw.



Test the connections to the typewriter by shorting out rows and columns at the connector on the end of the ribbon. Check by referring to Fig. 1 that the typewriter prints the correct character.

The interface should next be connected to the computer RS232 port and powered up, preferably from an independent 5V

supply. Press S<sub>1</sub> to reset IC<sub>10</sub>, ensure that the led goes out and the CTS line to the computer goes high. A short program loop should be written to send a continuous stream of characters to the interface. Do not forget that it will be necessary to configure the computer for the correct baud rate. The row outputs from the interface

should be monitored to ensure that the appropriate row is pulsed low (use an oscilloscope or else a led in series with a 390Ω resistor to +5V). Check each row in turn by sending an appropriate character to select each one.

The interface should now be connected to the typewriter. Data should be sent by

the computer to test the entire character set.

The computer should be configured to output both carriage-return and line-feed characters whenever a new line is required. To check the sequence of the carriage-return and line-feed characters, position the print head at the right hand margin and send the typewriter a return signal from the computer. Check that the print head returns to the left margin before a line-feed takes place. If the line-feed occurs first, then link 5 should be changed (see Table 1). Led<sub>1</sub> should flash during the carriage-return period and computer output should be halted.

Finally check that the paper-out circuit is operating correctly by ensuring that the led lights and the CTS line goes low at the end of the line following a paper-out condition being detected.

### Modifying the typewriter

To attach the ribbon cable to the typewriter it is necessary to remove the typewriter top cover and the keyboard assembly. The pivoting cover on top of the typewriter should first be removed by swinging it upward and springing one of its ends away from the retaining bar on to which it is clipped. The other end can then be unclipped and the cover removed. The knobs on either end of the platen roller should then be removed by unscrewing them.


Next the four top cover retaining screws should be removed from the underside of the typewriter and the top cover taken off. Undo the two retaining screws at either side of the keyboard and lift the keyboard assembly away, taking care in the process to unplug the cables from its underside. The cable connectors are easily distinguished so there is no need to mark them for later re-assembly. The keyboard assembly consists of two circuit boards folded together and held apart by three spacers. The three nuts that fasten the circuit board to the spacers should be removed and the keyboard assembly unfolded. The ribbon cable should now be soldered to the main circuit board as shown in Fig.4 so that it emerges from between the two boards when they are folded together again. During re-assembly, take care to position the flexible ribbon to the print head so that it is not under tension when the head is at the extremes of its travel. It is necessary to cut away some projections on the inside of the top cover to prevent damage to the cable when the cover is refitted.

WW

Praxis typewriters are available through Wilding Office Equipment and other Olivetti dealers at around £260 for the Praxis 30 and £290 for the Praxis 35. Programmed eproms are available from the author at 18 Carnoustie Gardens, Glenrothes, Fife KY6 2QB for £9.60 each including postage and v.a.t. The other components can be obtained as a kit from Technomatic Ltd.

**Table 2: Eprom converts data received by the uart into a code to select the typewriter keyboard rows and columns via multiplexer and de-multiplexer. Table shows data and typewriter response to each incoming ASCII code. Data for eprom locations 80 to FF is identical to data in locations 00 to 7F with the exception of location 8A with data 36 and location 8D with data B7.**

Addr	Data	Char	Addr	Data	Char	Addr	Data	Char	Addr	Data	Char
00	00		20	3E	Spc	40	44	@	60	46	E
01	00		21	3E	Spc	41	61	A	61	21	a
02	00		22	42	"	42	56	B	62	16	b
03	00		23	3E	Spc	43	7B	C	63	38	c
04	00		24	3E	Sp	44	63	D	64	23	d
05	00		25	51	%	45	5B	E	65	1B	e
06	00		26	5E	&	46	64	F	66	24	f
07	00		27	75	'	47	7D	G	67	3D	g
08	2E	B.Spc	28	74	(	48	4E	H	68	0E	h
09	07	Tab	29	73	)	49	6C	I	69	2C	i
0A	B7	Express	2A	41	*	4A	4D	J	6A	0D	j
0B	00		2B	69	+	4B	4C	K	6B	0C	k
0C	00		2C	13	,	4C	4B	L	6C	0B	l
0D	36	Return	2D	32	-	4D	54	M	6D	14	m
0E	00		2E	12	.	4E	55	N	6E	15	n
0F	00		2F	43	/	4F	6B	O	6F	2B	o
10	00		30	33	0	50	6A	P	70	2A	p
11	00		31	01	1	51	59	Q	71	19	q
12	00		32	02	2	52	5C	R	72	1C	r
13	00		33	03	3	53	62	S	73	22	s
14	00		34	04	4	54	5D	T	74	1D	t
15	00		35	06	5	55	6D	U	75	2D	u
16	00		36	05	6	56	7C	V	76	3C	v
17	00		37	1E	7	57	5A	W	77	1A	w
18	17	1/2 Spc.	38	35	8	58	7A	X	78	3A	x
19	0F	M.Rel.	39	34	9	59	65	Y	79	25	y
1A	1F	M.Left	3A	4A	:	5A	79	Z	7A	39	z
1B	2F	M.Right	3B	0A	;	5B	3E	Spc	7B	3E	Spc
1C	2F	Tab set	3C	3E	Spc	5C	3E	Spc	7C	3E	Spc
1D	3F	Tab clr	3D	29	=	5D	3E	Spc	7D	3E	Spc
1E	28	S.Lock	3E	3E	Spc	5E	3E	Spc	7E	3E	Spc
1F	30	Repeat	3F	72	?	5F	45	-	7F	10	Del



# Aerial inefficiency at sea

*Innovation in marine aerals is badly needed: British thought in this area has been 'fossilized' for 50 years. But North Atlantic sea trials earlier this year of new British-designed components have shown 'excellent results.' This is the third of John Wiseman's startling revelations on the state of marine aerals.*


by J. J. Wiseman

We at sea are not the only people who have been forced by an unfavourable environment, to operate low-frequency transmitters into aerals less efficient than the textbook optimum. The photograph on this page shows a trench transmitter of the First World War, operating on wavelengths between 500 and 2000 metres with an aerial only a metre above the ground, and a range of 3 or 4km. With an aerial of specified 40 foot length and 15 foot height,

range was up to 80km. Even from this inadequate aerial, a useful service was still obtained, even more remarkable considering the primitive receivers of those days. Other 1914-18 War transmitters worked



**Fig. 1.** This l.f. trench transmitter operated into an aerial only a metre above ground, but others worked from aerals inside the trench. (20watt Mk 3 transmitter, 1917, has single-valve tuned-anode oscillator, but a second valve could be switched in parallel for maximum power. HT supplied by 1,000-volt battery or induction coil.)



**Fig. 2.** Those whose experience of a storm at sea is a rough ride to Calais on a stabilized passenger ferry can have little idea of the force of a North Atlantic winter gale. (Photo: P. F. Barber, Scarborough)



**Fig. 3.** Top-loaded unipole aerial of Scandinavian origin. The stays add to the top capacitance, also to the leakage. Has little height. (Photographed at Eleusis, Greece, 1982)

into aerals actually inside the trench, below ground level, operating at 80 to 100 metres wavelength.

The efficiency of the 500kHz marine aerial depends, as for any other other, on its height and dimensions; the special variable factor in the marine environment is leakage. A correspondent (WW February 1983 issue) has pointed out that an aerial height of 0.1λ, at perhaps 40 or 50% efficiency is about the least we can hope to get away with, and at 500kHz this corresponds to 60 metres, an impossible height. But according to a BBC Research Department report by H. Page, published in 1963: "... a capacitive top is often added to a low aerial with the object of increasing the radiation resistance. In this case, a large top changes the current distribution on the vertical portion of the aerial from linear to substantially constant, thus approximately quadrupling the radiation resistance ...". This might lead to the




Fig. 4. Hard-to-find classic French all-wire sausage aerials with high top capacitance, well sited on available structures. ('Dumont d'Orville,' French flag, b. 1977, 23910 g.r.t. photographed at Cr. Couronne, 1983.)




Fig. 5. This stubby mast accounts for 5% of aerial capacitance, 2% of its radiation, and 90% of its cost! It makes no economic or functional sense. Cargo cult design. ('Ile de la Reunion,' French flag, b. 1969, 16671 g.r.t. photographed at Rouen, 1983.)



Fig. 6. Traditional British feedthrough set-up, unchanged since the days of silent movies, photographed in 1983.



Fig. 7. Abbreviated version for a quick, cheap job on a 900-ton supply vessel failed repeatedly at sea. (Australian flag, photographed in Tasmania, 1976.)

hope that, with a good capacitive top, one could work with an aerial only 15 metres high with useful efficiency. We will get some lift over ground-level figures because the base of the aerial is already well elevated by the hull of the ship. Figures 3 & 4 show about the least and the most that can be done about 'tops' on an average ship. The bizarre arrangement in Fig 5 has all the correct ingredients, but has got them upside down: the money has been invested in the wrong end of the aerial. As well as improving radiation resistance, the 'top' improves the L/C ratio, minimizing arcing. As manufacturers keep on supplying transmitters specified to match aerials of "250 to 750pF", and shipyards tend to supply aerials toward the lower end of the 80 to 400pF range, the 'top' can only help, avoiding tuning difficulties particularly at the low end of the 405 to 535kHz band.

If the RC product is too small, charge put into the aerial each cycle may leak away almost as fast as it can be supplied (R is parallel leakage). Time between peaks is longer at lower frequencies. This is a further good reason for making C as large as possible. But what can be done about R?

The standard British feedthrough insulator arrangement, unchanged since 1930, is at its best and at its worst in Figs 6 and 7. The strain insulators are also standard British issue. Their presence adds to




Fig. 8. German 10-foot-tall glass-fibre feedthrough trunk shown on its side. Intelligent design, efficient and unobtrusive. Requires no safety fencing. Might benefit from a few rain cones along the shaft. Dieckmann & Klapper, Gerätebau GmbH, Hamburg.)



Fig. 9. Simple and effective conical skirts of common British telegraph pole insulators, in use for nearly a century, and only now recently adopted for marine use, Figs. 10 and 11.




Fig. 10. Tough German aerial strain insulator using skirt principle. Rated at 50kV (dry) at 500kHz. 700kg tensile load, mass 1.5 kg. (Dieckmann & Klapper.)

leakage, and cancels any useful effect the bells might have. In earlier times the trunking (Fig 6) would have been made of oiled teak, and could have contributed to the overall insulation. These days it is soggy plywood, even steel.

British thought in this area has been fossilized for 50 years; there has been reluctance to innovate or to produce any aerial hardware requiring much manufacturing. Books like "101 Things a Boy Can Make" have a lot to answer for. The ends of this kind of feedthrough insulator are sometimes unglazed and porous, absorbing water, and usually sealed with cork washers. A British firm makes a solvent-based silicone preparation which causes water on the surface of a ceramic insulator to collect in small drops, preventing formation of a conductive film. It requires oven curing. I have never seen it used at sea; it could be useful. The old 'bitumastic strap' insulator, a yard-long

tough rubber thong, worked on this principle, although it might have fried at 17MHz!

A German-made feedthrough trunk, based on a tough glass-fibre tube, is up to three metres long (Fig 8); polyester stays are available to brace it. There is minimal shunt capacitance, small surface area, and a long way indeed to leak or arc. It is rated at 30kV at 500kHz. A neat arrangement: beats soggy plywood, and probably doesn't cost much more.

The insulator shown in Fig 9, with its deep skirt, has been on British telegraph poles for nearly 100 years — simple and effective. Only recently has a German firm adapted the principle to insulators for marine use, Fig 10. The same idea is seen again on the base of a Russian mast aerial in Fig 11. Why has it taken so long?

The feedthrough insulator of Fig 12, with metal jacket and metal rain cone, was photographed on the British cruiser, HMS Belfast. If the Navy had advanced ideas, they did not seem to get passed on to the merchant fleet.

But British ingenuity, neglected as it may be, is still very much alive and well, and living in Britain.

Recently patented, British developed feedthrough and aerial link insulators (Figs 13 & 14) with protective mantles of elegant design have undergone testing by a national h.v. laboratory and sea trials in the North Atlantic in winter with excellent results, see Fig 15. The shrouding domes are made of transparent high impact plastics. The feedthrough unit is held to the bulkhead by non-metallic nylon bolts, and a stream of air blown into the inner dome to prevent penetration by moisture, warmed as well if necessary to prevent icing. The link insulator unit has a vaned, wind-driven rotating outer dome, running on non-metallic rollers. Water entering is thrown out through small holes in the rotating part. With salt-water spray directed into the gap between inner and outer domes for 30 minutes in laboratory tests, flashover occurred at 57kV. An unprotected insulator under similar conditions began to spark over at 11kV.

In North Atlantic sea trials, carried out on a British tanker from late January to early April, one aerial retained its British 'standard' brass bell fitted feedthrough, the other being supplied with the domed shrouding mantle assembly. The day-to-day log kept shows typically an equal 4A up either aerial in dry weather, but 'tuning impossible' with the standard aerial in bad weather, while the modified aerial was still drawing a good 2.8A, from the same 100watt transmitter at 500kHz. Later, link insulators with protective mantles were added to that aerial, with further improvement in results. While the standard aerial drew only 0.5, the modified aerial took 3.9A. What more can man do? Perhaps combine the best features of several of the systems described, no more. WW



Fig. 11. Base of Russian mast showing three deep-skirted rain cones on the central glass-fibre pole. (Photographed at Rouen, 1983.)



Fig. 12. Metal-jacketed naval feedthrough insulator on HMS Belfast, World War 2 cruiser, now museum. Plumbing suggests it might have been air blown.




Fig. 13. Recently-developed British feedthrough assembly with dual-domed protective mantle. Moisture is expelled from domes by air blower. (By P. F. Barber, Scarborough.)




Fig. 14. British invented link/strain insulator assembly with protective shrouding. Wind-driven rotating outer dome expels water by centrifugal action. (P. F. Barber, Scarborough.)




Fig. 15. Sea trials with one feedthrough protected, the other traditional. In later trials protected link insulators added.

In bad weather at 380 miles, on 500kHz, US coastguard gave (typically) QSA1 from traditional side, QSA4 from protected side, same transmitter. Had the usual shunting strain insulator been present traditional side would have fared even worse. (P. F. Barber, Scarborough.)

# Loudspeaker measurements simplified

Acoustic measurement techniques designed to avoid the vagaries of personal prejudice and room acoustics normally require a calibrated microphone. Using the principle of reciprocity three transducers can be calibrated with reasonable accuracy and no specialized equipment

by Peter F. Dobbins

The design of loudspeaker cabinets may be reduced to the analysis of an equivalent electrical circuit<sup>1</sup>. In principle it should be within the capabilities of an electronics engineer to devise his own speakers for special applications, or simply as a less expensive and/or better quality option to commercial offerings. Problems arise however when attempting to confirm the performance of the finished product. A subjective listening test may be adequate in some circumstances, but the vagaries of personal prejudice and room acoustics can affect the results, and it is difficult to determine the cause of a fault should the speaker not sound satisfactory.

The subject of acoustic measurements has been discussed previously in *Wireless World*. Hiscocks<sup>2</sup> described a gated tone-burst method of eliminating the effects of reverberation and echoes, and Grubb<sup>3</sup> showed how a fast Fourier transform spectrum analyser might be used to achieve the same end. But before such sophisticated signal processing can be applied the acoustic field must be measured. This implies the use of a microphone of known sensitivity and response, probably not available to the home constructor. An application of the principle of reciprocity is described in this article which leads to the absolute calibration of three transducers by means of purely electrical observations.

The three transducers required are a transmitter, a receiver and a reversible device. Most forms of acoustic transducer in general use are reversible, and the method is admirably suited to the calibration of a microphone and a pair of loudspeakers.

The reciprocity theorem states that in a passive linear four-pole network the ratio of excitation to response is constant when the positions of excitation and response are interchanged. But more particularly, the two open-circuit transfer admittances are equal.

Two reversible electroacoustic transducers coupled to the same medium and accessible only through the two pairs of electrical terminals form a four-pole network. A general proof of the validity of the law has not been given for this case, to my knowledge, but it has been proven for special cases. Furthermore, in practice it is easy to check that a particular network is reciprocal, as described, and for this reason the validity is assumed. It is further assumed that the principle applies to individual transducers. Consider Fig. 1(a), which shows a current  $i_1$  flowing into terminals 1 & 2 of a network causing an open-circuit voltage  $e_1$  to appear across terminals 3 & 4. In (b) the connections are reversed, and an input current  $i_2$  at terminals 3 & 4 causes an open-circuit output voltage  $e_2$  at terminals 1 & 2. Reciprocity may be stated as

$$i_1/e_1 = i_2/e_2 \quad (1)$$

In a transducer terminals 3 & 4 may be regarded as a point in the acoustic medium




Fig. 1. Four-port network is reciprocal if its transfer admittance is the same in both directions.

at a distance  $r$  from the device. Network (a) represents a transmitter or loudspeaker. An input current  $i$  produces a sound pressure  $p$  at the output. Network (b) represents a receiver or microphone and an acoustic source of strength  $Q$  at the input produces an open-circuit voltage  $e_0$  at the output terminals. Equation 1 may then be written:

$$i/p = Q/e_0 \quad (2)$$

For those unfamiliar with acoustic terminology, the rate of flow in the medium from source is

$$Q(t) = \int_A u(t) \cdot dA$$

where  $A$  is the area of the vibrating surface and  $u(t)$  is the velocity of that surface. Generally, for simple harmonic motion

$$Q(t) = Qe^{j\omega t}$$

where  $Q$  is the strength of the source. At low frequencies a loudspeaker cone may be regarded as a rigid piston, and the source strength is simply the effective area multiplied by the cone velocity. The acoustic pressure  $p$  at a distance  $r$  from this source is inversely proportional to  $r$ , if spherical spreading is assumed, and related to  $Q$  by the equation

$$p(t) = \frac{j\rho ck}{4\pi r} Qe^{j(\omega t - kr)} D(r, \theta, \phi)$$

$\rho$  is the density of the medium,  $c$  is the sound speed,  $k = \omega/c$  is the wave number or spatial frequency, and  $D$  is a function describing the directivity of the source with arguments  $r, \theta, \phi$  in spherical co-ordinates. For this discussion directivity is neglected, as once the sensitivity has been found in the straight-ahead direction it is a simple matter to rotate the source and measure the relative response in other directions and so determine the beam pattern. Phase angle may be retained in these calculations but is generally neglected because of exper-

imental difficulties encountered in accurately determining both the distance between transducers and the sound speed in the medium, so only the amplitude is considered here. Thus  $D$  is set equal to one, and the exponential time dependence may be dropped:

$$p = \frac{\rho ck}{4\pi r} Q \quad (3)$$

where  $p$  and  $Q$  are r.m.s. amplitudes. Both spherical radiation and free-field conditions are implicit in equation 3, and the consequences of these assumptions will be discussed when the practical application of this theory is considered.

The free-field voltage sensitivity  $m$  of a transducer used as a microphone is the ratio of the open-circuit voltage output  $e_0$  to the free-field sound pressure  $p$ :

$$m = e_0/p \quad (4)$$

The transmitting voltage (or current) response,  $s_v$  ( $s_i$ ), of a transducer used as a speaker is the ratio of the sound pressure at unit distance from the transducer to the voltage applied across (or the signal current flowing into) the electrical input terminals:

$$s_v = p/v \text{ or } s_i = p/i \quad (5)$$

Combining equations 3 & 4:

$$m = \frac{4\pi r e_0}{\rho ck Q} \quad (6)$$

From equation 5 and the reciprocity relationship (equation 2):

$$Q = e_0/s_i$$

Thus, substituting for  $Q$  in equation 6,

$$m = \frac{4\pi r s_i}{\rho ck} \quad (7)$$

Noting that  $s$  is defined for unit distance (i.e.  $r=1$ ), and that  $k$  may be expressed in terms of frequency,  $k=2\pi f/c$ , equation 7 becomes

$$\frac{m}{s_i} = J = \frac{2}{\rho f} \quad (8)$$

where  $J$  is the reciprocity parameter or acoustical transfer admittance for spherical radiation. By modifying the form of equation 3, reciprocity parameters may be derived for other conditions, such as plane waves, and examples will be found in reference 5. Equation 8 is derived from MKS units and if other systems are used a conversion constant must be included. A note on units used in acoustics is given in the Appendix.

As engineers prefer everything in logarithmic form so that they can add and subtract rather than multiply and divide, equation 8 may be re-written

$$S = M + 20 \log f + 20 \log \rho / 2 - 20 \log |Z|$$

where  $S = 20 \log s_v$  (dB relative to 1 Pa/V at 1 m),  $M = 20 \log m$  (dB re 1 V/Pa), and  $|Z|$  is the input impedance of the transducer (only the magnitude is needed as only the magnitudes of  $M$  and  $S$  are to be found).

Finally, taking the density of air as  $1.2 \text{ kg} \cdot \text{m}^{-3}$ , a new reciprocity factor  $K$  is defined by

$$S = M - K \quad (9)$$

$$\text{with } K = 20 \log |Z| - 20 \log f + 4.4 \quad (10)$$




Fig. 2. Schematic three transducer reciprocity calibration. Drive voltage  $e_{CB}$  is applied to transducer C, which transmits to transducer B, at a distance  $d_{CB}$ , giving an output voltage  $v_{CB}$ . Test is repeated with C transmitting to A and B transmitting to A.

## Three transducer method

The practical application of reciprocity in acoustic calibration requires three linear transducers, of which at least one is reversible, and also that measurements be carried out under free-field conditions and in the far field of each transducer. These conditions must be met if results are to have any meaning, and some simple checks are described in the section on measurement techniques.

The three transducers required are a microphone A, a reversible device B and a speaker C. The terms microphone and speaker refer only to the usage of the transducer for these tests, and the term transducer is taken to mean any device that converts acoustic energy to electrical energy or vice versa. A transducer is reversible if the conversion operates in both directions, and this is true of almost any device that contains no active components, obvious examples being the ordinary moving coil loudspeaker and dynamic microphone.

Both transmit and receive sensitivities may be obtained for all three transducers under test by full use of reciprocity. Three sets of measurements are done:

- speaker to reversible device
- speaker to microphone
- reversible device to microphone

The sequence is shown schematically in Fig. 2. Assuming spherical spreading, the relationship between drive voltage and received voltage for a test between transmitter I and receiver J is

$$e_{IJ} = \frac{v_{IJ} m_I s_J}{d_{IJ}}$$

or in logarithmic form and with some rearrangement

$$A_{IJ} = D_{IJ} - S_I - M_J \quad (11)$$

where  $A_{IJ} = 20 \log (v_{IJ}/e_{IJ})$  is attenuation and  $D_{IJ} = 20 \log d_{IJ}$  is spreading loss. The relationship between  $M$  and  $S$  for one transducer is given by equation 9 as  $S_I = M_I - K_I$ , where  $K$  is the reciprocity term from equation 10.

The three sets of measurements give

$$A_{CB} = D_{CB} - S_C - M_B \quad (12)$$

$$A_{CA} = D_{CA} - S_C - M_A \quad (13)$$

$$A_{BA} = D_{BA} - S_B - M_A \quad (14)$$

Combining the first two by eliminating  $S_C$  gives

$$M_A = D_{CA} - D_{CB} + A_{CB} - A_{CA} + M_B$$

But  $M_B = S_B + K_B$  and substituting for  $S_B$  from the third equation leads to

$$M_A = 1/2(D_{CA} - D_{CB} + D_{BA} + A_{CB} - A_{CA} - A_{BA} + K_B)$$

The receive sensitivity of the microphone has now been found in terms of distances and electrical quantities by use of the reciprocity factor. The rest is plain sailing. Using equations 13 & 14

$$S_C = D_{CA} - A_{CA} - M_A \text{ and}$$

$$S_B = D_{BA} - M_A - A_{BA}$$

and by reciprocity:

$$M_B = S_B + K_B$$

The transmit sensitivity of the speaker and both transmit and receive sensitivities of the reversible device are now known. The speaker and microphone may not be reciprocal. For instance, an electret microphone usually has a built-in preamplifier so is obviously not reversible, and as the terminals of the transducer are not directly accessible the impedance cannot be calculated. However, if either or both of these transducers are reversible the remaining sensitivities are easily found:

$$S_A = M_A - K_A$$

$$M_C = S_C + K_C$$

These last six equations give absolute calibrations for each of the transducers, obtained without a reference transducer. The measurements and calculations must be repeated at each frequency of interest, and at first glance the process may seem tedious. But the amount of experimental work is no greater than carrying out three separate frequency response procedures using a standard transducer, while the calculations are simple arithmetic and easily programmed for a computer or calculator. If practicable, some easing of the workload can be achieved by making distances and drive voltages constant for all tests.

## Measurement techniques

Before the calibration procedure can begin the impedance of each transducer must be found as a function of frequency so that the reciprocity factor can be calculated. If a bridge is not available the simple circuit of Fig. 3 generally provides satisfactory results. To keep errors low,  $R$  should be a low resistance ( $R < |Z|/100$ ) if the transducer is a high impedance device, and the impedance obtained from  $|Z| \approx V_1 R / V_2$ . If the transducer is a low impedance device then  $R$  should be a high resistance ( $R > 100|Z|$ ) and the impedance obtained from  $|Z| \approx V_3 R / (V_1 - V_3)$ .

Most transducers have very low electro-mechanical coupling coefficients so no special precautions need be taken, provided the active face is not pointing directly at a nearby reflecting surface. Some devices such as piezoelectric tweeters are very efficient, and any obstacle within several wavelengths may affect the measured impedance. A sensible procedure is to suspend the transducer in mid-




Fig. 3. In the absence of a bridge the input impedance of a transducer may be determined by measuring the voltage drop across a series resistor.

air, allowing it to swing freely. If the impedance does not appear to change as the device moves then all is well. Transducers such as tweeters, whilst not requiring a cabinet for their operation, should be mounted as they will be in service, because the presence of baffle will affect both impedance and sensitivity at frequencies where the device is small compared with the wavelength.

The basic measurement set-up is shown in Fig. 4. The hardware need not be sophisticated, but before discussing the instrumentation the acoustic environment and the necessary conditions must be considered.

Measurements should be made in the far-field of the transducers, which means that the projector is assumed to be a point source from which spherical waves spread, and the receiver is assumed sufficiently small that the wavefront may be considered plane over the transducer face. As both have finite size there must be sufficient distance between them before the assumption can be considered valid. For a working rule the minimum distance should be  $a^2/c$  or  $5a$ , whichever is the greater, where  $a$  is the maximum dimension of the larger transducer and  $c$  is the sound speed. In air,  $c=343\text{ms}^{-1}$ . The size should include the housing, not just the active face of the transducer, as any discontinuity can act as a secondary source.

The free-field condition is generally the most difficult to deal with, and essentially means that the sound waves must be free to radiate spherically with no disturbance by boundaries or obstacles within the field of interest. In principle the receiving transducer should not distort the wavefront, but there is little that can be done to ensure this, given a particular device. There are a number of ways to tackle the free-field problem:

- 1 - measure in an anechoic chamber
- 2 - measure out of doors
- 3 - use pulse techniques
- 4 - measure in a room and correct for reverberation by calculation or signal processing
- 5 - measure in a room and ignore room effects.

The effect of reverberation is to introduce ripples into the measured frequency response. If the ultimate in precision is not required it is generally possible to estimate the mean level, and (5) may prove satisfactory. An anechoic chamber is not usually available, so weather permitting, (2) may be the best compromise. Solution (4) usually requires specialized instrumentation or vast computing power, but an interesting discussion of a typical tech-

nique is given in reference 6. The pulse method (3), is described in detail in references 2 and 3, but the principle is summarized here.

In an enclosed environment signals travel from transmitter to receiver by paths other than the direct one. Because sound travels fairly slowly in air it is possible to transmit short tonebursts and measure the received signal before reflections reach the receiver, Fig. 5. It is usual to use a gating and sampling system to achieve this result, but careful oscilloscope observation can result in accuracies better than 0.5dB. If a gated signal generator is not available, a simple fet switch can be constructed, as described in reference 2.

Maximum pulse length is determined by the difference between direct and first reflected path length. The minimum pulse length is determined either by the rise-time (and therefore the bandwidth) of the transducers or by the time constant of the detector. As frequency becomes lower a longer pulse is needed to encompass a sufficient number of cycles, and the method becomes unuseable when the wavelength approaches the differences between direct and reflected path lengths. In average-sized rooms this is typically around 500Hz. The maximum pulse repetition rate is determined by the time it takes for reflections to decay to negligible amplitude. These times may be calculated, but are easily set empirically by direct observation of the signals.

Free-field and far-field conditions are easily checked by confirming compliance with equation 3. If the transmitter is driven at constant frequency, constant voltage, and the receiver output voltage measured as a function of distance, this voltage is then inversely proportional to distance.

The total transmission chain should be linear, with no saturation effects. It is not generally appreciated that the acoustic medium itself may become non-linear at high pressure amplitudes, especially at high frequencies or when the transmission path is constricted as in a horn. Testing for proportionality between transmitter drive voltage and receiver output will check for both linearity and an adequate signal-to-noise ratio.





Fig. 4. Minimum instrumentation is a signal generator and suitable power amplifier, a frequency counter and a means of monitoring the transmitter drive level and receiver output voltage.



Peter Dobbins began his career as a technician apprentice with BAC, Hurn, obtaining a City & Guilds qualification in aeronautical radio and instrumentation at day release and evening classes. His first professional contact with acoustics was at Ultra Electronics, Greenford, where he worked on the development of transducer arrays for sonobuoys. He joined BAe at Weymouth (formerly Sperry Gyroscope) in 1976 to work in electronics design, but transferred to the underwater technology department in 1981. Since then he has gained an honours degree in applied mathematics from the Open University, and has recently been elected a member of the Institute of Acoustics. In 1982 he became a founder member of a specialist transducer group at BAe, and is now a senior engineer working on underwater acoustic transducer and array design, with interests in long-range propagation and non-linear generation of low frequency sound.

Reciprocity must also be confirmed. It is not possible to check that the individual transducers are reciprocal without direct measurements on the acoustic field, but it is possible to test the combined transmitter/receiver chain, simply by measuring the transfer admittance in both directions. With two transducers in their final measurement positions drive one, noting the input current  $i_1$  and measure the output voltage  $e_1$  from the other. Reverse the connections and measure the new input current,  $i_2$ , and output voltage,  $e_2$ . This should be repeated at a number of frequencies over the range of interest. If  $i_1/e_1 = i_2/e_2$  at each frequency, then both transducers may be regarded as reciprocal.

Making the calibration measurements is straightforward. It is assumed that continuous rather than pulsed signals are being used and that some suitable location has been found, perhaps out of doors, enabling free-field and far-field conditions to be met. Typically the transducers under test will be two loudspeaker drivers and a microphone, one of the speakers being used as the reversible device, taking care to distinguish between the two speakers.

The first job is to select the frequencies to be used, and common practice is to have third-octave steps, the sequence being 1,

1.25, 1.6, 2, 2.5, 3.15, 4, 5, 6.3, 8, 10 etc. This is not essential, the point being to keep to the same frequencies for each set of measurements.

The speaker and reversible device should be positioned, pointing directly towards one another, at the appropriate free-field distance and as high above the ground as possible to reduce the effect of reflections. The distance between the transducers should be measured. Measure from the diaphragm, if exposed, otherwise from the plane of the baffle or front of the mounting structure.

Instrumentation is set up as in Fig. 4, using the speaker as transmitter and reversible device as receiver in the first test. There are no special requirements of the signal generator and three-digit accuracy is adequate for the frequency counter. The power amplifier could be one channel of a hi-fi unit, and to get the best signal-to-noise ratio the drive level should be as high as possible, subject to linearity, transducer power handling and complaints from neighbours.

One point about the detector. The theory described here applies specifically to open-circuit output voltage, so the detector input impedance must be much greater than the output impedance of the transducer or results will be meaningless. It is not necessary to have separate instruments to measure transmit and receive voltages, but it does make the work less complicated.

Once the equipment is operating satisfactorily the drive voltage and received voltage must be noted at each frequency of interest. This procedure is then repeated with the speaker as transmitter and microphone as receiver, and finally with the reversible device as transmitter and microphone as receiver. The required sensitivities can then be calculated from equations.

## Results

Repeated and careful reciprocity measurements can result in a sensitivity accuracy of 0.5dB or better, but real life acoustics is not that exact. The transducers themselves are not particularly stable. Their sensitivity will certainly vary with temperature. More importantly, the radiation resistance is proportional to the density of the air and the speed of sound, both of which can change with temperature pressure and humidity. This change will be reflected in the input impedance, and




Fig. 5. In suppressing echoes by pulse technique, the transmitted pulse is short enough to allow the received signal to be measured before the arrival of reflections.

with an efficient transducer the impedance term in equation 10 might vary by  $\pm 0.5\text{dB}$  over the normal range of meteorological conditions. Additionally, density is included directly in the reciprocity relationship. The density of air can vary from less than 1.0 to over  $1.3\text{kg.m}^{-3}$ , which represents an uncertainty in equation 10 of over  $\pm 1\text{dB}$ .

Another potential source of error, neglected in the theory, is absorption. Generally the dissipation of acoustic energy in air due to mechanisms such as molecular relaxation and viscous losses is low enough to be ignored. At high audio frequencies, however, and under conditions of high relative humidity the attenuation due to absorption may be as high as 1.0dB per metre.

These, and many other imponderables, mean that an accuracy of better than 1 or 2 dB cannot be guaranteed in uncontrolled conditions. This, however, is more than adequate for most domestic applications, where the main requirement is to ensure that the frequency response of a transducer is essentially flat, and that there are no unwanted resonances. It is unlikely that these results can be bettered with a calibrated microphone under similar conditions.

## References

1. Leo L. Beranek. (1954 'Acoustics' Ch. 7, 8, 9. McGraw-Hill.
2. P. D. Hiscocks, Measuring transducer directivity *Wireless World*, vol.84, 1978. No. 1512, pp. 61-66.
3. R. N. Grubb. Non-echoic acoustic measurement with the HP 3582A, *Wireless World*, vol.86, 1980. No. 1531, pp. 45-49.
4. L. D. Luker and A. L. Van Buren, Phase calibration of hydrophones, *J. Acoust. Soc. Am.*, vol.70, 1981. No. 2, pp. 516-9.
5. W. R. MacLean, Absolute measurement of sound without a primary standard, *J. Acoust. Soc. Am.*, vol.12, 1940, pp. 140-6.
6. R. B. Randall and J. Hee, Cepstrum analysis. *Wireless World*, vol.88, 1982. No. 1553, pp.77-80, No. 1554, pp. 88-90 and No. 1556, pp. 78-80.

## Appendix: units

Rationalized MKS units have been used throughout this article, which is something of a novelty in acoustic circles. In underwater acoustics MKS is in general use, but the Navy sticks by the traditional fathoms, knots, kiloyards, millibars and so on. Hi-fi people seem happy to use a similar mixture, with an annoying habit of quoting sound levels in decibels without stating a reference pressure, and who knows what terms like Noy, Sone and NEF mean, as used by environmental noise and architectural acoustics people.

Conversions between imperial, c.g.s. and MKS units are straightforward, but take care over whether to add or subtract when dealing with decibels. One worth remembering is


$$1 \text{ yard} = 0.9144\text{m} = -0.8\text{dB relative to 1m.}$$

It is customary to specify air at a temperature of  $20^\circ\text{C}$  and at standard atmospheric pressure in defining standards of acoustic intensity, impedance, pressure, and so on. Under these conditions the density of air is  $1.21\text{kgm}^{-3}$  and the speed of sound is  $343\text{ms}^{-1}$ , giving for the standard characteristic impedance of air  $\rho c = 415$  rayls. Unless other conditions of temperature and pressure are known to exist in a particular situation, the above values should be used for the solution of problems.

The commonly used reference standard of intensity for airborne sound is  $10^{-12}$  watt  $\text{m}^{-2}$ , which is approximately the intensity of a 1kHz pure tone that is barely audible to normal human ears. This corresponds to an effective (root mean square) pressure of

$$p = \sqrt{I\rho c} = \sqrt{415 \times 10^{-12}} = 2 \times 10^{-5} \text{Nm}^{-2}$$

The diagram gives the relationships between the most commonly used reference pressures. Although calculations are made much easier by keeping to MKS units



Reference pressure levels in common use and the relationships between them.

throughout the results may be expressed in any convenient units A simple example demonstrates its use. A typical speaker sensitivity would be

$$\begin{aligned} S &= 110\text{dB re } 1\text{Pa/V at } 1\text{m} \\ &= 110 - 26 = 84\text{dB re } 2 \times 10^{-5} \text{Nm}^{-2}/\text{V} \\ &= 110 - 100 = 10\text{dB re } 1 \text{bar/V at } 1\text{m} \\ &= 110 - 120 = -10\text{dB re } 1\text{Pa/V at } 1\text{m.} \end{aligned}$$

A more complicated conversion might be as follows. A loudspeaker manufacturer states that the sensitivity of one of his products is

$$96 \text{ dB at } 1 \text{ yard for } 0.6\text{W input.}$$

Experience suggests that the reference pressure is probably  $2 \times 10^{-5} \text{Nm}^{-2}$ . If the impedance is nominally  $8\Omega$  an input power of 0.6W requires a drive of 2.2V.

$$20 \log 2.2 = 6.9\text{dB relative to } 1\text{V.}$$

The sensitivity is thus

$$S = 96 - 6.9 = 89.1\text{dB rel. } 2 \times 10^{-5} \text{Nm}^{-2}/\text{V at } 1 \text{ yard.}$$

Subtract 0.8dB to refer to 1m

$$S = 89.1 - 0.8 = 88.3\text{dB rel. } 2 \times 10^{-5} \text{Nm}^{-2}/\text{V at } 1\text{m.}$$

And subtract 94dB to refer to 1 Pa

$$S = 88.3 - 94 = -5.7 \text{ dB rel. } 1\text{Pa/V at } 1\text{m.}$$

WWW

# How to make electric charge from a radio wave

*A wave in free space can be persuaded to enter a transmission line where its velocity may be reduced whilst still conserving its field pattern. If the transmission line is formed into a closed circle it may be spun at the same angular velocity as that of the wave to produce an electrostatic field in the laboratory, just as from a charged surface, but the primary energy is entirely in the wave field. Which then is the more fundamental, charge or field – do we really need two criminals where one may suffice?*

by R. C. Jennison

In recent years there have been a number of controversial articles in *Wireless World* questioning the very basis of the principles which are fundamental to wireless and wired communication. One is often tempted to comment in the letter columns but it is entertaining to sit back and witness battles which, too frequently, are re-plays of conflicts that one has fought on similar battlegrounds in days gone by. I will not enter directly into the controversies, although it may be clear in which direction my sympathies lie, but I will present a little conundrum and show how a partial solution has been demonstrated with simple apparatus that can be constructed at home by many readers of *Wireless World*.

What is electric charge? What is it made of and why does it have, and appear to behave as the source of, an associated electric field, whatever that may be? If you do not like the concept of an electric field, but prefer to live in my old friend Sandy Scott Murray's particulate world, substitute for the field a horrific flow of virtual photons, whatever they may be. The answer that charge is simply an excess or deficit of electrons, is not sufficiently fundamental. What is the nature of the charge on a single electron? Even if the electronic charge is made of minuscule sub-particles which defy discovery the same question remains: what is charge, is it a special sort of green cheese which acts as the source of an electric field? Its only purpose seems to be to support the field, or complex of virtual photons, and couple it to matter, but after all it is a very old concept that predates Friday's work on fields. At the present time we appear to have two separate unknown criminals who travel hand-in-hand, the electric charge and the electric field. Can we not form a model which causes the two criminals to coalesce and thereby remove at least one of the unknowns?

Start by considering an imaginary exper-

iment using some of the radiation that has been around since the time of the 'big bang'. The 3K radiation which pervades our part of the universe is thought to be the dying remnant of immaculately conceived radiation which cannot be associated with the radiation from particulate matter. We can pick up some of this radiation on a millimetre-wave antenna and pop it down a transmission line in which the velocity of propagation of the disturbance depends on the dielectric properties of the line. In principle the dielectric constant can be as high as we wish so that the disturbance moves at a leisurely pace. (Wave velocity in a transmission line is given by the reciprocal of the square root of the product of the inductance and capacitance per unit length, which is

$$c' = (LC)^{-1/2} = (\mu\epsilon)^{-1/2} = c/(\mu_r\epsilon_r)^{1/2},$$

the same as for an electromagnetic wave in the medium when no conductors are present). Coil the line around so that the circumference is precisely one wavelength in the line, Fig. 1(a). We now have to work very quickly but remember that we are discussing an imaginary experiment at this stage! Chop a section out of the line which carries exactly one wavelength and couple the input of the section immediately to the output of the same section, (b). We now have one wavelength trapped in a continuous transmission line of one wavelength circumference. The radiation will quickly decay but we can at least imagine a transmission line with very low losses so that the wave circulates for a finite time.

You may not care for the idea of changing the connection so quickly, so if you wish to be a little more practical, substitute the arrangement in Fig. 2 where two isolators are used to achieve the same result.

Now take stock of the situation. We have a single loop of transmission line which originally contained no energy other than that associated with its rest mass but which now contains an additional packet of pure electromagnetic energy whose origin can be traced right back to the start of our present universe, about 15,000,000,000 years ago. This energy, in the good old-fashioned concepts of wireless, is in the form of an electromagnetic wave comprising a sinusoidal pattern of electric and magnetic fields which are together in phase and are travelling around the loop at the languid velocity  $c'$ . The fields are not coming directly from the electrons in the conductors of the transmission line but these electrons mirror the passage of the wave as they are influenced by the induction from the waves whose origin we have traced. The frequency at which the wave circulates around the loop is the same as that of the original received signal, say 300GHz in round figures, whereas the wavelength is reduced by the effect of the dielectric to only a tiny fraction of its original length.

We are now ready to perform the final trick. Take the little loop containing the wave and spin it, about an axis through its centre, in the opposite direction to that in which the wave is travelling, increasing the speed of rotation until it is rotating anticlockwise at exactly the same angular speed as the wave is rotating clockwise. The trapped wave is now precisely at rest in the laboratory although the transmission line is spinning round at high speed. It is in fact spinning at  $-c'$ , very much less than the free space velocity of light  $c$ , so that from the point of view of the mechanics the principle is demonstrable, as indeed we shall shortly see.

If we now examine the space in close proximity to the little loop we find a static electric field. It is not a standing wave but a truly stationary, unvarying field, the intensity of which is a maximum in one




Fig. 1. A wireless wave from the original 'big bang' radiation is picked up on a folded dipole and fed into a 300 ohm transmission line, as shown (a). In principle, the coiled section may be removed and connected full circle whilst the wave is still in the line (b).

direction (say +) in one part of the line, a maximum in the other direction (say -) diametrically opposite and a minimum at the two quadrant points in between. Remember that this is the field that we originally trapped from space and the electrons in the wires are simply slaves to its influence. Relative to the centre of the disc, it is in fact a static dipole field for the particular configuration of the experiment in which both conductors are in the plane of the disc, one of slightly smaller radius than the other. Relative to the laboratory as a whole the vectors are continuous in the upper and lower halves.

Returning to the fundamental point raised at the beginning of this article, we have produced a static field but where are the charges which provide the source of that field? There are none; the electrical energy is the original wave energy and the electronic charges in the conductors are simply catalytic. We have essentially produced a 'charge' from the electromagnetic wave, for one cannot differentiate between the static field that we have produced and another that could be set up by a suitable distribution of 'real' electric charges on a stationary ring in the laboratory.

## Practical demonstration

It may well be that you consider that all the above is a lot of academic guesswork and that nothing like it could be achieved in practice. To prove the point I constructed two demonstration systems. One of these uses inexpensive and readily available electronic components and can be built quite easily at home. To this end the frequency is scaled down to the sub-audio range but the apparatus could still, in principle, contain a wave from the virgin past. The apparatus and its implications have been discussed in *Journal of Physics-A* vol. 15, 1982, pp.405-8.

To achieve exceptionally slow velocities of propagation in a transmission line it is usual to increase the permeability and permittivity  $\mu_r$  and  $\epsilon_r$  or equivalently to increase the capacitance and inductance per unit length by the use of 'lumped' circuits, in which discrete large values of L

and C are cascaded to form a continuous line of discrete sections. The physical principles in such a line remain the same electromagnetic principles as those in a continuous distributed line which for an equivalent propagation velocity would require impractical values of permittivity and permeability. Phenomenologically, the set of lumped circuits in the apparatus to be described form a dense medium, whereas at low frequencies the molecules in a 'continuous' dielectric behave, on a microscopic scale, as separate systems below resonance.

The arrangement uses a lumped-circuit transmission line in which there are 32 sections giving a total delay of 120ms. The inductors are small 1:1:1 transistor coupling transformers (RS Components) with their windings connected in series to increase the inductance. The capacitors are 1μF polycarbonate types from the same supplier. There is a small loss of the order of 1dB in each section of the line and small linear repeater amplifiers are included in the circuit to compensate for this loss. These repeater amplifiers consist of an f.e.t. input stage feeding a bipolar output stage and the gain is set to compensate for the loss in the adjoining section of line. The complete line is looped on itself in a geometrically circular configuration as in Fig. 3.

Energizing the linear repeater amplifiers in the completely closed circular loop causes an oscillation to build up in which a sinusoidal wave with a period of approximately 120ms propagates around the system in a clockwise direction. A slight roll-off in the response of the system, together with the maintenance of just sufficient gain to compensate for the losses, ensures that the waveform remains sinusoidal for long periods. The continuity of the cycling sinusoidal wave places the system in the general category of phase-locked particles\*, the particular mode corresponding to one complete wavelength around an annular system. It is possible to inject a signal into the system to initiate the circulation of the wave but one cannot differentiate such a wave from that resulting from self-oscillation, and the last-mentioned serves equally well to demonstrate the phenomenon under discussion.

The whole system is arranged mechanically in a well-balanced configuration on a strong laminated plastics disc, and power to the repeaters is supplied from two small 9 volt batteries strapped symmetrically behind the disc. At the centre of the disc there is a hub which is firmly attached to a small variable speed electric motor.

Upon energizing the repeater amplifiers, a travelling wave moves round the system in a clockwise direction and the travelling field may be sampled at take-off points associated with each of the capacitors. The

\* Jennison, R. C. and Drinkwater, A. J. *J. Phys. A.* vol. 10 1977, pp. 167-79. Jennison, R. C. *J. Phys. A.* vol. 11 1978, pp. 1525-33. *J. Phys. A.* vol. 13 1980 pp. 2247-50. Second Oxford Quantum Gravity Conference (London: OUP) pp. 657-69. *J. Phys. A.* vol. 15 1982, pp. 405-8. *Wireless World* vol. 85 1979, June pp. 42-7.

32 elements give a sufficiently close approximation to a continuous line and a reasonably pure sinusoidal wave may be detected passing each of these points. An alternative display system consists of a set of red light-emitting diodes, each of which glows on the passage of the positive crests of the wave, and a set of green light-emitting diodes, each of which glows on the passage of the negative troughs. When at rest the disc then exhibits a circle of rapidly flickering red and green lights corresponding to the circular rotation of the wave system at about 8Hz.

The disc is now spun in an anticlockwise sense at such an angular frequency that it is precisely equal and opposite to that of the wave. At this velocity, the wave, whilst still travelling relative to the disc, becomes stationary in the laboratory. The resulting potentials may be sampled to confirm the stationary state of the field system, but the most vivid demonstration of its state is given by the light-emitting diodes which form two stationary arcs, as shown on the front cover, one of positive (red) and the other of negative (green) potential relative to the centre. With careful adjustment of the speed of rotation, this static dipole electric field may be maintained indefinitely in the laboratory.

It should be stressed that the effect is truly that of a static field and neither a rapidly reversing field, as in standing wave systems, nor a stroboscopic artefact. The crests and troughs of the travelling wave are truly brought to rest in the laboratory and indeed it is possible to reverse the original direction of propagation, without reflection, by increasing the rotational speed of the motor.

An interesting conceptual problem then arises with regard to the magnetic field of the wave. The particular apparatus described here is not designed in such a way that the magnetic field may be sampled and there can be two schools of thought on whether or not it is also stationary. One argument is that as the charges are not moving in the laboratory there ought to be no magnetic component. The other argument is that as the travelling wave has a magnetic field in phase with the electric field this magnetic field should appear stationary when the electric field is ren-




Fig. 2. More practical arrangement for putting the wave into the circular line.

# CIRCUIT IDEAS




Fig. 3. Artificial delay line whose construction is described in the text in which a wave runs in the clockwise direction. Rotation of the system in an anticlockwise direction at the same angular frequency as that of the wave produces a static field. Red and green light-emitting diodes, connected at the points marked + and -, indicate the stationary wave, as on the cover photograph.

dered stationary. It appears that the first argument is fallacious for it ignores the motion of the system relative to the wave and there is also no known mechanism whereby the Maxwellian property of the wave system should break down even when the velocity, relative to the observer, is reduced to zero.

This demonstration is crude but very enlightening. We have got rid of one of the criminals who were travelling hand-in-hand at the beginning of this article. Nature probably has a much better way of achieving the same thing by so convoluting the electromagnetic field in the unique mechanism of electron-positron pair pro-

Professor Roger C. Jennison, B.Sc., Ph.D., C.Eng., F.IEE, FIP, FRAS, PPIE, FRSA, was born in Grimsby and studied engineering in Hull before volunteering for aircrew in 1942. Demobilized in 1947, he decided to start again and read physics at Manchester University, graduating with an Honours degree in 1950 and a Ph.D. in radio astronomy in 1954. In this period he deduced that the Cygnus A radio 'star' was double, invented 'closure phase' and a number of other techniques and was successively lecturer in radio astronomy, then senior lecturer in radio astronomy, and later in physics. In 1959 he turned his attention to medium-wave radio astronomy and cosmic dust research. He developed the first foil detectors and with experiments on rockets and the Ariel II satellite he showed that there was no danger to space travel from the cosmic dust which had previously been thought to be a severe hazard. In the early 1960s he became interested in problems of gravitation and rotation and was also elected President of the



Institution of Electronics. In 1965 he accepted the chair of physical electronics at Canterbury where he founded the Electronics Laboratories and recently added a chair of radio astronomy to his titles. He has maintained an interest in trying to understand fundamentals and has contributed an alternative explanation of inertia and quantization among his 90 published works.

duction that a perfect system is formed which has all the stable and wonderful properties of an electron and merits the concept of charge which is now fully ingrained in our conception of the properties of matter.

Having formed a static field from a travelling electromagnetic wave I am quite content, contrary to other views expressed in *Wireless World*, that if I hurl it around on a string it will give rise to freely propagating electromagnetic waves at the frequency of rotation, the energy coming from my muscles as I whirl the string. If, however, you ask me what these electromagnetic fields are then I must confess, along with Feynman, that I have not the faintest idea. It is a pity that some of the classical apparatus has disappeared from modern teaching. It is my belief that every budding researcher should be given a gold leaf electroscope to contemplate for a few minutes every day. Ultimately someone may really explain the phenomenon which keeps the leaves apart. **WW**

## LITERATURE RECEIVED

Over 40 different types of coaxial cables for data transmission, radio and microwave frequency transmission and communications are listed in a brochure from Greenpar Connectors, PO Box 15, Harlow, Essex, CM20 2ER. **WW401.**

A tutorial manual describes the generation of graphics using Regis (remote graphics instruction set) for use with the VT125 terminal. The VT125 Regis Primer consists of 11 chapters in 130 pages and provides a full description of each command or function with worked examples and illustrations. £6 from Rapid Terminals, Denmark Street, High Wycombe, Bucks HP11 2ER. **WW402.**

'Magnetic materials and components' is a folder containing information on the Arnold ranges of Mo-permalloy powder magnetic cores, and other iron powder cores, tape-wound cores, and other magnetic materials. Walmore, who issued the folder as well as stocking other manufacturers' magnetic materials, also manufacture ferrite toroidal cores for use in switching power supplied. Walmore Electronics Ltd, 11 Betterton Street, London WC2H 9BS. **WW403.**

The Toolrange catalogue in its latest 1983/84 edition is even bigger than its predecessors, listing tools, tool kits and tool boxes as well as a range of test instruments and other production aids. Anything from tweezers to power drills. Toolrange Ltd, Upton Road, Reading, Berks RG3 1BR. **WW404.**

SATN and TK!SATN, two publications from Software Arts, are for users of Visicalc and TK!Solver data processing packages. Available from Software Arts Products Corp, 27 Mica Lane, Wellesley, MA 02181, USA. **WW405.**

Photomultiplier tubes (with high efficiency arc rubidium-caesium types), according to literature from Thorn EMI Electron Tubes Ltd, Bury Street, Ruislip, Middlesex HA4 7TA. The new tubes are plug-in replacements for the older ones in the Thorn EMI range. **WW406.**

## Direct reading cable reflectometer


This circuit measures the length of a cable by comparing the delay of a reflection of a rising edge sent down the cable with a standard time interval.

A 20µs 2V square wave is driven into the cable from 75Ω and a fast dual comparator

NE521 and nand gate give 0 output during the period that the waveform is between ½ and 1½V. During negative half-cycles the comparator is gated off to prevent falling edges on an open circuit triggering it. The resulting waveform is amplified and clipped, filtered to leave only average d.c., and applied to a digital panel meter. Zero cable length gives approximately 1V d.c.;

1000m gives approx. 2V, thus 1mV = 1m = 10ns. Open/short circuit indication is given by latching the output of the comparator with the higher (1½V) threshold just before the falling edge of the drive waveform.


J. Andrew Suter  
Thames TV Ltd  
London



## Predictable relay oscillator

A single relay connected to interrupt its own supply simply behaves like a buzzer. And the same is true for a pair of relays connected so that each cuts the supply to the other when energized. So the usual oscillator employed by British Telecom uses three relays, as described by Atkinson (Telephony II, page 304). The relays are arranged in a ring, so that each when energized cuts the supply of its predecessor. Also each coil has a resistor connected in parallel, to delay release. When power is applied to the ring there is a short and unpredictable struggle, followed by regular cyclic oscillation.

A predictable two relay oscillator is shown below. Contact positions are drawn for S open (Except for B<sub>2</sub> - sorry).



This arrangement cannot act like a buzzer, because of the toggle action. Thus relay A cannot cancel its instruction to relay B at once, but instead its changeover contact must move right across its gap. Output can be taken from a further contact. Frequency is 3-10Hz, depending on obvious factors.

A relay oscillator will usually be started by the contact S when output is required, so start-up is of interest. The version illustrated has entirely predictable start-up, and saves a relay. It has functioned cheerfully for 20 years in a private telephone exchange. M. McLoughlin  
Haberdashers' Aske's School  
Elstree


## Opto-coupled trigger for electronic ignition

This circuit is designed to improve the triggering performance of capacitor-discharge ignition systems using thyristors as the discharge element. This is accomplished using an opto-thyristor which, while providing an enhanced drive to the discharge s.c.r., requires a reduced drive from the points circuit. This circuit has been tested with both the Marston (Jan 1970) and Cooper (March 1982) circuits described in *Wireless World*.

One of the problems in ignition design is that of the gate sensitivity of the discharge thyristor; if it is high the circuit can be triggered by transients and the s.c.r. is more costly. If it is low, large RC values are needed in the differentiator circuit, which may upset timing at high revs.

This circuit avoids these problems by the use of an opto-s.c.r. obtainable from RS as 308-001 or the GE H11C4/Monsanto MCS2-400. It is a 6-pin d.i.l. package.

A 100mA gate-sensitivity s.c.r. is used with a 2.2kΩ resistor mounted directly from gate to cathode. When the opto-s.c.r. is triggered current flows via the 220Ω resistor until the conventional s.c.r. fires. The opto-s.c.r. then self commutates, effectively giving d.c. gating. Components C<sub>1</sub> and R<sub>3</sub> are chosen to give best suppression of transients over a wide temperature range. Reducing R<sub>3</sub> would reduce the sensitivity of the opto-s.c.r. but would in-




crease the light drive required for operation at low temperatures. If the unit is to be potted C<sub>1</sub> should be increased in value to cope with the increased coupled dV/dt due to the μ<sub>r</sub> of the potting compound. The drive circuit is basically that used by Cooper with revised differentiator values

and a diode in inverse parallel to the l.e.d. in the opto-s.c.r. The circuit has been in operation for several months and has shown no sign of false triggering. P. J. Dinning  
Burnopfield  
Newcastle upon Tyne

## Economical monitor conversion

Many recent teletext colour tvs can be used as RGB-input monitors as this interface for a BBC computer and a tv set using the TDA3561 series colour-decoder i.c.s shows. Synchronization signals from the computer operate a miniature four-pole relay to switch RGB signals to data inputs of the TDA3561 and route computer sync. signals to line and field timebases. The p-n-p transistor forces the TDA3561 data/video control terminal to the data state and might be used to disable the i.f./detector i.c. to prevent video breakthrough. RGB outputs of this computer are not standard video levels and require attenuation; long connecting leads should be avoided since synchronization output is t.t.l.


Teletext decoders are often fed by the composite-video signal sent to the tv timebases and it is worth ensuring that the decoder also receives computer synchronization signals at its video input. With some makes of receiver, switching to teletext mode will remove interlace flicker on the computer display. Check that the receiver chassis is mains isolated before making the modification. Richard Norwood  
London SE25



## Non-volatile ram module

A non-volatile ram module can be constructed using a low-power static chip and a few additional components. The basic requirement for non-volatility is to maintain the static ram in a standby mode when it is removed from the external circuit or when the external power supply is switched off. The standby mode is achieved by maintaining about 3 to 5 volts on the supply pins of the ram and by holding the chip enable line, CE, within a few millivolts of the positive rail. The low-power static rams, such as the HM6116LP-4, draw only 4μA in a standby mode. Thus small mercury cells may be used as a 'power' supply that will last, theoretically, for years. It is important that the stand by cells do not drain down to the external circuit when the external supply is switched off. It is also important that no voltage exists between any two pins of the non-volatile ram module when unpowered.

The circuit shown achieves all these requirements. Three 1.4V mercury cells (type MP675H, or similar) maintain a potential of about 4V on the chip in the absence of external power. The OA47 diode, in series with the cells, protects them from the external supply. All other pins of the chip (except GND) are maintained at the positive supply rail potential through 47kΩ resistors. To isolate the mod-



ule from external circuitry when the external supply is switched off, a transistor switch is placed in the GND line. The presence of an external supply turns the transistor 'on' and its absence turns it 'off'. The OA47 diode in series with the transistor prevents the mercury cells from discharging through R1 and the transistor's base-collector diode.

N.B.: The 6116, 2K by 8 bit, low-power static rams come in many guises; some lower power than others. The following information may be of some help:


- HM6116P-3 150ns access time, 180mW active, 100μW stand-by
- HM6116P-4 200ns access time, 180mW active, 100μW stand-by
- HM6116LP-3 150ns access time, 160mW active, 20μW stand-by
- HM6116LP-4 200ns access time, 160mW active, 20μW stand-by

These are pin-equivalent to the 2716 eeprom. A. J. Ewins  
North Harrow  
Middlesex

## Two-signal bargraph



Here is a circuit which enables two signals to be displayed on one driver/display. Suitable drivers are type LM3914, 5, 6 which provide linear, logarithmic or VU response. The simplest arrangement is to use a dot mode display and multiplex the two input signals at high speed. Two leds are thus lit and represent each of the input signals. A stereo VU meter can therefore be configured with one display. The multiplexer uses two sections of a 4066 analogue switch and three inverter gates to form a clock oscillator. The remaining gates of the 4066 can be used to give an alternative display format by switching the display driver between dot and bar modes in synchronism with the input multiplexer. One input signal is then represented as a bar and the other as a dot. Clearest indication is obtained when the dot amplitude exceeds that of the bar. This arrangement was used to provide simultaneous display of peak and r.m.s. values of an audio signal.

Richard Golding  
Shrewsbury  
Salop



Format 1: two dots  
Omit components within chained area and link pins 9 and 11 on LM3914.

Format 2: Bar and dot



Sound-generator interface. Pins nine and 15 of this circuit idea in the May issue are transposed and so are their signal names.

# Shortcuts in analysis

Next time you need to determine the voltage or current in a circuit, one of these shortcuts may save you time. Calculations are saved and the possibility of making an error is reduced.

Several simple but powerful network analysis shortcuts can be easily applied to reduce circuit calculations. These include voltage and current dividers, Thévenin and Norton equivalent circuits and the superposition principle. Quite often, they are overlooked, and circuit problems are solved using more tedious methods. This article reviews network analysis shortcuts and gives you an opportunity to check your understanding with a short quiz.

## Voltages and current dividers

Perhaps the simplest shortcut is based on the voltage and current divider effect. The voltage divider effect allows one to calculate the voltage or IR drop across any resistor in a series circuit without first finding the current. For example, the IR drops across  $R_1$  in Fig. 1, is obtained using the expression

$$\frac{V_{IN}R_1}{R_1+R_2+R_3}$$

and equals two volts. In general, the voltage across any series resistor is obtained by multiplying the source or input voltage times the resistor of interest and then dividing by the total series resistance of the circuit.

In many circuit applications, resistors are connected in parallel to form current dividers as shown in Fig. 2. The current divider principle allows one to quickly determine the current in each branch. The formula is analogous to the voltage divider with one important difference: the reciprocal of each resistor is used. For example, in Fig. 2(a), the branch current through  $R_1$  is found using the formula

$$I_1 = \frac{I_T \times \frac{1}{R_1}}{\frac{1}{R_1} + \frac{1}{R_2} + \frac{1}{R_3}}$$

The particular case involving just two parallel branches occurs frequently as shown in Fig. 2(b). Resulting expressions are

$$I_1 = \frac{I_T \times R_2}{R_1 + R_2} \quad \text{and} \quad I_2 = \frac{I_T \times R_1}{R_1 + R_2}$$

For these special cases, each branch current is found by multiplying the opposite branch resistor times the total current and then dividing by the sum of the branch resistors. In Fig. 2(b),  $I_1 = 3\text{mA}$ , using the above shortcut. When using the current

by Wesley A. Vincent

divider principle, there is no need to find the voltage across the resistor before branch currents are found. Calculations are saved, and the possibility of making an error is reduced.

## Thévenin and Norton theorems

Frequently in circuit analysis, we are interested in determining how the voltage varies at two terminals. In the amplifier circuit, for example, the effect of changing the load resistor may be required. Thévenin's theorem reduces circuits using resistors, capacitors and inductors, along with voltage or current sources to a simple series circuit. To illustrate the theorem, the circuit in Fig. 3 is used as an example. To find the Thévenin voltage, denoted  $V_{TH}$ , first open the terminals a-b for the network on the right and then calculate the open circuit voltage without  $R_L$  connected. For this circuit,  $V_{TH}$  is found using the voltage divider

$$\frac{V_{IN} \times R_3}{R_1 + R_3} \quad \text{or} \quad 3V.$$

Note that, with the terminals a-b open, no current exists in  $R_2$ , so it has no effect in determining the Thévenin voltage. The Thévenin equivalent resistance,  $R_{TH}$ , is determined by calculating the equivalent resistance seen looking into the terminals




Fig. 3. Making use of the Thévenin theorem; both circuits have the same responses at the output terminals a-b.




Fig. 4. Finding the Norton circuit from the Thévenin circuit.




Fig. 1. Voltage divider consists of a voltage source and series resistors. (Positive current notation is used in this article.)





Fig. 2. Current dividers formed with parallel branch resistors.

a-b with the voltage source shorted. For the circuit shown,  $R_{TH}$  is the parallel combination of  $R_1$  and  $R_3$  in series with  $R_2$  and equals  $2.5\text{k}\Omega$ . If current sources are present in a circuit, they are opened (removed) when finding  $R_{TH}$ . For the Thévenin equivalent circuit in Fig. 3, it's easy now to calculate the output voltage across the terminals a-b as  $R_L$  varies. All that's needed is application of the voltage divider principle as discussed in the last section. More complex circuits are reduced in a similar manner, even though  $V_{TH}$  and  $R_{TH}$  may be more difficult to determine. But it's easier than the alternative of solving simultaneous loop equations for each different value of  $R_L$ .

Another useful circuit theorem, called the Norton theorem, results in the "dual" of the Thévenin circuit and is shown in Fig. 4. The Norton current source, denoted  $I_N$ , is the current through the terminals a-b if they were shorted. The equivalent resistance,  $R_N$ , is the resistance seen looking into the terminals a-b with any voltage sources shorted or current sources removed from the circuit. The Norton equivalent circuit is particularly useful for determining the current through different load resistors connected to the output terminals.

## Superposition principle

One of the most powerful circuit analysis tools is the concept of superposition. This principle applies to circuits containing more than one voltage or current source and allows the total response from a circuit to be found as the sum of each source acting alone.






Fig. 5. Using superposition to find the dc bias on the gate of a j-fet amplifier. Original circuit (a), determining the effect of  $V_{SS}$  (b), and determining the effect of  $V_D$  (c).




Fig. 6. Using superposition with a current and voltage source. Original circuit (a), circuit with current source open (b), and circuit with voltage source shorted (c).

The usefulness of superposition is demonstrated by finding the d.c. bias on the gate terminal of the j-fet amplifier in Fig. 5(a). (Only leakage current exists through the gate terminal of the j-fet, and its effects will be considered negligible in the calculations.) The effect of each source acting alone is determined from the circuits shown in (b) and (c). The responses from each circuit are added together to give a gate voltage of 4V for the circuit in (a). The gate voltage can be found almost by inspection using this technique. It's important to note that, except for the source under consideration, other voltage sources in the circuit are shorted and current sources are opened.

Figure 6 illustrates the use of superposition, along with voltage and current dividers, when a current source is present. In (b), the current source is first removed, and the output across terminals a-b is found. Here, the voltage divider principle is used with  $R_1$  and the parallel combination of  $R_2$  and  $R_L$ . In (c), the voltage source is shorted, and the current divider principle is applied to find the output voltage. Once the output voltage for the circuits in (b) and (c) are determined, their results are added to give the output voltage for the original circuit in (a). For the circuit shown, the voltage across the terminals a-b is 5V.


## Capacitors and inductors

All of the circuits in this article contained only resistors. But all the shortcuts discussed apply to circuits containing capacitors and inductors as well. Instead of resistance, reactance is used and impedance replaces combinations of resistors and resistance.


## Test yourself

As a test of your understanding of the principles discussed, try your hand at the quiz below. Then turn to page 57 to determine your score.

- Question 1. What is the voltage across  $R_2$  in Fig. 1, using the voltage divider principle?
- Question 2. What is the voltage across  $R_3$  in Fig. 1?
- Question 3. For the circuit shown in Fig. 2(b), how much current exists through  $R_2$ ?
- Question 4. What is the IR drop across  $R_1$  in Fig. 2(b)?
- Question 5. If  $R_2 = 1\text{k}$  instead of  $2\text{k}\Omega$  in Fig. 3, what is the value of the Thévenin voltage  $V_{TH}$ ?
- Question 6. If  $R_2 = 1\text{k}$  instead of  $2\text{k}\Omega$  in Fig. 3, what is the value of the Thévenin resistance  $R_{TH}$ ?
- Question 7. What is the Norton equivalent current,  $I_N$ , for the circuit below?



- Question 8. What is the Norton equivalent resistance,  $R_N$ , for this same circuit?
- Question 9. Using the superposition principle, what is the IR drop across the  $2\text{k}\Omega$  resistor in the circuit below?



- Question 10. If the polarity of the 4V source is reversed, what is the IR drop across the  $2\text{k}\Omega$  resistor?

# Forth computer

Construction tips for the 6809-based Forth computer — part four.

by B. Woodroffe


Most of the prototype version of this computer was constructed on one wire-wrap board. The number of signal buses rendered anything other than a multilayer printed circuit board an impractical solution without splitting the circuit into sections. Splitting the circuit was rejected to eliminate buffers associated with long cable runs. Wire wrapping provides connections at least as good as solder joints through cold welding between the wire and edges of the pin.

All main memory, refresh circuit, microprocessor rom and interface i.c.s are mounted on the main 229 by 178mm board, as are the video-display processor and memory. The analogue video gate and RS232 driver are built on two 16-pin dip headers. User-port hardware and the disc-drive interface between the floppy-disc controller and the drive are housed on a second wire-wrap board. There are many connections on the board so a powered wrapping tool, a stripping tool and different coloured wires for different functions are useful. Copper-clad board was used for the power supply, which should be constructed before the main processor board.

Dynamic ram takes little static current but substantial pulses, reaching toward

Brian Woodroffe works in research and development at Hewlett Packard.

80mA per device over a few nanoseconds on some clock edges. Although the rams work within a 10% voltage tolerance, for reliable operation substantial local decoupling must be included in the +12 and -5V rails to overcome power-line inductance; each ram has a 0.1µF ceramic capacitor on both supplies. Further 10µF bulk decoupling capacitors were used, one be-



Voltage transients at the 4116 dynamic rams showing from top to bottom the E clock signal and +12V, +5V and -5V supply lines with a 200ns/div timebase.

tween each four devices. Decoupling capacitors for the 5V rail were used throughout the design at the rate of one 100nF component for each six i.c.s. As with the RAS/CAS/WE damping resistors, the design seems robust since the ram was initially built and worked without decoupling (see photograph).

This is a large project and all construction errors were found to be the result of either miswiring or plugging in the i.c.s wrongly. Dynamic rams I currently use got very hot when I plugged them in back-to-front. Construction should start with a minimum system, i.e. c.p.u., p.i.a., e.proms and a 16K ram. At switch on, the lamp connected to the p.i.a. B-port D<sub>0</sub> line will go on then off. The state of this lamp then monitors the state of i/o data on the line. Ram-select lamps will stay off. V.d.u. hardware is self-contained so an idea of its performance can be seen on a tv screen without involving the main processor as the video i.c. generates its own characters.

Connection of the parity circuit to HALT should only be made after the ram circuits are known to work, i.e. when the system ready message can be displayed consistently. Should the RS232 connection fail to work, the most likely cause, especially if a signal at the a.c.i.a. output can be seen on resetting, is that data lines on pins two and three are crossed. Another problem could be that the RS232 terminal

## Main-board components

Value	Qty	Function
10k	8	pull-up, FIRQ, IRQ, NMI, VFOE, RESET, video and RS232 output
10k	2	pull-out parity, video ram, 9-resistor sil packs
100	1	dot-clock
500	1	dot-clock trimmer
20k	1	monostable timing, 5%
400	4	pull-up, led
33	5	damping, RAS, CAS, R/W
75	1	video output
150	1	video output
1k	5	video and RS232 output
2.3k	1	video output
4.7k	1	video output
2k	1	video output
2k	1	video output, trimmer
5.1k	2	RS232 output

Value	Qty	Function
100µ	2	+5V decoupling, 25V
20µ	2	+12V decoupling and reset, 25V
10µ	8	-5V and +12V decoupling, 25V
100n	57	-5, +5 and +12V decoupling
20p	2	crystal decoupling, 10%
51p	1	dot clock, 5%
20p	1	monostable timing, 5%

## Integrated circuits

Ref	Qty	Pins	Type	Comments
11	1	14	LS280	parity checker
12-110	9	16	4116	see note
21	1	28	13242	address multiplexer
22-210	9	16	4116	see note
31,67	2	20	LS245	bi-directional buffer
32-310	9	16	4116	see note
41,44	2	14	LS04	hex inverter
42,47	2	14	LS00	quad 2-input NAND
43,72	2	12	LS02	quad 2-input NOR
45	1	16	LS112	dual JK bistable multivibrator
46,53	2	16	LS161	sync. binary counter
47,48	2	14	LS37	quad 2-input NAND clock driver
51	1	40	M6809A	microprocessor, 1.5MHz
52	1	16	LS139	dual 2-to-4 decoder
53	1	14	LS122	monostable multivibrator
54	1	40	WD1793	floppy-disc drive controller
55	1	40	M6821	p.i.a.
62,63	2	24	I2732	4K by eeprom, T <sub>acc</sub> =450ns
56	1	16	LS175	quad D bistable
66	1	16	LS157	quad 2-to-1 line multiplexer
71	1	24	M6850	a.c.i.a.
73	1	14	LS86	quad 2-input ex-OR gate
74	1	14	LS132	quad 2-input Nand, schmitt
75	1	28	EF96364	video display controller
76	1	20	LS240	octal 3-state inverter
77,78	2	18	2114	1K by 4 static ram
81	1	14	LS00	quad 2-input NAND
83	1	14	LS04	quad 2-input NOR
84	1	16	LS161	sync. binary counter
85	1	24	I2716	2K by 8 eeprom, T <sub>acc</sub> =450ns
86	1	20	LS273	octal D bistable
95	1	16	LS165	8-bit serial shift reg.

See note for other i.c. locations

## Other components

2N2222 5 video, RS232 output transistors  
 1N4150 2 video, RS232 output diodes  
 2N2907 1 RS232 output transistor  
 L.e.ds 4 parity checking, high-efficiency red  
 6.00MHz crystal  
 1.008MHz crystal  
 DIP headers for video and RS232 output  
 25-pin D-type connector for RS232 output  
 Single-pole two-way switch for display-page select  
 Three, 16-way insulation-displacement connectors  
 Vero 07-0130A wire-wrap board  
 Wire-wrap pins (1 packet), wire, tool, un-wrap tool and wire stripper. Wire-wrap sockets:

Pins	Quantity
14	14
16	39
18	4
20	4
24	4
28	2
40	3

## Notes

Memory circuit was designed using Mostek MK4116-3 data sheet and most critical timing specification was T<sub>acc</sub>=135ns (column-address strobe). Positions IC<sub>57,82,92</sub> are 16-pin dip for plugs a,b and c respectively. Positions IC<sub>91,93</sub> are also 16-pin dip for RS232 and video signals. Resistors are 10% and capacitors are +80/-20% except where tolerances are given.

## Disc interface


Type	Qty	Pins	Comments
LS244	1	20	octal buffer
'38	2	14	standard t.t.l. quad NAND, o.c.
LS123	1	16	dual monostable multivibrator
LS161	1	16	4-bit binary counter
LS163	1	16	4-bit binary counter
LS74	1	14	dual D bistable multivibrator
LS14	1	14	hex inverter, schmitt
LS04	1	14	hex inverter
K1160	1	14	8MHz oscillator (Motorola)
LS138	2	16	3-to-8 line decoder

## Other components

Wire-wrap socket, 14 pin (4 off)  
 Wire-wrap socket, 16 pin (10 off)  
 Wire-wrap socket, 20 pin  
 Wire-wrap board 176 by 110mm, e.g. Vero 02-0120H  
 34-way insulation-displacement connector  
 34-way insulation-displacement cable to drive  
 Disc drive, e.g. Teac FD50A (up to 4)  
 Drive power connector (AMP1-480424-0)  
 Pins for above connector (AMP60617-1, 60619-1, 4 off)  
 Decoupling capacitors, 100n (6 off)  
 Decoupling capacitor, 100µ  
 Input resistors, 333 (4 off)  
 Input resistors, 220 (4 off)  
 Timing resistors, 30k (2 off)  
 Timing capacitor, 2µ 10V  
 Timing capacitor, 33µ 10V

## Alternative oscillator components

Hex inverter, LS04  
 Resistor, 464 (2 off)  
 Capacitor, 20p  
 Crystal, 8MHz



Wire-wrapped disc interface board bottom, and the disc-drive main circuit board.

takes too much current from the -5V supply, an indication being that the rams persistently give parity errors on power up which disappear when the RS232 terminal is disconnected. Forth response OK is preceded by the stack depth.

The problem of driving capacitive loads

with l.s.t.t.l. outputs showed up as undershoot in signals passing from the interface board to the controller. Although the prototype worked with the undershoot, it was cured by taking an inverted version of the required signal back to the main board and inverting it

## Power supply

MC3405 op-amp/comparator, alternative 158 op-amp and 193 comparator  
 12V, 1A regulator  
 n-p-n (4 off)  
 p-n-p (2 off)  
 p-n-p (2 off)  
 p-n-p (2 off)  
 s.c.r.  
 1N437 ref. diode, alternative 1N960B 9V zener  
 1N4371 zener, 2.7V  
 1N4372 zener, 3V, alternative 2.7V  
 1N751 zener, 5.1V  
 1N963 zener, 12V  
 MR852 fast recovery diode  
 MDA970-2 bridge rectifier, 4A  
 1N4150 diode, alternative 30V switching diode, pref. Schottky  
 HLMP-1300 high-efficiency red led, 2.2V drop

## Capacitors

1n 10%  
 470n (2 off)  
 100n (2 off)  
 22µ 10V tantalum  
 22µ 20V  
 1m 12V low equivalent series resistance, e.g. Sprague 672D046 or Dubilier UPC1052  
 8m 40V, alternatively 4m

## Resistors

0.13 1W  
 100 (2 off)  
 133 0.25W  
 200 0.25W  
 680 0.25W (6 off)  
 1k  
 1.5k  
 1.96k  
 3.16k (2 off)  
 10k (6 off)  
 28.7k  
 75k  
 100k (5 off)  
 50k preset pot.

Transformer is a 15V r.m.s. 2A type and should be protected by a 500mA slow fuse. A mounting kit is required for the 2N6476, a cooling tab for the T05 transistor, and the toroid is an Arnold A-930157-2 with 35 turns of 21 s.w.g. (not 19 s.w.g. as on the drawing). The toroid is available from Walmore Electronics Ltd, 11 Betterton Street, Drury Lane, London WC2H 9BS.

there with a spare l.s.t.t.l. gate. Capacitance of the insulation-displacement connection between the two boards was avoided in this way. Spare connections on the inter-board connector should be grounded and ground should be placed near active signals, e.g. clocks, disc data.

Although for 8K of memory one gets a compiler and operating system and programming and execution unit there is still much to be done. I think that games are one of the best ways to learn about computers for the definition of a problem to be solved is often as difficult as solving the problem. Forth is particularly suited to games programs — the *Byte* game contest was won by a game written in Forth<sup>10</sup>.

## Reference

10. A. Saunton-Angus, *Cosmic conquest, Byte*, Dec. 1982, p.124.

## Further reading

C. H. Ting, *Systems Guide to Fig-Forth*, Mountain View Press.  
 Forth Dimensions, Forth Interest Group, PO Box 1105, San Carlos, CA94070 (house magazine for members).

Brian Woodroffe has found a way of speeding up disc operations and data-transfer rates so that faster units such as the Sony Microdrive and 8in drives can be used with the Forth computer. Descriptions will follow.

# 300baud full-duplex modem

Direct-coupled modem described in the July issue has a separate circuit board for the auto-answer protocol required by CCITT





by Des Richards

This unit provides the interface between the telephone line and the equipment and is suitable for both private wire circuits and the public switched network. It also provides the necessary isolation of dangerous voltages and the transmission of the required signals together with the auto-answer protocol required by British Telecom in accordance with CCITT recommendation V25. The isolation is achieved in two ways: the ringing current is isolated by a discrete-component optocoupler  $D_2$  and  $Tr_1$  and both the a.c. signal isolation and d.c. terminating conditions are achieved by a reed relay and isolating hybrid transformer (which will carry a primary current of up to 120mA d.c. without causing transmission loss to the signal path).

Operation is as follows. The ringing current is detected by  $D_2$  and  $Tr_1$ , and causes  $C_1$  to be charged via  $Tr_1$  and  $R_2$

until the voltage across  $C_1$  reaches the threshold potential of the unijunction  $Tr_2$ . This conducts, discharging  $C_1$  and causing the collector voltage to fall from 12V to about 0.7V. This negative-going transition changes the state of the two monostables  $IC_{1a}$  and  $IC_{1b}$ . The first has a time constant of approximately 30 seconds and the second a time constant of  $2.15 \pm 0.35$  seconds. The output of  $IC_1$  drives  $Tr_3$  to operate the reed relay  $RL_1$  and answer the incoming call by placing a d.c. loop ( $T_1$  primary) across the line terminals. Simultaneously with the call being answered  $IC_{1b}$  triggers and operates  $RL_2$ , which places a 600 $\Omega$  termination on the

equipment side of the hold transformer. This gives the silent period of 1.8 to 2.5 seconds as required by V25. When  $IC_{1b}$  returns to its stable state the negative-going output triggers  $IC_{2a}$  which has a time



constant of within  $3.3 \pm 0.7$ . This operates  $RL_3$  to switch the secondary of the transformer to the output of the 2100Hz oscillator, to feed tone at -12dB to line. This is another requirement of V25, to disable any echo suppression equipment as used on the telephone trunk and international circuits. When  $IC_{2a}$  returns to its stable state it triggers  $IC_{2b}$  to switch  $RL_2$  and give another silent period of  $75 \pm 20$ ms. This completes the auto-answering protocol and the secondary of the transformer is fed via  $RL_2$  and  $RL_3$  to the modem board.

The 2100Hz oscillator is a standard

Wein-bridge circuit with a thermistor to stabilize its amplitude. The output level of the oscillator to line should be less than -10dB and is normally set at -12dB.

## Power supply



The mains input is fully isolated from the d.c. outputs and protected by a 100mA anti-surge fuse, in the author's circuit. Regulated to give outputs at +12 and -12 volts, there are no adjustments necessary and the voltages should be as specified  $\pm 0.5$  volts. The supply is capable of supplying a total of 25VA and can power a number of modems. A straightforward cir-

cuit and board layout are obtainable from the editorial office.

## Construction

The complete modem was designed to be housed in two four-inch, 3U high rack modules, one being the power supply and the other containing the auto answer unit and the modem. The power supply p.c.b. mounts on the side of the module and all the components, except mains transformer are mounted on this board.

A modified rear plate has been made to enable the mains input to be made by a separate connector to the d.c. outputs. An



IEC 3-pin connector is used for the mains supply and a 24-way connector for the d.c. supplies. The mains socket and fuseholder should be fully shrouded and all wiring to the board and 24-way connector sleeved at both ends.

The modem unit is built in the second module with two p.c.bs mounted on either side of the unit. The holding transformer is mounted on the base plate between the boards. Connections in and out of the unit are made by a 24-way edge connector at the rear of the module.

Assembly of both boards should not present any problems especially as the

components mount directly on the boards, with the exception of the l.e.ds which are wired to the front panel.

The infra-red diode and phototransistor are glued together with epoxy resin and painted black. This method gives greater pin spacing on the p.c.b. on the ring-detect circuit than would be achieved by using a d.i.l. opto-isolator, and thus meets BT specifications for p.c.b. spacing within protection barriers. Again, all connections to the p.c.b., switch and rear connector should be sleeved to prevent accidental bridging of the protection barriers created by the opto-coupler and the isolating

transformer.

The transformer should be 600 ohm impedance type with 1+1:1 turns ratio.

*The Reticon switched-capacitor filter shown in the July circuit can be obtained from Reticon's UK agent EG&G Instruments, at 34 Market Place, Wokingham, Berks RG11 2PP (tel. 0734 788666) for £8.50. A complete kit of parts including transformer and printed circuit boards is being organised by the author - send a stamped and addressed envelope for details to 18 Tulsa Close, Berryhill, Stoke-on-Trent ST2 9PT.* WW

## AERIALS AT SEA

It is hard to understand the logic of Mr Benyons' statement (Letters, WW, May, 1983) that it is "unfair" to look at Soviet ships' aerials because these ships are "under military control". I would like to point out that:

● By no means all Soviet bloc ships have "good" aerials. As General Booth said to the Salvation Army band, "why should the devil have all the best tunes?", so why should the "red peril" have all the best aerials?

● The experience of the Falklands war shows that British ships are also under "strict military control". Even Mr Benyon would wish them the best possible radio communications capability.

Could it be that the USSR has better trained engineers than we have, not subject to the dollar veto of penny-pinching shipowners, nor rubber-stamp government supervision?

Mr Benyon correctly perceives that short aerials lack much radiation resistance, but I don't see his 20 foot vaulting pole aerial as being any "great leap forward", for the following reasons.

All existing marine transmitters, at 500 kHz, rely on the aerial to provide the tank circuit capacitance. The helical whip has none.

Only low driving-point impedance will confer any benefit. As well as altering all transmitters, it would be necessary to provide feeders and matching coils, introducing more losses than gains. Marine transmitters, unlike their broadcast counterparts, are free from this extra paraphernalia at present.


ARRL "antenna book" points out that a vertical helical wound aerial of quarter wave electrical equivalence, should be a minimum of 0.05 wavelength long. At 600 metres, that comes to 30 metres, so nothing is gained in the area of the height problem. The same book also relates that "some helical antennas have acted as Tesla coils with high power transmitters and have actually caught fire at the high impedance end!"

Back to the drawing board, Mr Benyon.

John Wiseman  
Hawthorn  
Victoria, Australia




## ELECTROMAGNETIC DOPPLER

In the answer to Mr D. Hall (June letters) I suggest that he studies the following picture.



It represents a boat on a lake. Waves are being generated and are propagating across the lake at constant velocity. The point of interest is that there is no way of telling whether the boat is stationary or is moving, the reason being that the wavelength is the only observable parameter and that is unaffected by the velocity of the boat.

The frequency is the number of waves passing the boat in unit time. Clearly the faster the boat moves in the same direction as the waves the less waves will overtake it in unit time. If there are two boats travelling across the lake at different velocities they will experience different frequencies and if we call the velocity of propa-



gation C then the formula is:

$$\frac{f_1}{f_2} = \frac{c-v_1}{c-v_2} \quad (1)$$

This is a general formula for any two observers, observing the same wave. If one of the observers is also coincident with the source he may be conventionally described as the source. The wavelength which the source would have produced if it had not been moving is a non-existent parameter, because the source is moving and at no time does that wavelength appear even to the observer at the source. Not only is the propagation velocity constant, but so is the wavelength. The difference in frequency is due purely to the fact that the velocities of the two observers relative to the waves are different. I claim that this model for water also holds for sound waves and therefore cannot be the same for e.m. waves without violating the constant-velocity postulate of relativity.

Mr Hall suggests that the e.m. Doppler equation is only an approximation and should more accurately be as equation 1. This cannot be so because the second order terms such as  $v_2(v_2-v_1)/c^2$  cannot be expressed purely in terms of the relative velocity  $(v_2-v_1)$ . If accurate measurement did in fact detect such a term it would also have detected other drift. The relativistic Doppler equation is supposed to be accurate even when  $v$  is very close to  $c$  and the term it contains is  $(c-v)/c$ .

Mr Hall's point about photons, waves and interference I accept. I'll go away and think about it.  
J. Kennaugh  
Callington  
Cornwall


## DIGITAL TAPE CLOCK

The following alternative method for producing the 'forward' and 'reverse' inputs to the counter/display section may be of interest.

The two optical sensors are both mounted on the 'length-of-tape' timing disc, with a quarter-cycle 'phase' difference between them, as simply shown in Fig.1. If these sensors' outputs are fed, suitably buffered, into the circuit of Fig.2, a 90Hz version of the forward and reverse signals results. This can easily be counted down with 2 more 74192s.

Also I am unable to understand the buffering circuitry for the 'length-of-tape' opto-coupler. I would use a circuit like that of Fig.3., with positive feedback for jitter-free operation.

M. S. Farmiloe  
Camberwell  
London



## A HERETIC'S GUIDE TO MODERN PHYSICS

Tut, tut, Mr Coleman of July! A photon of visible light has a wavelength?

If it did not bounce back and forth between and amongst its neighbours it would simply keep going in a straight line without a wavelength. But then, a photon, being a packet of energy carried by a bouncing building block doesn't bounce at all, does it? The building blocks merely play "pass the parcel", and the parcel moves linearly if spewed out of a laser, otherwise it is split up providing the so-called square-law effect which is part of an expansion of a spherical surface.

As I said in my letter of July, it takes one particle an impossible amount of work to make a wave. A wave is an integrated effect of a lot of moving particles. It is hoped that there is not some mental mix-up here with spin velocity, which determines the amount of energy within the particle and thus its relativistic mass, and thus in turn the gravitational gradient in the immediate environment of the particle?

I doubt very much indeed whether an individual photon can remove even a conduction electron from a metal, at least not in these parts: its spin velocity would have to be so high that catastrophe was being approached, somewhere near the boundary of the universe perhaps? Of course it takes a wave, an integration of a lot of bouncing building blocks, and therein lies the strength of wave mechanics which sadly explain nothing more than the cause of an effect at the subjective level of apparency, delightfully demonstrative of a shallow and superficial analysis.

Until the specialists of this world come to realise and thus accept that the absolutes are really asymptotes, modern science will remain stuck in its glorious mud. I have in mind absolute zero, absolute resistance, the speed of light, and the basic building block. The asymptotes can not be reached because a multiple lamination of short Planck's constants gets there first.

Space, of course, is purely reactive, there being no friction within chaos: only genuine fully-fledged masses can demonstrate friction at work, in their interactions so demonstrating the decay therefrom. Space, like any other reactive device, is an energy-store out of which mass condenses.

How I wish that the specialists of this world would stop their silly arguments and learn!

James A. MacHarg  
Wooler  
Northumbria

I continue to read with interest Dr Scott Murray's series on modern physics. However, I must take issue with what I regard as a fallacious argument in the 7th part.

He points out that it is possible, after the event, to determine the position and momentum of an electron "to any accuracy we please". He then goes on to assert that our ability to do this indicates that the electron's behaviour was determinate, and that it must have obeyed the law of causality. Hence, the Copenhagen doctrine is false.

Later, though, he admits that he is unable to prove that the law of causality is obeyed throughout inanimate nature, although there is no evidence against that assertion. Herein lies the flaw, for we can only determine the past properties of the electron if the law of causality has been obeyed. That is, we deduce where the electron was and what it was doing by knowing where it has been subsequently and what interactions it has undergone. If causality did not apply, then we would still be faced with the indeterminacy of instantaneous observation, so an argument that assumes causality cannot be used to refute any doctrine to the contrary.

Almost 30 years ago I was taught by my professor of physics that causality was the underlying assumption in the study of physics. This meant that, given a knowledge of the causal relationships governing inanimate matter, it would be possible to predict the future from a knowledge of the present, which was the goal of the Victorian physicist. The indeterminacy principle, we were told, strikes not at causality but at our knowledge of the present. If that is uncertain, our predictions must change from certainties to probabilities. Perhaps I move in the wrong circles, but I have not met anyone who seriously contested that interpretation. I have to admit that much of my working life has been spent among engineers.

R. T. Lamb  
British Telecom  
Milton Keynes

Dr Scott-Murray's articles on a heretic's guide to modern physics have clearly shown that the Copenhagen philosophies and mathematical theories of statistical wave mechanics have left scientists without a fundamental theory of matter.

Probably the most glaring error made by the Copenhagen School is their deduction that superfluid helium is a special type of quantum

liquid, to which they have devoted many papers and given many names: Liquid Helium II, Landau's two-fluid liquid, Bose-Einstein Condensate.

The common sense approach of Faraday, Newton, and Galileo, recommended by Dr Scott-Murray, easily deduces that superfluid is a powder. It is a fluid like table salt and pepper but it is not a fluid like vinegar, which is a liquid. Scientific studies of all the properties of superfluid helium show that every experiment demonstrates that superfluid helium is the solid phase of helium in the physical form of a very fine transparent amorphous powder which is only 3°C below its boiling point; hence it is a rapidly subliming powder.

Because university students have to accept without question the beliefs of the Copenhagen statisticians, they have to believe that this powder is a form of magic liquid with antigravity properties. They are all baffled because it doesn't behave like other liquids.

Throughout my career in science I have used the wave concept of light and the particle concept for an electron. I can explain the photoelectric effect without resorting to a photon particle concept and I can explain the behaviour of an electron in an electron microscope without resorting to a wave concept for an electron. Hence I agree with Dr Scott-Murray's statement "All the indications explored in this series support the view that the Copenhagen myths, although undoubtedly propounded by their originators in complete sincerity, constitute one of the biggest hoaxes of self-delusion of the twentieth century".

When I left Cambridge (with a first-class science degree) in 1949 I was a firm believer in the photon, wave mechanics and quantum liquid, but thirty years of scientific experiment and study has shown to me that photons, phonons and rotons are myths and superfluid helium is, as one would expect by common sense, solid helium in the form of a very fine powder. When this powder melts at 2.2K it absorbs latent heat (the  $\lambda$  effect) and becomes normal liquid helium which boils at 4.2K.

P. Holland  
Egremont, Cumbria.

Now that Dr Scott Murray's series of articles on physics has ended, I hope that you will continue to have a physics section in *Wireless World*. If so, why not name it, "Frontier Physics". There are no doubt others like myself who buy your journal not for its electronics but solely to enjoy reading those controversial physics articles — and, of course, the Letters section in which wayward physicists express their ideas can certainly stimulate one's own thoughts.

It is a pity that physics has become dogmatic. Some years ago I proved that Special Relativity was mathematically and physically wrong, but I couldn't convince others. However, I did discover that there was a 'closed loop' acting in physics.

The closed loop is an argument. It consists of a main theme, which cannot be disputed, and which begins and ends any discussion. For example, the closed loop of Special Relativity can be used to prove that time dilates as follows:

1. Special Relativity is true (main theme)
2. Its equations show that time dilates.
3. Its equations cannot be wrong.
4. Therefore time must dilate.
5. Special Relativity is true. (main theme).

In a scientific journal recently, the closed loop is used to show that the cost of accepting com-

mon time (Newtonian time) would be too high a price to pay in physics. The closed loop is as follows:

1. Special Relativity is true. (main theme).
2. Inserting common time into Special Relativity's equations gives a daft answer for the speed of light.
3. This daft answer means that either Special Relativity's equations are wrong or that common time is wrong.
4. Special Relativity's equations cannot be wrong.
5. Hence, common time must be wrong.
6. Special Relativity is true. (main theme).

In the past, the closed loop has been used to give a satisfactory answer to the late H. Dingle's challenging question, "Of two uniformly-moving clocks, A and B, which ticks the faster?" The closed loop gives the well-known answer.

1. Special Relativity is true. (main theme).
2. Moving A ticks slower than stationary B.
3. But stationary B can be regarded as moving and moving A can be regarded as stationary (by the principle of relativity).
4. So A ticks slower than B and B slower than A!
5. Either commonsense is wrong or Special Relativity is.
6. Special Relativity cannot be wrong.
7. Therefore commonsense is wrong.
8. Special Relativity is true. (main theme).

It can be seen that the closed loop is an invincible argument. Of course, the above examples seem obviously silly because they are presented in skeletal form. When the closed loop is clothed with advanced maths, though, its use is by no means obvious; you must look carefully for it!

A. H. Winterflood  
Muswell Hill  
London

## DESIGN COMPETITION

Although I applaud your initiative in setting a competition for electronic devices to assist the disabled, I fear that many potentially suitable devices will not be entered. This is because they may originally have been designed for other purposes, where their commercial value is such that publication of their design is precluded. It would be useful if your journal could also act as a clearing house for information on the existence of these devices.

In many cases, I imagine that the designers of these devices would be prepared to spend some of their own time in adapting them to the needs of disabled people, but cannot reveal how they work.

As an example, Hydraulics Research Ltd has collaborated with the Weed Research Organisation on the development of a low-cost "plant sensor". At present the devices exist in two forms:

- (i) is a linear readout instrument which can be used to indicate the relative health of plants, their degrees of maturity, or the proportion of a field of view which contains plants. It can, for example, indicate on an analogue meter the degree of wear on a grass playing field.
- (ii) is a switch which energises a load when it sees a plant. This is intended for incorporation into a "robot" crop sprayer, when the load would be the coil of a solenoid valve in the line to a spraying nozzle.

The designs originate from the need to make

simple measurements of crop cover during a project which was intended to evaluate the protection which leaf canopy provides from soil erosion by heavy rainfall, and version (ii) is a natural extension of the resulting design into a commercial application.

Both versions will shortly be available from Churchill Controls Ltd of Headley Road East, Woodley, Reading.

One of my colleagues has commented that modified versions of these devices might be very useful to blind or partially sighted people. Such applications would be outside our experience, but we would be pleased to discuss them with anyone who could provide a specification for what is needed, or would like to incorporate one of these sensors in a design of their own.

D. K. Fryer  
Hydraulics Research  
Wallingford  
Oxfordshire

I was interested to see that one reader has come up with the idea of informing blind persons the contents of cans and packages without opening them. No further information was given.

I should like to suggest (if this is not the method used) that it would be a simple matter to 'read' the bar codes that are appearing increasingly on modern packaging by means of a light reader: decoding the information and removing extraneous information normally used in stock control; and presenting the edited information to the blind person by means of a voice synthesizer through a private earpiece.

Being completely without technological training I would nevertheless suggest that in this day of the Chip it would not be beyond the realm of possibility to produce a fairly lightweight pack which could be worn like a handbag over the shoulder and weigh about the same.

Once the technique had been perfected there is no reason why bar-code labels could not be used in other circumstances to aid the blind to read. We already see these codes on the edges of supermarket shelves and on packaging. Why not make complete sentences and print books in the same manner. Naturally a monotonous Dalek 'voice' would never replace the enjoyment of silent reading as Braille offers but this would be ideal for official pamphlets for the blind, direction signs and other informatory instructions.

J. Devereaux  
Wordsley  
West Midlands

## WAVES IN SPACE


Ivor Catt (March, 1983) says "the voltage is half of what one would expect". The curious point to me is on what he bases his expectations. If the charged line is regarded as a voltage source of impedance  $Z_0$  (the characteristic impedance) connected to another impedance  $Z_0$  through the switches, as in the accompanying sketch, then the voltage is exactly what one would expect. The finite duration of the pulse stems from the fact that the charged line is an energy storage device (electrostatic field) and not a source of e.m.f. which implies energy conversion. It is worth adding that the impedance technique also enables one to predict occurrences when the  $Z_0$  of the long line is not equal to that of the charged line.

As to the claimed paradox that "electromagnetic energy promptly rushes away from the path suddenly made available", if Mr Catt will

examine Poynting's vector in the charged line after the switches are closed, he will find that the electromagnetic energy moves only into the long line, that is, from left to right.

It is possible to regard the condition of the charged line as the result of interference between two waves travelling in opposite directions, just as one can treat a straight line as the arc of a circle of infinite radius. There are times when they are useful models of reality. The real paradox of the article is the question of where Mr Catt (and, for that matter, *Wireless World*) have been all this time. To my knowledge, the Royal Air Force used this approach to transmission lines as pulse generators in 1959, and I have no doubt that the technique goes back much further in time.

R. T. Lamb  
British Telecom  
Milton Keynes



I refer to Mr Catt's article in the March 1983 issue.

In a letter, I could not hope to reproduce the great body of scientific and engineering knowledge that has amply demonstrated the non-relativistic interpretation of Maxwell's Equations or of Einstein's treatment using special relativity. If the theory is so seriously flawed it is surprising that we can design and build antennas and microwave devices. Nevertheless, I cannot let Mr Catt's analysis of the pulse generator go unchallenged, especially as it is so easy to demolish his arguments.

Firstly, if a piece of charged coax. really has equal and opposite waves running in each direction why are they not attenuated by the losses in the line? After all in one second each of his waves would have travelled nearly 2,000 miles in lossy coax.

Secondly, if I connect an antenna to a piece of coax. I can still charge up the line. Why do not these waves of which he speaks radiate into space? Or, at least, the high-frequency components of the pulse to which the antenna will be matched.

The conventional solution to his 'exotic' problem can be found by solving the transmission line equations for a cable under the stated starting conditions (see reference). As this is rather tedious and since Mr Catt seems to prefer hand waving to mathematics I will at least demonstrate where the 2m pulse length comes from.

When the extra length of line is connected to the 1m line, charge starts to move down the new line charging the distributed capacitance of the line through its distributed inductance as it goes. (Maxwell's equations applied to circuits show us that capacitors connected together share their charge). This leaves a void which the 10V (1m) line fills. The void propagates towards the open end of 1m line at the speed of the line. The charge close to the open end of the line will be liberated at a time equivalent to 1m of line and will take 1m to propagate to the other end,

Reference: Brown and Glazier: *Signal Analysis* pp. 345-349.

explaining the 2m length of the pulse.

The pleasing aspect of the above argument is that we do not have to destroy a century of successful electro-magnetic theory to produce it. If Mr Catt has so much more insight into electro-magnetic theory than the rest of us it is surprising that he has not produced any new microwave devices that demonstrate his superior understanding.

Timothy C. Webb  
Columbia, MD  
USA

I was not too sure whether I should be amused or startled by Ivor Catt's article on "Waves in Space" in which he postulated the existence of electromagnetic energy in a static electric field, when I reminded myself that the date was 1st April. It had never occurred to me, even remotely, that a magnetic field could be directly caused to exist by the presence of an electric field. However, being sympathetic to the idea that all things appear to be possible in this day and age, I allowed my mind to be bent a little further and read on.

The production of a voltage pulse in a transmission line which is half the amplitude and twice the length of that existing statically in piece of coaxial cable, can form the basis of a number of interesting experiments. For example, Mr Catt's travelling pulse can be converted back into a static charge again if his coaxial cable is terminated into an open circuit but with a pair of switches 1 metre from the end as shown in Fig. 1. When the switch at B is closed and the resulting pulse eventually reaches D, it will of course, be reflected (double back on itself); however, if switch C, is opened at the instant the leading edge meets the trailing edge, no great drama ensues but we are left with a 1 metre piece of statically charged coaxial cable as before. It is also interesting to consider what happens if point D is terminated into a short circuit. This time, the pulse will be converted into one of twice the current at zero voltage and the leading and trailing edges will be locked together and oscillate back and forth converting the pulse between a current at zero voltage and a voltage at zero current until this activity decays due to losses.

However, perhaps it would be more interesting to consider what would happen if this final 1 metre of coaxial cable is made superconducting and instead of isolating switches at C, a short circuiting switch is provided as shown in Fig. 2. If the switch at C is closed at the instant the leading and trailing edges meet, electrons at zero voltage, will continue to flow around the 1 metre coaxial circuit as a direct current. It would, perhaps, be better to say that current drifts around, because depending on the construction of the coax., it could take hours for any single electron to work its way around the circuit. It should, of course, be remembered,




Fig. 1.




Fig. 2.

that as no voltage is present, the density of the electrons in the closed circuit is the same as that in the remainder of the uncharged transmission line.

Unless someone comes along and throws into doubt that an electric field exists between adjacent electrons and protons it is easy to demonstrate that in the above circuit condition, countless billions of electric fields exist alongside the magnetic field caused by the current, although no measurable voltage exists. Similarly in the case of the purely electrostatic condition, the same large number of magnetic fields exist due to the rotating and spinning electrons. However, I doubt somehow whether this has anything to do with the way the charged section of coaxial cable propagates a pulse whose length is twice that of the charged section. And I must confess, that the prospect of opposing magnetic fields oscillating back and forth along the cable as Mr Catt suggests, appears to be even less likely.

Surely, the answer to his paradox is simply that on closing the switch at B, the electrons that flow out of the negatively charged conductor and those that flow into the positive conductor of the cable not only cause a wave front of current and voltages to be transmitted along the line but also back into the charged section itself. And since the energy has to be shared between both fronts, the voltage will be halved. The discharging current flowing into the charged section will set up a magnetic field, which, on collapsing, will produce an equal pulse of voltage and current to follow on the heels of the pulse which has already departed from the originally charged section.

R. J. Hodges  
Bath  
Avon

## ORBITING ELECTRONS

A puzzling feature of the atomic model which depicts the positively charged nucleus of the atom surrounded by negatively charged particles (or electrons), is that the orbiting electrons do not radiate away energy in the form of electromagnetic waves, and so spiral into the nucleus. This follows from the fact that electrons, when accelerated, generate e.m. waves, by means of which the energy given to the electrons to accelerate them is carried away by the wave, and since the electrons orbiting the atomic nucleus are said to be accelerating towards the nucleus, with the value of the acceleration being  $v^2/r$  where  $v$  is the velocity of the electron in orbit, and  $r$  the radius of the orbit, they should radiate e.m. waves.

I would suggest that the reason they do not, is that it is not sufficient merely for the electron to be accelerating — but energy needs to be given to the electron from outside the system (if we regard the electron in its orbit as a closed system of constant energy), in order to raise its energy level. This system then behaves in such a way as to oppose the input of energy, i.e. to lower its energy level and return to its original state. This it does by means of the e.m. waves travelling at the velocity  $c$ , via the lines of force which radiate out from the electron.

A change under "inertial" conditions (i.e. at rest, or moving with uniform velocity), possesses a constant amount of energy, hence, no e.m. waves are emitted from it. The electron will only gain energy when an external impressed force acts on it in which case a human observer located on the electron would be able to detect

this force, and measure it.

If we consider an electron in orbit around the atomic nucleus, and we replace the electrostatic force which keeps it in orbit with a gravitational one of the same strength, then a human observer, since he would be accelerating at the same rate as the electron, would not be able to detect any force acting on the electron, or anywhere in its vicinity, thus, he would conclude that the electron was under inertial conditions, and would not see any e.m. waves emitted, indeed, if he did see such a phenomenon, he would be unable to account for it. In order for such a system to radiate energy in the form of e.m. waves, I would suggest that it would be sufficient for the electron to collide with some other particle e.g. a photon or another electron. Then, a force could be detected by the observer on the electron, and he would conclude that energy had been given to the electron, and e.m. waves would be radiated, whether or not this raised the level of the system as a whole.

P. R. Griffiths,  
Retford,  
Notts.

## THE NEW BUREAUCRACY

I could write at length to refute D. W. Scott's extraordinary assertion in March, 1983 Letters, that "None of us (programmers) likes the von Neumann architecture — we spend our lives trying to circumvent it." Those experienced in the art know this to be false.

I shall limit myself to a simple test of loyalty for Scott and other programmers who might want to bite the (von Neumann) hand that feeds them.

As an accredited MAPCON consultant, the government pays up to £3,000 of my consultancy fees provided my recommendations to my client are that the system he installs contain a von Neumann machine. Please would Scott and other forward-looking programmers write to *Wireless World* to the effect that MAPCON should remove the following paragraph from page 9 of their book entitled "Guidelines for Feasibility Study Grants, March, 1982."

"Note that the use of the word "microelectronics" implies electronic large-scale integrated circuits (LSI) of at least the complexity of microprocessors. Applications which solely use medium and small scale integrated circuits (MSI and SSI) do not fall within the scope of MAPCON."

This quote relates neatly to my first paragraph on page 48, *Wireless World*, December, 1982.

Ivor Catt  
St Albans  
Hertfordshire

## MIXED LOGIC

On page 29 of the July issue, M. B. Butler writes

"A new symbol is introduced to indicate application of a convention: the 'flag' or polarity indicator."

This is not a new symbol. The second most commonly used standard for drawing logic diagrams, the IEEE's ASA Y32.14 — 1962, says on page 8

"4.4.1 A small, open, right triangle, at the point where a signal joins a logic symbol

indicates that the line's 1-state (activating) with respect to that logic symbol is the less positive potential (current)."

The competing, and much better, symbol is the small circle. The de facto standard for logic diagrams, US MIL-STD-806B, 26 Feb. 1962, used in 80% of logic diagrams today, says on page 4

"5.3.1 A small circle at the input to any element . . . indicates that the relatively low (L) input signal activates the function. Conversely, the absence of a small circle indicates that the relatively high (H) input signal activates the function."

"5.3.2 A small circle at the symbol output indicates that the output terminal of the activated function is relatively low (L). This small circle shall never be drawn by itself on a diagram."

On page 32, Butler writes

" . . . an oblique 'slash' is placed across any line over which a logical not operation has occurred."

Butler should withdraw this proposal, because it contradicts MIL-STD-806B, page 8, and elsewhere, which defines the oblique slash as indicating multiple lines. This has gained a degree of acceptance in the industry.

The main thrust of Butler's article is to introduce the good philosophical approach outlined in Tony Cassera's article, *WW* November, 1980. It is a pity that neither writer gave credit to S. U.S. MIL-STD-806B for originating it.

My approach to this important and neglected subject is contained in the chapter "Choice of type of logic symbols" in my book *Digital Electronic Design Vol. 2*, pub. C.A.M. Publishing, 1979.

(Perhaps I should repeat that in my opinion U.S. MIL-STD-806B is the best, and that I am willing to supply copies at cost.)

Ivor Catt  
St Albans  
Hertfordshire

## WOODPECKER

In June 1983 issue of *WW*, Pat Hawker described the "woodpecker" as following "the m.u.f. up and down the h.f. band". Rather than the m.u.f., I would have thought that it follows, more precisely, the optimum traffic frequency.

No doubt I will be corrected if I am wrong.

P. Thompson  
Southport  
Lancashire

## ORGAN INTERFACE

We have been asked to point out that a recording system for pipe organs with electric actions, similar in principle to that described in these articles, has been marketed by Christie Music Transmission Systems Limited, Colchester, since 1979. This originally used a 32Kbyte ram and tape back-up but is now available with 64K memory and disc back-up, giving uninterrupted solid-state recording or playback for about 20 minutes (depending upon the complexity of the music).

A full length item can be saved or loaded from disc in 3 seconds, and a short item using less than 9Kbytes, requiring only one track of the disc, is dealt with in half a second. Provision is made for listing items to give a recital of several hours duration.

**Developments in Teletext** (IBA Technical Review No. 20): Independent Broadcasting Authority, Crawley Court, Winchester, Hampshire SO21 2QA. Teletext users who have noticed the mysterious pages of apparent rubbish lurking here and there in the Ceefax and Oracle services will be aware that development of the UK Teletext system still continues. This collection of articles describes some of the advanced techniques now in use and some that are still to come. Subjects covered include the preparation of subtitles for deaf viewers; alpha-geometric coding methods for transmitting high-definition graphics; and techniques for redefining the character set to give alternative alphabets.

**Guide to amateur radio**: 19th edition, by Pat Hawker G3VA. 154 pages. Radio Society of Great Britain, Alma House, Cranborne Road, Potters Bar, Hertfordshire EN6 3JW. Price £2.75, by post £3.44, paperback. This new edition has been expanded to include some of the latest developments in the world of amateur radio, rules and regulations as well as techniques and equipment. An excellent guide for the newcomer.

**VHF/UHF Manual**: fourth edition, edited by G. R. Jessop, G6JP. Radio Society of Great Britain. 528 pages. Price £8.50, by post £10.31 worldwide, hard backs. This handbook provides practical information and a full range of constructional designs for amateur bands from 30MHz to the microwave region. The new edition has been revised extensively — notably the chapters on propagation and space communications, which should be of interest even to black-box operators.

**Teleprinter Handbook**: second edition, edited by A. G. Hobbs, E. W. Yeomanson and A. C. Gee. Radio Society of Great Britain. 368 pages. Price £12, by post £13.84, hardback. Conversing by teleprinter might be thought a rather unso-called method of communicating, but it has its enthusiasts. What is surprising about this book in view of the advanced techniques being used in other areas of amateur radio is that it confines itself almost exclusively to the care and operation of electromechanical equipment. It might be supposed that the newcomer to data communications would want to make use of his home computer. But apart from a nine-page chapter describing the construction (using standard t.t.l.) of a v.d.u. for radio-teleprinter use, there is nothing about AMTOR or packet-switching or indeed about computers or computer techniques at all.

**Nothing Local about it: London's Local Radio** by Local Radio Workshop. 213 pages. Marion Boyars Publishers and Comedia, £3.95 paper cover.

**BBC Radiophonic Workshop** by Desmond Briscoe & Roy Curtis-Bramwell. 175 pages, BBC £7.75 paper cover.

**Introduction to Video** by D. K. Matthewson, 175 pages. Bernard Babani £1.95 paper cover.  
**Tomorrows Television Today** by Michael J. Stone 118 pages. M. Stone £9.85+65p p&p paper cover.

**Television Engineers Pocket Book** by Malcolm Burrell & S. 314 pages. Newnes £7.95 paper cover.

**Tower's International Digital IC Selector** by T. D. Towers. 246 pages. Foulsham £9.95 paper cover.

**Interface Projects for the Apple II** by Richard C. Hallgren. 170 pages. Prentice Hall International £10.35 paper cover.

**Radio Antennas** by Stephen Gibson. 165 pages. Prentice Hall International £11.85 paper cover

**Medical Effects of Nuclear War** by British Medical Association. 188 pages. Wiley £4.50, \$8.95.

**Digital PLL Frequency Synthesizers** (Theory and Design) by Ulrich L. Rohde. 494 pages. Prentice Hall International £44.95 hard cover.

**Local Telecommunications** by J.M. Griffiths. 265 pages. Peter Peregrinus £19.

**Broadcasting and Society 1918-1939** by Mark Pegg. 293 pages. Croom Helm Ltd £14.95 hard cover.

**Bond Graphs for Modelling Engineering Systems** by Alan Blundell. 151 pages. Wiley £16.50 hard cover.

**Transistor Circuit Techniques** by G. J. Ritchie. 168 pages. £10.95 hard cover.

**RF Circuit Design** by Chris Bowick. 176 pages. Prentice Hall International £17.20 paper cover.

**Microchips with Everything** by Paul Sieghart. 150 pages. Comedia £3.50 paper cover.

**CBasic Users Guide** by Adam Osbourne, Gordon Eubanks, Martin McNiff, 212 pages. McGraw-Hill £11.95 paper back.

**Confidential Frequency List** by Oliver P. Ferrell. 224 pages. Gilfer Associates Inc (PO Box 239, 52 Park Avenue, Park Ridge, NJ07656, USA) \$14 paper cover.

**The World Wired Up** by Brian Murphy. 154 pages. Comedia £3.50 paper cover.

**What's this Channel Four?** by Simon Blanchard and David Morley. 186 pages. Comedia £3.50 paper cover.

**Annual Report and Handbook 1983** by BBC. 240 pages. BBC £4.50 paper cover.

**Television & Radio 1983** by IBA. 224 pages. Independent Broadcasting Authority £3.50 paper cover.

**Handbook of Antenna Design** by A. W. Rudge, K. Milne, A. D. Olver, P. Knight. 945 pages. Peter Peregrinus hard cover.

**Power of Speech** (History of STC) by Peter Young. 221 pages. George Allen & Unwin £9.95.

**Fiction Stranger than Truth** by N. Rudakov. 175 pages. N. Rudakov (PO Box 723, Geelong, Vic 3220, Australia) \$10 paper cover.

**Popular Circuits**

**Electronics Projects**

**Digital Circuits**

**Communication Circuits**

**and Special Circuits** (Ready Reference series) by J. Markus. 161-216 pages. McGraw-Hill £9.50 each paper covers.

**Electronics: A Course Book for Students** by G. H. Olsen. 425 pages. Newnes £17.50 hard cover.

**Practical Electronic Building Blocks — 2** by R. A. Penfold. 94 pages. Babani £1.95 paper cover.

**Computer Programs for Electronic Analysis & Design** by Dimitri S. Bugnolo. 261 pages. Prentice Hall £15.25 paper cover.

**Microcomputer Experimentation with the Synertex SYM-1** by Lance A. Leventhal. 500 pages. Prentice Hall £19.75 paper cover.  
**Basic & Pascal in Parallel** by S. J. Wainwright. 60 pages. Babani £1.50 paper cover.

**ZX Spectrum User's Handbook** by R. J. Simpson & T. J. Terrell. 199 pages. Newnes £6.95 paper cover.

**STD Bus Interfacing** by Christopher A. Titus, Johnathan A. Titus & David G. Larsen. 286 pages. Prentice Hall £11.15 paper cover.

**Interfacing to Microprocessor & Microcomputers** by Owen Bishop. 147 pages. Newnes, £4.95 paper cover.

**ZX8000 Handbook** by Martin L. Moore. 390 pages. Prentice Hall £11.95 paper cover.

**Basic Handbook** second edition, by David A. Lien. 480 pages. CompuSoft \$19.95 paper cover.

**Assembly Language** by Randy Hyde. Prentice Hall £16.95 paper cover.

**Introduction to Electronic Speech Synthesis** by Neil Scater. 134 pages. Prentice Hall £7.60 paper cover.

**Electronically Speaking: Computer Speech Generation** by John P. Cater. 230 pages. Prentice Hall £12.70 paper cover.

**Z-80 Microprocessor Advanced Interfacing with Applications in Data Communications** by J. C. Nichols, E. A. Nichols & K. R. Musson. 347 pages. Prentice Hall £16.95 paper cover.

**Microprocessors and Microelectronics** by Ian Williamson. 171 pages. Cambridge Learning £6.50 paper cover.

**6502 Assembly Language Subroutines**, by Lance A. Leventhal & Winthrop Saville. 550 pages. McGraw-Hill. £10.50 paper cover.

**Interface Projects for the TRS-80** by Richard C. Hallgren. 152 pages. Prentice Hall. £11 paper cover.

**Practical Interfacing Techniques for Microprocessor Systems** by James W. Coffron & William E. Long, 401 pages. Prentice Hall £25.15 hard cover.

**TRS-80 Model III Assembly Language** by Hubert S. Howe 344 pages. Prentice Hall £14.40 paper cover.

**Radiation safety of laser products, BS4803 parts 1-3**. British Standards Institution. 13 + 16 + 30 pages. Members £33 paper cover.

**European Electronic Component Distributor Directory** by Mackintosh Consultants. 464 pages. Benn Electronics Publications £37.50 paper cover.

**New Technology and Industrial Change** by Ian Benson and John Lloyd. Kogan Page £4.95 paper cover.

**Newton's Error** by A. H. Winterflood. 72 pages. From H. K. Lewis & co, 136 Gower Street, London WC1E 6GS £3 paper cover.

**Transient Analysis Aided by Network Theorems** by Harry E. Stockman. 176 pages. Sercolab (PO Box 78, Arlington, Mass. 02174, USA) \$13.30 (abroad +10%) soft cover.

**Telegraphy on Stamps** by W. C. L. Gorton. 16 pages. Picton (Citadel Works, Bath Road, Chippenham, Wilts) 95pence paper cover.

**Art of Programming the 16K ZX81** by M. James & S. M. Gee. 125 pages. Babani £2.50 paper cover.

**Computer-Assisted Home Energy Management** by Paul E. Field. 182 pages. Sams \$15.95 paper cover.

**Learning IBM Basic** by David A. Lien. 425 pages. CompuSoft \$19.95 paper cover.

**Art of Programming the ZX Spectrum** by M. James. 138 pages. Babani £2.50 paper cover.

*Literature Received this month appears on pages 38 & 73.*

# Ultrasonic ranging for robots

Simple ultrasonic transmitters and receivers with microprocessor control can give a robot the capability of determining the distance of objects near to it, even in a noisy environment.

Ultrasonic transducers provide highly directional characteristics which permit the construction of a ranging system that operates on principles similar to those of radar.

The underlying principle is simply to measure the time interval between the transmitting and receiving of ultrasonic pulses. I have used momentary bursts with a fundamental frequency of 40kHz. The velocity varies with temperature, pressure etc, and the greatest accuracy can only be obtained if these factors are taken into account. However over the comparatively short range of the system it is doubtful that any normal variations of these factors will significantly affect the measurement.


The time interval between the transmitted and reflected pulse is a linear function of the distance. If we call the velocity of sound  $V$ , and the target range  $r$  then the timing interval  $\Delta t$  is  $2r/V$ . Thus the accuracy of the measurement depends chiefly on the accuracy of the time measurement. We need now to examine how this can be interpreted by the robot's computer into useful sensory information. Most robots incorporate a microcomputer to convert incoming data, from sensors, and from instructions in the control program, into responsive actions. The

by H. W. Gleaves

complex relationship between input data and output action is determined by the software of the control unit.

**Hardware.** A block diagram of the sensing unit is shown below. The ultrasonic transmitter is a simple c-mos squarewave oscillator which may be adjusted a few kHz each side of the chosen frequency of 40kHz. The squarewave output is fed through a c-mos analogue transmission gate and transmitted in short bursts. The receiver is a combination of op-amps designed to amplify and filter the very weak received signals. The overall gain of the receiver is over 80dB. The amplified signal is fed to a comparator which switches very rapidly between 5V and 0V on the receipt of a signal. This output is used to interrupt the robot's computer. I decided to compromise between hardware and software by using the computer to count the time delay. Other parameters such as pulse width and p.r.f. were chosen to suit the application and may be varied for different ranges, etc.

Only two connections were needed




Block diagram of the ultrasonic frequency ranging system.



"My main interest is in designing robot systems. At present I am working on a machine using two microprocessors and ultrasonic ranging. I believe that robot software will need to be considerably different from normal computer software, since unlike a computer a robot has very poorly defined data entering its system. "Because of the employment difficulty, I took A-level mathematics and physics at night school. From there I entered Old Swan technical college to finally receive a diploma in telecommunications."

between the ranging sensor and the computer. I used an Acorn system 1 microcomputer which has proved to be excellent. It is physically small, of two vertically stacked boards with the upper one having a hexadecimal keyboard for programming. Only one bit of an 8-bit port was used to pulse the transmitter on for a period determined by the software. The output from the receiver is connected to the microcomputer's interrupt request, IRQ, terminal and will interrupt the processor whenever sounds containing a 40kHz component are detected. The IRQ on the 6502 microprocessor used in the Acorn system 1 may be ignored or acted upon, the choice being under software control, depending on whether the 'interrupt disable bit' in the 6502 status register is set or clear. The software is designed so that while the transmitter is active, the interrupt is disabled and as soon as the transmitter has stopped, the interrupt is enabled. At the moment when the interrupt is enabled, a special test register is cleared and an 8-bit register starts counting. As long as the test register remains clear, the counter continues to increment. When an interrupt signal is received the test register is set to FF<sub>16</sub> and



the count stops. The processor returns to the main program but the count register contains a number proportional to the distance measured.

**The effect of noise.** Ideally only one measurement is required as described above, but in any normal environment there are inevitably extra noises that could trigger false readings. I have given a full explanation of the mathematical method used to determine the probability of noise affecting readings in the appendix. It is sufficient to say here that if a number of measurements are taken, then a certain proportion of them will give the same reading while noise will add random readings. So if a number of readings are compared, those that have the same reading most often will indicate the true distance while the other readings may be ignored. For example, I set up the transducers some 150mm away from a fixed object. With no ambient noise, 32 measurements were all the same. I then repeated the experiment while jangling a bunch of keys about 100mm away from the transducers. There was a wide diversity of measurements but the most common value, occurring seven times, was the correct value, identical to that in the first experiment, while the remaining values were random, with no value occurring more than three times.

**Software.** A machine-code program is used the range measurement technique discussed. Two versions are included for two processors; the 6502 and the Z80. I have called them 'Mode' as they calculate the mode of the acquired data. Users of other processors may be able to compile

Flowchart for FDA (frequency distribution analysis).  $R_1$  and  $R_2$  are two range values in the range table.  $R_1'$  and  $R_2'$  are the frequency of occurrence in the table of  $R_1$  and  $R_2$ .

similar programs by referring to the flowcharts. 'Mode' on the 6502 can process a block of data up to 255 bytes length. The program will determine the value that occurs most frequently and place this in a specific location in memory (address 0020) with the frequency stored at address 0022. If all the values in the table are different, a value of 01 is placed in the 'Error' address, 0024.

The first value is taken from the top of the table. The number of times the same value occurs in the table is counted. This count is then compared with the next count derived in the same way and the value corresponding to the greater is stored. The process is repeated to the end of the table. If, during the process two counts are the same, then Error is set to 01 if subsequently another count is greater, then Error is reset to 00.

The program for the Z80 is very similar. It can process a block of data longer than 255 bytes if necessary, provided that no single value occurs more than 255 times.

**NVT (number of values in a table) subroutine.** This subroutine accepts an 8-bit number that has previously been stored at address 002E and then determines how often it appears in the table of values stored in ram. The count is stored in 002F. Other important addresses are 020E which contains the value of the length of the table (+1), so if the table contains 32 values the




number 21<sub>16</sub> is stored; 0208 and 0209 contain the 2-byte base address of the table (in low-byte/high-byte order). In my system, the table started at 0300 and ended at 0320 so addresses 0208 and 0209 contained 00 and 03 respectively

0200	LDA#00	A9 00
0202	STAZ 2F	85 2F
0204	TAX	AA
0205	LDAZ 2E	A5 2E
0207	CMPX 0300	DD 00 03
020A	BEQ 06	F0 06
020C	INX	E8
020D	CPX*21	E0 21
020F	BNE F6	D0 F6
0211	RTS	60
0212	INCZ 2F	E6 2F
0214	JMP 020C	4C 0C 02

**FDA (frequency distribution analysis) subroutine.** This analyses the data obtained by the range sampling process, and then gives the true value for the range of the object in the robot's path. It works by internally examining the frequency distribution of the data and determining the range value that occurs most often, i.e., it is finding the peak of the histogram of the data. The program uses the NVT subroutine explained above, and also makes use of the 6502 X and Y registers. After calling this subroutine (JSR 0217), the value that occurs most often is found in address 0034. This is the measured range and may be used to direct the robot or for any other purpose. The start address of the table must be the same as that used in the NVT routine and it is important that the table is the same length or gross errors will occur. Address 0243 contains the length of the table +1, as in the NVT routine.








For flexibility, the loading network at the collector of Tr<sub>1</sub> is constructed on a separate board which plugs into the main one.

Tr<sub>1</sub>. Remember to set the a.g.c. trimmer R<sub>1</sub> to give about 2.5V to the tuner a.g.c. pin (or pins as the case may be). Finally make up a rectifying circuit with a couple of signal diodes and a 100Ω resistor as shown in Fig. 1 and connect it between the tuner output and the oscilloscope probe. Having connected the sawtooth waveform driving the oscilloscope to R<sub>5</sub>, set the sweep to a very low speed (about one sweep every five seconds), put the voltmeter on the collector of Tr<sub>1</sub> and adjust R<sub>5</sub>, the shift control R<sub>2</sub>, and if necessary, everything else, until the tuner control voltage is sweeping through the full 30V. Then increase the sweep frequency enough to give a readable trace and put a signal within the frequency range into the tuner. One or more spikes on the trace should show that the first stage of your spectrum


analyser is working.

The next job is to make a comb generator (see box 00). When this is connected to the tuner the display should resemble that shown in Fig. 2. The main purpose of the comb generator is to help in optimising the linearity of the sweep. Note how in Fig. 2 the spikes are crowded together at the left and spread out at the right. This indicates that the same control voltage change causes more tuning shift at the beginning of the sweep than the same change causes at the finish. To put this right, zener diodes are fitted to the small plug-in board to modify the load resistance for Tr<sub>1</sub>. As the voltage across the load increases the diodes will successively conduct, reducing the load resistance and compensating for the increased frequency-to-voltage sensitivity.

Now that we have a picture to work to, we can easily make the whole system linear. Remove the small plug-in board, readjust the trimmer from 8kΩ to about 15kΩ and wire in the first zener. Use a 15V type for a first try, and set the trimmer in series with it to the maximum 50kΩ and replace the board. Now fiddle the load trimmer and R<sub>5</sub>, and if necessary R<sub>2</sub> and the rest, until the display is similar to what it was before. Use R<sub>2</sub> to make sure there are no harmonics off the right hand side of the screen. Now close up the spacing until a centimetre or so on each side of the



The same linearity correction should be effective on more than one band. This shows a u.h.f. display from 500 to 850MHz with 50MHz spacing.




If the oscilloscope sweep speed is too fast, as it is here, the tuner frequency may still be dropping when the next sweep begins. This can arise because voltage-controlled tuning circuits usually incorporate some capacitance for stability, for example, C<sub>x</sub> in Fig. 1.

screen is clear and reduce the resistance of the trimmers in series with the 15V zener diode. If the value of the zener is correct then all the harmonic spikes except the last two on the right should move to the left. If either of the last two moves the zener voltage is too low. Try one of, say, 18V. If three or more of the right hand spikes do not move, the voltage is too high. When you get the voltage correct, adjust the trimmer until the third spike from the right has exactly the same spacing as the first two. With any luck the fourth may also now be correct.

Continue in exactly the same way with another zener diode, selecting one which shifts only the spikes not already spaced correctly, until the display is similar to that shown in Fig. 3. If you are very unlucky and the tuner has both v.h.f. and u.h.f. ranges you may have to use a second plug-in board for the other range; but in every case experienced so far (several tuners have been tried) the same compensation settings are adequate for both ranges. The more zeners and trimmers used, the more accurate the correction; but three are usually enough, at least for a first attempt. As a final check, make sure that with all zeners conducting the load current is about 4mA. If it is more and the regulation is dropping out then increase the level at R<sub>5</sub> and try again.

The basic spectrum analyser is now complete, although it still has a number of limitations. It is uncalibrated, it is not very sensitive, it has a restricted frequency range and the i.f. bandwidth is too broad for some applications. But by progressive additions such as switched bandpass i.f. filters, a logarithmic amplifier to improve the sensitivity and the range, heterodyne mixers to extend the frequency range and a calibrated variable sweep the final result could be limited only by the patience and enthusiasm of the constructor.

The ELC2060 tuner is available for £8.63 including inland postage and v.a.t. from Sendz Components, 63 Bishopsteignton, Shoeburyness, Essex SS3 8AF. WW



Connection details for the Philips tuner. Other tuners may be equally suitable.

# Did Morse get it right?

## A statistical background to the code

*Morse speed in words-per-minute presupposes a defined mean word. A value for this can be derived from an analysis of Samuel Morse's own data. Recent trials support the original work for English but not for French or German. Certain aspects might even have surprised the great man himself.*

Morse code must be reasonably familiar to most readers of *Wireless World* but some of the finer points of its structure and certain practical difficulties in its application might not be immediately obvious to the non-specialist. In particular, there is an inherent uncertainty in relating transmission rate to the more traditional measure of words per minute. The last-mentioned introduces the concept of a standard word length which must be statistically derived from an analysis of plain language text, and the results may differ significantly between one language and another. This article looks at present-day practices and relates these to statistical data available for English and five other European languages. The need for such a reappraisal can be justified by the increasing use of automatic keyers, practice code generators and the like, which, with their capability for greater precision in code formation, has led to a general desire to define transmission speed more closely and more uniformly than has been the custom in the past.

### Statistical beginnings

By the early 1830s Samuel Morse had become fully aware of the potential that a variable code would offer in arranging shorter combinations of signals to be allocated to the more frequent letters of the alphabet and it is recorded<sup>1</sup> that a visit to a local newspaper printing room enabled him to deduce from the number of type pieces held for each letter of the alphabet the relative frequency of use. From this information, Morse devised combinations of short and long signals specifically designed to maintain the product of character length and frequency at a more constant level than would otherwise be the case, and thereby to produce the shortest messages overall. Morse's original code (not quite the same as that in use today, see Appendix) together with the letter frequency table he compiled are given in Reference 1.

For the immediate task of providing a basis for calculation, it is necessary to state here the parameters of the mark-space structure as follows. The dot length (period) can be regarded as the basic element and the dash is given a length equal to three dots. The spaces between the elements within one character are equivalent to one dot and the spaces between characters are given three dots duration. Words

are separated by seven dot elements. For brevity, the term bit is used synonymously with dot element making the dot rate equal to half the bit rate (baud or bit per second).

The length of a morse character can be expressed in terms of the number of dot elements or bits it contains: for example, the letter A (dot dash) can be said to comprise five bits. However, as one character cannot follow another without inserting a space of some kind, it is preferable to in-

clude the standard inter-character space (three bits) as part of the letter itself bringing the letter A to eight bits, alphabet shows a range from four to 16 with a mean value of 11.23 bits. The full range of bit counts is given in the Appendix.

### Random code

When letters are selected at random they appear, by definition, at uniform relative frequency and a mean five-letter word in code is equal to five times the mean letter plus four bits to make up the remainder of the word space. Taking a rounded value for the mean letter as 11.2 bits, the mean word comes to  $5 \times 11.2 + 4 = 60$  bits. Code speed in words per minute is then numerically equal to the bit rate or twice the dot rate. Figure characters also can usually be regarded as random in their occurrence and a similar analysis to that for letters gives the mean character length as 17 bits from which the mean five-figure group (including word space) comes to  $5 \times 17 + 4 = 89$  bits. Speed in word/min can then be shown to be equal to  $1.35 \times$  dot rate.


### English language

The fact that plain text does not make use of all letters of the alphabet with uniform frequency presents the major difficulty in setting a value for the mean (plain language) word. It is safe to say, however, that the figure is bound to be significantly less than the value for the random case, otherwise there would be no benefit to be gained from the use of a variable length

code and, in fact, the ratio of the two figures can be regarded as a measure of achievement in optimizing the design.

Before going on to report the results of trials it must be conceded straight away that a standard word for a plain language does seem to have established itself already: a scrutiny of published material shows a consensus for a nominal standard of 50 bits (including word space) and the word 'Paris' is sometimes quoted as representing this value. Frequently the information is given directly in terms of word/min and dot rate as, for example, word/min =  $2.4 \times$  dot rate (1 word/min = 50 wpm/60 baud). Seldom is the reader provided with any basis for the figures quoted and variations do appear from time to time not only in the literature but in the observed calibration of automatic keyers and practice tapes.

It was against this background that I felt the need to satisfy myself that any standard being quoted, and in particular the 50 bit word, had a reasonably sound statistical basis for its application and had not established itself merely by common usage. At the same time, it had to be admitted that,



Clues  
 B' D' E' F' = 6    A' B D F' = 6  
 B' D E' F' = 4    B' D E = 6  
 B D E F' = 6    A D' E F' = 3  
 B D E F = 6    C E F = 8

### Crossword - by N. Darwood

Using the digits 1 to 8 each row and each column adds up to eight. The first clue, and its consequences for the top row, is given. No entry need be guessed. Solution next issue.

even if a 'better' result were to be found, there might still be a case for retaining a round figure such as 50 bits in the interests of easy standardization, providing the figure did not depart too far from reality.

To derive a standard word for plain language it is necessary to combine the bit count for each letter with its relative frequency of occurrence to obtain a measure of the overall effectiveness of the letter in a long run of text. Relative letter frequencies must, of course, be estimated by statistical trial and in the first instance I selected three quite different sources of available data.

The first was the original frequency table<sup>1</sup> compiled by Samuel Morse around 1830 and reproduced in ref. 1. The second was taken from a work<sup>2</sup> on cryptography by H. F. Gains first published in the late 1930s, which not only provided two sets of data by different analysts (Meaker and Ohaver) on English but data on five other European languages as well. The third was obtained during correspondence following publication of an article<sup>3</sup> by a beginner operator describing his attempts to relate the dot rate on his automatic keyer to the amateur radio morse test at 12 word/min. It was not in the least way possible to foretell what the outcome of the exercise might be, but in the event the results proved to be so gratifying that I undertook a count of letter frequencies myself to provide extra data for analysis. The method used for this exercise and the results obtained are given in the appendix.

Given suitable data on letter frequencies, the procedure to determine the length of the standard word was the same for all sources of material. For all letters designated  $r_1$  to  $r_n$ , the product of bit count  $x_r$  and frequency  $f_r$  gave a table of values from which an overall mean letter size could be calculated. In the usual notation, the mean value  $\bar{x}$  is

$$\bar{x} = \frac{1}{N} \sum_{r=1}^n x_r f_r$$

where N is the size of the sample. Defining the mean word as comprising five mean letters plus four extra bits to make up the word space, a value for the standard word was calculated. The results of the exercise using letter frequency data from the five sources listed are given in Table 1. The total dispersion of the mean over the five results is gratifyingly small considering the wide differences in source and sample size. A global mean value for the mean word comes to 49.4 bits and is unchanged (to three significant figures) when the data points are restricted to the middle three values.

### Other languages

In addition to two sets of data on English, reference 2 provides letter frequency tables for five other European languages. The exercise to find a value for the standard word was extended to include these languages and the results obtained are given in Table 2. Data for French, Italian and Spanish were compiled from a count made by the author, but the origins of data for

German and Portuguese are said to uncertain.

The results show significantly low values of the mean word for French and German relative to the other language trials, including English. This seems likely to be due to the fact that the frequency table for German shows zero count for letters J, Y, Q, and Z (all long symbols in morse) while the count for letter E (the shortest symbol) was the highest encountered over all languages. The relatively low value for French cannot be so easily explained with zero count for K and W (letters of around average size in morse) but a fairly high count for E. Spanish and Portuguese, producing equal results, are the only two languages in the six tested to show a mean word exceeding 50 bits.

### The standard word

Results for English show a value for the mean word estimated over five trials as 49.4 bits with an overall dispersion of +0.4 to -0.3 bit. There can be little doubt therefore that a standard word of 50 bits will meet all normal requirements for the measurement of morse speed in English. Of the five other languages, Italian, Spanish and Portuguese all show values for the

mean word within  $\pm 1\%$  of 50 bits which value can be accepted as the standard for these languages also, albeit on the basis of smaller samples.

**Table 1.** Results of five independent trials to determine the mean word for English.

Origin	Sample size	Mean word (bits)
Morse	106,400	49.8
Gains (Meaker)	10,000	49.5
Gains (Ohaver)	10,000	49.3
Chester	10,000	49.3
Wood	1,798	49.1

French and German deviate much more from the 50 bit standard at -4.8% and -7.4%, respectively, and it may be worth considering whether any additional trials should be undertaken on these languages to verify the low values obtained from the published data used.

Given a standard word length of 50 bits, the word Paris is often used to represent this value. Whether it is really necessary to quote an actual example of a 50 bit word is debatable but there must be other internationally recognisable words of this length

Morse symbols and bit content including inter-character space together with frequency count. Taken from the *Sunday Times* of 18 July 1982 using a wide range of material by different writers. But specialist subjects were avoided, as were passages containing undue repetition of proper names and

frequent use of foreign words. The combined result is from a total sample of 10,000 letters. Following the style of Gains, relative frequencies are given as the percentages of the sample while dropping the decimal point gives the actual count.

Letter	Morse symbol	Bit content	Relative frequency
A	.. ---	8	8.25
B	--- ..	12	1.78
C	--- .. ---	14	3.14
D	--- ..	10	3.38
E	..	4	12.77
F	.. --- ..	12	2.38
G	--- .. ---	12	2.04
H	.. --- ..	10	5.06
I	.. ..	6	7.03
J	.. --- .. ---	16	0.19
K	--- .. ---	12	0.58
L	.. --- ..	12	4.30
M	--- .. ---	10	2.29
N	--- ..	8	7.02
O	--- .. ---	14	7.13
P	.. --- ..	14	2.03
Q	--- .. ---	16	0.14
R	.. --- ..	10	6.30
S	.. --- ..	8	7.06
T	--- ..	6	9.17
U	.. --- ..	10	2.83
V	.. --- ..	12	1.20
W	--- .. ---	12	1.80
X	.. --- ..	14	0.28
Y	.. --- .. ---	16	1.76
Z	--- .. ---	14	0.09

\* On this basis a bit count for all the letters of the ...  
 62 red: WW sept 83 pag 62

from which to choose. It was during a search through a list of suitable candidates for an alternative to Paris that I stumbled on the fact that the word Morse is one of precisely 50 bits (including word space) and, being more than relevant to the

**Table 2.** Results of trials to determine the mean word for the five European languages given.

Language	Origin	Sample size	Mean word (bits)
German	Uncertain	Not given	46.3
French	Gains	10,000	47.6
Italian	Gains	10,000	49.7
Spanish	Gains	10,000	50.4
Portuguese	Uncertain	Not given	50.4

subject in hand, could hardly be bettered as an international standard.

### Morse practice and test criteria

Traditionally, morse speed for plain language transmission is estimated by marking off groups of five letters in a passage of text (ignoring word spaces) and then sending the passage normally arranged in groups of five and the counting of 'words' is then straightforward. It is common practice to send code at a rate some 20% lower than that for plain language with the intention of presenting the same overall degree of difficulty to the operators. Whether this practice is entirely justified is arguable but a quantitative measure of one aspect of the problem is given in the following paragraphs.

**Table 3.** Standard words for three categories of morse against corresponding wpm/dot rate (dot rate in dots per second = half a bit rate).

	Plain	Code	Figures
Standard word (bits)	50	60	89
Ratio wpm/dot rate	2.40	2.00	1.35

Given a standard word length for each of the three categories of morse, it is simple to find the corresponding ratio of transmission speed in word/min to dot/s. Table 3 gives standard word lengths derived from the data produced in this article with the required ratio. The dot rate for plain language can be adjusted down if necessary by 1% since the mean word length for English estimated by trial has been found to be about this much short of 50 bits. For certain other languages, the dot rate could be much greater in error; see the results for these in Table 2.

When using automatic keyers, the dot rate can readily be set to a level corresponding to the required word speed. In such cases, it may be useful to remember a few equivalents such as 24 word/min in plain language corresponds to 10 dot/s. It is also interesting that this same dot rate will produce a speed in code of 20 word/min and on this basis a combined morse test in plain and code would have to be sent at word speeds in the ratio 24/20 to represent the same 'pace' to the operator. The method, however, would not take into account the difference in letter predictabil-

ity between the two categories of text and it could be argued that if plain text in the operator's own language is easier to copy than random code at the same dot rate, then the word-speed ratio between the two should be *increased* to redress the balance. Unfortunately, this aspect is difficult to quantify and seems to depend on the individual operator's training and experience.

An exercise which started out to test the validity of the 50 bit standard word has shown the figure to agree with the result of statistical trials to within about  $\pm 1\%$  for English and three other European languages. But unfortunately, the standard doesn't seem to fit the German or French languages as well as the others and users in these countries may wish to consider whether conformance to a round-figure standard is more important than precise alignment with the result of one statistical trial. More generally, and especially for non-European languages, the problem of the standard word can be avoided altogether by the universal adoption of dot rate as the only reliable measure of the 'pace' of transmitted morse.

### References


1. C. Cherry, *On Human Communication*, p.35. Wiley, New York; Chapman & Hall, London.
2. H. F. Gains, *Cryptanalysis*, appendix. Dover Publications, 1956 New York.
3. I. T. Wood, *The true measurement of morse speed*, *Short Wave Magazine*, vol. 39, February 1982. WW

# NEWS

## Liquid crystals add colour to monochrome c.r.t.

A solution to the problem of producing colour display devices with a high enough resolution for measuring instruments and computer displays has been developed by Tektronix in the form of a monochrome c.r.t. with a two-colour liquid crystal switch. This is not the first display of its kind, but the developer claims to have solved the problem of colour-switch speed. Tektronix manufacture their own tubes and the liquid crystal switch is described as 'proprietary' but Fred Rose, information officer of Tektronix UK, could not tell us in plain terms whether or not his company manufactures the device. "We have tried to clear up one or two ambiguities" he said, "but Tektronix are not prepared to release any more details. The display is ready to be used and I speculate that we could see it incorporated in one of our products within the next twelve months."

The display has the same resolution as current monochrome tubes and does not suffer from convergence problems. A high contrast ratio is claimed, as is ruggedness through the absence of a shadow mask and complex gun, but Tektronix are not so clear about the price of such a display and will only say that it is "potentially low cost." Phosphor coating on the tube is plain with two separate emission peaks that are typically, but not limited to, red



and green. In any field, information written on the screen appears in the colour selected by the electronic switch. Each colour is repeated at 60Hz, requiring the two-field system to run at 120Hz. This field-sequential system provides all possible mixtures of the two primary colours emitted by the phosphor and research is continuing to extend the concept to three fields to produce the full colour spectrum.

Colour displays for measuring instruments and computers with the resolution of current monochrome instrument tubes could appear within the next twelve months. Tektronix have developed a system combining a fast liquid-crystal filter and monochrome c.r.t. to provide a high-resolution display producing all colours between red and green on a field-sequential basis. Research into producing a three-colour version continues.

## Electronic mail-order for electronics

Items from the large component catalogue issued by STC Electronic Services can now be ordered electronically. A new service called Estelle allows direct access to the company's mainframe computer at Harlow for any customer equipped with a suitable modem and a computer or v.d.u. having an RS232 port. Estelle (a somewhat tortured acronym standing for Electronic Services telephone link for order entry) claims to be the first system of its kind introduced by a major components distributor. Users can obtain up-to-the-minute information about product availability and pricing and may place orders straight away or else browse through catalogue items. A menu system enables them to find their way about. The service is aimed not only at business and industrial customers: the company is keen also to attract the hobby-

ist, who can gain access with a home computer linked to a low-cost acoustic modem and pay for goods by typing in a credit-card number.

Services similar to Estelle, although perhaps less comprehensive in scope, are available from two retailers already well known to the hobbyist - Ambit International and Maplin Electronics. Ambit's Rewtel is predominantly an information service. It allows customers to make rapid searches of the company's database by typing in keywords; and the system responds by sending any pages containing those keywords in their heading. There is also an electronic bulletin board which allows customers to leave messages for the company or for other users. Component ordering and the several other facilities on Rewtel are available only to subscribers, who pay a fee of £10 per year.

The service launched by Maplin, called Cashtel (standing for computer-aided shopping by telephone), is available to Maplin's existing mail-order customers. To make a purchase the user enters the appropriate code numbers from the company's catalogue. Cashtel also allows users to check on stock levels and to follow the progress of their previous orders. Like the other systems it has features designed to ensure confidentiality and to protect

against misuse. Later on there is to be a bulletin board for private or public messages and an information service for various home computer user-groups: pages for Atari computer owners are already available. One attraction for potential Cashtel users is a modem offered by Maplin in kit form for less than £40: the modem conforms to the 300 baud CCITT standard and is transformer-coupled to the telephone line.

The telephone number for Cashtel is 0702-552941; and for Rewtel (300-baud Datel 200 service) the number is 0277-232628. Estelle is available on three numbers - 0279-443511 (300baud Datel 200 service); 0279-441188 (1200baud Datel 600 service); and 0279-441222 (1200baud Datel 1200 service).

Another company, Display Electronics of Thornton Heath, Surrey, though not a component retailer in the ordinary sense, can claim to have been the first in this field with its 300baud Distel service. This allows customers to search the company's large stock of computer and electronic goods and to order by credit card. Distel can be accessed 24 hours a day on 01-683 1133.

For further information, code WW500 (Estelle), WW501 (Rewtel), WW502 (Cashtel), WW503 (Distel).

## Heatless laser etching

A new phenomenon has been discovered which allows organic polymers and biological materials to be etched by laser without heating. Called ablative photodecomposition by its IBM discoverer R. Srinivasan, the phenomenon could be used to directly etch images in photolithographic i.c. fabrication, which would greatly simplify the production process by eliminating the image development stage using photosensitive layers and chemical solvents. In the medical field, the phenomenon could mean precise laser surgery,

since cuts are determined solely by the geometry of the beam and, because heat produced is negligible, charring associated with laser surgery is eliminated.



Using far-ultraviolet lasers, Srinivasan found that an intensity threshold exists above which "numerous small molecules are suddenly ejected from the irradiated area of the material". High intensity is not directly responsible for the etching effect. Srinivasan believes that absorbed radiation probably breaks chemical bonds between atoms in the organic material producing

smaller molecules that vaporize at relatively low temperatures. These smaller molecules carry away excess energy from the laser pulse - hence the term ablative.

Pulses of 12ns at 1Hz or higher from a 193nm argon-fluoride excimer laser were used in Srinivasan's experiments. Other experiments using this type of laser have shown that ultraviolet radiation may be the key to submicron lithography.

Heatless laser etching could be used to directly etch images, left, in photolithographic i.c. fabrication, eliminating the usual image development stage using photosensitive layers and chemical solvents. This scanning-electron micrograph shows a commercial plastic film with 5µm-wide lines etched using a phenomenon known as ablative photodecomposition. With biological and polymer materials, a far-ultraviolet laser above a certain intensity threshold causes excess energy to be carried away in ejected molecules and the material remains cold.

Potential for heatless laser etching in medical applications, right, is illustrated by these cuts in cartilage tissue. Heating and charring caused by commonly used visible and infrared lasers, left, is not apparent in the 250µm-wide channel on the right which was cut using a far-ultraviolet laser and the ablative photodecomposition phenomenon. Geometry of the cut is determined solely by the beam geometry.



\* in a given time. For random code letters are..


## Erasable optical disc

Using an enhancement to existing record-playback optical storage systems, Matsushita has developed the world's first optical disc that can be erased and rerecorded. Sensitivity of the disc is high enough to allow broadcast pictures to be recorded in real time, its capacity is one gigabyte and it can be erased and recorded over one million times which makes it suitable for both video and computer storage applications. This would seem to make both perpendicular magnetic recording (see February News) and metal-powder tape obsolete but it is too early to compare such factors as cost-per-bit of storage, portability of media and manufacturing costs. Matsushita do not indicate that their development is ready to be manufactured.

The erasable disc, part of a \$600m research and development project, has a tellurium suboxide layer the same as used in existing optical-disc record/playback systems. Heating this layer results in it changing its reflective properties (see March News). But by adding metals such as germanium, indium and lead to the suboxide layer and using two separate laser beams, the change in reflectivity caused by changing the layer from a crystalline to



A Matsushita laser disc recorder that can play back one of 15 000 images in under half a second.



An erasable optical storage disc for video images and data developed by Matsushita uses two separate lasers for recording and erasing through a common optical system. The one gigabyte disc can record broadcast pictures in real time and be erased over one million times but when the disc might be available is not yet certain.

amorphous state is made reversible. In the record process the high-reflectivity crystalline phase is converted to a low-reflectivity amorphous state; during erasure, the opposite occurs. Two semiconductor lasers are used — a  $0.83\mu\text{m}$  8mW device for recording and playback and a  $0.78\mu\text{m}$  10mW type for erasure — with a common optical system.


## Submillimetre-wave telescope

Work has begun in Hawaii on the world's largest telescope capable of operating at wavelengths shorter than 1mm. Due to be completed in 1986, the telescope will help explain the formation of new stars, the nature of quasars and the evolution of galaxies. "Chemists", say the Science and Education Research Council, "will have the opportunity to study complex molecules in space which may provide the key to life itself."

SERC, who are building the telescope in conjunction with the Netherlands Organization for the Advancement of Pure Science, says requirements are pushing microwave technology beyond the limits of current applications. Detectors using ele-

ments as small as  $1\mu\text{m}^2$  and cooled to a few degrees above absolute zero have been developed to solve a main problem of viewing at submillimetre wavelengths — that of the receiver sensitivity. Engineering and installation of the telescope is being carried out at SERC's Rutherford Appleton Laboratory by a team working in collaboration with universities and observatories in the UK and Netherlands including the Mullard Radio Astronomy Observatory at Cambridge University and the council's Royal Observatory in Edinburgh.

Tolerance of the 15m-diameter paraboloid form will be within  $50\mu\text{m}$  — including distortions due to gravity when the antenna is turned.



## Ariane launches new satellites

A much needed boost for Europe's satellite-launching project came on 16 June with the near perfect launch of Ariane L6 in Guiana. Had the rocket failed — representing the third failure of six attempts — orders said to be worth about £300m could have been lost and the future of Europe's independent means of launching satellites put into serious doubt. Ariane's payload consisted of Europe's first communications satellite ECS-1 and the German Amsat Phase 3B.

ECS is a continuation of the OTS formula to provide trunk telecommunication between countries belonging to CEPT (European conference of posts and telecommunications), especially telephony and data transmission. Its other purpose is to provide colour television relays with sound and multiple commentary channels. Designed for a lifetime of seven years, ECS has a payload that includes twelve 20W, 11-to-14GHz repeaters and six antennae.

The other satellite launched from Ariane L6 is the Amsat III-B, called Oscar 10 when fully operational. This satellite for amateur radio is designed to serve as an educational aid — to establish back-up communications networks over long periods covering most of the Earth using simple and inexpensive components, to study multi-user transponders and frequency-division multiple-access, to assess

the effectiveness of a highly eccentric orbit, and to demonstrate the practicability of using an onboard microcomputer for managing and monitoring the satellite's operation.

The telecommunications module consists of four main transponders, the first one (L1) with an uplink frequency of 435.175MHz downlink of 145.828MHz; Transponder L2, uplink 435.165MHz downlink 145.838MHz; Transponder H1 uplink 435.025MHz, and downlink 145.978MHz; Transponder H2 uplink 435.030MHz, downlink 145.973MHz. There is also an Amsat net and calling frequency with an uplink of 435.040MHz and a downlink of 145.936MHz. The general beacon is transmitted at 145.810MHz and an engineering beacon at 145.987. At the time of writing the satellite has yet to be fully oriented toward the sun — battery charging is low and so the beacons are only being activated for short periods. The satellite has an expected life of three years.

Ariane L7, 8 and 9 launchers have been assigned to Intelsat V satellites F7, F8 and F9 and are scheduled for launch on 26 August, 4 November 1983 and January 1984 respectively.

## Satellite news trial


To give "a valuable early indication of benefits from using satellites on a commercial scale in the future", BT are to carry out a three month trial distributing news and information by satellite starting in July. In the trial, Europe's first, Exchange Telegraph Co (Extel) will send speech and data from BT's Fleet building in London to its nine regional offices in the UK via European test satellite OTS. Working experience of locating and using small satellite aerials for businesses in urban areas will also be gained from the trial. Receive-only dish antennas of one or 1.8m diameter will be used at the regional offices.

## Microphone on a chip

Using its recently developed zinc-oxide thin-film deposition technique, Honeywell has produced a microphone with microelectronics on a single silicon substrate, which is said to give better performance, sensitivity and reliability than current ceramic microphones at a fraction of the cost. Compared with ceramic devices which lose sensitivity at around 20Hz, the integrated zinc-oxide device operates at frequencies down to 0.1Hz. Honeywell say their 6.5 by 6.5mm 'mike-on-a-chip' can detect 1 $\mu\text{bar}$ , at which pressure the signal-to-noise ratio is 5:1, and that it is smaller and lighter than its ceramic counterpart measuring typically 6.5 by 12.5mm excluding electronics and leads.

Zinc-oxide thin-film techniques used produce a substance with characteristics

similar to those of piezoelectric crystals but compatible with standard i.c. fabrication processes. Like piezoelectric ceramic materials, zinc-oxide produces thermally-induced voltage fluctuations but the manufacturer claims to have eliminated this effect by using concentric electrodes. Existing semiconductor processes and equipment are used to fabricate the sensors which presumably accounts for their low cost.



## Data-base for telecomms

Abstracts and references to articles from more than 250 international periodicals, congress proceedings and reports are contained in a data base for the telecommunications industry recently brought on line by a Dutch company, Samsom Data Systemen bv. Including some 100 000 bibliographic references dating from 1976, the data base also contains information on 250 000 products, 7000 systems and 18 000 companies. The service is conveyed through the Euronet, Tymnet, Telenet, Teleglobe, Datapak and normal telephone channels. Search languages used are Common-Command Language, CCL, which was developed for the Commission of European Communities, and the IBM-related Storage Information Retrieval System known as Stairs.



In June, Russian satellite monitors received mayday signals from a radio distress beacon and an air/sea search was carried out. The beacon was later found in the wardrobe of a man living in Erskine near Glasgow.

Two new data banks covering electronic satellite equipment produced in Europe, Sateldata, and information on spacecraft components, Spacecomps, have been opened by European Space Agency Information Retrieval Service. These banks are produced by ESA Research and Technology Centre in the Netherlands and by ESA-IRS. Computers holding the information are based in Italy and linked to all major national/international data transmission networks and ESANET.

## In brief . . .

During June, the Radio Regulatory Department was transferred from the Home Office to the Department of Trade and Industry but the Broadcasting Department and Directorate of Telecommunications stay with the Home Office. The Radio Regulatory Department is responsible for band planning and general policy on the use of the UK radio spectrum, civil radio licensing, representation of the UK in international frequency negotiations and liaison with foreign administrations. RRD also has general responsibility for the Wireless Telegraphy Acts, including their enforcement, and control of interference.

## Corrections

Precision analogue voltmeter in W. J. Hornsby's design, June 1983, the junction of D<sub>7</sub> and D<sub>8</sub> should be linked to R<sub>17</sub>, R<sub>18</sub> and IC<sub>3</sub> by a 0.47 $\mu\text{F}$  capacitor (C<sub>7</sub>) and not by a direct connection as shown in Fig. 1. Also omitted from Fig. 1 was a 68 $\mu\text{F}$  capacitor (C<sub>10</sub>) across the positive supply. Both components are shown correctly on the printed circuit layout. In the resistance measuring unit (July issue), R<sub>21</sub> (180 $\Omega$ ) should be a fixed-value resistor.

Autoranging frequency meter. In the article by F. P. Caracausi on page 36 (March issue), or second line of the centre column, for MCP read MST. On page 37, line 13 should read "from the timing module" not the counting module. Line 4 under the subheading "Timing," MCE goes low, not high. Line eight under "timing," MCE also goes low if . . . In the caption under Dr Caracausi's picture, he works at the Cassa Centrale di Risparmio and not as printed. In Fig. 1, the pin marked 17 on the display should be 7. Fig. 2, the pin marked 5 on the IC<sub>12</sub> should be 15, and finally in Fig. 6, the inputs marked DP on the counting module should have the same designation as the inputs from the scaling circuit to which they are connected.

Mixed logic. M. B. Butler tells us he made two errors in his July article (page 28 et seq.) — in Fig. 18 the flag or polarity indicator was missed off the 7427 gate, and also off the first output marked A in Fig. 27. But to come clean we also made a few. In Fig. 8, negate the C symbols in both output functions; and Fig. 9 refers to the third point in the summary, not the fourth (delete 'below'). In Fig. 15 case (vi), transpose the A and B columns, and in Fig. 16 make the bottom output of the voltage table H, not L. Insert the symbol 1 in the lower three alternative rectangles of Fig. 17, and finally note that IC<sub>31</sub> in Fig. 28 is an or-gate, not a nand-gate.

# Assembly language programming

To avoid extra processing time, microprocessors manipulate negative numbers in twos complement signed binary form. In this fifth article, converting such numbers, branching and bit manipulation conclude the section on microprocessor instructions for the 6805.

In twos complement conversion, positive numbers are represented as before but negative numbers are a ones complement with one added. For minus five,

```
+5      0000 0101
ones complement  1111 1010
twos complement  1111 1011
```

Adding plus eight and minus five becomes

```
+8      0000 1000
-5      1111 1011
binary sum (1) 0000 0011
```

and the binary sum of plus three is now correct.

The branch instruction expects to find a twos complement value in the immediate byte which it adds to the program counter and execution proceeds from the new address. When assembling, the assembler (or you if you are programming by hand) must calculate this value and insert it in the object code. Assembled, and with the addresses filled in, the example discussed last month,

```
      LDA # $05
LOOP DECA
      BNE LOOP
      SWI
```

becomes

```
030 A605      LDA # $05
032 4A      LOOP DECA
033 26xx     BNE LOOP
035 83      SWI
```

where xx is the twos complement offset. One calculates the offset by subtracting the branch address of the instruction following the branch (035) from the branch destination address (032)

```
$032      0011 0010
$035      (1) 0011 0101
result    1111 1101
```

In hexadecimal, the result is FD; (1) is an imaginary borrowed number. During execution, the two bytes of the branch instruction enter the c.p.u. from program memory and the program counter is incremented. The program counter will now contain 35 (hex.). If the branch condition is met, the program counter and offset byte are added together

```
$035      000 0011 0101
$FD      (111) 1111 1101
result $032 (1) 000 0011 0010
```

by R. F. Coates

As the offset has fewer bits than the program counter, the sign bit is extended into the remaining three bits.

Twos complements may seem complicated but they make the most efficient use of the microprocessor and result in fast execution. Computer assemblers calculate the offset automatically and there are easier ways of determining the offset when working by hand. Using the previous example count in hexadecimal past each byte of the op-code starting from the address of the instruction following the branch until the destination address is reached. When going backwards count 00 is followed by FF then FE, etc, as in the example

Offset	Op-code	
\$00	83	
\$FF	xx	
\$FE	26	
\$FD	4A	(destination address)

This method is quick in practice but it is easy to make mistakes with long branches. To solve this problem, a branch calculator program is included in the Picotutor (and Nanocomp) monitor. With Picotutor\*, press the bc key and S will be displayed to request a three-digit starting address for the branch. This is the address of the branch instruction and not the instruction following it. When 033 from the example is entered d is displayed, indicating a request for the destination address, 032, and entering this will display the twos complement offset required, FD.

A branch can only go forward 127byte or back 128 - if you try to branch further the error message will be displayed. Should you wish to branch conditionally, further than this, there are two means. One way is to use a second, or more,

\*Picotutor is an assembly-language programming aid described in *Wireless World* Dec. 1982 and Jan. 1983.

branch instruction to hop to the desired location

```
      BEQ LABEL1
```

```
LABEL1 BRA LABEL2
```

LABEL2

A second method is to use a combination of the complement of the branch instruction required and a jump. Extended jumps will allow the program to jump anywhere in memory

```
      BNE BYPASS
      JMP LABEL
BYPASS (next instruction)
```

LABEL

When the branch-not-equal-to-zero (BNE) condition is true, the program branches past the jump and executes the next instruction, in effect just continuing the sequence. If the condition is not met, JMP is executed and the program can jump anywhere in the memory. Combining BNE and JMP amounts to a jump-if-equal-to-zero instruction.

To summarize, when assembling by hand leave blanks in the object code where a branch offset is required, assemble the program and fill in the addresses then use the branch calculator program to help fill in the offsets.

**Branch instruction range.** There are 17 branch instruction for the 6805, excluding bit-test-and-branch described in the next section. They all require two bytes, the op-code and the eight-bit offset. None of them affect the condition-code register; only one addressing mode applies, which is relative.

Branch always, BRA, is an unconditional branch, that is, a branch will always occur when this instruction is encountered

Branch never, BRN, a branch instruction which never causes a branch, has the dubious function of performing a two-byte no-operation which takes the same time as two NOP instructions. Its only value is with the cmos 6805 where it only requires

three cycles to execute so timing delays can be set to a resolution of one cycle instead of two.

Branch to subroutine, BSR, unconditionally branches to a subroutine and is the same as BRA except that the return address is stored on the stack.

Branch if lower or same, BLS, causes a branch when either C or Z bits in the condition-code register are set. If a comparison (subtraction) is performed prior to this instruction and the numbers are the same, the Z bit will be set. When the number in the accumulator or index register is less than the number being subtracted from it, a borrow value occurs and the C bit is set, i.e.

```
CPX # $12
BLS LABEL
```

will cause a branch if the index register contains 12 or less.

Branch if higher, BHI, is the complement of BLS, causing a branch if both C and Z bits are clear,

Branch if interrupt pin low, BIL, allows the interrupt input to be used as an extra input line if the interrupt mask is set, when the instruction causes a branch if the interrupt signal is logical 0.

Branch if interrupt pin high, BIH, causes a branch if the signal at the interrupt input is logical 1.

Remaining branch instructions cause a branch depending on the condition of just one of the condition-code register bits. The half-carry bit is set as a result of a carry from bit three to bit four in the accumulator with instructions ADD or ADC, and is used in decimal arithmetic described later.

BCC Branch if carry clear, which may also be referred to as branch if higher or same, BHS.

BCS Branch if carry set, which may also be referred to as branch if lower, BLO.

BNE Branch if not equal to zero, i.e. when the Z bit is clear.

BEQ Branch if equal to zero, i.e. when the Z bit is set.

BHCC Branch if half carry clear.

BHCS Branch if half carry set.

BPL Branch if plus, i.e. if N bit is clear.

BMI Branch if minus, i.e. if N bit is set.

BMC Branch if interrupt mask, bit I, is clear.

BMS Branch if interrupt mask is set.

## Bit manipulation

The final section of the instruction set covers bit-manipulation instructions for the 6805. Although the Z80 has similar instructions, 6800, 6802 and 6809 type microprocessors do not. Bit-manipulation instructions fall into two categories - bit set/clear and bit-test and branch. They are intended for manipulating i/o port data for setting or clearing a single output port line which may for instance drive a relay, or for

testing the status of an input line which may be connected to say a switch causing a branch depending on its state. As these instructions are intended for i/o control only direct addressing is allowed, which means that they can only be used to operate on addresses in the range 00 to FF.

**Bit set/clear.** Any bit in any byte in address locations between 00 and FF may be set to a one or cleared to zero using these instructions. They are two-byte instructions consisting of the op-code and a direct address and their mnemonics are BSET and BCLR. Two arguments are required in the operand field, the number of the bit to be operated on, between zero and seven, and the direct address of the byte which contains the bit. BSET 3,\$32 will cause bit 3 of address location 32 to be set.

When assembling, the bit number modifies the bit-set instruction op-code and 32 goes into the second byte of the instruction. From the instruction-set table (WW April 1983, page 64) the op-code is calculated using 10+2n where n is the bit number (working in hexadecimal). For bit three, n is three which gives 10+6 so the assembled version of the above instruction is

```
1632 BSET 3,$32
and it can be tried out using this example
040 3F32 CLR $32
042 1632 BSET 3,$32
044 83 SWI
```

When the program finishes, check the contents of address location 32 using the memory-open key (mo); it should hold eight because the address was cleared before bit three was set.

```
bit number      7 6 5 4 3 2 1 0
contents of location 32 0 0 0 0 1 0 0 0
```

**Bit test and branch.** Instructions BRCLR and BRSET cause a branch when the specified bit in a byte in address range 00 to FF is clear or set respectively. These are three byte instructions. The first two bytes are the op-code modified by the bit number and the direct address of the byte, as with bit set/clear. Byte three holds the twos complement branch offset. Three arguments are required in the operand field, the bit number, the direct address and the branch label/address, e.g.

```
040 0E00FD LOOP BRSET 7,$00,LOOP
043 203B      BRA $80
```

## Op-codes for bit-manipulation instructions

Op-code	Mnemonic	Op-code	Mnemonic
00	BRSET 0	10	BSET 0
01	BRCLR 0	11	BCLR 0
02	BRSET 1	12	BSET 1
03	BRCLR 1	13	BCLR 1
04	BRSET 2	14	BSET 2
05	BRCLR 2	15	BCLR 2
06	BRSET 3	16	BSET 3
07	BRCLR 3	17	BCLR 3
08	BRSET 4	18	BSET 4
09	BRCLR 4	19	BCLR 4
0A	BRSET 5	1A	BSET 5
0B	BRCLR 5	1B	BCLR 5
0C	BRSET 6	1C	BSET 6
0D	BRCLR 6	1D	BCLR 6
0E	BRSET 7	1E	BSET 7
0F	BRCLR 7	1F	BCLR 7

The op-code for BRSET is 2n and in this case n is seven which gives a hexadecimal result of 0E. Provided that bit seven of address 00 is set to one, this program branches to the label loop, i.e. back to the start of the same instruction, and repeatedly executes the same instruction until the branch condition is not met.

Address 00 is the eight-bit i/o port on the 68705. In Picotutor, this port is connected to the eight-way dual-in-line switch with bit seven connected to the left-most switch. At switch on this port is automatically set as eight input lines and if the switch for bit seven is open a pull-up resistor in the processor makes this bit appear as a 1 (set) when address 00 is read. When the switch is closed, the associated processor input pin is connected to 0V so bit seven appears as a 0 (clear) when address 00 is read.

If the program is run with the switch open, the branch-if-bit-set instruction is repeatedly executed and the display blanks as the monitor program is no longer operating it. With the switch closed the branch-if-bit-set condition is no longer true as bit seven is clear so the loop is broken and the next instruction executed. This also causes a branch, but to the monitor re-entry point so the Picotutor dash prompt is displayed.

Branch offsets may be calculated on the Picotutor even though the function was designed for two-byte numbers and not three. For three-byte bit-test-and-branch instructions the result from the calculator must be decremented by one, as in the following key sequence

Key	Display
bc	S
040	d
040	FE

where the offset minus one is FD. Having to calculate op-codes for bit manipulation instructions can be tiresome; the table lists all combinations of these instructions and equivalent op-codes.


Programming techniques are the subject of the next article.

## In brief . . .

Paisley College are to receive a £63,000 grant from the Science and Engineering Research Council for research into ferrite-loaded microwave i.c.s operating at frequencies between 20 and 100GHz. Several i.c.s have already been built by research student David Sillers who will "spend some time at Philips and BT research laboratories, who are both collaborating in this work."

Four carrots for the Berlin International Audio and Video Fair 1983, 2 to 11 September - the world's smallest studio-quality u.h.f. pocket transmitter from Senheiser, a professional mobile video recorder from Grundig for teaching, research work, information services and advertising, Hitachi's VHS recorder giving 8h of uninterrupted film from a standard 4h tape and Sony's Beta camera/recorder weighing 2.5kg and giving three recording hours from a standard cassette.






Memory routine

controlled crystal oscillator in 100Hz steps up to 9.9kHz. If a particular memory frequency is in use the set will wait for a period determined by the number of time that the routine at 191D is called using code between 1A94 and 1AA2. The current program calls the routine at 191D four times.

Unit two looks at the channel switch and compares it with the last position of the switch stored in ram location 001A (CHNO 001A). If the two are the same nothing happens but a difference between the two causes the stored channel number to be updated. The processor then loads the index register with the content of the memory location corresponding to the channel-switch position using a subroutine called MORT located between 1B07 and 1B16. Data for the synthesizer and voltage-controlled oscillator is then loaded into the processor and sent to the synthesizer using a data-output routine, abbrevi-

ated DOP. Locations 1B71 to 1BE2 hold the data-output routine, which besides controlling the synthesizer converts binary

±600kHz subroutines



ated DOP. Locations 1B71 to 1BE2 hold the data-output routine, which besides controlling the synthesizer converts binary to condensed multiplexed b.c.d. to drive the display. Every time the frequency is changed in any mode, the data-output subroutine is used.

Unit three takes the frequency in use before memory mode was entered and places it in the memory locations pointed to by the channel switch then the program jumps back to unit two to send the data to the synthesizer. Unit four allows repeater mode to be used while in memory mode and provides the way out of memory mode, restoring the original operating frequency. When the program is in memory mode, the original operating frequency is stored in ram locations 0012 and 0013 for synthesizer and voltage-controlled oscillator data respectively.

±600kHz subroutines. Positive shift, PVE and negative-shift, NVE routines reside in locations 18AB to 18B5 and 18A1 to 18A7 respectively and add or subtract

Specification		
Frequency coverage	144 to 146MHz	Power
Frequency steps	100Hz or 25kHz	16.5W f.m. and 14.0W p.e.p. s.s.b. with 13.8V supply
Frequency display	7-digit l.e.d. with 100Hz resolution up/down buttons on microphone or channel switch (select memory channel)	Spurious outputs
Tuning method	9 memories programmed by push button - may be scanned with six second hold	Harmonics
Memory	scan memory channels or scan band (144 to 146MHz) with provision to skip up to 40 channels l.s.b., u.s.b., f.m. simplex, repeater and reverse repeater	Carrier suppression
Scanning		Squelch threshold
Modes		Bandwidths
		Sensitivity
		Receiver image response
		Third-order intercept point (receiver)
		Size
		Antenna impedance

600kHz from synthesizer data stored in 0010. Hexadecimal value 3C is the equivalent of 600kHz in this case. Both of these routines use the data-output routine, DOP, to modify the synthesizer and display.

Four lesser routines remain. The first, located between 18B6 and 18CD, takes the frequency down in 25kHz steps and the second between 18CE and 18E7 takes the frequency up in 25kHz steps. Two similar routines causing 100Hz steps up and down

are in locations 18E8 to 18FA and 18FB to 180D respectively. These routines may be modified to make the set operate with any channel spacing. Readers considering modifying the software will find the Motorola MC146805E2L microprocessor applications manual helpful.

Photocopies of p.c.b. track diagram and component positions can be obtained by sending a large s.a.e. to Wireless World Transceiver, Room L303, Quadrant House, The Quadrant, Sutton, Surrey SM2 5AS. Programmed eproms at £8 and software listing at £1.50 including UK postage and vat are available from T. Forrester, 125 Seven Way, Blechley, Bucks.

### Modules

- 1 Receiver converter, 144MHz to 9MHz November 1982. pp.35-38
- 2 Transmit converter, 9MHz to 144MHz December 1982. pp.61-63
- 3 Transmit power amplifier and power regulators -December 1982 pp.61-63 January 1983 pp.42-45
- 4 Discriminator, squelch, noise blanker, a.f. power amp January 1983 pp.42-45
- 5 Synthesizer logic January/February 1983 pp.42-45
- 6 Synthesizer voltage-controlled oscillator, power change over February 1983 pp.38-41
- 7 9MHz s.s.b. transceiver, 9MHz f.m. exciter February 1983 pp.38-41
- 8 Microprocessor control and interfaces March 1983 pp.39-42
- 9 Frequency-display driver March 1983 pp.39-42
- 10 1750Hz tone-burst and receive a.f. pre-amp April 1983 pp.69-71

## LITERATURE RECEIVED

A comprehensive 64-page catalogue of radio-frequency interference filters for mains power and other uses has been published. It lists 120 filters from a plug-and-socket model to keep noise out of home computers or hi-fi to a 800A power filter or a 32-line filter for data transmission which can handle 9.6Kbit/s. Belling Lee Intech Ltd, 240 Great Cambridge Road, Enfield EN1 3QW. **WW407**

The first issue of the Electronics for Peace Journal reports on the first national conference of the Electronics for Peace movement and includes articles on the reliability of digitally-controlled weapons, the dangers of Ada, the computer language designed for use by the US Department of Defence, which could be error-prone. On the positive, and peaceful, side there is an article on information networks at the domestic level. Membership of Electronics for Peace, including a free subscription to the Journal, is £5 (£3 for the unwaged) to Steve Holmes, 151 Courthouse Road, Maidenhead, Berks SL6 6HY. **WW408**

Stepping motors and suitable drives and some useful design features explained in a four-page brochure. Evershed and Vignoles Ltd, Acton Lane, London W4 5HJ. **WW409**

Television and audio spare parts, especially for the Rank Bush/Murphy equipment forms the core of the Mastercare catalogue, which also has service aids and tools, instrument and test

equipment and various accessories and other components. Mastercare Components, 653 London Road, High Wycombe, Bucks HP11 1PH. **WW410**

Microwave products including ferrite devices, valves, noise generators, noise standards and power units are fully illustrated in a product guide. There are precise descriptions of five different types of waveguide circulators/isolators, together with information on transitions/isolators, and a design service. Nore Microwave Ltd, 36 Towerfield Road, Shoeburyness, SS3 9SH. **WW411**

Training schemes for schools, college and apprentice use are described fully in a booklet from Taran. Blackboard-sized breadboards illustrate circuits which can be built and demonstrated to a class or group. Students can get hands-on experience of circuits from the very simple to advanced studies in microwaves, digital electronics, control and automation, and communications. Taran International Ltd, Raynham Road, Bishop's Stortford, Herts CM23 5PG. **WW412**

A 'budget range' of toroidal transformers with dual secondary windings rated at 9 to 240V and single 110, 220 or 240V primaries, or a double 120V primary are available off-the-shelf from the manufacturers who have also published a leaflet describing them. Cotwold Electronics Ltd, Kingville Road, Kingsditch Trading Estate, Cheltenham, Glos GL51 9NX. **WW413**

The Bi-Pack semiconductor catalogue costs £1 (including postage) but does include some useful information such as pin-outs for a number of devices. Despite the title, there are a number of other components and tools, test gear, audio

modules and data books. Bi-Pack Semiconductors, PO Box 6,6A High Street, Ware, Herts SG12 9AG. **WW414**

The Zehntel p.c.b.-handling robot can identify boards and can position them at an automatic test station or a repair bench to within 0.5mm. Motion is six axes is claimed to be unique. Details in a brochure from Zehntel Ltd, 62 Tanners Drive, Blakelands, Milton Keynes MK14 5BP. **WW415**

A folder-full of 34 different sections make up the Verospeed catalogue which offers over 5,000 components from 120 manufacturers. New sections are cable accessories, data books, computer accessories and opto-electronics. Verospeed, Stanstead Road, Boyatt Wood, Eastleigh, Hants SO5 4ZY. **WW416**

Automated design and production facilities are available to designers of electronic equipment. These and the test facilities, all claimed to be at highly competitive prices, are described in a brochure from Tasbian Ltd, 2 Burrington Way, Plymouth, Devon PL5 3LS. **WW417**

The preliminary product brief for the Zilog Z800 family of microprocessor units specifies 8/16-bit devices with many added instructions including signed and unsigned multiplying and division, on-chip counter/timers, two versions also have on-chip u.a.r.t. and direct memory access channels. All versions include paged memory management to address 512Kbytes while two of them can cope with 16Mbytes. Also from Zilog is a user's manual for the Z8000 floating-point emulation package. Zilog (UK) Ltd, 43 Moorbridge Road, Maidenhead, Berks SL6 8PL. **WW418**

# NEW PRODUCTS

## Audio oscillator with ultra-low distortion

Less than 0.0005% distortion is claimed for the Bang & Olufsen TG8 audio oscillator. Intended for circuit testing, test-gear calibration, and production-line product testing, its typical distortion is 0.00015% (harmonic) over the audio range 20Hz to 20kHz. The instrument is also a signal generator for 1Hz to 100kHz and has a wide range of facilities. Voltage output is from 3mV to 10V checked against a built-in voltmeter. David Bisset Ltd, 52 Luton Lane, Redbourne, Herts AL3 7PY. **WW301**




**WW301**

## Autodial modem

Any computer that uses the S-100 bus can be fitted with the Modem-100 which provides a complete autodial viewdata modem and display driver on a single card. It gives full colour display output. The card includes an 8749 microprocessor, on-board ram and rom and a calendar clock which allows for timed autodialling. Modem-100 costs £695 but a cheaper (£495) alternative is Prattle (Programmable receive and transmit telephone line equipment) built around a Z80 processor, with rom and ram programs modem buffering, autodial and answering etc, using single byte commands. Prattle also interfaces with the S-100 bus. High Technology Electronics Ltd, 303 Portwood Road, Southampton SO2 1LD. **WW302**

## Multi-counter

A dual-channel facility on the Norma D3655 counter enables frequency ratios and time intervals to be measured. The measuring periods of 10ms, 1ms, 1s and 10s allow frequency measurement up to 120MHz and event counting in the range 10Hz to 10MHz. A self-test facility checks on the internal



**WW303**

oscillator. D3655 is available with an IEEE 488 or an IEC 655 interface and so can be linked in with a data processing system. Cropico Ltd, Hampton Road, Croydon, Surrey CR9 2RU. **WW303**

## Controlled soldering

A temperature range of 216 to 426°C may be regulated to within 5°C using a slim, lightweight, micro-tipped soldering iron along with the Ungar 9000 control unit that incorporates a led bar-graph temperature display and the ability to calibrate it at the work station. Model 9000 has a fast heat-up time and temperature recovery and the iron is supplied with a variety of interchangeable, iron-clad, chrome plated tips. HB Electronics Ltd, Lever Street, Bolton, Lancs. **WW304**




**WW304**

monitoring, aids for the handicapped and childrens' games can be recorded and then edited to change pitch, emphasis or other parameters, and the edited version then programmed into an eeprom for use in a product. The package can also be used in an 'immediate' mode, being used as a peripheral processor to a host computer which can store the speech produced. Each stored phrase can be up to 10 seconds in length with sampling rates of 8 or 10kHz. The distributors are also offering a message programming service using the Speech Lab. VSI Microsystems, Roydonbury Industrial Park, Horsecroft Road, Harlow, Essex CM19 5BY. **WW305**

## High-speed rectifiers

For use as output rectifiers and flywheel diodes in high frequency p.w.m. and switching regulator applications, the RUR series of low-cost epitaxial silicon rectifiers offer high reverse voltage capability. Several advantages are



**WW306**


claimed for the diodes including low spikes, low electromagnetic interference requiring little or no RC damping, and low dissipation when compared with Schottky devices. The RUR-810 series are single rectifiers while the RUR-D810 are double i.cs with a common cathode. Rated for a forward current of 8A with a maximum forward voltage drop of 0.89V, the maximum reverse voltage is 200V. Voltage ratings vary for different diodes in the series from 100 to 200V r.m.s. Reverse recovery time is less than 35ns. VSI Electronics (UK) Ltd, Roydonbury Industrial Park,

Horsecroft Road, Harlow, Essex CM19 5BY. **WW306**


## Very nice dear, but what's it for?

A company with a problem is Regisbrook of Reading who have samples of a very sensitive humidity sensor — so sensitive, they say, that it will detect the moisture in exhaled breath at a distance of 0.6m. It is battery powered and pocket sized with an adjustable mounting bracket. The sensing grid consists of interleaved gold filaments on a ceramic substrate. There is an integral alarm bleeper which is not triggered if the gold elements are shorted together. The alarm stops when the sensing grid is wiped dry.

The problem is: what can be done with it? A first prize of champagne, with ten runners up to get the sensor itself, for the best suggestions, serious or imaginative, which should be sent to Regisbrook Ltd, Studio House, 215 Kings Road, Reading, Berks RG1 4LS. **WW307**




**WW307**



**WW308**

## Infrared emitters

Two gallium-aluminium arsenide i.r. diodes emit radiant flux at a wavelength of 880nm. They are designed to have better coupling efficiency with silicon photodiodes and to be particularly suitable for use in pulsed applications. Output in pulsed operation is 100mW, and for continuous operation 10mW. The C86038E has a glass lens to produce a narrow beam, while the C86038E/F has a flat glass window and no lens. The devices may be used in high-speed sorting and counting, intrusion alarms, edge indicators, collision protection, optical coupling and isolation, data transmission and in photoelectric smoke detection. RCA Solid State, Lincoln Way, Windmill Road, Sunbury on Thames, Middlesex TW16 7HW. **WW308**



crash and barrier testing, rocket launching and monitoring, vibration testing and control, and basic laboratory experiments. Entran Ltd, 8 The Mall, London W5 2PJ. **WW309**

## Accelerometer withstands 10000 g

A miniature transducer for the measurement of acceleration vibration and shock, the EGAX-125 weighs less than half a gram. The active semiconductor strain-gauge bridge gives a full scale output of 250mV. Built-in over-range stops and damping provide the ability to cope with high g. Static and dynamic measurement is available in various ranges from 5 to 5000 g, with a temperature range of -5 to 120°C. Its ability to operate at 10000 g overrange makes it suitable for automotive

## Driver for stepper motors

Specifically designed to drive small to medium-sized permanent magnet stepper motors, the UCN4202A i.c. uses a full-step double pulse driver that optimizes the efficiency of the motor torque. Input/output circuitry is t.t.l.

compatible and a minimum of external components are needed, to provide 600mA outputs suitable for 15V motors. Higher current ratings or bipolar operation is possible by using the device to drive power transistors or other motor drivers. Semiconductor Specialists (UK) Ltd, 159 High Street, Yiewsley, West Drayton, Middlesex UB7 7XB. **WW310**

## Switchmode kit

To demonstrate the capabilities of their m.o.s. power transistors and pulse-width modulators, Siliconix have brought out a 38-piece kit which assembles into a dc-to-dc converter able to output 5V, 10A from a 24V input. Operating at a frequency of 400kHz, the completed circuit is claimed to have better than 1% accuracy in regulation and less than 60mV output ripple. In addition to demonstrating the operation of such a circuit, the kit also shows its small size and low cost measuring 80 by 110mm and weighing 140g. £29.95 from Siliconix Ltd, Morriston, Swansea SA6 6NE. **WW311**

## Game of logic

A board game that teaches Boolean algebra, digital logic, the Karugh map and Venn diagrams is based on a game invented by Lewis Carroll.

The beginners' pack, while said to be fun to play, teaches the elements of the workings of computers, hence the title of the game — Computer. Additional packs increase the number of 'memory bits' and variables up to a 'professional' level. Computer is made in cut-out cardboard. Beginners' pack is £1 from N. Darwood Ltd, Halfacre, Stroud, Petersfield, Hants. **WW312**

## Connections verified

When a p.c.b. has been wire-wrapped there follows a tedious system of checking the interconnections to make sure that all is correct before populating the board with expensive i.cs. A way of overcoming this is to use



interconnect verifiers which are made in d.i.l. i.c. packages and incorporate arrays of l.e.ds with one to indicate the status of each pin, from eight to 48. By grounding one pin all the l.e.ds on one node are lit; incorrect connections will also be lit and points not connected, which should be, are not lit. Dim displays would indicate poor connections. This technique would not be suitable for mass production where a test rig would be set up, but offers a low-cost alternative for board development and for small batches. Track Equipment Corporation, PO Box 3181, Nashua, New Hampshire 03061, USA. **WW 313**

If you would like more information on any of the items featured here, enter the appropriate WW reference number(s) on the mauve reply-paid card bound in this issue. Overseas cards require a stamp.

# MICRO PRODUCTS

## Local processor

The problem of waiting for main-frame computer time for computation can be overcome by the use of the AP500 array processor from Analogic. The unit incorporates the MC68000 16/32-bit processor and uses 32-bit floating point arithmetic. This gives it a very high speed: the manufacturers quote its ability to invert a 100 by 100 matrix in 649ms. Using a technique of distributed control of memory, input/output and arithmetic, the central processing section can run high-level language or assembly language programs. 128Kbytes of program memory are available in the basic version, expandable up to 256K. Data memory provided is 16K by 32-bits which can be expanded to 912K 32-bit words.

The processor may be used for radar data processing, seismic research, body-scan tomography, nuclear magnetic resonance spectroscopy, image processing, speech analysis, and testing and control procedures. It need only interrupt the host computer if a certain pattern is detected among the incoming data or when a report has been compiled.

Interfaces enable it to be used as a peripheral device, as a co-processor, or to be linked through a local-area network. For many applications it could be used as a stand-alone computer. Analogic Ltd, The Centre, 68 High Street, Weybridge, Surrey.

WW314



WW314



WW315

## Eprom programmer

A microprocessor-controlled eprom emulator/ programmer has been designed to work with all popular m.o.s. eproms. The EP8000 includes all the necessary 'personality' differences between the various eproms in software and the instrument adapts itself automatically for emulating or programming a specific device. It provides a video output so that the user can examine the contents, which may also be displayed a line-at-a-time on the eight-character led display built in. Serial and/or parallel i/o buses are provided. Data can be loaded from a pre-programmed rom, through the serial or parallel ports or from an audio cassette. GP Industrial Electronics Ltd, Unit E, Huxley Close, Newnham Industrial Estate, Plymouth PL7 4JN.

WW315



despite their title, are not cube shaped but built on Eurocards. Intended for industrial and control applications, the core of the system is Eurocube, a 2MHz single card microcomputer based around a 6502 or a 6809 processor. Included on the board are four memory sockets which can hold, for example, an operating system, a Basic or other language interpreter in rom, and ram which can retain its contents with the help of a back-up battery mounted on the board and which can also maintain an on-board calendar clock. The computer cards plug into a rack

## Modular computers with BBC Basic

A series of microcomputer modules constitute the Cube range which,

modular approach, but for industrial use it is probable that many of those facilities are not needed, as all extensions are compatible with each other, and with the Acorn BBC micro.

An extension board called Beebox which plugs into the 1MHz-bus port on the BBC has slots for many of the Cube range of modules. Up to 1Mbyte of memory may be added with battery back-up to provide what the makers call a 'silicon disc'. Control Universal Ltd, Unit 2, Andersons Court, Newnham Road, Cambridge CB3 9EZ. (This address may be temporary as the company is looking for more area to expand into.)

WW316

## Daisywheel Interface

Those who are unable or unwilling to tackle the RS232C interface for an Olivetti Praxis typewriter, featured on page 24, might be interested in another already built. Designed with the Acorn/BBC computer in mind, it is suitable for any computer with an RS232C/423 outlet operating at 300 Baud. Full handshake and busy signalling is incorporated and the printing speed is 10 to 12 characters/s. The slim unit may be unobtrusively fitted to the side of the machine and there is no interference with normal operation as a typewriter. Inclusive price with easy-to-follow fitting instructions is £69, from Timtom Micro, 9 Ilton Road, Penylan, WW317

## Logical design

Developed at Brunel University and implemented by the same designers at Cirrus Computers, Hilo-2 features gate-level and function-level logic design simulation and timing verification. It is a high-speed universal logic design simulator and is a powerful tool for integrated circuit design, according to GenRad who market it. Tests may be simulated and validated and all functions modelled by using the menu-driven interface. The system runs on 32-bit virtual memory computers. Reduction in i.c. design and development time is claimed for Hilo-2 which may be used in conjunction with the GenRad v.l.s.i. test system. Included in the software is hazard spike analysis, 'worst case' modelling, interactive design analysis and hierarchical simulation for managing the complexity of a design. Implementations are available for Acorn/BBC computer. To get all the facilities of the BBC it would indeed cost more using this

which can also accommodate a wide range of input/output control modules and interfaces, including black and white or colour video output, cassette and disc controllers, keyboard inputs, and additional memory.

Control Universal have an agreement with Acorn Computers to use their firmware including the BBC Basic interpreter. This means that a control computer incorporating BBC Basic can be put together at a lower cost than buying the Acorn/BBC computer. To get all the facilities of the BBC it would indeed cost more using this

## Your own customised Communications Monitor



The vast range of available options allows you to customise the FM/AM 500 Micro-Monitor to suit your specific needs, and weighing in at just 16 lbs your 'field-tests' can now be precisely that!

For a practical demonstration to prove our point contact:-  
**Mike Dawson on 01-897 6446.**



**Fieldtech Heathrow**

**Fieldtech Heathrow Limited**  
Huntavia House 420 Bath Road  
Longford Middlesex UB7 0LL  
Telex: 23734 FLDTEC G

WW - 009 FOR FURTHER DETAILS

## pantehnic THE SPECIALISTS

### POWERFET AMPLIFIER MODULES

MODEL	POWER RANGE (Continuous RMS)	TYPICAL LOADS	PRICES (one off)
PFA 100	50W-150W	4Ω, 8Ω	£20.65
PFA 200	100W-300W	4Ω, 8Ω	£27.35
PFA 500	250W-600W	2Ω, 4Ω, 8Ω	£42.00
PFA HV	200W-300W	4Ω, 8Ω, 16Ω	£36.04

#### Key features:

- **RELIABLE** - Powerfet freedom from thermal runaway and secondary breakdown
- **LINEAR** - TID zero, IM/THD < 0.01% full power (mid-band THD down to 0.0015%)
- **FAST** - Slow rate > 30V/μs (45V/μs typical)
- **QUIET** - Signal to noise ratio 120dB
- **BRIDGEABLE** - Without extra circuitry
- **STABLE** - Unconditionally
- **LOW COST** - 10 watts to 20 watts per £, depending on model and quantity

As they stand these modules suit most P.A. and industrial applications and satisfy all foreseeable audiophile requirements. (The HV is aimed at digital audio.) Where aspects of performance fail to meet specific requirements (e.g. in speed or power) low-cost customising is often a possibility. Alternatively entirely new boards can be produced.

**ALSO -**  
PAN 20 - Ultra-low-noise/distortion, mono preamp board, £7.61  
PAX 2/24 - 2-way active crossover board (24dB/octave) plus regulators, £9.70  
THE HEAT EXCHANGER - New, super-efficient heatsink; handles 300W or 1.2kW when blown; 7in. x 4in. x 2 1/4in., £7.50

*This is just a fraction of the new products available from Pantehnic - check us out!*

Prices exclude V.A.T.

Carriage 75p

Price and Delivery  
**PANTECHNIC (Dept. WW8)**  
17A WOOLTON STREET  
LIVERPOOL L25 5NH  
Tel: 051-428 8485

Technical Enquiries contact  
Phil Rimmer  
on  
01-800 8667

WW - 062 FOR FURTHER DETAILS

## HEMMINGS ELECTRONICS AND MICROCOMPUTERS

16 BRAND ST  
HITCHIN  
HERTS  
SG5 1JE

Tel: (0462) 33031

Shop open Mon-Sat. 9 a.m.-5.30 p.m.  
Closed all day Wednesday

Professional quality electronic components, brand new and fully guaranteed. Mail order by return of post. Cash/Cheque/P.O. or Banker's Draft with order, payable to Hemmings Electronics Ltd. Official orders from schools, colleges and universities welcome. Trade and export enquiry welcome. P.&P. add 45p to all orders under £10. Telephone your Access orders, using our 24-hr. Ansaphone service. Please send SAE for full price list.

VAT - All prices exclusive of VAT - Please add 15% to total cost including P.&P. No VAT on export orders or books.

COMPUTER ICs	MEMORIES	CRYSTALS	CHASSIS MOUNTING
6502 250p	Static RAM	32.768KHz 100p	2 x 15V at 100mA 155p
6522 340p	2114L-200nS	1.000MHz 320p	2 x 20V at 67mA
6800 290p	6116P3-150nS	1.8432MHz 240p	2 x 8V at 500mA
6802 340p	6116P3-150nS	2.000MHz 180p	2 x 12V at 250mA
6809 845p	Dynamic RAM	2.4576MHz 225p	2 x 15V at 200mA
6809 1350p	4116-200nS	3.000MHz 240p	2 x 20V at 150mA
6809E 1295p	4164-200nS	3.5795MHz 120p	6-0-6V at 100mA 120p
6810 120p	Eprom	3.8864MHz 240p	9-0-9V at 100mA 125p
6821 160p	2708-450nS	4.000MHz 150p	12-0-12V at 100mA 145p
6821 215p	2716-450nS	4.1943MHz 190p	15-0-15V at 0.5A 350p
6840 390p	2532-450nS	5.0688MHz 240p	9-0-9V at 1A 270p
6840 390p	FLOPPY DISC CONTROLLERS		12-0-12V at 1A 320p
6844 1295p	FD1791 1950p		30-0-30V at 0.5A 395p
6845 795p	UPD765A 1850p		
6850 140p	CRT CONTROLLER		
6852 250p	SFF9364 800p		
6854 680p	ZENER DIODES		
6875 490p	BZY88 Series		
8126A 120p	500mW E24		
8128 250p	2V7 to 35V 8p		
8251 300p	2V7 to 35V 8p		
8253 450p	43V to 110V		
8255 280p	BZV55 Series		
8257 450p	1.3W E24		
8259 450p	2V7 to 35V 15p		
8279 450p	43V to 82V 20p		
75107 90p	BRIDGE RECTIFIERS		
75108 90p	1A/100V 25p		
75110 88p	1A/400V 30p		
75111 160p	1A/800V 40p		
75182 95p	2A/400V 40p		
75450 85p	2A/800V 70p		
75451 50p	6A/400V 95p		
75452 50p	10A/400V 280p		
75453 75p	35A/400V 315p		
75461 40p	BY164 52p		
75491 70p	TRIACS		
75492 70p	TIC206D 55p		
AY-3-1015D 300p	TIC228E 95p		
MC1408 295p	T2800D 95p		
MC1488 55p	DIACS		
MC1489 55p	2N-37V 25p		
MC3459 285p			
UPD7002 450p			
Z80ACPU 350p			
Z80APIO 300p			
Z80ATC 300p			
Z80ADART 750p			

**PCB TRANSFERS**  
Make your own Printed Circuit Boards with Alfac Etch Resist PCB Transfers  
★ Draw your artwork on 0.1" grid  
★ Transfer to copper board using carbon paper  
★ Burnish the Alfac transfers to the board using a spatula using carbon marks to assist in accurate alignment  
★ Use Alfac chemical eraser to correct mistakes  
★ Etch in Ferric Chloride

**EPSON FX-80**  
We now have in stock the new Epson printer, the FX-80, which replaces the MX80 F/T III. If you thought the MX80 was good, you will agree that the FX-80 is brilliant. All the MX80 features are there plus the following extras:  
★ 160 cps print speed  
★ 80 cps special quiet mode  
★ Program selectable character set which can be downloaded from your computer  
★ 9 different bit image modes up to 1920 dots per line  
★ Print styles emphasised, condensed, proportional, elite, italic and all MX80 styles  
★ Program control of skip-over perforation, number of columns, character sets  
★ Fully compatible with MX80 control codes

**PRINCE MONITOR**  
A 12" monochrome monitor 24MHz video bandwidth ideal for most personal computers, word processors, scientific work etc.  
INPUT VIDEO  
1 volt p-p composite video  
EXTERNAL CONTROLS  
Brightness, contrast, vertical hold, on/off  
INTERNAL CONTROLS  
Horizontal width, linearity, frequency, phase, focus, black level, vertical blanking and linearity  
TECHNICAL CHARACTERISTICS  
Scan 625 lines/50Hz, Deflection 110°, Character display 80 by 24 lines, Video input PHONO, X-ray radiation I.C. spec no 65  
SCREEN PHOSPHORS  
Black/white, green, or orange  
Green or orange filters available to order

**THE COMMODORE 64**  
MEMORY SIZE  
System memory 20K ROM 3K RAM  
User area 38K RAM or 54K if BASIC interpreter is not used  
SCREEN DISPLAY  
Full colour display 25 by 40  
255 combinations of screen and border colours  
16 Text/Character colours displaying alphanumerics or PET graphics  
Connection to a TV set or a colour or monochrome monitor  
HF modulator internal to the computer  
GRAPHICS  
High resolution graphics 320 x 200 pixels  
62 predefined graphic symbols available from the keyboard displayed in normal or reverse in all 16 colours  
SPRITE GRAPHICS  
High resolution moveable object blocks 24 pixels wide by 21 pixels deep  
Up to 8 Sprites which can be layered for 3D effects  
Sprites can be one of 8 colours or multicolour up to 4 different colours in one sprite  
Sprites can be moved independent of text, graphics or other Sprites  
SOUND  
Music Synthesis chip provides 3 voices, 8 octaves 4 waveforms - sawtooth, triangle, pulse or noise  
Programmable attack, decay, sustain and release  
Programmable filter - low pass, band pass, high pass or notch outputs  
Variable resonance and master volume control  
INPUT/OUTPUT  
User port with RS232C  
Cartridge port for games and ROM based software  
2 joystick/paddle/light pen ports  
LANGUAGE  
BASIC interpreter future options are BASIC compiler, Pascal, COMAL, LOGO and FORTH

**LIQUID CRYSTAL DISPLAY MODULES**  
PCIM177 Frequency Counter 5 Digits, 0.35" FM, SW, MW, MHz, KHz Annunciators, Sample and Hold Capability, Reset Capability, 25 Selectable IF Offsets, Prescaler Available, Incandescent Backlighting, Supply Voltage 5v, Operating Current 4mA 1715p  
PCIM 178 Digital Voltmeter, 3 1/2 digits, 0.5" +, - and Decimal Point, 200mV Full Scale Input, True Differential Input, Guaranteed '0' Reading, Single 8v Operation, Power Consumption 20mW, Accuracy 0.15%, +/- 1 Count, Temperature drift 80ppm/C, Low Battery Indicator 1950p  
Both Modules are supplied with a data sheet.

**TEMPERATURE METER**  
A fully self-contained digital temperature meter, battery operated with an LCD display  
★ Temperature range 0-99.9°C  
★ Accuracy 0.40°C +/- 0.2°C  
★ 40-70°C +/- 0.4°C  
★ 70-99.9°C +/- 1.0°C  
★ Battery 5v alkaline. Lifetime approx. 1 year  
★ External temperature probe £16.95

**TRANSFORMERS**  
PCB MOUNTING TYPE  
All types have dual primaries of 0-120, 0-120 for inputs of 120V or 240V - Primary and Secondary wound on a Split Bobbin providing superior isolation  
3VA 2 x 6V at 250mA  
2 x 12V at 125mA


£299 + VAT SECURICOR ES

WW - 042 FOR FURTHER DETAILS

BBC Micro Computer System

OFFICIAL DEALER

Please phone for availability



BBC Model B £399 (incl. VAT) Carr £8/Unit

Model A to Model B upgrade kit £50 Fitting charge £15

Individual upgrades also available TELETEXT ADAPTOR £195 WORDWISE 8K ROM £39 TORCH Z80 DISC PACK £780 WORD PROCESSOR 'VIEW' 16K ROM £52

BUSINESS, EDUCATION AND FUN SOFTWARE IN STOCK

CASSETTE RECORDER

SANYO Data Recorder DR101 A superior quality data recorder with dedicated computer output and monitoring facility on both record and play £39.50 + £1.50 carr. SLIMLINE Cassette Recorder complete with counter and remote control £24.50 + £1.50 carr. Computer Grade Cassettes £0.50 each. £4.50 for 10 + £1 carr. Cassette lead £3.50.



NEC PC 8023 BE - C

100CPS, 80 cols Logic Seeking, Bi-directional, Forward and Reverse Line Feed, Proportional Spacing, Auto Underline, Hi-Res and Block Graphics, Greek Char. Set. Only £345 + £8 carr.

MONITORS

MICROVITEC 1431 14in Colour Monitor £249 + £8 carr MICROVITEC 2031 20in Colour Monitor £319 + £8 carr KAGA 12in RGB Monitor £255 + £8 carr Lead for KAGA/SANYO RGB £10 SANYO HI RES GREEN MONITOR £99 + £6 carr SANYO HI RES RGB MONITOR £445 + £8 carr.

PRINTERS

SEIKOSHA GP 100A

80 cols 30 CPS Full ASCII and Graphics 10" wide paper Now only £180 + £6 carr. GP250A £235 + £8 carr.

EPSON RX80 and FX80

RX 80 100CPS 80 col Tractor Feed £298 FX80 160CPS 80 col F & T Feed £389 MX100 F/T3 £425 (Carr./printer £8)



Parallel Printer lead for BBC/Atom to most printers £13.50 Variety of interfaces, ribbons in stock. 2,000 fan fold sheets 9 1/2" x 11" £13.50 + £3 p&p

FLOPPY DISC INTERFACE incl. 1.2 Operating System

BBC FLOPPY DISC DRIVES

Single Drive 5 1/4" 100K £230 + £6 carr. Double Drive 5 1/4" 800K £699 + £8 carr. BBC COMPATIBLE 5 1/4" DISC DRIVES These drives are supplied in BBC matching colour cases. SINGLE DRIVES: 100K £150; 200K £215\*; 400K £265 SINGLE DRIVES: with PSU 100K £185; 200K £260\*; 400K £330 DUAL DRIVES: with PSU 200K £355; 400K £475\*; 800K £595 \*These drives are provided with a switch between 40 and 80 tracks. DRIVE CABLES: SINGLE £8, DUAL £12. DISC MANUAL & FORMATTING DISKETTE £17.50

Phone or send for our BBC leaflet

BBC BOOKS (no VAT; p&p £1)

Basic on BBC £5.95 30 House Basic £5.95 Programming the BBC Micro £6.50 BBC Micro An Expert Guide £6.95 Assy Lang Prog. for BBC £8.95 6502 Machine Codes for Beginners £6.95

RUGBY ATOMIC CLOCK

This Z80 micro controlled clock/calendar receives coded time data from NPL Rugby. The clock never needs to be reset. The facilities include 8 independent alarms and for each alarm there is a choice of melody or alternatively these can be used for electrical switching. A separate timer allows recording of up to 240 lap times without interrupting the count. Expansion facilities provided. See July/August '82 ETI for details. Built and tested £145 + £2 p&p.

MICROTIMER

6502 Based Programmable clock timer with 24 switching times/week cycle 22-hour 7-day timer 4 independent switch outputs directly interfacing to thyristor/triacs 6 digit 7 seg. display to indicate real time, ON/OFF and Reset times Output to drive day of week switch and status LEDs. Full details on request. Price for kit £57

DISC DRIVES FOR THE FORTH COMPUTER

5 1/4" Teac FD55 Slim Line Mechanisms. FD55A 40 track SSDD 250kbytes unformatted Bare: £135; Cased: £155 2 x FD55A 40 track SSDD 500kbytes unformatted Cased x psu £350 FD55E 80 track SSDD 500kbytes unformatted Bare: £180; Cased: £205 2 x FD55E 80 track SSDD 1 Mbyte unformatted Cased + psu £475

5 1/4" Mitsubishi M4853 Slim Line mechanism 80 track DSSD 1 Mbyte unformatted Bare: £225; Cased: £245 2 x M4853 2 Mbytes Cased + psu £590

Single drive cable £8; Dual Drive cable £12 Other parts for FORTH COMPUTER available send SAE for details.

NEW COMPREHENSIVE CATALOGUE AVAILABLE PLEASE SEND FOR PRICE LIST

SOFTY II INTELLIGENT PROGRAMMER

The complete microprocessor development system for Engineers and Hobbyists. You can develop programs, debug, verify and commit to EPROMs or use in host computer by using softy as a romulator. Powerful editing facilities permit bytes, blocks of bytes changed, deleted or inserted and memory contents can be observed on ordinary TV. Accepts most +5V Eproms. Softy II complete with PSU, TV Lead and Romulator lead £189

UV ERASERS

UV1B up to 6 Eproms £47.50 UV1T with Timer £80 UV140 up to 14 Eproms £81.50 UV141 with Timer £78 (Carr £2/eraser) All erasers are fitted with mains switches and safety interlocks.

'WIRELESS WORLD' PROJECTS

Semiconductors inc. I.C.s., Transistors and Sockets for most projects are stocked by us

SPECIAL OFFER

2532 350p 2732 350p 2764-25 450p 27128-25 £25 4164-2 450p 6116P-150NS 350p

BOOKS

(No VAT p&p £1) CRT Controller H/Book £8.50 Programming the Z80 £11.50 Z80 Microcomp Handbook £8.95 Programming the 6502 £10.25 6502 Assy. Lang. £12.10 6502 Applications £10.25 6502 Software Design £9.05 6502 Games £10.25 Large selection of databooks, interfacing books, books on BBC, etc in stock. Ask for our list. WW-12

Table of electronic components including Linear ICs, Computer Components, Voltage Regulators, Transistors, Diodes, Triacs, Thyristors, and more.

TECHNOMATIC LTD MAIL ORDERS TO: 17 BURNLEY ROAD, LONDON NW10 1ED SHOPS AT: 17 BURNLEY ROAD, LONDON NW10 (Tel: 01-452 1500, 01-450 6597, Telex: 9222800) 305 EDGWARE ROAD, LONDON W2

# Anglia Industrial Auctions

Specialist Auctioneers to the Radio and Electronic Industry

5 STATION ROAD, LITTLEPORT, CAMBS CB6 1QE  
Telephone: ELY (0353) 860185

## AUCTION SALES

OF OVER 700 LOTS

Including: Electronic and electrical equipment, components, test gear, radio telephones, laboratory equipment, valves, transistors, scrap and general works effects.

Forthcoming sales to be held on the following dates:

August 10th, 1983, September 14th, 1983  
October 19th, 1983, November 23rd, 1983, January 11th, 1984  
February 15th, 1984, March 21st, 1984, April 25th, 1984  
May 30th, 1984, July 4th, 1984

Catalogues available 10 days prior to sale, price 60p inc. p.&p. or for each sale for a year £5 (10 sales)  
Entry forms on application.

Large stocks of electronic components, test gear, radio telephones, transistors, etc. are offered for sale on tender. Please apply for forms

WW - 053 FOR FURTHER DETAILS

## TEST EQUIPMENT

Marconi TF144H Signal Generator	£195
Solartron CD1740 50MHz Scope	£295
Tektronix 453A 60MHz Scope	£450
Tek.191 Constant Amp. Sig. Gen. 100MHz	£115
Tek. 184 Time Mark Generator	£125
Tek. 106 Fast Rise Pulse Generator	£95
Tek. 2901 Pulse Generator	£105
Tek. 067-0502 Standard Amp Calibrator	£95
Tek. 465B + DM44 DVM with handbooks, Temp. Probe and Accessory Pouch - as new	£1,800
Tequipment D83 50MHz Scope	£395
Racal 9514 100MHz Counter IEEE	£395
Tequipment D54 10MHz Dual Channel	£150
Avometers from	£50

Uncased 19in. B & W X-Y Monitors, require 30-0-30v. supply - new quantities available; made by Electrohome of Canada

Ribbon Cable, 14-way, 100 metres .....£25  
10-way, 100 metres .....£20

Carriage and V.A.T. extra

## TIMEBASE

94 ALFRISTON GARDENS  
SHOLING, SOUTHAMPTON SO2 8FU  
TELEPHONE: 431323 (0703)



Callers welcome



Access/Barclaycard : Telephone your order

WW - 060 FOR FURTHER DETAILS

### CLEF ELECTRONIC MUSIC

#### PIANOS

SPECIALISTS SINCE 1972  
DOMESTIC OR STAGE  
SIX OR 7/4 OCTAVES  
KITS OR MANUFACTURED

The most advanced form of touch-sensitive action simulating piano key inertia by patented technique.

Four mixable voices for serious tone variation plus electronic chorus and flanger effects.

Component Kits include Keyboard.

Full Kits further contain: Cabinets, Harness, Power Amp and Speaker.

DOMESTIC PRICES		
E	SIX	7/4
Comp	234	266
Full	398	442
MFD	520	695

#### Kit BAND-BOX

An Electronic Backing TRIO, Drums, Bass & Chord Instrument. User Programmable for 50-100 scores, using microprocessor.

#### Kit MASTER RHYTHM

User Programmable DRUM MACHINE. Twenty-four patterns. Eight parallel tracks. Twelve instruments sequence operation.

Write or Phone for full details of our range of high quality Kit and manufactured Electronic Musical Instruments. Prices include V.A.T., Carr. & Ins. and we operate Telephone BARCLAYCARD/ACCESS.

Competitive EXPORT Quotations given.

#### CLEF PRODUCTS (ELECTRONICS) LIMITED

Dept. W, 44a Bramhall Lane South  
Bramhall, Stockport, Cheshire SK7 1AH  
061-439 3297

#### RELAYS. 6V DC 95p. 12V DC £1.25. 18V £1.25. 24V £1.30

#### ALUMINUM CHASSIS. 6"x4" £1.75; 6"x6" £2.20; 16"x10" £3.30; 12"x3" £2.30; 14"x3" £2.50.

#### ALUMINUM PANELS. 6"x4" 55p; 6"x6" 90p; 14"x3" 90p; 10"x7" £1.15; 12"x8" £1.30; 12"x5" 90p; 16"x6" £1.30; 14"x9" £1.75; 12"x12" £1.80; 16"x10" £2.10.

#### ALUMINUM BOXES. 4x4x1 1/2 £1.20. 4x2 1/2x2 £1.20. 3x2x1 £1.20. 6x4x2 £1.90. 7x5x3 £2.90. 8x6x3 £3.10. 10x7x2 1/2 £3.60. 12x5x3 £3.60. 12x8x3 £4.30.

#### ALL ANGLE BRACKET 6"x3/4"x3/4in. 30p.

#### BRIDGE RECTIFIER 200V PIV 2a £1.4a £1.50. 6a £2.50.

#### TOGGLE SWITCHES SP 40p. DPST 50p. DPDT 60p.

#### MINIATURE TOGGLES SP 40p. DPDT 80p.

#### RESISTORS. 100 to 10M. 1/4W, 1/2W, 1W, 2p; 2W 10p. Low ohm 1 watt 0.47 to 3.9 ohm 10p.

#### HIGH STABILITY. 1/2W 2% 10 ohms to 1 meg. 10p.

#### WIRE-WOUND RESISTORS 1 watt, 10 watt, 15 watt 20p.

#### PICK-UP CARTRIDGES SONOTONE STACH £3.80.

#### BSR Stereo Ceramic SC7 Medium Output £2. SC12 £3.

#### PHILIPS PLUG-IN HEAD. Stereo Ceramic. AU1020 (G306 - GP310 - GP233 - AG3306, £2. A.D.C. GLM 30/3 Magnetic £5. STYLUS Most Ceramic Accos, Sonotone, BSR, Garrard Philips Diamond £1.50 ea.

#### MAGNETIC STYLUS. Sony, JVC, Sanyo, Goldring, etc. £4.

#### LOCKTITE SEALING KIT DECCA 118. Complete £1.

#### VALVE OUTPUT Transformers push/pull 15 watt £14; 30W £18; 50W £20; 100W £24. Post £2. 100V/Line 20W £3.75.

#### MICROSWITCH. 50p. Miniature 65p. SPDT.

#### ANTEX SOLDERING IRON 'C' 15W £5.25. 25W 'X25' £5.50.

#### WAFER SWITCHES. 1 1/4" dia. 60p ea.

#### 1P 12W; 2P 2W; 2P 6W; 3P 4W; 4P 2W; 4P 3W.

#### FERRITE ROD. 6"x1/2", 6"x3/8", 8"x5/16" 50p.

#### XLR Lead Plug £2.40. Lead socket £2.75

#### XLR Chassis Plug £2.20. Chassis Socket £2.55.

#### BANANA 4mm Plugs/Sockets, red/black 20p

#### JACK PLUGS Mono Plastic 25p; Metal 30p. Sockets 25p.

#### JACK PLUGS Stereo Plastic 30p; Metal 35p. Sockets 30p.

#### FREE SOCKETS - Cable end 30p. Metal 45p.

#### 2.5mm and 3.5mm JACK SOCKETS 25p. Plugs 25p.

#### DIN TYPE CONNECTORS

#### Sockets 3-pin, 5-pin 15p. Free Sockets 3-pin, 5-pin 25p.

#### Plugs 3-pin 20p; 5-pin 25p; Speaker plugs 25p; Sockets 15p.

#### PHONO PLUGS and SOCKETS ea. 20p; Double sockets 30p.

#### Free Socket for cable end 20p. Screened Phono Plugs 25p.

#### B.N.C. PLUGS £1. Sockets £1. Free Sockets £1.10.

#### U.H.F. PLUG 50p. Socket 50p. Reducer 20p. Coupler 50p.

#### 300 ohm TWIN RIBBON FEEDER 10p vc

#### 300 ohm to 75 ohm AERIAL MATCHING TRANSFORMER £1.

#### U.H.F. COAXIAL CABLE SUPER LOW LOSS. 75 ohm 25p vd.

#### COAX PLUGS 30p. COAX SOCKETS 20p. Lead Sockets 65p.

#### NEON INDICATORS 250V, round 40p. Rectangular 45p.

#### MORSE CODE TAPPER and BUZZER SET £3.

#### CAR CASSETTE MECHANISM. 12V Motor Stereo Head £5.

WW - 015 FOR FURTHER DETAILS

## RADFORD

Audio Measuring Instruments, Audio Amplifiers, Loudspeakers and Loudspeaker Components for the professional and enthusiast

### RADFORD AUDIO LTD.

10 BEACH ROAD  
WESTON-S-MARE, AVON BS23 2AU

TEL. 0934 416033

WW - 011 FOR FURTHER DETAILS

## U.K. RETURN OF POST MAIL ORDER SERVICE, ALSO WORLDWIDE EXPORT SERVICE

### RECORD DECKS SINGLE PLAY

Large Turntables  
240 volt AC. Post £2

Make	Model	Drive	Cartridge	Price
BSR	P170	Rim	Ceramic	£20
BSR	P232	Beit	Ceramic	£24
GARRARD	G200	Rim	Ceramic	£22
GARRARD	Delux	Beit	Magnetic	£40

BSR	P232	12 volt	Magnetic	£24
AUTOCHANGERS 240 VOLT				
BSR	Budget	Rim	Ceramic	£16
BSR	Delux	Rim	Ceramic	£18
BSR	Delux	Rim	Magnetic	£26

MAINS PRE-AMP FOR MAGNETIC CARTRIDGES to low gain amplifier. 10mv to 1/2 volt, mono £5, stereo £7. P.&P £1

### HEAVY METAL PLINTHS

Cut out for most Garrard decks. Black or silver grey finish. Size 16x13 3/4in. Post £2

DECCA TEAK VENEERED PLINTH. Post £1.50

Superior finish with space and panel for small amplifier. Board is cut for B.S.R. 16 3/4in. x 14 1/4in. x 4in. Black/chrome fascia trim. Also with boards cut out for Garrard £3. Tinted plastic cover £5

### TINTED PLASTIC COVERS

17 7/8 x 13 1/8 x 3 1/4in.	£5	18 1/4 x 12 1/2 x 3in.	£5
17 1/4 x 9 3/8 x 3 1/2in.	£3	14 3/8 x 12 1/2 x 2 7/8in.	£5
16 1/2 x 15 x 4 1/2in.	£5	16 3/8 x 13 x 4in.	£5
17 x 12 7/8 x 3 1/2in.	£5	14 1/2 x 13 1/8 x 2 9/4in.	£5
22 5/8 x 13 7/8 x 3in.	£5	17 1/4 x 13 3/4 x 4 1/8in.	£5
21 1/2 x 14 1/4 x 2 1/2in.	£5	21 x 13 7/8 x 4 1/8in.	£5
23 3/4 x 14 x 3 7/8in.	£5	30 3/4 x 13 3/8 x 3 1/4in.	£5

### THE "INSTANT" BULK TAPE ERASER

Suitable for cassettes and all sizes of tape reels. AC mains 200/250V. Hand held size with switch and lead (120 volt to order). Will also demagnetise small tools and computer tapes.

Tape Head Demagnetiser only £5

### BATTERY ELIMINATOR MAINS TO 9 VOLT D.C.

Stabilised output, 9 volt 400 m.a. U.K. made in plastic case with screw terminals. Safety overload cut out. Size 5x3 1/4x2 1/2in. Transformer Rectifier Unit. Suitable Radios, Cassettes, models, £5. Post £1.

### DRILL SPEED CONTROLLER/LIGHT DIMMER KIT.

Easy build kit. Controls up to 800 watts AC mains with plastic case 4 x 3 x 1 1/2in, £5, less case £4. For brush motors, power tools, drills and lighting. Post 65p.

### R.C.S. LOW VOLTAGE STABILISED POWER PACK KITS

All parts and instructions with Zener diode printed circuit, mains transformer 240V a.c. Output 6 or 7 1/2 or 9 or 12V d.c. up to 100mA or less. Please state voltage required.

RELAYS. 6V DC 95p. 12V DC £1.25. 18V £1.25. 24V £1.30

ALUMINUM CHASSIS. 6"x4" £1.75; 6"x6" £2.20; 16"x10" £3.30; 12"x3" £2.30; 14"x3" £2.50.

ALUMINUM PANELS. 6"x4" 55p; 6"x6" 90p; 14"x3" 90p; 10"x7" £1.15; 12"x8" £1.30; 12"x5" 90p; 16"x6" £1.30; 14"x9" £1.75; 12"x12" £1.80; 16"x10" £2.10.

ALUMINUM BOXES. 4x4x1 1/2 £1.20. 4x2 1/2x2 £1.20. 3x2x1 £1.20. 6x4x2 £1.90. 7x5x3 £2.90. 8x6x3 £3.10. 10x7x2 1/2 £3.60. 12x5x3 £3.60. 12x8x3 £4.30.

ALL ANGLE BRACKET 6"x3/4"x3/4in. 30p.

BRIDGE RECTIFIER 200V PIV 2a £1.4a £1.50. 6a £2.50.

TOGGLE SWITCHES SP 40p. DPST 50p. DPDT 60p.

MINIATURE TOGGLES SP 40p. DPDT 80p.

RESISTORS. 100 to 10M. 1/4W, 1/2W, 1W, 2p; 2W 10p. Low ohm 1 watt 0.47 to 3.9 ohm 10p.

HIGH STABILITY. 1/2W 2% 10 ohms to 1 meg. 10p.

WIRE-WOUND RESISTORS 1 watt, 10 watt, 15 watt 20p.

PICK-UP CARTRIDGES SONOTONE STACH £3.80.

BSR Stereo Ceramic SC7 Medium Output £2. SC12 £3.

PHILIPS PLUG-IN HEAD. Stereo Ceramic. AU1020 (G306 - GP310 - GP233 - AG3306, £2. A.D.C. GLM 30/3 Magnetic £5. STYLUS Most Ceramic Accos, Sonotone, BSR, Garrard Philips Diamond £1.50 ea.

MAGNETIC STYLUS. Sony, JVC, Sanyo, Goldring, etc. £4.

LOCKTITE SEALING KIT DECCA 118. Complete £1.

VALVE OUTPUT Transformers push/pull 15 watt £14; 30W £18; 50W £20; 100W £24. Post £2. 100V/Line 20W £3.75.

MICROSWITCH. 50p. Miniature 65p. SPDT.

ANTEX SOLDERING IRON 'C' 15W £5.25. 25W 'X25' £5.50.

WAFER SWITCHES. 1 1/4" dia. 60p ea.

1P 12W; 2P 2W; 2P 6W; 3P 4W; 4P 2W; 4P 3W.

FERRITE ROD. 6"x1/2", 6"x3/8", 8"x5/16" 50p.

XLR Lead Plug £2.40. Lead socket £2.75

XLR Chassis Plug £2.20. Chassis Socket £2.55.

BANANA 4mm Plugs/Sockets, red/black 20p

### MINI-MULTI TESTER NEW

De luxe pocket size precision moving coil instrument. Impedance + Capacity - 4000 o.p.v. Battery included.

11 instant ranges measure: DC volts 5.25, 250, 500, AC volts 10, 50, 500, 1000, DC amps 0-250µA, 0-250mA, Resistance 0 to 600K ohms.

De Luxe Range Doubler Model £19.50  
50,000 o.p.v. 7x5x2in. Post £1  
43 Ranges, 1,000V, AC-DC, 20 meg. etc.

### PANEL METERS

50µA, 100µA, 500µA, 1ma, 5ma, 50ma, 100ma, 500ma, 1V, 2 amp, 25 volt, VU

2 1/4 x 2 x 1 1/4. Stereo VU  
3 1/4 x 1 1/2 x 1 in. £4.50 Post 50p

### RCS SOUND TO LIGHT CONTROL BOX

Complete ready to use with cabinet size 9x3x5in. 3 channel, 1000 watt each. For home or disco £27

OR KIT OF PARTS £19.50 Post £1

Light Boxes, red, yellow, blue, green. £15. Post £2.

Disco bulbs 100 watt, blue, green, yellow, red, amber, screw or bayonet £2 each. Post £1.50 per six.

"FUZZ" lights, red, blue, green, amber, 240V. £23. Post £1

200 Watt Rear Reflecting White Light Bulbs. Ideal for Disco Lights, Edison Screw. 6 for £4, or 12 for £7.50. Post £1.50. Suitable panel mounting holders 85p.

### RCS "MINOR" 10 watt AMPLIFIER KIT £14

This kit is suitable for record players, guitars, tape playback, electronic instruments or small PA systems. Two versions available: Mono, £14; Stereo, £20.

10W per channel; size 9 1/2 x 3 x 2 1/2in. SAE details. Full instructions supplied. 240V AC mains. Post £1.

### RCS STEREO PRE-AMP KIT. All parts to build this pre-amp. Inputs for high, medium or low imp

per channel, with volume control and PC Board. Can be ganged to make multi-way stereo mixers £3.50 Post 65p

### MAINS TRANSFORMERS

250-0-250V 80mA, 6.3V 3.5A, 6.3V 1A £8.00 £2  
350-0-350V 250mA, 6.3V 6A CT £12.00 £2  
220V 25ma 6V lamp £3.00 £1  
250V 60mA, 6V 2A £4.75 £1

### Step-Up

115V to 240V 150W £9. 250V £10. 500W £12.00 £2

### GENERAL PURPOSE LOW VOLTAGE

Tapped outputs available

2 amp. 3, 4, 5, 6, 8, 9, 10, 12, 15, 18, 25 and 30V £8.00 £2  
1 amp. 6, 8, 10, 12, 15, 18, 20, 24, 30, 36, 40, 48, 60 £10.50 £2  
2 amp. 6, 8, 10, 12, 15, 18, 20, 24, 30, 36, 40, 48, 60 £12.50 £2  
3 amp. 6, 8, 10, 12, 15, 18, 20, 24, 30, 36, 40, 48, 60 £16.00 £2  
5 amp. 6, 8, 10, 12, 15, 18, 20, 24, 30, 36, 40, 48, 60 £21.00 £2  
5-8-10-16V. 1/2 amp. £2.50 £1  
6V. 1/2 amp. £2.00 £1  
6-0-6V. 1/2 amp. £2.50 £1  
9V. 3 amp. £1.50 £1  
9V. 3 amp. £1.50 £1  
9-0-9V. 50ma £1.50 £1  
9-0-9V. 1 amp. £3.50 £1  
10-0-10V. 2 amps £4.00 £1  
10-30-40V. 2 amps £4.50 £1  
12V. 100ma £1.50 £1  
12V. 750 ma £2.50 £1  
12V. 3 amps £4.50 £1  
12-0-12V. 2 amps £4.50 £1

### CHARGER TRANS

6-12 volt 3a £4.50 £2  
6-12 volt 4a £6.50 £2

### RECTIFIERS

6-12 volt 2a £1.10+80p  
6-12 volt 4a £2.00+80p

### OPUS COMPACT SPEAKERS £22 pair

TEAK VENEERED CABINET  
11 x 8 1/2 x 7 in, 15 watts

50 to 14,000 cps. 4 ohm, 8 ohm or 16 ohm

OPUS TWO 15 x 10 1/2 x 7 3/4 in 25 watt  
2-way system £39 pair. Post £3

### LOW VOLTAGE ELECTROLYTICS

Wire ends All 10p ea.

1mF, 2mf, 4mf, 8mf, 10mf, 16mf, 25mf, 30mf, 50mf, 100mf, 250mf, All 15 volts. 22mf/6v/10v; 25mf/6v/10v; 47mf/10v; 50mf/16v; 68mf/6v/10v/16v/25v; 100mf/10v; 150mf/6v/10v; 200mf/10v/16v; 220mf/4v/10v/16v; 330mf/4v/10v; 500mf/6v; 680mf/6v/10v; 1000mf/2.5v/4v/10v; 1500mf/12v/15v; 2200mf/6v/10v; 3300mf/6v; 4700mf/4v.

500mF 12V 15v; 25V 20p; 50V 30p; 100mF 70p 80p.

1000mF 12V 20p; 25V 35p; 50V 50p; 100V £1.20.

2000mF 30V 42p; 40V 60p; 100V £1.40; 1500mF 100V £1.20.

2200mF 63V 90p; 2500mF 50V 70p; 3000mF 50V 65p;

4700mF 30V 75p; 40V £1; 63V £1.80.

# ELECTRIC SHOCK

## 2 WAYS TO RECOVERY

ACT AT ONCE - DELAY IS FATAL

### ELECTRIC SHOCK ACT AT ONCE - DELAY IS FATAL

make sure it is safe to approach

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

if the casualty is breathing

if the casualty is NOT breathing

start artificial respiration - speed is essential

if AFTER FOUR INFLATIONS casualty does not respond to artificial respiration

external heart compression

Display the ELECTRICAL REVIEW shock first aid chart (356x508mm) supplied in thousands to destinations world-wide. Recent deliveries include consignments to companies in Papua New Guinea, Dubai, United Arab Emirates, The Philippines, apart from UK commercial and industrial, educational, Central Government, Local Authorities' orders.

Carry the ELECTRICAL REVIEW pocket-size shock card (92x126mm) designed to help safety and training officers, medical and welfare personnel; all who might find themselves called to save a life. Always pocket your card; there's a useful two-year calendar on the back.

GET IT - READ IT - PRACTISE 1-4

BE READY TO SAVE A LIFE. SOMEONE MIGHT SAVE YOURS.

## ACT AT ONCE - DELAY IS FATAL!

To Electrical-Electronic Press  
General Sales Department  
Room 205  
Quadrant House  
Sutton SM2 5AS  
Surrey  
England

Company Registered Number: 151537 (ENGLAND)  
Registered Office: Quadrant House, The Quadrant  
Sutton, Surrey SM2 5AS

Please send . . . . . copy/copies as indicated

Pocket Card @ 70p each inc VAT   
Paper Chart @ £1.00 each post free   
Card Chart @ £2.00 each post free   
Plastic Chart @ £3.00 each post free

Discounts: 100 + copies 10%  
500 + copies 15%

(Overseas surface and air mail rates supplied on application.)

VALVES		Minimum Order £1	VALVES VAT IS INCLUDED									
A1065	1.40	EY51	0.95	U27	1.15	GAT6	0.90	12BA6	0.90	6550	7.20	
A2293	8.80	EY81	0.85	U191	0.85	GAU6	0.80	12BE8	1.25	6570	14.00	
A2900	13.75	EY86/87	0.60	U281	0.70	6AV6	0.85	12BH7	1.95	6973	4.40	
AR8	0.75	EY88	0.65	U301	0.85	6AX4GT	1.30	12BY7A	2.30	7360	10.80	
ARP3	0.70	EZ80	0.70	U600	11.50	6AX5GT	1.30	12C8	0.65	8552	8.20	
ATP4	0.50	EZ81	0.70	U601	0.90	6BA6	0.55	12E1	1.85	39P1	11.00	
B12H	3.90	GM4	5.90	UBC41	1.20	6BE6	0.60	12J5GT	0.70	4EP1	35.80	
CY31	1.40	GY501	1.30	UABC80	0.75	6BG6G	1.60	12K7GT	0.70	4EP1	35.80	
DAF96	0.70	GZ32	1.05	UAF42	1.20	6BJ6	1.30	12K8GT	0.80	8BJ	14.00	
DE122	28.50	GZ33	4.20	UBF80	0.70	6B07A	0.85	12Q7GT	0.60	8BL	14.00	
DF96	0.70	GZ34	2.75	UBF81	0.70	6BR7	4.80	12SC7	0.65	CV156	18.00	
DH76	0.75	GZ37	3.95	UCC84	0.85	6BW6	6.20	12SH7	0.85	DG7-32	34.80	
DL92	0.60	KT66	10.95	UCC85	0.70	6BW7	1.80	12SJ7	0.70	DG7-36	36.00	
DY86/87	0.65	KT88	16.10*	UCF80	1.30	6C4	0.50	12SQ7	1.45	DPM9-11	38.40	
DY802	0.70	KT88	12.85	UCH42	1.65	6C6	0.55	12SQ7GT	0.95	D13-33GM	41.80	
E92CC	2.80	ML6	2.50	UCH42	1.65	6C6	0.55	12SQ7GT	0.95	D13-33GM	41.80	
E180CC	4.20	ML6	2.50	UCL82	0.95	6CL6	2.75	13D3	2.80	* spec Q		
E180F	7.70	ML6	2.50	UF41	1.35	6CW4	8.50	13D5	0.90			
E182CC	6.25	MX120/01		UF80	0.95	6CX8	3.80	13D6	0.80	PLUMBICON		
EA76	2.25	N78	21.50	UF85	0.95	6CY5	1.15	14S7	1.15	P800 3LF		
EBC80	0.80	O2	0.70	ULB4	0.95	6D6	0.70	19A05	0.80	P800 IR		
EB91	0.60	O2	0.70	UM80	0.90	6F6	1.60	19G3	11.50	P800 IB		
EBC33	1.15	OB2	0.80	UM84	0.70	6F6GB	1.10	19G6	8.50	XQ1020R		
EBC90	0.90	PABC80	0.60	UY82	0.70	6F7	2.80	19H5	39.55	XQ1020B		
EBC95	0.70	PC86	0.75	UY85	0.8*	6F8G	0.50	20D1	0.80			
EBF83	0.60	PC86	0.85	VR105/30	1.25	6F12	1.50	20F2	0.60	SPECIAL V		
EBF89	0.80	PC88	0.90	VR150/30	1.35	6F14	1.15	20E1	1.30	4CX 1000A		
EC52	0.85	PC97	1.25	X66	0.95	6F15	1.30	20P1	0.85	4CX 5000A		
EC91	4.40	PC900	0.90	X81M	1.70	6F17	3.20	20P3	0.75	BM 25L		
EC94	0.50	PC904	0.50	XR1-6400A		6F23	0.75	20P4	1.25	BW 153		
ECC81	0.85	PC989	0.85			6F24	1.75	20P5	1.35	BM 25LB		
ECC82	0.60	PC189	0.85	Z759	19.00	6F33	10.50	25L6GT	0.95	YL 1420		
ECC83	0.85	PCF80	0.80	Z749	0.75	6F8	12.50	25Z4G	0.75	YL 1430		
ECC84	0.80	PCF82	0.70	Z800U	3.45	6GA8	1.95	30C15	0.80	YL 1440		
ECC85	0.80	PCF84	0.75	Z801U	3.75	6GH8A	1.60	30C17	0.80	CV156		
ECC88	0.80	PCF86	1.50	Z803U	16.00	6H6	1.60	30C18	2.45	CV1587		
ECC89	0.95	PCF87	0.50	Z900T	2.45	6JU6	5.85	30F5	1.15	CV2116		
ECC804	0.90	PCF200	1.45*	1A3	0.85	6J4	1.35	30FL2	1.40	BR 189		
ECC805	0.85	PCF201	1.65	1L4	0.50	6J4WA	2.00	30FL12	1.25	BR 179		
ECC806	0.85	PCF202	1.65	1RS	0.60	6J5	3.70	30PL13	1.25	MIL 5948/1754		
ECC807	1.05	PCF801	1.75	1S4	0.45	6J5GT	0.90	30L15	1.10	GMU 2		
ECC834	2.25	PCF802	0.70	1S5	0.45	6J6	0.65	30L17	1.10	TY4-500		
ECH35	1.70	PCF806	1.20	1T4	0.45	6J8W	0.90	30P12	1.15	BK485/5552A		
ECH42	2.10	PCF808	1.45	1T4	0.45	6J8C	3.70	30P13	1.25	MIL 5948/1754		
ECH43	1.20	PCF809	1.25	1X2B	1.40	6J8C	3.70	30P14	2.45			
ECH81	0.70	PCL81	0.75	2D21	1.10	6K7	0.80	35L6GT	1.40	IC		
ECH84	0.80	PCL82	0.95	2K25	1.85*	6K6	4.50	35W4	0.80	SN5402N	0.28	
ECL80	0.70	PCL84	0.90	2K25	24.50	6L6M	2.80	35Z4GT	0.80	SN5410F	0.32	
ECL82	0.75	PCL86	0.75	2X2A	79.50*	6L6G	2.50	50C5	1.15	SN5470F	0.48	
ECL83	1.40	PCL86/85	0.75	3A4	2.50	6L6GC	2.65	50C6G	1.20	SN54196J	1.20	
ECL85	0.80	PCL86/85	0.75	3A4	0.70	6L6GT	1.25	75B1	1.25	SN7407N	0.29	
ECL86	0.90	PFL200	1.10	3AT2	2.40	6L7G	0.65	75C1	1.70	SN7408N	0.18	
EF37A	2.15	PL36	2.80*	3B28	12.00	6L8	0.70	76	2.20	SN7445F	0.85	
EF39	1.20	PL81	0.85	3D6	19.50*	6L6G	2.95	78	2.25	SN74453P	1.10	
EF83	1.75	PL82	0.70	3D22	0.50	6LD20	0.70	80	2.50	SN74453P	1.10	
EF85	0.60	PL83	0.60	3E29	19.00	6Q7G	1.30	80	2.55*	SN7474N	0.30	
EF86	0.75	PL84	0.95	3S4	0.80	6SA7	1.00	807	1.25	SN7485N	0.95	
EF89	1.80	PL504	1.00	3S4	0.80	6SA7	1.00	807	1.30*	SN7485N	1.10	
EF91	1.50	PL508	2.40	5B/254M	16.90	6SJ7	1.05	813	19.32	SN7485N	1.10	
EF92	2.90	PL509	5.65	5B/255M	14.50	6SK7	0.95	813	68.50*	SN74123N	0.42	
EF95	0.65	PL519	5.80	5B/258M	12.50	6SL7GT	0.85	829B	16.00	DM74123N	0.38	
EF96	0.60	PL802(5E)	2.95	5C22	29.90	6SN7GT	0.80	832A	8.90	SN15836N	0.26	
EF98	0.85	PL81	0.85	5C22	1.80	6SR7	1.10	866A	3.80	SN15836N	0.26	
EF184	0.80	PY80	0.70	5L4G	0.75	6SQ7	0.95	866E	6.25	SN76013N	1.80	
EF812	0.75	PY81/800	0.85	5V4G	0.75	6V6G	1.50	831A	13.80	SN76003N	1.60	
EFL200	1.85	PY82	0.65	5Y3GT	0.95	6V6GT	0.95	954	1.20	SN76033N	1.35	
EH90	0.85	PY83	0.80	SZ4	1.50	6X4	0.95	955	1.20	MC6800P	5.80	
EL32	1.10	QV03	0.80	SZ4G	0.75	6X4WA	0.10	956	1.20	MC68800P		
EL34	1.80	QV500A	2.10	SZ4GT	1.05	6X5GT	0.65	957	1.70	MC14511BA	6.40	
EL37	2.90*	QV809	6.45	6/30L2	0.90	6Y6G	0.90	1625	1.80	MC14511BA		
EL37	5.20	QV810	0.80	6AB7	0.70	6Z4	0.70	1629	1.85			
EL82	0.70	QV03/10	3.20	GAC7	1.15	7B7	1.75	2051	2.90	B1702AL	3.30	
EL84	0.80	QV06/40	7.50*	GAG5	0.90	8BN8	2.95	5763	4.80	MM6300-1J		
EL86	0.95	QV03-20A	6AH6	1.15	9D2	0.70	5842	7.50	5881	3.80	MCM6810AP	
EL90	1.00	QV03-25A	6AK5	0.85	9D6	2.90	5881	3.50	5881	3.50		
EL91	4.20	QV03-25A	6AK8	0.80	10C2	0.85	5933	6.90	5933	6.90		
EL95	0.80	QV06/40	36.50	GAL5	0.85	10F1	0.70	6057	2.20	6340-1J	3.80	
EL504	1.70	QV06/40	6ALB	0.85	10P13	1.50	6060	1.70	6060	1.70	NIC945-5D	0.28
EL803	5.90	16.10	6AM5	4.20	11E2	19.50	6064	2.30	6064	2.30	NIC936-5D	0.22
EL509	3.95	QV03-12	4.20	6AM6	1.50	12A6	0.70	6065	3.20			
EL821	8.20	SP61	1.									

# LOGIC ANALYSERS

Thandar's comprehensive range of professional specification instruments now includes 8 and 16 channel logic analysers to expand your test capabilities. Both analysers feature DC to 20MHz sampling rates, synchronous or asynchronous clocking and 15ns glitch capture in latch mode. There is also a powerful compound trigger delay by event and/or clock (two level triggering on TA2160), selectable trigger position, variable trigger filter and clock qualifier and arm facilities. All inputs are high impedance with TTL or variable threshold. Both have a composite video output to drive an external display or video printer and offer disassembler options for common microprocessors. Accessories are available for serial data capture and hard copy record printout.

**TA2080 (8 CHANNEL)** Full system information always shown in display; 8 bit data and reference memories, both 252 bytes deep; 23 bit triggering (8 data bits, 15 trigger bits). Timing display shows all 252 bytes of the 8 data channels in timing diagram format with x1, x4, x8 expansions available; State display shows 24 sequential bytes in either binary plus ASCII or hex plus octal plus ASCII; Automatic or manual compare between recording and reference memories for equality or inequality.

**TA2160 (16 CHANNEL)** 16 bit data and reference memories, 252 samples deep. Both data and reference memories configurable as 16 bit x 252 samples, 8 bit x 504 samples, or 2 x 8 bit x 252 samples; 34 bit triggering (16 data, 12 trigger and 6 qualifiers). Independent clocks and clock qualifiers in 2 x 8 bit modes; Sample or latch assignable on a per pod basis; Timing display shows 252 bytes of any 8 channels in timing diagram format with x2, x4, x8 expansions available; State display shows 16 sequential state locations of any 4 memories in 4 columns; each memory can be displayed in either binary, hex, octal, decimal, ASCII, or EBCDIC; Automatic or manual compare between any part of any two memories for equality or inequality; TTL or variable threshold assignable on a per pod basis; RS232 interface permits dumping and loading of reference memories and all system parameters.



TH11

Send for our complete catalogue and price list  
Thandar Electronics Ltd, London Road, St. Ives  
Huntingdon, Cambridgeshire, PE17 4JH.  
Telephone (0480) 64646. Telex 32250.

**thandar**  
ELECTRONICS LIMITED THE LOGICAL CHOICE

WW - 041 FOR FURTHER DETAILS

## CONCEPT 09 Microcomputers

British designed microcomputer systems that bring together the processing power of the 6809 Microprocessor with the renowned FLEX operating system. The cost-effective solution to software development.

Languages:

Basic 'C'  
Pascal BCPL  
Fortran PL9  
Forth

### CONCEPT 09 Microsystem

Low cost compact design  
MC6809 Microprocessor  
Dual 5.25 Disc Drives  
56k Dynamic Ram  
Serial Console Port  
Centronics Printer Port  
24 Lines Parallel I/O  
Powerful EPROM Monitor  
Flex Operating System

£995

Assemblers etc.:

6809 assembler  
6800 cross-assembler  
6805 cross-assembler  
6502 cross-assembler  
Z80 cross-assembler  
68000 cross-assembler  
6502 simulator  
6805 simulator  
6800 translator  
6502 translator  
6809 debug  
Labelling disassembler

Applications:

Word Processors  
Spelling Checker  
Mail Merge  
Dyncalc  
Data Base Management

### CONCEPT 09 Workstation

High performance, three processor design  
MC6809 Main Processor - Full Cursor Control  
Dual 5.25 Disc Drives - 56k Dynamic Ram  
Serial RS232 Port - Centronics Printer Port  
Intelligent VDU Controller (6802)  
40/80 by 24 Character Display  
Programmable Character Attributes  
Up to four selectable character sets  
Dumb Terminal Emulation - Non-reflective Display  
FLEX Disc Operating System

£1850



**Micro Concepts**

8 SKILLICORNE MEWS · QUEENS ROAD · CHELTENHAM · GLOUCESTERSHIRE GL50 2NJ · Telephone: Cheltenham (0242) 510525

WW - 056 FOR FURTHER DETAILS

## CRICKLEWOOD ELECTRONICS LTD.

40 Cricklewood Broadway, London NW2 3ET. Tel. 01 452 0161. Tlx. 914977.

Here's a selection from our vast stocks. Full price list free on request. Orders by phone quoting credit card no. or by mail order. Callers welcome. All products first grade franchised source. All in stock items despatched same day. Official orders welcome from Govt. Depts., schools, etc. Please add 60p p&p + 15% VAT. Overseas orders no VAT but allow 12 000 min. p&p. Quantity discounts negotiable.

TRY US NOW - WE'VE GOT WHAT YOU NEED.

<p><b>RESISTORS</b></p> <p><b>CARBON FILM</b> 5% HI-STAR LOW NOISE 100 to 10MΩ 1/4W E24 2p 1/4W E24 2 1/2p 1W E12 6p 2W E12 12p</p> <p><b>METAL FILM</b> ULTRA STABLE 0.4W EXTRA LOW NOISE 100 to 1MΩ 2 1/2 E24 5p 1 1/2 E24 5p</p> <p><b>LOW OHMIC</b> GLAZE 1/4W 0.22Ω to 9.2Ω E24 11p</p> <p><b>WIREWOUND</b> E1 SERIES 0.2 to 3 WATT 2 to 7 WATT 0.4 to 0.68 33p 10 to 11 WATT 1/2 to 33Ω 37p</p> <p><b>POTS &amp; PRESETS</b></p> <p><b>ROTARY POTS</b> LOW NOISE E3 SERIES 4K7 to 2M LIN 32p 4K7 to 2M 32p As above with DP means Switch 79p As above stereo (no switch) 89p</p> <p><b>PRE SETS P1HER</b> (DUSTPROOF) E3 SERIES Mini Vertical 15p Mini Horizontal 15p Standard Vert 16p Standard Horiz 18p</p> <p><b>CERMET 20</b> TURN PRECISION PRE SETS X3 Series 50Ω to 500K 89p</p> <p><b>CAPACITORS</b></p> <p><b>CERAMIC 100V</b> DISC (PLATE) E12 MICRO MINI typically -5% 7p</p> <p><b>POLYCARB 5%</b> SIEMENS 7.5mm MINI-BLOC E12 250V 100mA 95p 1A 2.65</p> <p><b>1nF to 6nF</b> 7p <b>8nF to 47nF</b> 8p <b>50nF to 150nF</b> 10p <b>100nF to 150nF</b> 10p <b>100nF to 270nF</b> 12p <b>180nF to 270nF</b> 12p <b>470nF to 550nF</b> 20p <b>680nF</b> 26p <b>1µF (10mm)</b> 35p</p> <p><b>POLYESTER</b> 250V RADIAL (C280) 10nF - 15nF 22p 33nF - 47nF 89p 100nF - 150nF 10p 150nF - 220nF 13p 330nF - 470nF 13p 680nF 18p 1µF 22p 1µF 33p</p> <p><b>FILM</b> VO BOARD 1.92 100 Pins 55p Track Cutter 1.48 22 swg 3.10</p> <p><b>HIGH VOLTAGE</b> Capacitors please enquire many types in stock</p> <p><b>TANT BEADS</b> 1.35V 14p 2.2 35V 14p 33 35V 14p 47 35V 14p 88 35V 14p 10 35V 14p 2.2 35V 14p 3.3 35V 18p 4.7 16V 18p 6.8 25V 20p 6.8 25V 21p 10 16V 18p 10 35V 27p 15 10V 22p 15 10V 30p 15 10V 30p 15 25V 32p 22 16V 29p 22 16V 29p 33 10V 30p 47 3V 14p 47 3V 34p 47 16V 39p 100 13V 32p 100 10V 55p</p> <p><b>ELECTROLYTICS</b> Mainly Matsushita Siemens Panasonic etc 420 - 245mm 195p</p> <p><b>AXIALS</b> (wires each end) µF V 47 100 9p 47 300 9p 1 83 8p 1 100 8p 1 500 40p 2.2 25 8p 2.2 63 9p</p>	<p>Single sided 100 x 160 1.55 100 x 220 1.90 203 x 114 1.85 233 x 220 3.99</p> <p><b>Double sided</b> 100 x 160 1.55 100 x 220 2.18 203 x 114 2.21 233 x 220 4.55</p> <p>Developers for above (do not use Silicon Hydroxide) 2N3054 120p 2N3250 36p 2N3251 36p 2N3439 27p 2N3440 80p 2N3441 1.25 2N3442 1.95 2N3443 1.95 2N3444 4.80 2N3445 5.72 2N3446 5.72 2N3447 5.72 2N3448 3.90 2N3449 1.06 2N3450 1.06 2N3638 55p 2N3638A 70p 2N3702 10p 2N3703 10p 2N3704 10p 2N3705 10p 2N3706 10p 2N3707 44p 2N3708 10p 2N3709 10p 2N3710 10p 2N3711 10p 2N3712 2.00 2N3713 1.38 2N3714 3.31 2N3715 3.31 2N3716 3.60 2N3717 3.60 2N3718 3.60 2N3719 3.60 2N3720 3.60 2N3721 3.60 2N3722 3.60 2N3723 3.60 2N3724 3.60 2N3725 3.60 2N3726 3.60 2N3727 3.60 2N3728 3.60 2N3729 3.60 2N3730 3.60 2N3731 3.60 2N3732 3.60 2N3733 3.60 2N3734 3.60 2N3735 3.60 2N3736 3.60 2N3737 3.60 2N3738 3.60 2N3739 3.60 2N3740 3.60 2N3741 3.60 2N3742 3.60 2N3743 3.60 2N3744 3.60 2N3745 3.60 2N3746 3.60 2N3747 3.60 2N3748 3.60 2N3749 3.60 2N3750 3.60 2N3751 3.60 2N3752 3.60 2N3753 3.60 2N3754 3.60 2N3755 3.60 2N3756 3.60 2N3757 3.60 2N3758 3.60 2N3759 3.60 2N3760 3.60 2N3761 3.60 2N3762 3.60 2N3763 3.60 2N3764 3.60 2N3765 3.60 2N3766 3.60 2N3767 3.60 2N3768 3.60 2N3769 3.60 2N3770 3.60 2N3771 3.60 2N3772 3.60 2N3773 3.60 2N3774 3.60 2N3775 3.60 2N3776 3.60 2N3777 3.60 2N3778 3.60 2N3779 3.60 2N3780 3.60 2N3781 3.60 2N3782 3.60 2N3783 3.60 2N3784 3.60 2N3785 3.60 2N3786 3.60 2N3787 3.60 2N3788 3.60 2N3789 3.60 2N3790 3.60 2N3791 3.60 2N3792 3.60 2N3793 3.60 2N3794 3.60 2N3795 3.60 2N3796 3.60 2N3797 3.60 2N3798 3.60 2N3799 3.60 2N3800 3.60 2N3801 3.60 2N3802 3.60 2N3803 3.60 2N3804 3.60 2N3805 3.60 2N3806 3.60 2N3807 3.60 2N3808 3.60 2N3809 3.60 2N3810 3.60 2N3811 3.60 2N3812 3.60 2N3813 3.60 2N3814 3.60 2N3815 3.60 2N3816 3.60 2N3817 3.60 2N3818 3.60 2N3819 3.60 2N3820 3.60 2N3821 3.60 2N3822 3.60 2N3823 3.60 2N3824 3.60 2N3825 3.60 2N3826 3.60 2N3827 3.60 2N3828 3.60 2N3829 3.60 2N3830 3.60 2N3831 3.60 2N3832 3.60 2N3833 3.60 2N3834 3.60 2N3835 3.60 2N3836 3.60 2N3837 3.60 2N3838 3.60 2N3839 3.60 2N3840 3.60 2N3841 3.60 2N3842 3.60 2N3843 3.60 2N3844 3.60 2N3845 3.60 2N3846 3.60 2N3847 3.60 2N3848 3.60 2N3849 3.60 2N3850 3.60 2N3851 3.60 2N3852 3.60 2N3853 3.60 2N3854 3.60 2N3855 3.60 2N3856 3.60 2N3857 3.60 2N3858 3.60 2N3859 3.60 2N3860 3.60 2N3861 3.60 2N3862 3.60 2N3863 3.60 2N3864 3.60 2N3865 3.60 2N3866 3.60 2N3867 3.60 2N3868 3.60 2N3869 3.60 2N3870 3.60 2N3871 3.60 2N3872 3.60 2N3873 3.60 2N3874 3.60 2N3875 3.60 2N3876 3.60 2N3877 3.60 2N3878 3.60 2N3879 3.60 2N3880 3.60 2N3881 3.60 2N3882 3.60 2N3883 3.60 2N3884 3.60 2N3885 3.60 2N3886 3.60 2N3887 3.60 2N3888 3.60 2N3889 3.60 2N3890 3.60 2N3891 3.60 2N3892 3.60 2N3893 3.60 2N3894 3.60 2N3895 3.60 2N3896 3.60 2N3897 3.60 2N3898 3.60 2N3899 3.60 2N3900 3.60 2N3901 3.60 2N3902 3.60 2N3903 3.60 2N3904 3.60 2N3905 3.60 2N3906 3.60 2N3907 3.60 2N3908 3.60 2N3909 3.60 2N3910 3.60 2N3911 3.60 2N3912 3.60 2N3913 3.60 2N3914 3.60 2N3915 3.60 2N3916 3.60 2N3917 3.60 2N3918 3.60 2N3919 3.60 2N3920 3.60 2N3921 3.60 2N3922 3.60 2N3923 3.60 2N3924 3.60 2N3925 3.60 2N3926 3.60 2N3927 3.60 2N3928 3.60 2N3929 3.60 2N3930 3.60 2N3931 3.60 2N3932 3.60 2N3933 3.60 2N3934 3.60 2N3935 3.60 2N3936 3.60 2N3937 3.60 2N3938 3.60 2N3939 3.60 2N3940 3.60 2N3941 3.60 2N3942 3.60 2N3943 3.60 2N3944 3.60 2N3945 3.60 2N3946 3.60 2N3947 3.60 2N3948 3.60 2N3949 3.60 2N3950 3.60 2N3951 3.60 2N3952 3.60 2N3953 3.60 2N3954 3.60 2N3955 3.60 2N3956 3.60 2N3957 3.60 2N3958 3.60 2N3959 3.60 2N3960 3.60 2N3961 3.60 2N3962 3.60 2N3963 3.60 2N3964 3.60 2N3965 3.60 2N3966 3.60 2N3967 3.60 2N3968 3.60 2N3969 3.60 2N3970 3.60 2N3971 3.60 2N3972 3.60 2N3973 3.60 2N3974 3.60 2N3975 3.60 2N3976 3.60 2N3977 3.60 2N3978 3.60 2N3979 3.60 2N3980 3.60 2N3981 3.60 2N3982 3.60 2N3983 3.60 2N3984 3.60 2N3985 3.60 2N3986 3.60 2N3987 3.60 2N3988 3.60 2N3989 3.60 2N3990 3.60 2N3991 3.60 2N3992 3.60 2N3993 3.60 2N3994 3.60 2N3995 3.60 2N3996 3.60 2N3997 3.60 2N3998 3.60 2N3999 3.60 2N4000 3.60</p>	<p>4041 2.85 4042 90p 4043 90p 4044 90p 4045 90p 4046 90p 4047 90p 4048 90p 4049 90p 4050 90p 4051 90p 4052 90p 4053 90p 4054 90p 4055 90p 4056 90p 4057 90p 4058 90p 4059 90p 4060 90p 4061 90p 4062 90p 4063 90p 4064 90p 4065 90p 4066 90p 4067 90p 4068 90p 4069 90p 4070 90p 4071 90p 4072 90p 4073 90p 4074 90p 4075 90p 4076 90p 4077 90p 4078 90p 4079 90p 4080 90p 4081 90p 4082 90p 4083 90p 4084 90p 4085 90p 4086 90p 4087 90p 4088 90p 4089 90p 4090 90p 4091 90p 4092 90p 4093 90p 4094 90p 4095 90p 4096 90p 4097 90p 4098 90p 4099 90p 4100 90p 4101 90p 4102 90p 4103 90p 4104 90p 4105 90p 4106 90p 4107 90p 4108 90p 4109 90p 4110 90p 4111 90p 4112 90p 4113 90p 4114 90p 4115 90p 4116 90p 4117 90p 4118 90p 4119 90p 4120 90p 4121 90p 4122 90p 4123 90p 4124 90p 4125 90p 4126 90p 4127 90p 4128 90p 4129 90p 4130 90p 4131 90p 4132 90p 4133 90p 4134 90p 4135 90p 4136 90p 4137 90p 4138 90p 4139 90p 4140 90p 4141 90p 4142 90p 4143 90p 4144 90p 4145 90p 4146 90p 4147 90p 4148 90p 4149 90p 4150 90p 4151 90p 4152 90p 4153 90p 4154 90p 4155 90p 4156 90p 4157 90p 4158 90p 4159 90p 4160 90p 4161 90p 4162 90p 4163 90p 4164 90p 4165 90p 4166 90p 4167 90p 4168 90p 4169 90p 4170 90p 4171 90p 4172 90p 4173 90p 4174 90p 4175 90p 4176 90p 4177 90p 4178 90p 4179 90p 4180 90p 4181 90p 4182 90p 4183 90p 4184 90p 4185 90p 4186 90p 4187 90p 4188 90p 4189 90p 4190 90p 4191 90p 4192 90p 4193 90p 4194 90p 4195 90p 4196 90p 4197 90p 4198 90p 4199 90p 4200 90p</p>	<p>BC547A 14p BC547B 14p BC548 12p BC549 13p BC548B 15p BC548C 15p BC549A 15p BC549B 15p BC549C 15p BC550 15p BC550C 25p BC551 15p BC551B 16p BC551C 16p BC552 14p BC552A 14p BC552B 14p BC552C 14p BC553 14p BC553A 14p BC553B 14p BC553C 14p BC554 14p BC554A 14p BC554B 14p BC554C 14p BC555 14p BC555A 14p BC555B 14p BC555C 14p BC556 14p BC556A 14p BC556B 14p BC556C 14p BC557 14p BC557A 14p BC557B 14p BC557C 14p BC558 14p BC558A 14p BC558B 14p BC558C 14p BC559 14p BC559A 14p BC559B 14p BC559C 14p BC560 14p BC560A 14p BC560B 14p BC560C 14p BC561 45p BC561A 45p BC561B 45p BC561C 45p BC562 14p BC562A 14p BC562B 14p BC562C 14p BC563 14p BC563A 14p BC563B 14p BC563C 14p BC564 14p BC564A 14p BC564B 14p BC564C 14p BC565 14p BC565A 14p BC565B 14p BC565C 14p BC566 14p BC566A 14p BC566B 14p BC566C 14p BC567 14p BC567A 14p BC567B 14p BC567C 14p BC568 14p BC568A 14p BC568B 14p BC568C 14p BC569 14p BC569A 14p BC569B 14p BC569C 14p BC570 14p BC570A 14p BC570B 14p BC570C 14p BC571 14p BC571A 14p BC571B 14p BC571C 14p BC572 14p BC572A 14p BC572B 14p BC572C 14p BC573 14p BC573A 14p BC573B 14p BC573C 14p BC574 14p BC574A 14p BC574B 14p BC574C 14p BC575 14p BC575A 14p BC575B 14p BC575C 14p BC576 14p BC576A 14p BC576B 14p BC576C 14p BC577 14p BC577A 14p BC577B 14p BC577C 14p BC578 14p BC578A 14p BC578B 14p BC578C 14p BC579 14p BC579A 14p BC579B 14p BC579C 14p BC580 14p BC580A 14p BC580B 14p BC580C 14p BC581 14p BC581A 14p BC581B 14p BC581C 14p BC582 14p BC582A 14p BC582B 14p BC582C 14p BC583 14p BC583A 14p BC583B 14p BC583C 14p BC584 14p BC584A 14p BC584B 14p BC584C 14p BC585 14p BC585A 14p BC585B 14p BC585C 14p BC586 14p BC586A 14p BC586B 14p BC586C 14p BC587 14p BC587A 14p BC587B 14p BC587C 14p BC588 14p BC588A 14p BC588B 14p BC588C 14p BC589 14p BC589A 14p BC589B 14p BC589C 14p BC590 14p BC590A 14p BC590B 14p BC590C 14p BC591 14p BC591A 14p BC591B 14p BC591C 14p BC592 14p BC592A 14p BC592B 14p BC592C 14p BC593 14p BC593A 14p BC593B 14p BC593C 14p BC594 14p BC594A 14p BC594B 14p BC594C 14p BC595 14p BC595A 14p BC595B 14p BC595C 14p BC596 14p BC596A 14p BC596B 14p BC596C 14p BC597 14p BC597A 14p BC597B 14p BC597C 14p BC598 14p BC598A 14p BC598B 14p BC598C 14p BC599 14p BC599A 14p BC599B 14p BC599C 14p BC600 14p BC600A 14p BC600B 14p BC600C 14p BC601 14p BC601A 14p BC601B 14p BC601C 14p BC602 14p BC602A 14p BC602B 14p BC602C 14p BC603 14p BC603A 14p BC603B 14p BC603C 14p BC604 14p BC604A 14p BC604B 14p BC604C 14p BC605 14p BC605A 14p BC605B 14p BC605C 14p BC606 14p BC606A 14p BC606B 14p BC606C 14p BC607 14p BC607A 14p BC607B 14p BC607C 14</p>
--	--	---	---

# THE Northern Computer Fair

Personal computers  
Home computing  
Small business systems

Sponsored by:

Practical Computing and YOUR COMPUTER



## The right place . . . . . The right time

Following the overwhelming success of the 1982 Northern Computer Fair, the sponsors announce that an even bigger and better show will be held again this year at Belle Vue, Manchester from November 24th-26th

This is the North's premier exhibition for the rapidly expanding home and small business computer market, mounted at a time now recognised as a peak buying period for this type of equipment. It is now one of a nationwide series of exhibitions designed to attract the broadest possible cross-section of both home computer enthusiasts and the rapidly increasing body of personal computer users found throughout business and the professions.

Make a date for Belle Vue, Manchester, November 24-26, 1983, and post the coupon below for more details.

Belle Vue, Manchester, November 24-26, 1983.

THE Northern Computer Fair  
Personal computers  
Home computing  
Small business systems

The Exhibition Manager, Northern Computer Fair, Reed Exhibitions, Surrey House, 1 Throwley Way, Sutton, Surrey SM1 4QQ

I am interested in exhibiting.

Name \_\_\_\_\_  
Position \_\_\_\_\_  
Company \_\_\_\_\_  
Address \_\_\_\_\_  
Telephone \_\_\_\_\_

# If you can buy it cheaper we'll refund the difference.\*

This month's offer is another winner — a consignment of 14" R.G.B. colour monitors manufactured by J.V.C. — at prices never seen before in the U.K. Suitable for use with BBC Micro,

Lynx, Oric, Apple II, Apple III and IBM etc. It's safe to put a cheque in the post today. Because, if you find someone who's cheaper, we'll refund the difference.

## RGB MEDIUM RES £199.00


Resolution, 370 x 235 Pixels.  
Display, 80 characters x 25 lines. Slot Pitch 63mm.  
Input, Video — RGB Analogue with TTL input.  
SYNC — Separate SYNC on RGB. Features, On/Off switch with pilot light. Brightness control.  
Power 220/240V 50/60HZ.

## RGB HIGH RES £299.00

Resolution, 580 x 235 Pixels.  
Display, 80 characters x 25 lines. Slot pitch 41mm.  
Input, Video — RGB Analogue with TTL input  
SYNC — Separate SYNC ON RGB.  
Features, On/Off switch with pilot light.  
Brightness control. Power, 220/240V 50/60HZ

## IBM COMPATIBLE £349.00

Spec as above with IBM Interface.



## TEAC DISC DRIVES

TEAC 55F — 5 1/4" D/S 80 track. Formatted single density 400K Double density 800K. **only £229.00**

Case to hold two drives with power supply and blanking plate. **only £39.95**

Ribbon lead to connect one drive to BBC. **£12.00**

Dual Ribbon lead **£15.00**

Power lead to connect one drive to BBC. **£5.00**

Ideal for use with BBC Micro. Full warranty. Low power consumption. Slimline latest technology. Switchable 40/80 track.

## CANON DISC DRIVES

MDD 6106 5 1/4" S/S 40 track. Formatted single density 100K. Double density 200K. **£129.95**

Case to hold single drive. **£9.95**

Leads as with TEAC DRIVES

## THE ORGANIZER DESK

At last a desk designed for the personal user. Full size desk. Suitable for all leading micros. On castors. Teak finish. DEALER ENQUIRIES INVITED. **only £49.50**

## DOG FIGHT

If you have a BBC 32K with any O.S. become a flying ace with our wonderful new game Dogfight. An exciting 2 player game with 8 levels of difficulty. **only £8.65**

## 12" GREEN SCREEN MONITOR

One year warranty, ex stock delivery, 18 MHZ, Phono connector. Limited quantity. **only £69.95**

Lead to connect to BBC **£5.95**

## NASHUA FLOPPY DISCS

Minis	8" Discs
S/S S/D £16.95 for 10	S/S S/D £17.95 for 10
S/S D/D £19.95 for 10	S/S D/D £23.95 for 10
D/S D/D £22.95 for 10	D/S D/D £24.95 for 10
S/S 80 Track £24.95 for 10	
D/S 80 Track £26.95 for 10	

With full 5 year warranty. All mini discs have hub rings and a FREE plastic library case.

## 8" DISC DRIVES SHUGART COMPATIBLE

FD514 S/S Dual density. Formatted 600K Byte **only £149.00**

FD650 D/S Dual density. Formatted 1.2M Byte **only £199.50**

Pertec 90 day warranty.

Case to hold 2 drives — complete with power supply and fan. **only £99.95**

## VIEW DATA TERMINALS

Prestel, Built in modem. G.P.O. approved, slimline design. **only £199.00**

\*Our price pledge only applies to the JVC monitor

To order: Add carriage at the following rates: — Discs 85p. Other goods £7.00. Add VAT at 15% to total and send your order to:

# OPUS SUPPLIES

158, Camberwell Road, London SE5 0EE  
Tel: 01-701-8668 (3 lines) 01-703-6155/6/7



Government and educational orders welcome.




WW - 058 FOR FURTHER DETAILS





# MARK 1983 WITH GAPS IN CIRCUIT FILES WELL-PLUGGED

**WIRELESS WORLD CIRCARDS** last year benefited many 'new generation' readers who bought at 1976 bargain prices + 10% discount for 10 sets!  
**Most sets are still available although companion volumes CIRCUIT DESIGNS 1, 2 and 3 are out of print (CIRCARDS sets 1 to 30).**



**The Offer stands, so order now your sets of 127 x 204mm cards in plastic wallets. These unique circuit cards normally contain descriptions and performance data of 10 tested circuits, together with ideas for modifying them to suit special needs.**

- 1 Basic Active filters 2 Switching Circuits, comparators and Schmitts (But these gaps cannot be filled) \*  
 6 Constant current circuits 7 Power amplifiers 8 Astable circuits 9 Optoelectronics 10 Micro power circuits 11 Basic logic gates 12 Wideband amplifiers 13 Alarm circuits 14 Digital Counters 15 Pulse modulators 16 Current differencing amplifiers - signal processing 17 Current differencing amplifiers - signal generation 18 Current differencing amplifiers - measurement and detection 19 Monostable circuits 20 Transistor pairs 21 Voltage-to-frequency converters 22 Amplitude modulation and detection 23 Reference circuits 24 Voltage regulators 25 RC oscillators - 1 26 RC oscillators - 2 27 Linear cmos - 1 28 Linear cmos - 2 29 Analogue multipliers 30 Rms/log/power laws 31 Digital multipliers 32 Transistor arrays 33 Differential and bridge amplifiers 34 Analogue gate applications - 1 35 Analogue gate applications - 2.

\*Photocopies only: 3 Waveform generators 4A.C. measurement 5 Audio circuits @ £3.20 each set.

**To Electrical-Electronic Press  
 General Sales Department  
 Room 108  
 Quadrant House  
 Sutton  
 Surrey SM2 5AS**

**Company Registered Number: 151537 (ENGLAND).  
 Registered Office: Quadrant House, The Quadrant  
 Sutton, Surrey SM2 5AS**

Please send me the following sets of  
 Circards.....£2 each,  
 £18 for 10 post free.  
 Remittance enclosed ..... payable  
 to **BUSINESS PRESS INTERNATIONAL LIMITED**  
 Name (Please print) .....  
 Address (Please print).....

## Superior Quality Precision Made NEW POWER RHEOSTATS

New ceramic construction, heavy duty brush assembly, continuously rated.  
**25 WATT** 5/10/25/50/100/250/500/1kΩ/1.5kΩ £3.10 + 30p p&p (£3.91 inc. VAT)  
**50 WATT** 25Ω £5.50 + 50p p&p (£6.90 inc. VAT)  
**100 WATT** 1/5/10/25/50/100/250/500/1kΩ/1.5kΩ/2.5kΩ/3.5kΩ £7.25 + 75p p&p (£8.20 inc. VAT)  
**Black Silver Skirted Knob** calibrated in Nos. 1-9, 1 1/2in dia. brass bush. Ideal for above Rheostats 30p ea. + VAT.

**SOLID STATE E.H.T. UNIT**  
 Input 230V A.C. Fully isolated. Approx. 15kV. Built-in 10 sec. Timer. Easily modified for 20 sec. 30 sec. to continuous operation. Size 155x85x50mm. Price £5 + 75p p&p (Total inc. VAT £6.61).

**240V A.C. SOLENOID VALVE**  
 Designed for Air/Gas at 0-7. Water 5 psi. Inlet/outlet 3/8". Forged brass body. Manuf. Dewaswitch Asco. Price: £5.80 + £1 p&p (£7.48 inc. VAT). N.M.S.

**METERS (New) - 90mm DIAMETER**  
 AC Volt. 0-300V, 0-150V.  
 AC Amp. Type E2T2, 0, 1A, 0-5A.  
 DC Volt. 0-50V, 0-100V, 0-10A, 0-50A, 0-100A. DC Volt 30V. All types £2.60 ea. + p&p 75p (£5.00 inc. VAT) except 0-50A DC, 0-100A DC. Price £6.00 + 75p p&p (£7.75 inc. VAT).

**ULTRA VIOLET BLACK LIGHT FLUORESCENT TUBES**  
 4ft 40 watt £8.70 inc. VAT £10.00 (callers only).  
 2ft 20 watts £5.20. Post £1.25 (£8.57 inc. VAT & p&p).

(For use in standard bi-pin fittings).  
 12in 8 watt £3.00. + 45p (£3.97 inc. VAT p&p).  
 9in 6 watt £2.50. + 45p (£3.39 inc. VAT p&p).  
 6in 4 watt £2.50. + 45p (£3.39 inc. VAT p&p).  
 Complete ballast unit for either 6V, 8V or 12V tube 230V AC op. £5.50 Post 55p (£6.96 inc. VAT p&p). Also available for 12V DC £5.50 Post 55p (£6.96 inc. VAT p&p).

**BLACK LIGHT BULBS**  
 Self-ballasted Mercury U.V. 175W Bulbs. Available for either B.C. or E.S. fitting. Price £11.79 incl. p&p and VAT.  
 12in 8 watt £3.00. + 45p (£3.97 inc. VAT p&p).  
 400W UV LAMP AND BALLAST complete £38.00 post £3.50 (£47.73 inc. VAT & p&p). 400W UV LAMP only £14.00 post £2.00 (£18.40 inc. VAT & p&p).

**VORTEX BLOWER & SUCTION UNIT**  
 Powerful multi-stage dynamically balanced, totally enclosed, 9" dia. Rotators. 3500 rpm. 1 1/2" I.D. Inlet and outlet. 110V A.C. Price £20.00. Suitable transformer for 240V A.C. £5.00 + £3.00 p&p (total incl. VAT £32.20)

Quiet smooth-running **COOLING** or **EXTRACTOR FAN**. Size: 454x304x112. Supplied for 240V A.C. operation. Price £4.75 + £1 p&p (total incl. VAT £6.62).

**FROM STOCK AT PRICES THAT DEFY COMPETITION!**  
 AC GEARED MOTORS  
 DC MOTORS  
 MICROSWITCHES  
 RELAYS  
 REED SWITCHES  
 SOLENOIDS A.C. or D.C.  
 PROGRAMME TIMERS

## VARIABLE VOLTAGE TRANSFORMERS

INPUT 230/240V a.c. 50/60	OUTPUT 0-260V
200W 1 amp inc. a.c. voltage	£15.00
0.5 KVA (2 1/2 amp MAX)	£19.00
1 KVA (5 amp MAX)	£25.00
2 KVA (10 amp MAX)	£41.00
3 KVA (15 amp MAX)	£49.00
5 KVA (25 amp MAX)	£79.00
10 KVA (50 amp MAX)	£174.00
15 KVA (75 amp MAX)	£270.00

**3-PHASE VARIABLE VOLTAGE TRANSFORMERS**  
 Dual input 200-240V or 380-415V. Star connected  
 3 KVA 5 amp per phase max £13.40  
 6 KVA 10 amp per phase max £170.10  
 10 KVA 16 amp per phase max £245.45

**Comprehensive range of L.T., AUTO (110-240V), ISOLATION TRANSFORMERS** available for immediate delivery. Leaflet on request.

**EPROM ERASURE KIT**  
 Why waste money? Build your own EPROM ERASURE for a fraction of the price of a made-up unit. Complete kit of parts less case, to include 12" 8 watt 2537 Angstrom Tube. Ballast unit, pair of bi-pin leads. Neon indicator, safety microswitch, on/off switch and circuit.  
 LESS CASE. Price: £13.60 + 75p p&p (Total incl. VAT £16.50).  
 Warning: Tube used in this circuit is highly dangerous to the eyes. Unit MUST be fitted in suitable case.

**FROM STOCK AT PRICES THAT DEFY COMPETITION!**  
 C.F. BLOWERS  
 AC CAPACITORS  
 STROBE KITS  
 FLASHTUBES  
 CONTACTORS  
 SYNCHRONOUS MOTORS

**PHONE IN YOUR ENQUIRIES**  
 Stockists for Finnigans Hammerite paint and Waxoyl products

**SERVICE TRADING CO**  
 57 BRIDGMAN ROAD, CHISWICK, LONDON W4 5BB, 01-995 1560  
 ACCOUNT CUSTOMERS MIN. ORDER £10

WW-035 FOR FURTHER DETAILS

## GEARED MOTORS

5rpm 240V A.C. Mt. by Carter. £6.05 £1 p&p (£8.11 inc. VAT)  
 7 1/2rpm Motor approx 30lb in. 110V A.C. complete with Transformer for 240V A.C. £10.75 + £1.50 p&p (total inc. VAT £14.09)  
 71rpm WYNSCALE motor approx. 10lb in. A.C. supplied with auto transformer 240V. A.C. operation. £10.75 p&p £1.50 (£14.09 inc. VAT). N.M.S.  
 CROWN 42 rpm 110/230V A.C. 50 Hz. 100 lb.in. approx. reversible geared Motor. Price £18.15 + £2.50 p&p (total incl. VAT £23.75)  
 38.3 rpm GEARED MOTOR. Torque 35lb.in. reversible 115V AC inc. start capacitor. Price £11.55 + £2 p&p (total incl. VAT £15.58) N.M.S.  
 Suitable TRANSFORMER 230V A.C. operation. Price £4.50 + 50p p&p (total incl. VAT £5.75).

**N.E.C. GEARED MOTOR** 152 rpm. 200lb.in. 230V A.C. 50Hz. Ratio 9.2 to 1. Non reverse. Incl. capacitors. Fraction of maker's price. £41.25 + Carr + VAT. N.M.S.

**INDUSTRIAL STROBE KIT**  
 Ideal for Industrial and Educational purposes. Produces high intensity flash variable from approx. 1 to 70 f.p.s. Price less case £27 + £2 p&p (total incl. VAT £33.36)

**HY-LYGT Mk V**. Designed for Disco, Theatrical uses, etc. Approx. 4 joules. Adjustable speed. Price £27 + £2 p&p (Total incl. VAT £33.36). Case and reflector price £12.50 + £2 p&p (total incl. VAT £16.68). Footscap SAE for further details including Super Hy-Lyght. Suitable case and reflector for either of above kits, price: £12.50 + £2 p&p (total incl. VAT £16.68).

**COMPRESSOR**  
 Thomas single diaphragm. Max. 20 psi. 1 1/4" cfm., approx. 110V A.C. £16 + £2 p&p (total incl. VAT £20.70). OR, to include Transformer for 230/240V A.C. £26.45 incl. VAT.

**BLOWER/VACUUM PUMP**  
 3 phase A.C. motor 220/250V or 380/440V. 1.425 rpm, 1/8 h.p. cont. Direct coupled to William Allday Alcosa carbon vane blower/vacuum pump. 0.9 cfm 8hg. £22 + £4 p&p (total incl. VAT £29.90).

**INSULATION TESTERS NEW**  
 500 VOLTS 500 megohms £49 p&p £2. (£58.65 inc. VAT & p&p).  
 1000 VOLTS 1000V 555 p&p £2 (£65.55 inc. VAT & p&p). SAE for leaflet.

**SANGAMO WESTON TIME SWITCH**  
 Type S251 200/250 AC 2 on/2 off every 24 hours. 20 amps contacts with override switch. Diameter 4" x 3", price £9.50 + £1.50 p&p (£12.65 inc. VAT & p&p). Also available with solar dia. R&T. Also available Sangamo Weston 60 amp and AEG 80 amp. Phone for details.  
 Type S288 1 on, or 1 timed c/o every 24 hours. dual omitting device. Price £11 + £1 p&p (£13.80 incl. VAT). N.M.S.  
 Type S388. As above, plus 36 hours spring reserve. Less perspex cover. Price: £13 + £1 p&p (£16.10 incl. VAT). N.M.S.

N.M.S. - New Manufacturers' Surplus.  
 R&T - Reconditioned and Tested.  
 Personal callers only. Open Saturdays  
**9 Little Newport Street  
 London WC2H 7JJ  
 Tel: 01-437 0576**

## LOW COST PROFESSIONAL TEST INSTRUMENTS

Digit 9

- ★ FREQUENCY COUNTERS
- ★ ANALOGUE METERS
- ★ DIGITAL METERS
- ★ FUNCTION GEN
- ★ OSCILLOSCOPES
- ★ POWER SUPPLIES
- ★ LOGIC PROBE
- ★ SCOPE PROBES

**BLACK STAR LTD.**  
 9A, Crown Street, St.Ives,  
 Huntingdon, Cambs. PE17 4EB.  
 Tel: (0480) 62440 Telex: 32339

WW-008 FOR FURTHER DETAILS

### ELECTRONIC SOFTWARE LINEAR CIRCUIT ANALYSIS

An all-machine code program for the rapid analysis of linear electronic circuits that may contain active and/or passive components. Capacity 20 nodes, 40 passive components, 10 active sources. Components may be R, L, C, transformer, transmission line, transistor, FET, Op-amp, etc. Handles complex source and load impedances and complex active sources. Simple rapid component or parameter value changes. Draws graphs with LOG/LIN/DB scales as required. Hardcopy of all results.  
 For PET/CBM 3000/4000/8000 series ONLY. State model, tape, disc. Price £120 inclusive (no V.A.T.).  
 The following programs are written in Basic and are available for CBM/BBC/Apple.  
 Price £40 each inclusive (no V.A.T.). State model, disc or tape.  
 VHF/UHF AMPLIFIER DESIGN: S parameters, stripline or discrete  
 TRANSISTOR PARAMETER CONVERSIONS: S, h, z to y, any configuration  
 DESIGN OF ACTIVE FILTERS: Butterworth, Chebyshev, any no. of poles  
 DESIGN OF LOSSLESS MATCHING NETWORKS: Complex to resistive

Full details on request  
**S. J. BRANSON, 111 PARK ROAD, PETERBOROUGH - Tel: 0733 67804**

WW-063 FOR FURTHER DETAILS

### Modem Kit Only £39.95

- ★ CCITT standard
- ★ 300 baud full duplex
- ★ Direct connection - greatly reduces data loss associated with acoustic couplers
- ★ Powered from phone lines therefore no power supply required
- ★ Opto coupled data in and data out for intrinsically safe operation.

Build it yourself for £39.95 including VAT and postage (note - case not included).

**Racom Ltd., Dept. B  
 81 Cholmeley Road, Reading, Berks RG1 3LY  
 Tel: 0734 67027**

WW-049 FOR FURTHER DETAILS



# Appointments

Advertisements accepted up to 12 noon Tuesday, August 2nd, for September issue, subject to space available.

DISPLAYED APPOINTMENTS VACANT: £17 per single col. centimetre (min. 3cm).  
LINE advertisements (run on): £3.50 per line, minimum £25 (prepayable).  
BOX NUMBERS: £5 extra. (Replies should be addressed to the Box Number in the advertisement, c/o Quadrant House, The Quadrant, Sutton, Surrey SM2 5AS).  
PHONE: IAN FAUX, 01-661 3033 (DIRECT LINE)  
*Cheques and Postal Orders payable to BUSINESS PRESS INTERNATIONAL LTD. and crossed.*



## ALWAYS AHEAD WITH THE BEST!

£5,000-£18,000

- ★ **Where does your interest lie:** Communications; Computers; Weapons; Radar; Sonar; Data-Comms; Signal Processing; Medical; Telemetry; Simulation; Satcom; Local Area Nets; ATE?
- ★ **Experienced in:** Mini/Microprocessor Hardware or Software; Digital and Analogue circuitry; RF and Microwave techniques?
- ★ **There are opportunities in:** Design; Test; Sales and Service for Engineers and Managers.
- ★ **Act now:** Just dial 100 and ask for FREEFONE JOBLINE or send your c.v. to:

**ELECTRONIC COMPUTER AND MANAGEMENT APPOINTMENTS LIMITED**  
Freeport, Barkway, Royston, Herts SG8 8BR

(1926)

Metropolitan Police Office

## Telecommunication Officer

The Command and Control Computer System provides the Metropolitan Police with a message switching system and is used for the efficient handling of emergency calls and the use of Police resources.

The successful candidate will control and co-ordinate the activities of the shift computer and network operation personnel: control and direct the operations shift support officer with particular regard to recovery and back-up procedures and services to the Force Training School at Hendon; correlate system performance data and prepare computer systems performance reports, including recommendation for action to improve system performance.

Candidates must have TEC Higher or SCOTEC Higher Certificate in Electronics, Telecommunications or similar discipline: OR C&G Full Technological Technicians Certificates Parts I, II and III in Telecommunications: OR HNC in Electrical/Electronic Engineering: OR an equivalent or higher acceptable qualification. All candidates must have had appropriate training and should normally have 10 years experience of computer operations and telecommunications. Knowledge of Sperry Univac 1100 series machines advantageous. Senior ex-service personnel with TEC/SCOTEC/C&G recognised exemptions will also be considered.

Starting salary £9340 rising to £10800. In addition this post attracts £1250 Inner London Weighting. Promotion prospects.

RELOCATION ASSISTANCE MAY BE AVAILABLE.

For further details and an application form (to be returned by 12 August 1983) write to Civil Service Commission, Alencon Link, Basingstoke, Hants, RG21 1JB, or telephone Basingstoke (0256) 68551 (answering service operates outside office hours). Please quote ref: T/6012.

SEVERN TRENT WATER AUTHORITY

## Senior Communications Engineer

£9,033-£9,999 p.a.

## Communications Engineer

£8,154-£9,033 p.a.

The Authority is currently installing a regional network of microwave radio links to connect principal offices throughout its area. The network, which consists primarily of 1.5 GHz links, is used for both speech and data and is due for completion in August of this year.

The successful candidates should be qualified to HND/HNC level in Electronics/Electrical and are required to maintain and enhance radio, multiplex and other ancillary and terminal equipment associated with the system. Experience in the installation, commissioning and maintenance of a broad variety of electronic and electrical equipment is necessary. Both post holders will be required to undertake certain emergency repair duties outside normal office hours.

While the two posts are based in Finham on the southern outskirts of Coventry in the Avon Division both engineers will however, in the course of their duties, be required to travel extensively throughout the Authority's Region.

Application forms are available from the Personnel Office, Severn Trent Water Authority, Avon Division, Avon House, De-Montfort Way, Cannon Park, Coventry CV4 7EJ. Telephone: Coventry (0203) 416510.

Closing date for the return of application forms: 3 August, 1983.

(2199)

SEVERN TRENT WATER  
WIRELESS WORLD AUGUST 1983

# Electronic Test Engineers/Technicians

Racal Radar Defence Systems part of the Racal Electronics Group is undergoing a period of rapid growth. To meet our increasing production demands, we need to recruit a number of Test Technicians and Test Engineers at the following locations in Surrey - New Malden, Chessington and Hersham, and at Leicester.

The Company manufactures a wide range of products aimed principally at the Defence Industry including radar early warning and guidance systems, military displays and ECM and ESM systems.

The Test Department is responsible for the test and diagnostic functions on a wide range of complex radar equipment using high quality manual and automatic test equipment.

Applicants should be educated to HNC/HTC standard and have practical knowledge or experience of radar and/or microwave systems.

Conditions of employment are excellent including a competitive salary, five weeks holiday, and company pension and life assurance scheme.

Interested? Then phone me on: 01-397 5281 or alternatively write with brief details of qualification experience and current salary to:

Mr P N Willis,  
Senior Personnel Officer,  
Racal Radar Defence Systems Ltd.,  
Davis Road, Chessington, Surrey.

Racal's people are Racal's success



## FIELD SERVICE ENGINEER

LKB Instruments Limited, the UK subsidiary of a major international scientific instrument company is further expanding its range of products for the diagnostic clinical chemistry market and as a result a vacancy exists for a Field Service Engineer within their Customer Service Department.

Applicants should have a sound knowledge of digital and analogue electronics, and field service experience in clinical or medical instrumental diagnostics would be a distinct advantage.

The work involves the repair and maintenance of instrumentation situated mainly in Hospitals and University Laboratories. Preference will be given to applicants living in the London area.

Conditions of employment are excellent and in addition to a good basic salary and company car, the company has a profit-sharing scheme, BUPA participation and four weeks' annual holiday.

Contact Mrs. D. Duff, for Application Form



LKB INSTRUMENTS LIMITED  
232 Addington Road, Selsdon  
South Croydon, Surrey CR2 8YD

Tel: 01-651 5313

(2184)

WIRELESS WORLD AUGUST 1983

## RF SERVICE ENGINEER

We are responsible for all aspects of sales, service and warranty in Europe for the Plasma Therm range of RF generators, plasma processing equipment and inductively coupled plasma systems throughout UK, Europe and Scandinavia. The Plasma Therm product range is a market leader in its field and has an enviable track record of profitable growth and product innovation.

**THE JOB.** RF service engineer based in London to provide RF service and technical support throughout UK, Europe and Scandinavia. The candidate should be a self starter, willing and able to work on his own, and be able to trouble-shoot and solve problems in the field.

**REMUNERATION.** The right candidate will be offered an attractive financial package to include a performance-related bonus scheme, pension and a company car.

Applications and cvs should be addressed to:

Mr J. F. Stackhouse  
PLASMA THERM LTD.  
Kangley Bridge Road, Sydenham  
London SE26 5AR

(2156)

WIRELESS WORLD AUGUST 1983

## CUT THIS OUT!

Clip this advert and you can stop hunting for your next appointment. We have a wide selection of the best appointments in Digital, Analogue, RF, Microwave, Micro-processor, Computer, Data Comms and Medical Electronics and we're here to serve *your* interests. Call us now for posts in Design, Sales, Applications or Field Service, at all levels from £6,000-£16,000.



11 Westbourne Grove, London W2. Tel: 01-229 9239.

1935

Akai (UK) Limited, a leading name in the consumer electronic market, specialising in hi-fi and video products, now have the following vacancies at their Heathrow headquarters:

### VIDEO TECHNICIAN

As one of the leaders in the video market we are seeking a Video Technician, aged 25+ who is a fully qualified, experienced Television Engineer. Applicants will have some experience of repairing video recorders as this opportunity is in our busy in-house Servicing Department.

We work to high standards and need someone who will maintain them, as well as being self-motivated with the ability to handle technical queries both by telephone and letter.

### SENIOR AUDIO TECHNICIAN

The successful candidate will be fully qualified with some years experience in the servicing and repair of high quality hi-fi equipment. This will suit someone who is looking for a more supervisory position where duties will include the control of a small workshop, answering technical queries and dealing with the public, in addition to normal servicing work.

Communication skills both written and oral are necessary, as is the ability to cope with the pressure in this highly active department.

### AUDIO TECHNICIAN

Due to our ever increasing growth we now need another Audio Technician to join our servicing team. Applicants will be fully qualified and have some experience in the servicing and the repairing of high quality hi-fi equipment.

The above positions offer competitive, negotiable salaries on the basis of age and experience, an attractive benefits package and the opportunity of joining a Company that is progressive in its outlook.

Men and women interested should write or telephone for an application form to: (no agencies). (2208)

Pat Mann, AKAI (UK) Ltd., Haslemere Heathrow Estate, Parkway, Hounslow, Middlesex TW4 6NF. Telephone: 01-897 6388.




## E.L.A.C. REQUIRE AN ACOUSTIC ENGINEER

Electro Acoustic Industries Limited, a progressive and expanding Company, require an enthusiastic Engineer to assist in the development of loudspeakers for all purposes, covering a range from specialist telecomm. applications HiFi, M.O.D. Marine to 'In Car' entertainment. The successful candidate will be aged between 25 and 35 years and have had some practical experience in the design and application of test equipment. Experience in the use of Bruel & Kjaer frequency measuring equipment is particularly relevant.

Write including a C.V. to: MR. R. N. WALTON TECHNICAL DIRECTOR ELECTRO ACOUSTIC INDUSTRIES LTD STAMFORD WORKS TOTTENHAM N15 4QU (2181)

## Test & Calibration Engineers



Having introduced an extended new product range, many of which are microprocessor based, Marconi Instruments has once again confirmed itself as Europe's leading manufacturer of sophisticated test and measurement systems. Our products are selling throughout the world and we are naturally developing further new and innovative designs.

A key role in our organisation is that of our Luton based Service Division, where a group of Technicians satisfy a very wide range of customer needs in the repair and calibration of test equipment.

When you join our team you will quickly become individually responsible for work assignments involving many different kinds of propriety products.

Prospects are excellent. The Division is part of a large company with its main Instrument Design/Manufacturing Base at St. Albans, a Microwave Plant at Stevenage and a further substantial Design Manufacturing Group at Donibristle in Scotland. The Company is proud of its policy of promoting men and women from within, as future Salesmen, Managers and Engineers.

Salaries, which are dependent upon experience and ability are excellent and regular overtime is normally available. Progress for competent engineers and technicians can be rapid. Relocation assistance is available in approved cases. Special consideration is given to 'ex-forces' personnel.

Whatever your level of experience we would like to hear from you. Cut out the coupon and send it to John Prodder, Recruitment Manager, Marconi Instruments Limited, FREEPOST, St. Albans AL4 0BR. Tel: (0727) 59292.

Name	Age			
Address				
Tel. No.				
Years Experience				
Present Salary:	£6,000	£7,000	£8,000	Over
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	£7,000	£8,000	£9,000	£9,000
Qualifications				
Present Job				

(2143)



### CHELSEA COLLEGE University of London

Applications are invited for the post of

#### TECHNICIAN GRADE 5

to join an Electronic/Development Workshop working with the departments of basic medical sciences. The work undertaken consists of the design, development and construction of analog and digital equipment for use in the life sciences. The successful applicant will have a good knowledge of electronics and an interest in or experience of the application of these techniques to solving biological problems.

Salary scale: £6279 - £7332 pa plus £1220 London Allowance.

Application forms from the Personnel Office, Chelsea College, 552 King's Road, London SW10 0UA. Closing date: 3rd August 1983. (2192)

### CHIEF ELECTRONICS TECHNICIAN

DARTFORD and GRAVESHAM HEALTH AUTHORITY based at JOYCE GREEN HOSPITAL, DARTFORD, KENT

Qualifications - ONC, HNC preferred. Salary Scale - £7,386 to £9,212 Medical Physics Technician II This is a newly established post offering an exceptional opportunity for the establishment of a section responsible for the maintenance of electronic and bio-medical equipment.

Candidates, male or female, should possess broad experience of electronics together with an understanding of the safety aspects of equipment.

In addition to a sound technical background applicants should possess the managerial qualities required to organise and supervise both subordinate staff and contracted work and be capable of developing and sustaining successful working relationships with all levels and disciplines of hospital staff.

For job description and application form write to: District Personnel Dept., Darenth Park Hospital, Dartford, Kent. PREVIOUS APPLICANTS FOR THIS POST WILL BE CONSIDERED AND NEED NOT RE-APPLY. (2195)

### LEEDS WESTERN HEALTH AUTHORITY THE GENERAL INFIRMARY AT LEEDS

#### MEDICAL PHYSICS TECHNICIAN

GRADE III or IV (Electronics)

Electronics Technician required in the Medical Physics Department. Duties of the post include the development, commissioning, testing, maintenance and repair of a variety of electro-medical and computing equipment. The post becomes available on 1st November, 1983.

Experience in electronics is essential and the appointment will be made in Grade III or IV depending on the qualifications and experience of the successful candidate. Salary will be in the range £6132 to £7926 (Grade III) or £5171 to £6798 (Grade IV).

Application forms and job descriptions are obtainable from The Personnel Officer, Leeds General Infirmary, Great George Street, Leeds LS1 3EX.

Closing date: 29th July, 1983. (2209)

### LOGEX ELECTRONICS RECRUITMENT

Specialists in Field & Customer Engineering appointments, all locations and disciplines.

Logex House, Burleigh, Stroud Gloucestershire GL5 2PW 0453 883264 & 01-290 0267 (24 hours)

R & D OPPORTUNITIES. Senior level vacancies for Communications Hardware and Software Engineers, based in West Sussex. Competitive salaries offered. Please ring David Bird at Rediffusion Radio Systems on 01-874 7281. (1162)

## RF ENGINEER

TO CARE ABOUT A PRODUCT THAT CARES FOR THE USER

YORKSHIRE

£11,000

Our client, Tunstall Telecom, designs and manufactures the UK's most used emergency communications system for the elderly or infirm.

The increasing demand for greater flexibility and mobility of use has created the need for a further RF Engineer.

The work will be on varied low power RF frequency projects and will involve significant theoretical and practical design.

You will work in co-operation with other areas of R & D and part of the task will be to liaise with the Home Office.

The position will suit someone with proven design experience from a commercial background, a degree and most of all a mature approach to cost effective and 'producible' design work.

Apart from an excellent negotiable salary and benefits package (with relocation assistance where necessary) this is an opportunity to make a very personal 'stamp' on a product that will have a very beneficial effect on the elderly and infirm within the country.

To discuss this position in greater detail telephone or write to Paul Hecquet on Lewes (07916) 71271.

(2174)

## Electronic Engineers - What you want, where you want!

TJB Electrotechnical Personnel Services is a specialised appointments service for electrical and electronic engineers. We have clients throughout the UK who urgently need technical staff at all levels from Junior Technician to Senior Management. Vacancies exist in all branches of electronics and allied disciplines - right through from design to marketing - at salary levels from around £5000-£15000

If you wish to make the most of your qualifications and experience and move another rung or two up the ladder we will be pleased to help you. All applications are treated in strict confidence and there is no danger of your present employer (or other companies you specify) being made aware of your application.

TJB ELECTROTECHNICAL PERSONNEL SERVICES, 12 Mount Ephraim, Tunbridge Wells, Kent. TN4 8AS.

Tel: 0892 39388



Please send me a TJB Appointments Registration form:

Name .....

Address .....

(861)

Premier international electronics companies – very secure and expanding in London and the south of England – require professional senior staff (including departmental heads). Relocation allowance up to £3,000.

## ELECTRONIC ENGINEERS

Electronic engineers required with degree – H.N.C. – tech. cert. – O.N.C. Almost any background required but software and hardware experience will bring salary of absolute minimum of £6,500 p.a. and could be up to £11,000 p.a.

## ELECTRONIC DESIGN/DEVELOPMENT

Engineers required with experience of circuit or component design or development for microwave equipment or digital logic or computer peripherals or electronic packaging or film technology or telecommunications. Also above for updating in modern techniques. Salaries up to £15,000.

## SOFTWARE PROGRAMMERS & ENGINEERS

Engineers or mathematicians required for development of commissioning and design proving programmes from assistant to team leader level. Salaries up to £12,000 p.a.

Please contact by telephone, or letter, to discuss companies and possibilities. Watford 49456 anytime.

(2146)

## GORE MANAGEMENT SERVICES LTD

**SELECTION & TRAINING CONSULTANTS**  
218 St Albans Road, Watford, Herts.  
Tel: Watford 49456

# B&W

## LOUDSPEAKER ENGINEER

Rare opportunity to join the R&D team at B&W Loudspeakers in Sussex

The successful candidate will be involved with the design and development of both loudspeaker drive units and complete high-fidelity speaker systems, using our in-house computer and laser interferometer.

Applicants should be educated to at least HNC standard and preferably have experience of electronics and acoustics. A thorough understanding of the operation of a loudspeaker system is essential.

The salary is negotiable. Please apply in writing to Stephen Roe.

**B&W LOUDSPEAKERS LTD**  
Elm Grove Lane, Steyning, West Sussex (2207)

Royal Marsden Hospital,  
Fullham Road, London SW3

## Medical Physics Technician

MPT2

required in the Physics and Radiotherapy Departments. The appointed person will be responsible for the supervision of a pleasantly situated, well-equipped electronics workshop and the maintenance and service of an interesting variety of radiotherapy equipment.

The Department has 3 cobalt treatment machines, 150kv and 300kv X-ray units, a Philips 10mv linear accelerator and a simulator. Current developments include the installation of a Philips 5mv linear accelerator and caesium Selectron unit.

Applicants should hold ONC, HNC or similar qualification in electrical engineering or (preferably) in electronics, and have relevant technical experience particularly with Philips linear accelerators. To be appointed on to the MPT2 scale applicants should have served at least 2 years as MPT3 or equivalent. Salary scale £8,383-£10,209 per annum.

Application form and job description available from the Personnel Department, Royal Marsden Hospital, at the above address. Tel: 01-352 8171 Ext. 446/447. (2197)

## CAMBRIDGE HEALTH AUTHORITY

Physics Department  
Addenbrooke's Hospital, Hills Road, Cambridge

## Medical Physics Technician Grade II

(£7,386-£9,212)

An electronics technician is required to provide maintenance and support services to the CT Head Scanner at Addenbrooke's Hospital and to electro-medical equipment in the Thoracic Surgical Unit, Papworth Hospital.

Applicants should hold an appropriate HNC or equivalent qualification and have several years' experience in the field of electronics (mini computer experience advantageous).

For further details contact Mr P. E. Ward, Principal Physics Technician, at the above address. Tel: (0223) 245151 ext. 471.

Application form and job description from the Personnel Department ext. 7511. (2177)

## UNIVERSITY OF SURREY

Department of Electronic and Electrical Engineering

### RESEARCH OFFICER for the "UOSAT Spacecraft project"

Applications are invited from engineers with proven experience in RF and/or digital techniques for the post of Research Officer on the UOSAT spacecraft project.


The work will involve the initiation, implementation and operation of spacecraft ground support hardware/software and the design and fabrication of future spacecraft systems.

The UOSAT spacecraft, built in the Department of Electronic & Electrical Engineering at the University of Surrey, supported by UK Industry (AMSAT-UK and the RSGB), and launched by NASA in October 1981, is controlled from a command station located within the Department. The spacecraft currently supports a number of engineering, scientific, educational and amateur radio experiments and is expected to continue operating for several years.

The appointment will be for 12 months on Research and Analogous Scales up to a maximum of £8530 per annum.

Applications in the form of a curriculum vitae (3 copies) including the names and addresses of two referees should be sent to the Deputy Secretary (Personnel), University of Surrey, Guildford, Surrey, GU2 5XH, by 22 August 1983 quoting reference 170/WW. (2173)

## Test Engineers/Technicians here's a package worth looking into



As an international leader in the development and manufacture of advanced communication equipment, the package offered by Marconi Communication Systems Limited warrants very close inspection indeed by Test Engineers and Technicians.

When you're thinking about a move, you've got to be sure that both your career and lifestyle are going to benefit. And we believe we have a lot to offer on both accounts.

Right now we are seeking men or women to join our Space and Microwave, Digital Communications and Defence Departments to work on a wide range of equipment including satellite and tropo systems, data modems, PCM and associated ATE such as Graduate.

Of our reputation in advanced electronics there can be little doubt. Current projects, like Triffid, ICS3 and Modems for

**Marconi**  
Communication Systems

British Telecoms new data distribution service are among the most advanced of their kind, designed to meet the needs of military and civil communications for a generation to come.

In Chelmsford we're very conveniently located for London, the Essex countryside and coast. A modern town with good facilities and a variety of reasonably priced housing.

Applicants should preferably be qualified to HNC in Electronics although practical experience in a test or field services environment is equally important.

Vacancies cover a wide range of seniority and responsibility with salaries between £5,000 – £8,000 p.a. Our information package will tell you more so telephone now for your copy or write with full C/V to Gordon Short at Marconi Communication Systems Limited, New Street, Chelmsford, Essex, CM1 1PL. Tel. Chelmsford (0245) 353221, extension 592.



## VHF/Radio Engineer

### Middle East

Our client, involved in several major projects overseas, require a Telecommunications Engineer immediately to advise and monitor an important harbour system. Emphasis is on VHF radio links, operational control and port safety services.

Candidates should be graduates in an appropriate discipline, preferably with membership of a professional institution, and have relevant experience in VHF radio field. In addition to professional background, applicants must be skilled in liaison and consultancy practices, preferably gained overseas and be available for immediate interview and posting.

The post attracts an excellent tax-free salary package of

c. £24,000 together with usual overseas benefits, including free furnished accommodation, company car and medical cover. Candidates, aged 30-45, must hold relevant degree to qualify for interview.

Please write initially with full career details to Confidential Reply Service, Ref. DSV 8760, Austin Knight Limited, London, W1A 1DS.

Applications are forwarded to the client concerned, therefore companies in which you are not interested should be listed in a covering letter to the Confidential Reply Supervisor.

**Austin Knight Advertising**

## BORED ?

Then change your job!

- 1) Film-TV Equipment**  
Installation and maintenance of studio and TV equipment. UK and abroad.
- 2) Satellite Communications**  
Test Engineers required with experience of digital circuitry. £7,700 Surrey.
- 3) Microcomputers and Peripherals**  
Service Engineers required £8-£10,000 Camberley.
- 4) Data Communications**  
Service of microprocessor-based equipment. £8,000 + car. Reading.
- 5) Service Personnel (RAF, RN, Army)**  
We have many clients interested in employing ex-service fitters and technicians at sites throughout the UK. Phone for details.
- 6) £500 per week**  
We are paying very high rates for contract design and test engineers who have a background in RF, MICROWAVE, DIGITAL, ANALOGUE or SOFTWARE, at sites throughout the UK.  
Hundreds of other Electronic and Computer Vacancies to £12,500  
Phone or write:  
Roger Howard, C.Eng.,  
M.I.E.E., M.I.E.R.E.  
**CLIVEDEN CONSULTANTS**  
87 St. Leonard's Road, Windsor, Berks.  
Windsor (07535) 58022 (5 lines) (1640)

**CLIVEDEN**

### BOX NOS.

Box number replies should be addressed to:

Box No.....  
c/o Wireless World  
Quadrant House  
The Quadrant  
Sutton, Surrey, SM2 5AS



require

## A SAFETY/TECHNICAL CO-ORDINATOR

Pioneer High Fidelity (GB) Limited is a very successful and expanding company in the electronic consumer industry. We market a wide range of Hi Fi, Car Audio and Video products. A vacancy now exists in our Technical Department for a Safety/Technical Co-ordinator at our new premises in Greenford, Middlesex.

The job entails the submission of new products to B.E.A.B. for approval, liaising with our factories in Japan and with the United Kingdom Safety Authorities and the writing of technical service bulletins for our dealers and authorised service centres.

The successful applicant should be fully conversant with BS-415 safety standards, applicable to domestic electrical equipment, and should have had at least two years' experience in this field. He/she should be qualified to H.N.C. or equivalent standard in electronics and preferably with at least three years' experience in domestic HiFi and/or Video equipment. Some experience in technical writing is also essential.

Benefits include competitive salary, four weeks' holiday, subsidised restaurant, contributory pension scheme and private health cover.

For further information or an application form, please contact:  
Mrs C. A. Burrige, Pioneer High Fidelity (GB) Limited  
Field Way, Greenford, Middx. UB6 8UZ. Tel: 01-575 5757

(2196)

## ELECTRONICS ENGINEER

Rediffusion Music require an Electronics Engineer with a minimum of five years' experience in the professional audio field, covering real time and high speed magnetic tape duplicating systems.

The successful candidate will be involved with the design, development and technical back-up of studio and factory production equipment. Should be qualified to degree or HND level, and will be expected to have proven supervisory and communication skills.

For application form please contact:

Mrs Joanne Jarvis  
Personnel Officer  
Rediffusion Business Electronics Ltd.  
Music Division  
Cray Avenue  
Orpington  
Kent  
Tel: Orpington 32121

(2193)

INNER LONDON EDUCATION AUTHORITY  
Learning Resources Branch  
Television Centre  
Thackeray Road  
Battersea SW8 3TB

## ENGINEER - ELECTRONIC MAINTENANCE

Salary range: (ST2) £7,035 to £7,974 plus £1,284 London Weighting Allowance.

The ILEA's Television Centre produces a wide range of educational programmes on video and audio cassettes.

The Maintenance section numbers four persons and a vacancy has arisen for an engineer with a sound knowledge of the principles of colour television, and preferably a working experience of maintaining broadcast type TV equipment. Applicants must wish to specialise on the video side (cameras, vision mixers, telecine, etc.), and will receive appropriate training.

An engineering degree, TEC or other equivalent qualifications are desirable.

Application forms from the Education Officer (EO/Estab. 1B), Room 365, The County Hall, London SE1 7PB. Please enclose a stamped and addressed foolscap envelope. Completed forms to be returned by May 4, 1983.

ILEA is an equal opportunities employer.

(2201)



TELEVISION AUDIO MAINTENANCE LIMITED

## TECHNICAL TRAINING OFFICER

Television Audio Maintenance (TAM) is an expanding national Division of the Telefuson Plc Group (£80 million turnover) providing a Video/TV/Audio after sales service to leading electrical retailers, all of whom are household names.

This interesting and challenging new appointment will be of interest to engineers of City and Guilds Technician Education or equivalent who wish to broaden their experience across a wide range of modern merchandise and manufacturers. Applicants should preferably have had teaching or training experience.

The work involves conducting Central and Regional Courses, preparing material to be used by our national network of Local Trainers, providing technical servicing advice to our 50 Service Departments and liaising with manufacturers. The position is based at Blackpool. Considerable travelling is involved.

Salary is negotiable. Company car plus other fringe benefits. Reply with full details to:

Mr. R. M. Beaton, Group Personnel Manager,  
Telefuson Plc, Telefuson House, Preston New Road,  
Blackpool, Lancs.

(2198)

THE PAPUA NEW GUINEA UNIVERSITY OF TECHNOLOGY  
DEPARTMENT OF ELECTRICAL AND COMMUNICATIONS ENGINEERING

## PROFESSOR AND ASSOCIATE PROFESSOR (2 VACANCIES)

Applications are invited from suitably qualified candidates to fill the above posts. The Holder of the Chair of Electrical and Communications Engineering would be expected to assume leadership of the Department. The discipline of the Associate Professor would be chosen to complement that of the Professor.

The Department of Electrical and Communications Engineering has a current academic staff of 16, and a total student enrolment of 190. The Department is responsible for courses leading to a Bachelor's Degree with specialisation in either communication or power engineering, and to a Diploma or Graduate Diploma leading to a Master's Degree after further study, has recently been introduced. There is scope for developing related courses within the Department.

The applicants should have appropriate qualifications and extensive teaching and administrative experience in higher education, special expertise in some branch of electrical and communication engineering, and a recognition of some of the problems facing technological education in a developing country. He/she will be required to stimulate and pursue research and maintain and develop strong links with engineering employers and the profession.

The language of instruction is English.

SALARY:	Professor	K22,840
	Associate Professor	K21,720
	(K1=£0.7591)	

Initial contract period is for three years. Other benefits include gratuity of 24% taxed at 2%, appointment and repatriation fares for the staff member and family after 18 months of service, settling-in and settling-out allowances, six weeks paid leave per year, education fares and assistance towards school fees, free housing. Salary continuation and medical schemes are available.

Detailed applications with curriculum vitae together with names and addresses of three referees and telephone contact should be received by: The Registrar, PNG University of Technology, Private Mail Bag, Lae, Papua New Guinea by 31st August, 1983. (2186)

SALFORD COLLEGE OF TECHNOLOGY  
DEPARTMENT OF ENGINEERING

## LECTURER IN ELECTRONICS (AUDIO/MUSIC RECORDING)

Lecturer required from 1 September, 1983, to assist in the development of new three year full-time Diploma course in Music Recording Technology.

Candidates must have a degree in Electronics or Physics and should have practical experience of analogue and digital equipment. An ability and/or interest in music is essential.

In addition to teaching on the Music Recording Technology course the successful candidate will be required to teach on other full-time and part-time day courses in Electronics and related studies.

Further details and application forms (to be returned as soon as possible) are available from the Principal, Salford College of Technology, Frederick Road, Salford M6 6PU. Tel: 061-736 6541. (2200)

## STUDIO 99 VIDEO

## VIDEO ENGINEER

for bench and field work

Duties involve the maintenance and installation of professional video equipment. A candidate should be familiar with three tube colour cameras, U-Matic format video recorders and associated equipment.

Whilst a technical qualification is desirable, a minimum of five years' experience is required. This is an interesting job requiring a high level of expertise and self-motivation.

If you can match up to these expectations we would like to hear from you.

Company vehicle provided, salary commensurate with experience.

Please contact Mr Stone or Miss Whittick on 01-450 1313

(2171)

## TRANSMITTER/STUDIO ENGINEERS

LONDON BASED

Up to £13,000

These positions require Engineers with a considerable experience in the design and installation of transmission and studio equipment. FM, MW/SW up to 100KW and TV up to 30KW. The job entails overlooking an operation from the initial contract through to installation and as most of these are abroad, candidates must be prepared to spend up to 50% of the year outside the U.K. A working knowledge of French or German would be an advantage.

For an application form, please send your name and address to George Lowi, Beechwood Appointments Register, 221 High Street, LONDON W3 9BY or telephone 01-992 8647 (24-hour answering service).

(2204)



## ELECTRONICS ENGINEER

committed to Third World Development

to develop simple solar voltaic products and assist in establishing small scale manufacturing units in Botswana.

Practical experience of design and construction of electronic devices essential.

Two-year contracts including modest living allowance and flights. Regret no funding for dependants.

Write for details including short c.v. and s.a.e. to: International Voluntary Service, WW1, 53 Regent Road, Leicester LE1 6YL.



(2170)

## TOWNLEY EMPORIUM

Bargains for callers or send for catalogue

## ELECTRICAL, ELECTRONIC & MECHANICAL COMPONENTS

Vast range of surplus test equipment; Diodes; Thyristors; Resistors; Terminals; Switches; Relays; Screws; ICs; Tools.

Harehill Street off Bursley Road, Todmorden, Lancs OL14 5JY

(2172)

UNIVERSITY COLLEGE LONDON

Department of Phonetics & Linguistics

## RESEARCH ASSISTANT HEARING RESEARCH

PHYSICIST required to work in the field of electrocochlear stimulation in the totally deaf. A new five-year MRC-funded post (starting July 1983) in an established multi-disciplinary group with collaborating members in London (University College London and Guy's Hospital) and Cambridge (Laboratory of Experimental Psychology). The successful applicant will be based in London. Work involves speech signal processing, biocompatible materials, practical prosthesis design and work with individual patients. Preparation for a higher degree is possible. Salary £7,190 - £1,186 London Allowance.

Applications (no form) should be sent to Professor A. J. Fourcin, Department of Phonetics & Linguistics, University College London, Wolfson House, 4 Stephenson Way, London NW1 2HE.

(2178)

UNIVERSITY OF YORK

## SENIOR TECHNICIAN Grade 5

(Salary scale £6279-£7332)

Department of Psychology

A vacancy exists for a post of Electronic/Computer Technician in the Department's electronic workshop. The work will primarily involve the construction and development of interface systems and the maintenance of mini- and micro-computers.

Applicants are expected to have appropriate technical qualifications. Experience with PDP-11 type computers and a knowledge of Macro 11 assembly language would be an advantage.

Applications should be sent, together with the names and addresses of two referees, to Mr. D. Rymar, Assistant Bursar, University of York, Heslington, York YO1 5DD to arrive not later than 31 July.

(2205)

## ARTICLES FOR SALE

### MARCONI UHF SIGNAL GENERATOR

£79/Cos 0 Corrector £39. Wow/Flutter Meter £75. B.E. Double Pulse Generator £49. Wayne-Kerr Audio Analyser £45. Signal/Sweep Generators. Siemens Chart Recorder with Level Meter facility £49. Vibration Analyser £69. Pye Megohmmeter 200,000 M-ohm £47. Hivolt Linear Scale 30KV EHT Meter £32. Micro-Indexing Tables with electronic control, contractors, etc £295. 7-channel 1" tape recorder, six speeds £98. Valradio 50-60 c/s Static Converter £39. Swiss micro-lathe £45. Vortexion mixer 3-ch-ppm £45. 4-ch-cue lights £49. Leavers-Rich professional recorder 12y DC £95. 1" recording tapes NAB £4 ea. Marconi Double Pulse Generator £75. Hatfield Static Converter 50c/s in, 290-550c/s out, £75. Grubb Parsons Argon Analyser £50. Sullivan Precision Decade Mica Condenser, total 11uf £45. 040-376236. (2016)

BRIDGES, waveform/transistor analysers. Calibrators, Standards. Millivoltmeters. Dynamometers. KW meters. Oscilloscopes. Recorders. Signal generators - sweep, low distortion, true RMS, audio, FM, deviation. Tel. 040 376236.

VALVES, PROJECTOR Lamps, 6090 types, list 75p, world wide export. Cox Radio (Sussex) Ltd., The Parade, East Wittering, Sussex. Phone (024 366.2023. (1991)

# Challenging Opportunities with Sony Broadcast Ltd.

We are one of the World's leaders in the professional broadcast industry with our international headquarters for Europe, the Middle East and Africa located in North Hampshire. Continued growth and success has resulted in the following exciting opportunities:

### Field Service Engineer

To be engaged in the service and repair of our extensive range of equipment, including video cameras, VTR/VCR's, and editing control systems. A high level of self motivation and initiative is required in order to successfully undertake customer visits throughout our marketing territory.

### Senior Quality Assurance Engineer

To join a small team responsible for the evaluation of product performance. Responsibilities will include commissioning and assistance in product customisation. This will involve liaison with customers and the ability to effectively maintain this interface is essential.

Applicants, aged 25 plus, should have a background in broadcast television equipment supported by a relevant electronics qualification.

We offer a first class working environment in our prestigious engineering complex, together with an attractive salary and excellent conditions of employment, which include Company Pension/Life Assurance Schemes and private medical cover.

If you are interested please write with details of present salary and career to date to: David Parry, Assistant Personnel Officer, Sony Broadcast Limited, City Wall House, Basing View, Basingstoke, Hampshire RG21 2LA. Telephone Basingstoke (0256) 55011



Sony Broadcast Ltd.

City Wall House  
Basing View, Basingstoke  
Hampshire RG21 2LA  
United Kingdom  
Telephone (0256) 55 0 11

(2182)

SITUATIONS VACANT

The Papua New Guinea University of Technology Department of Electrical and Communications Engineering

Lecturer

Applications are invited for the above position in the Department of Electrical and Communications Engineering.

Candidates should preferably have experience in teaching communications engineering subjects to degree level. An interest in HF and UHF amateur radio techniques or satellite communication would be preferred. A higher degree would be an advantage.

SALARY: - Lecturer K16,020 - K17,870 (K1 = £0.7591)

Appointment level will depend upon qualifications and experience.

Initial contract period is for approximately three years. Other benefits include a gratuity of 24% taxed at 2%, appointment and repatriation fares, leave fares for the staff member and family after 18 months of service, settling in and settling-out allowances, six weeks paid leave per year, education fares and assistance towards school fees. Free housing, salary protection plan and medical benefit schemes are available.

Detailed applications with curriculum vitae together with the names and addresses of three referees and telephone contact should be received by:

The Registrar, PNG University of Technology, Private Mail Bag, Lae, Papua New Guinea by 31st August, 1983. (2187)

HIGHLAND HEALTH BOARD DEPARTMENT OF MEDICAL PHYSICS AND BIO-ENGINEERING, RAIGMORE HOSPITAL, INVERNESS

SENIOR TECHNICIAN/TECHNICIAN Electronics Section

A vacancy exists for a Senior Technician or Technician (MPT Grade III or IV). The work involves design, construction, repair and maintenance as well as clinical involvement.

Salary is: Grade III £6132-£7926 Grade IV £5171-£6798

National Health Service Conditions of Service.

A full job description and application form can be obtained from Area Personnel Officer, Highland Health Board, Reay House, 17 Old Edinburgh Road, Inverness.

For additional information contact Mr. A. R. Bowley, Deputy Director. Tel: Inverness (0463) 34151, Ext 276 or 277. (2206)

CAPITAL APPOINTMENTS LTD THE UK'S No. 1 ELECTRONICS AGENCY

If you have HNC/TEC or higher qualifications and are looking for a job in design, test, customer service, technical sales or similar fields:

Telephone now for free jobs list We have vacancies in all areas of the UK Salaries to £15,000 pa

01-637 5551 or 01-636 9659 (24 hours)

Or if you prefer send a FULL CV to:

CAPITAL APPOINTMENTS LTD 29-30 WINDMILL STREET, LONDON W1P 1HG (291)

ARTICLES FOR SALE

WAVEGUIDE, Flanges and Dishes. All standard sizes and alloys (new material only) from stock. Special sizes to order. Call Earth Stations, 01-228 7876, 22 Howie Street, London SW11 4AR. (2099)

LAMPS AND CABLE. Large amount of lamps and cable for sale - all types and sizes, domestic and industrial. Telephone MIRAGE LIGHTING on HITCHIN (0462) 733388 between 10am-7pm. (1809)

FREE PROTOTYPE of the finest quality with EVERY P.C.B. artwork designed by us. Competitive hourly rates, and high standard of work. Halstead Designs Limited. Tel: Halstead (0787) 477408. (2126)

BATCH PRODUCTION wiring and assembly to sample or drawings. McDeane Electricals Ltd, 19b Station Parade, Ealing Common, London W5. Tel: 01-992 8976. (169)

ARTICLES FOR SALE

TO MANUFACTURERS, WHOLESALERS BULK BUYERS, ETC. LARGE QUANTITIES OF RADIO, TV AND ELECTRONIC COMPONENTS FOR DISPOSAL

SEMICONDUCTORS, all types, INTEGRATED CIRCUITS, TRANSISTORS, DIODES, RECTIFIERS, THYRISTORS, etc. RESISTORS, C/F, M/F, W/W, etc. CAPACITORS, SILVER MICA, POLYSTYRENE, C280, C296, DISC CERAMICS, PLATE CERAMICS, etc.

ELECTROLYTIC CONDENSERS, SPEAKERS, CONNECTING WIRE, CABLES, SCREENED WIRE, SCREWS, NUTS, CHOKES, TRANSFORMERS, etc.

ALL AT KNOCKOUT PRICES - Come and pay us a visit ALADDIN'S CAVE, TELEPHONE: 445 0749/445 2713 BROADFIELDS & MAYCO DISPOSALS 21 Lodge Lane, North Finchley, London, N.12 (5 minutes from Tally Ho Corner) (1613)

QUARTZ CRYSTALS IN 24 HOURS ANY FREQUENCY 2-50 MHz FOR £5 inc

New fast service for C.W.O. only (state holder style). Clock oscillators for microprocessors in stock from £9.30.

McKnight Crystal Co Ltd, Hardley Industrial Estate Mythe, Southampton SO4 6ZY Tel. 0703 848961 (2008)

RACAL COMMUNICATION RECEIVERS

500kc/s to 30mc/s in 30 bands 1mc/s wide, RA17 MK11 £100, RA17L £150, RA17E £225. New metal louvered cases for above £25 each. All receivers are air tested and calibrated in our workshop. Supplied with manual and dust cover, in fair used condition. RACAL SYNTHESISERS (Decade frequency generator) MA350B Solid state for use with MA79 - RA117 - RA217 - RA1217 ETC. £100 to £150. MA250 16mc/s to 316mc/s £100 to £150. MA250B PRECISION FREQUENCY STANDARD 5mc/s, 1mc/s 100kHz £100 to £150. EDDYSTONE RECEIVER TYPE EC64/7K Solid state, single channel, SSB, mains or battery powered, 1.6 to 27.5mc/s and 400, 535kHz £100 with manual. REDIFON SSB RECEIVER TYPE R499 Solid state, 10 fixed channels, range 1.5 to 30mc/s and 255kHz to 525kHz, power mains or battery, complete with ISB adaptor ARU10A, £100 with manual. REDIFON TT11 AUDIO TELEPRINTER CONVERTOR Solid state, tested with circuit £25. CREED TYPE 75 TELEPRINTER 50 and 75 bauds for use with above convertor £25. OSCILLOSCOPES

COSSOR CDU150 35mc/s, twin beam, solid state £195 with manual. TEKTRONIX 422 Solid state, portable with internal battery pack, 15mc/s, dual trace £350. CT496 DUAL BEAM Oscilloscope, 6mc/s, TEKTRONIX 647A 10mc/s, dual trace, solid state £350 with manual. MARCONI TP995 SIGNAL GENERATORS From 2mc/s or 1.5mc/s to 220mc/s. AM-FM, A2M £100, A3 £100, A5 £150. BS £250 with manuals. TP200SR Two tone signal source audio £150. TP250 DIFFERENTIAL DC VOLT METER 0 to 1100volts £100. TP2002 AM SIGNAL GENERATOR 10kc/s to 72mc/s £400. TP2002AS FM and AM signal generator, 10kc/s to 72mc/s - £600. TP272Z DIGITAL SYNCHRONIZER For above £350. TP1068B/6 FM-AM SIGNAL GENERATOR 10mc/s to 470mc/s £200. TP245 CIRCUIT MAGNIFICATION METER and TP1245 Oscillator £200. H.P. SIGNAL GENERATOR £200 To 11 giga £100. H.P. SIGNAL GENERATOR 600 10-420mc/s - £70. MARCONI AF WATT METER CT44 NOT Absorption, 200 microwatts to 6 watts. in 10 ranges switched, 2.5ohms to 20K OHMS £45. TP900A AF WATT METER 1 milliwatt to 10 watts 25ohms to 20K ohms in 48 steps £65. THYRISTOR TEST SET, CT558 Voltages up to 2KV £100. TEKTRONIX 4002A GRAPHIC COMPUTER TERMINAL with joystick £1200. TEKTRONIX 4601 Hard copy unit for use with above £450. Both units for £1150. RACAL DIGITAL COUNTERS, TYPE 801M - 125mc/s £50. RACAL 836 COUNTER 35mc/s £50. VAT AND CARRIAGE ON ABOVE ITEMS EXTRA

All items are bought direct from H.M. Government, being surplus equipment. Price is ex works. SAE for all enquiries. Phone for appointment for demonstration of any item. JOHN'S RADIO, WHITEHALL WORKS, 84 WHITEHALL ROAD EAST, BIRKENSHEAD, BRADFORD BD11 2ER TEL: (0274) 684007 (848)

THE SCIENTIFIC WIRE COMPANY

811 Forest Rd, London, E.17. Tel. 01-531 0574

Table with columns for wire types (ENAMELLED COPPER WIRE, SILVER PLATED COPPER WIRE, TINNED COPPER WIRE) and prices per 100m.

1000 INSTRUMENT HANDBOOKS FOR SALE

Large range of well-known manufacturers - H.P., Tek, Air-mec, etc. Send s.a.e. for price list. Martin Associates (Electronics) Limited, Parthia House, Beckhamton, Nr. Marlborough, Wilts SN8 1QJ (21810)

OPERATIONAL AMPLIFIER EXPERIMENTAL MANUAL

- by G. B. Clayton £3.50
DIGITAL ELECTRONIC CIRCUITS & SYSTEMS £5.50
by N. M. Morris
ELECTRONIC MUSIC CIRCUITS £15.00
by B. Klein
THE CATHODE-RAY OSCILLOSCOPE AND ITS USE £5.50
by G. N. Patchett
VIDEOTAPE RECORDING £14.50
by J. F. Robinson
DOMESTIC VIDEO CASSETTE RECORDERS £15.00
A SERVICING GUIDE £15.00
by S. Beeching
MICRO COOKBOOK VOL 1: FUNDAMENTALS £13.50
by D. Lancaster
AN INTRODUCTION TO MICROCOMPUTERS VOL 1: BASIC CONCEPTS £10.50
by A. Osborne
WORLD RADIO TV HANDBOOK £12.00
by J. Frost
1983 THE RADIO AMATEUR'S H/B £10.00
by A.R.R.L.
★ ALL PRICES INCLUDE POSTAGE ★

THE MODERN BOOK CO.

BRITAIN'S LARGEST STOCKIST of British and American Technical Books 19-21 PRAED STREET LONDON W2 1NP Phone 01-402 9176 Closed Saturday 1 p.m. Please allow 14 days for reply or delivery (2023)

INVERTERS High-quality DC-AC; also 'no break' (2ms) static switch, 19In. rack. Auto Charger.

Image of an inverter unit with text: COMPUTER POWER SYSTEMS - Intorport Mains-Store Ltd. POB 51, London, W11 3BZ Tel: 01-727 7042 or 0225 310916 (8101)

ARTICLES FOR SALE

24 COLUMN PRINTER ONLY £69 EACH (inclusive) Standard 4-inch 3U mounting; inverted 4 double sized print; single 9V AC or 5V DC power supply; standard centronics interface or serial data; extends only 40mm behind panel. For further details contact: Benwick Electronics 9 Doddington Road, Benwick nr March, Cambs. PE15 0UX Telephone: Benwick (035477) 471

3 COMPARTMENT ICI ULTRASONIC CLEANER Offers: Laminar Clean Air Bench £475. Unitex 2-127-05 Parallel Gap Welding Head, c/w P.S.U. & Foot Pedal. Unused - £450. Phone: (067 23) 219 (2179)

ENCAPSULATING EQUIPMENT FOR coils, transformers, components, degassing silicone rubber, resin, epoxy. Lost wax casting for brass, bronze, silver, etc. Impregnating coils, transformers, components. Vacuum equipment, low cost, used and new. Also for CRT regunning metallising. Research & Development. Barratts, Mayo Road, Croydon CR0 2QP. 01-684 9917. (9678)

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ENCAPSULATING EQUIPMENT FOR coils, transformers, components, degassing silicone rubber, resin, epoxy. Lost wax casting for brass, bronze, silver, etc. Impregnating coils, transformers, components. Vacuum equipment, low cost, used and new. Also for CRT regunning metallising. Research & Development. Barratts, Mayo Road, Croydon CR0 2QP. 01-684 9917. (9678)

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

ANALOGUE integrated circuit design on a single chip. Phone Four-D Limited on 0279-29246. 2159

SURPLUS Top prices paid for surplus, redundant and obsolete test equipment, factories cleared. Also quantities of components. Immediate settlement. We will call anywhere in the United Kingdom. TIMEBASE 94 Afriston Gardens Shelling, Southampton SO2 8FU Telephone: (0703) 431 323 (1852)

ANTIQUE RECEIVING VALVES Unused and boxed in large quantity Tsutom Yoshihara C1-105, Deguchi-cho 34 Suita-shi, Osaka 564 JAPAN (2055)

LINSLEY HOOD DESIGNS 75Watt and 100W amps Audio Signal Generators 75Watt amp p.c.b. £2.30 100Watt Mosfet p.c.b. £4.00 p&p 50p S.A.E. for leaflets TELERADIO ELECTRONICS 325 Fore Street, London N9 0PE (1782)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

EX WD Radio equipment and test equipment. Over 500 sets in stock from £8. Send 50p for illustrated catalogue (including £1 voucher). Weirhead Ltd. 129 St. Albans Road, Watford, Herts. Tel: Watford (0923) 49456. (1974)

SERVICES

CIRCOLEC THE COMPLETE ELECTRONIC SERVICE Artwork, Circuit Design, PCB Assembly, Test & Repair Service, Q.A. Consultancy, Prototypes, Final Assembly. Quality workmanship by professionals at economic prices. Please telephone 01-646 5686 for advice or further details. Unit 4, Windmill Trading Estate Commonside East, Mitcham (1391)

FOR THE BEST PCB SERVICE AVAILABLE ★ Circuit Design & Development Digital and Analogue ★ Artwork Layout Work of the highest standard by experienced draughtsmen. No minimum charge. ★ Board Manufacture Prototype to semi-production, excellent rates. 24-hour prototype service from filmwork. ★ Wiring & Assembly PCB assembly, wiring and cable forming by qualified staff. ★ Test Full test facilities available. One or all services available, no order too small. Please telephone Chelmsford (0245) 357935, or write to HCR Electronics, The Industrial Unit, Parker Road, Chelmsford. (1169)

MAYLAND PCB CO. LTD. Maylandes Chelmsford, Essex CM3 6AB Tel: (0621) 741560 (2051)

PRINTED CIRCUIT BOARDS Manufacturers from A/W or film, small or large quantities, average turnaround two weeks. MAYLAND PCB CO. LTD. Maylandes Chelmsford, Essex CM3 6AB Tel: (0621) 741560 (2051)

EPROM PROGRAMMING From list and/or existing EPROM for most 5v N.MOS types. Charge £2.50 + 12 pence per 32 words manually entered. Erasing and EPROMS also available. Bandley Chipware 28 Boroughgate Appleby Cumbria CA16 6AG Tel: 0930 51027 (2202)

TV PICTURE TUBES. If you have interest in setting up a TV tube rebuilding plant we offer our consultancy service backed by more than 30 years experience. We will provide equipment new or used. Layout and fullest quality training. We also offer all component parts of every type for all tubes. Our service is worldwide and a joint participation venture may be considered in some countries. Box No. 2095.

PCBS & PANEL LABELS to your requirements. Design - Prototypes - Production. G. N. Slee Custom Products, 78 Derry Grove, Thurnscoe, Rotherham, Yorks SG3 0TP. Telephone (0709) 89525. (1892)

SMALL BATCH PCBs, produced from our artwork. also DIALS, PANELS, LABELS. Camera work undertaken. FAST TURNAROUND. Details: Winston Promotions, 9 Hatton Place, London EC1N 8RU. Tel. 01-405 4127/0960. (9797)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

Williams P.C.B. Artworks FAST TURNROUND Cost effective specialist layout and master artwork WILLIAMS ARTWORK GRAYS LANE MORETON-IN-MARSH, GLOS. Telephone 0386 840121 - to 9 p.m. (1971)

PCB/ELECTRONIC ASSEMBLY to sample or drawing. Short or continuous runs. Any quantity. 100% inspected. Special rates for small companies or large quantities. Fast turnaround and local deliveries if required. AUTRONICS, 23 Regency Gardens Yardley Wood, Birmingham B14 4JS 021-474 4638 (2020)

PCB & ELECTRONIC ASSEMBLY ● Assembly of all types of PCB ● Cable Harness & Chassis Wiring ● Testing Facilities ● Design & Development Service ● Small or Large Quantities WEB LOGIC SYSTEMS LTD 15 High Street, Harpenden Herts. Tel. 05827-62119 (2190)

DESIGN SERVICES. Electronic design development and production service available for digital and analogue instruments. RF Transmitters and receivers, telemetry and control systems. 20 years' experience. R.C.S. Electronics, Wolsey Road, Ashford, Middlesex. Phone Mr Falkner 53661. (8341)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

DESIGN AND DEVELOPMENT. ANALOGUE, DIGITAL, RF AND MICROWAVE CIRCUIT AND SYSTEM DESIGN. Also PCB design, mechanical design and prototype/small batch production. - Adenmore Limited, 27 Longshot Estate, Bracknell, Berks. Tel: Bracknell (0344) 52023. (656)

## COMPUTER APPRECIATION will shortly be moving to Oxford

Prior to our move we shall be selling by auction our entire stock on August 15th. Lots (many without reserve) will include: Complete systems (by DEC, Hewlett Packard, NCR, Texas Instruments); VDU Terminals (by Newbury Labs, Hazeltine and others); Hard and Floppy disc drives; DEC peripherals; Microscopes; Lasers; Printers (daisy wheel golfball and matrix) by DIABLO, TALLY, IBM; Mag tapes; NAGRA Sound Recorder; TEKTRONICS Model 335 oscilloscope; Word processors; paper tape equipment by FACIT, CLARY, TALLY; plotters, cardreaders, monitors, modems

Catalogues available (price £1 incl. postage) from:

Computer Appreciation, 86 High Street, Bletchingley, Redhill, Surrey RH1 4PA  
Tel: Godstone (0883) 843221

Lawrences, Norfolk House, High Street, Bletchingley, Surrey

## INDEX TO ADVERTISERS

Appointments Vacant Advertisements appear on pages 94-103

PAGE	PAGE	PAGE
Aero Electronics (AEL) Ltd..... 4	Farnell Instruments Ltd. .... Cover ii, 20	Pantechnic ..... 77
Ambit International ..... 8	Ferranti Electronics ..... Cover iv	PM Components ..... 18, 19
Armon Electronics Ltd. .... 14	Fieldtech Heathrow Ltd. .... 20, 77	P&R Computer Shop ..... 83
Aspen Electronics Ltd. .... 88		
Audio Electronics (Cubegate) Ltd ..... 9		
Avel Lindberg (Cotswold Electronics) ..... 14		
	G.P. Industrial Electronics Ltd. .... 10, 11	
	Griftronic Emission Ltd. .... 4	
		Racom Ltd. .... 91
Bamber, B. Electronics ..... 80		Radford Audio Ltd. .... 80
Barrie Electronics Ltd. .... 89	Harris Electronics (London) ..... 7	Radio Component Specialists ..... 81
Black Star Ltd. .... 91	Harrison Bros. Electronic Distributors ..... 3	RST Valves ..... 13
Branson, S. J. .... 91	Hart Electronic Kits Ltd. .... 6	
Broadfields & Mayco Disposals ..... 6	Hemmings Electronics and Microcomputers ..... 77	
	Henry's Computer Shop ..... 18	
	Hilomast Ltd. .... 5	
	House of Instruments ..... 15	
	H.W. International ..... Cover iii	
Cherry Electrical Products ..... 2		Samsons (Electronics) ..... 92
Circuit Services ..... 89		Service Trading Co. Ltd. .... 91
Clark Masts Ltd. .... 83		Skyleader ..... 92
Clef Products (Electronics) Ltd. .... 80		South Midland Communications Ltd. .... 2
Colomor (Electronics Ltd.) ..... 83		Sowter, E. A. Ltd. .... 7
Computer Appreciation ..... 104	Integrex Ltd. .... 8	Special Products (Distributors) Ltd. .... 3
Control Universal Ltd. .... 4	ILP Electronics Ltd. .... 12, 16, 17	Stewart of Reading ..... 88
Cricklewood ..... 85		Strumech Engineering Ltd. .... 15
		Surrey Electronics Ltd. .... 14
	Langrex Supplies Ltd. .... 13	
Delph Electronics ..... 6		
Display Electronics ..... 93	Midwich Computer Co. Ltd. .... 7	Technomatic Ltd. .... 78, 79
	Micro Concept ..... 84	Techtest Ltd. .... 2
		Thandar Electronics Ltd. .... 84
		Thanet Electronics Ltd. .... 4
		Thomas Business Systems ..... 2
		Thurlby Electronics (Reltech) ..... 12
		Timebase Ltd. .... 80
Eddystone Radio ..... 88	Northern Computer Fair ..... 86	
Electrical Review Shock Cards ..... 83	Nova Products (APB) Ltd. .... 88	
Electronic Brokers Ltd. .... 3, 5		
Electrostatic Ltd. .... 18		
Electrovalue Ltd. .... 92	Opus Supplies ..... 87	
Essex Electronics Centre ..... 9	Orion Scientific Products Ltd. .... 14	Wireless World Circards ..... 90

OVERSEAS ADVERTISEMENT AGENTS  
France & Belgium: Norbert Hellin, 50 Rue de Chemin Veat, F-9100, Boulogne, Paris.

Hungary: Ms Edit, Bajusz, Hungexpo Advertising Agency, Budapest XIV, Varosliget.  
Telephone: 225 008 - Telex: Budapest 22-4525 INTFOIRE

Italy: Sig C. Epis, Etas-Kompass, S.p.a. - Servizio Estero, Via Mantegna 6, 20154 Milan.  
Telephone: 347051 - Telex: 37342 Kompass.

Japan: Mr. Inatsuki, Trade Media - IBPA (Japan), B.212, Azabu Heights, 1-5-10 Roppongi, Minato-ku, Tokyo 106.  
Telephone: (03) 585 0581.

United States of America: Ray Barnes, Business Press International Ltd, 205 East 42nd Street, New York, NY 10017 - Telephone (212) 867-2080 - Telex: 238327.

Jack Farley Jr., The Farley Co., Suite 1584, 35 East Walker Drive, Chicago, Illinois 60601 - Telephone (312) 63074.  
Victor A. Jauch, Elmatex International, P.O. Box 34807, Los Angeles, Calif. 90034, USA - Telephone (213) 821-8581 - Telex: 18-1059.

Jack Mantel, The Farley Co., Suite 650, Ranna Building, Cleveland, Ohio 44115 - Telephone (216) 621 1919.  
Ray Rickles, Ray Rickles & Co., P.O. Box 2028, Miami Beach, Florida 33140 - Telephone (305) 532 7301.  
Tim Parks, Ray Rickles & Co., 3116 Maple Drive N.E., Atlanta, Georgia 30305, Telephone (404) 237 7432.  
Mike Loughlin Business Press International, 15055, Memorial Ste 119, Houston, Texas 77079 - Telephone (713) 783 8673.

Canada: Colin H. MacCulloch, International Advertising Consultants Ltd., 915 Carlton Tower, 2 Carlton Street, Toronto 2 - Telephone (416) 364 2269.  
\* Also subscription agents.

Printed in Great Britain by QB Ltd, Sheepen Place, Colchester, for the proprietors, Business Press International Ltd, Quadrant House, The Quadrant, Sutton, Surrey SM2 5AS.  
© Business Press International Ltd 1983. Wireless World can be obtained abroad from the following: AUSTRALIA and NEW ZEALAND: Gordon & Gotch Ltd. INDIA: A. H. Wheeler & Co. CANADA: The Wm. Dawson Subscription Services Ltd; Gordon & Gotch Ltd. SOUTH AFRICA: Central News Agency Ltd; William Dawson & Son (SA) Ltd.  
UNITED STATES: Eastern News Distribution Inc., 14th Floor, 111 Eighth Avenue, New York, NY 10011.

## THE WORLD'S FIRST AND ONLY AUTOMATIC MICROPHONE SYSTEM - FROM SHURE.



(Actual size)

Whenever someone has something to say in public, it's often the microphone system that makes or breaks their speech.

Clicks. Pops. Crackles. Background noises and missed syllables. Just a handful of the hazards that can turn a speaker's finest hour into a fiasco.

Which is why we'd like to introduce you to something completely new - the Shure AMS. Microphone, mixer and advanced logic technology, combined in a totally dedicated system.

In short - a sound revolution.

At the heart of the AMS are angle-sensitive microphones. Speak into any one of them within its own 120° 'window of acceptance' and it turns on; change the surrounding audio conditions

# IT'S SO SMART IT CAN

# 'MAKE' SPEECHES

and it compensates. Quickly. Quietly. Automatically.

The rear panel of every AMS mixer features logic terminals that not only give unprecedented flexibility but also eliminate many of the usual adjustments and controls.

As a result no other unit sets up as quickly; handles as easily. And for larger gatherings, AMS mixers combine simply to effectively control over 200 mics.


The new Shure Automatic Microphone System. It makes speeches not mistakes.

## SHURE

You simply can't make it any clearer.

WW - 018 FOR FURTHER DETAILS

# FERRANTI ZN451 EVALUATION KIT



# Better by design

## If you're the sensitive type, check out the new ZN451 DVM.

Measuring microvolt signal levels is easy with the new ZN451 DVM IC. It's the first DVM that auto-zeroes external signal conditioning circuits to give full-scale readings as low as  $\pm 1.999$  mV with no zero adjustment.

Two logic outputs are provided to control external analogue switches, allowing op-amps and other circuits to be put inside the auto-zero loop and have their offsets cancelled by the ZN451's digital auto-zero system.

Use the ZN451 with pressure transducers, thermocouples, strain gauges or any low output transducer.

To make it even easier there's the ZN451 Evaluation Kit, which contains everything\* you need to make a 2mV DVM, available from your Ferranti distributor price £29.50 inc. VAT.

### Distributors:

Celdis, Reading, Tel: 0734 585171  
Farnell Electronic Comps., Leeds,  
Tel: 0532-636311  
Intel Electronics, Henlow,  
Tel: 0462 812505  
STC Electronic Services, Harlow,  
Tel: 0279 26777  
Midwich Computer Co., Bickingham,  
Tel: 0379 898751  
Semicomps, Keighley, Tel: 0535 65191  
Semicomps, Kelso, Tel: 0573 24366  
Swift-Sasco, Crawley, Tel: 0293 28700

Ferranti Electronics Limited,  
Fields New Road, Chadderton,  
Oldham OL9 8NP, England.  
Tel: 061-624 0515 and 061-624 6661  
Telex: 668038



\*Batteries not included

# FERRANTI

## Semiconductors

WW-003 FOR FURTHER DETAILS

[www.ferranti.com](http://www.ferranti.com)